



Together with Nextel

10 Industrial Ave, Suite 3  
Mahwah, NJ 07430  
Phone: (845)499-4712  
Jennifer Notaro  
Real Estate Consultant

July 29, 2014

**Hand Delivered**

Ms. Melanie A. Bachman  
Acting Executive Director  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

CC to Property Owner  
Monte, LLC  
40 Woodland Street, Hartford, CT 06105

RE: Sprint Spectrum L.P. notice of intent to modify an existing telecommunications facility located at 81 Montevideo Road, Avon, CT 06001. Known to Sprint Spectrum L.P. as site CT03XC053.

Dear Ms. Bachman:

In order to accommodate technological changes, implement Code Division Multiple Access (“CDMA”) and/or Long Term Evolution (“LTE”) capabilities, and enhance system performance in the state of Connecticut, Sprint Spectrum L.P. plans to modify the equipment configurations at many of its existing cell sites. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and its attachments is being sent to the chief elected official of the municipality in which affected cell site is located.

CDMA employs Spread-Spectrum technology and special coding scheme to allow multiple users to be multiplexed over the same physical channel.

LTE is a new high-performance air interface for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in Sprint's operations at the site. Also included is documentation of the structural sufficiency of the tower to accommodate the revised antenna configuration.

The changes to the facility do not constitute modification as defined Connecticut General Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for the R.C.S.A. Section 16-50j-72(b)(2).

1. The height of the overall structure will not be affected.
2. The proposed changes will not extend the site boundaries. There will be no effect on the site compound.
3. The proposed changes will not increase the noise level at the existing facility by 6 decibels or more.
4. Radio Frequency power density may increase due to the use of one or more CDMA transmissions. Moreover, LTE will utilize additional radio frequencies newly licensed by the FCC for cellular mobile communications. However, the changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons Sprint Spectrum L.P. respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A. Section 16-50j-72(b)(2).

Please feel free to call me at (845)-499-4712 or email [JNotaro@Transcendwireless.com](mailto:JNotaro@Transcendwireless.com) with questions concerning this matter. Thank you for your consideration.

Sincerely,

Jennifer Notaro  
Real Estate Consultant

RADIO FREQUENCY FCC REGULATORY COMPLIANCE  
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT03XC053

Avon Mountain

81 Montevideo Road  
Avon, CT 06001

**July 27, 2014**

**EBI Project Number: 62144004**

July 27, 2014

Sprint  
Attn: RF Engineering Manager  
1 International Boulevard, Suite 800  
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:  
**CT03XC053 - Avon Mountain**

**Site Total: 3.02% - MPE% in full compliance**

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 81 Montevideo Road, Avon, CT, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limit for the cellular band (850 MHz Band) is approximately  $567 \mu\text{W}/\text{cm}^2$ , and the general population exposure limit for the 1900 MHz and 2500 MHz bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 81 Montevideo Road, Avon, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 3 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **147 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT03XC053 - Avon Mountain
Site Address	81 Montevideo Road, Avon, CT, 06001
Site Type	Self Support Tower

**Sector 1**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	147	141	1/2 "	0.5	0	208.04	0.38%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	147	141	1/2 "	0.5	0	39.00	0.12%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	147	141	1/2 "	0.5	0	138.69	0.44%
Sector total Power Density Value:															0.94%	

**Sector 2**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	147	141	1/2 "	0.5	0	208.04	0.38%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	147	141	1/2 "	0.5	0	39.00	0.12%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	147	141	1/2 "	0.5	0	138.69	0.44%
Sector total Power Density Value:															0.94%	

**Sector 3**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	147	141	1/2 "	0.5	0	208.04	0.38%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	147	141	1/2 "	0.5	0	39.00	0.12%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	147	141	1/2 "	0.5	0	138.69	0.44%
Sector total Power Density Value:															0.94%	

Site Composite MPE %	
Carrier	MPE %
Sprint	2.83%
T-Mobile	0.19%
<b>Total Site MPE %</b>	<b>3.02%</b>

## Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **2.83% (0.94% from sector 1, 0.94% from sector 2 and 0.94% from sector 3)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **3.02%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



**Scott Heffernan**  
RF Engineering Director

**EBI Consulting**  
21 B Street  
Burlington, MA 01803



# RAMAKER & ASSOCIATES, INC.

## STRUCTURAL ASSESSMENT - 150-FOOT SELF-SUPPORT TOWER FOR: TRANSCEND WIRELESS - SPRINT

**SITE NAME: AVON MOUNTAIN**  
**SITE ID: CT03XC053**

**TOWER: PASS - 90.1%**  
**FOUNDATION: NOT DETERMINED**

**RAMAKER & ASSOCIATES, INC.**  
**JOB NUMBER: 22984**

1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 ▲ Fax: 608-643-7999  
[www.ramaker.com](http://www.ramaker.com)

MATCHLINE SEE SHEET C106



**STRUCTURAL ASSESSMENT**

**SITE:** Avon Mountain (CT03XC053)  
81 Montevideo Road  
Avon, Hartford County, Connecticut 06001


**PREPARED FOR:** Transcend Wireless

**CONTACT PERSON:** Mike Kithcart  
Transcend Wireless  
48 Spruce Street, Oakland, NJ 07436

**PREPARED BY:** Ramaker & Associates, Inc.  
1120 Dallas Street  
Sauk City, Wisconsin 53583  
Telephone: (608) 643-4100  
Facsimile: (608) 643-7999

**RAMAKER JOB NUMBER:** 22984

**DATE OF REPORT ISSUANCE:** July 14, 2014

  
\_\_\_\_\_  
Jonathan Styx  
Engineering Technician

07/14/14  
Date

  
\_\_\_\_\_  
James R. Skowronski, P.E.  
Supervising Engineer

07/14/14  
Date



**TABLE OF CONTENTS**

**EXECUTIVE SUMMARY .....3**

**INTRODUCTION.....4**

    2.1 PROJECT INFORMATION

    2.2 PURPOSE OF REPORT

    2.3 SCOPE OF SERVICES

**MODEL DEVELOPMENT .....5**

    3.1 INTRODUCTION

    3.2 EXISTING STRUCTURE INFORMATION

    3.3 TOWER LOADING

    3.4 WIND AND ICE LOAD

**ANALYSIS RESULTS .....7**

    4.1 ANALYSIS RESULTS

    4.2 BASE REACTIONS

    4.3 MOUNT ASSESSMENT

**LIMITATIONS.....9**

**REFERENCES..... 10**

**LIST OF APPENDICES**

- A. TOWER FIGURES
- B. TOWER CALCULATIONS
- C. MOUNT CALCULATIONS

**SECTION 1**  
**EXECUTIVE SUMMARY**

This report summarizes the structural analysis conducted by Ramaker & Associates, Inc. (RAMAKER) for Transcend Wireless on behalf of Sprint, who intends to install additional equipment on an existing tower.

The Sprint proposed loading includes installing three (3) RFS APXV9TM14-ALU-120 panel antennas and three (3) Alcatel-Lucent TD-RRH 8x20 units on the two (2) existing steel mounting frames and one (1) proposed steel mounting frame at a centerline elevation of 147-feet AGL. The proposed antennas shall be fed with one (1) new 1-1/4-inch hybrid coax.

Results of our tower analysis show that the tower will be stressed to a maximum of 90.1 percent of capacity under proposed loading conditions. Information regarding the existing soils or the existing tower foundation was not available for analysis. **Therefore, no conclusions could be made regarding the adequacy of the existing foundations.**

Results of our mount assessment show that by engineering calculation and inspection, the antenna and RRH mounting structure is capable of supporting the existing and proposed Sprint 2.5 equipment deployment without causing an overstress condition in the antenna and RRH mounting structure, **provided the proposed structural modifications are completed prior to installation of new equipment per construction drawings by Ramaker & Associates.**

In summary, the tower will pass the TIA/EIA-222-F code requirements under proposed loading conditions. **However, the adequacy of the existing foundations could not be verified.** The mounting structure will pass the TIA-222 code requirements under proposed loading conditions.

## **SECTION 2**

### **INTRODUCTION**

#### **2.1 PROJECT INFORMATION**

This report summarizes the structural analysis conducted by Ramaker & Associates, Inc. (RAMAKER) for Transcend Wireless on behalf of Sprint, who intends to install additional equipment on an existing tower.

#### **2.2 PURPOSE OF REPORT**

The analysis activities of this report were conducted for the purposes of creating and analyzing a model of the subject structure under the required loading conditions. Base reactions from the resulting model were also determined for tower foundation and support development. Recommendations regarding the analysis results, loading configuration, and structural modifications are also provided.

#### **2.3 SCOPE OF SERVICES**

RAMAKER developed a finite element model (FEM) of the tower, using tnxTower, for member force, joint deflection, and structure reaction determinations. Subsequently, this report was drafted to provide our engineering recommendations. All information contained herein is valid only for the described structure configuration and loading conditions. RAMAKER reserves the right to modify our recommendations should alterations to the tower loading occur.

**SECTION 3  
MODEL DEVELOPMENT**

**3.1 INTRODUCTION**

RAMAKER developed a FEM of the tower superstructure. Required static loads consisting of the antenna configuration, wind forces, ice loads, and linear appurtenances (including cable loads) were then applied to the FEM. As a result, all member forces, allowable capacities, and base reactions were computed. Additionally, potentially overstressed members were identified.

**3.2 EXISTING STRUCTURE INFORMATION**

Existing structure information was gathered from:

- Previous structural analysis by RAMAKER, project number 22984, dated October 10, 2013.

**3.3 TOWER LOADING**

RAMAKER understands that the tower loading to be used for this analysis will consist of the existing and proposed antenna, mount, and cable configurations as shown in the following chart:

Elevation	Appurtenance	Mount	Coax	Owner	Status
149	Lightning Rod	Tower Leg	---	Tower	Existing
	8' Whip Antenna		(1) 7/8		
147	(3) RFS APXVSP18-C	Proposed Sector Frame (Alpha) Sector Frame (Beta) Stand-off (Gamma)	(6) 1-5/8 (1) 1-1/4 Hybrid	Sprint	Existing
	(3) ALU 1900 MHz 4x40W RRH				Proposed
	(3) ALU 800 MHz 2x50 RRH				
	(3) RFS APXV9TM14-ALU-120				
	(3) ALU TD-RRH 8x20 RRH				
136	(3) RFS APXV18-206516S-C	Sector Frame	(6) 1-5/8	T-Mobile	Existing
121	14' Whip Antenna	Standoff	(1) 7/8	Unknown	Existing
117	21' Whip Antenna	Standoff	(1) 1-1/4	Unknown	Existing
108	10' Dipole Antenna	Standoff	(1) 7/8	Unknown	Existing
105	8' Whip Antenna	Standoff	(1) 1-1/4	Unknown	Existing
102	6'-4" Antenna	Tower Leg	(1) 1/2	Unknown	Existing
98	12' Whip Antenna	Standoff	(1) 7/8	Unknown	Existing
84	3'-6" Microwave Dish	Standoff	(1) 1/4	Unknown	Existing
78	4'-0" Microwave Dish	Standoff	(1) 1/4	Unknown	Existing
74	GPS Antenna	Tower Leg	(1) 1/2	Unknown	Existing
72	4'-0" Microwave Dish	Standoff	(1) 1/4	Unknown	Existing
67	GPS Antenna	Tower Leg	(1) 1/4	Unknown	Existing
12	GPS Antenna	Tower Leg	(2) 1/2	Unknown	Existing

### **3.4 WIND AND ICE LOAD**

Wind forces used in model development are in compliance with the TIA/EIA-222-F Standard. These guidelines call for an analysis to be performed which assumes a basic wind speed of 80 miles-per-hour (mph) without ice in Hartford County. The tower is also designed for a 70 mph basic wind speed with 1.25-inch of radial ice.

**SECTION 4**  
**ANALYSIS RESULTS**

**4.1 ANALYSIS RESULTS**

The tower superstructure was analyzed with the combined existing and proposed antenna loading with and without radial ice. The computed maximum tower member stress capacities are as follows:

Component Type	Percent Capacity
Leg	90.1
Diagonal	49.0
Horizontal	37.3
Bolt	58.9
<b>RATING =</b>	<b>90.1</b>

**4.2 BASE REACTIONS**

The computed maximum reactions under the corresponding maximum moment are as follows:

Load Type	Original Design	Proposed Model
Total Axial (k)	--	75.0
Total Shear (k)	--	31.8
Total Moment (k-ft)	--	2597.3
Leg Uplift (k)	--	183.5
Leg Compression (k)	--	239.2
Leg Shear (k)	--	21.5

Information regarding the existing soils or the existing tower foundation was not available for analysis. **Therefore, no conclusions could be made regarding the adequacy of the existing foundations.**

## **AVON MOUNTAIN (CT03XC053)**

---

---

### **4.3 MOUNT ASSESSMENT**

Results of our mount assessment show that by engineering calculation and inspection, the antenna and RRH mounting structure is capable of supporting the existing and proposed Sprint 2.5 equipment deployment without causing an overstress condition in the antenna and RRH mounting structure, **provided the proposed structural modifications are completed prior to installation of new equipment per construction drawings by Ramaker & Associates.**

This assessment is inclusive of the entire antenna mounting structure, including tower platforms, arms, and all other aspects of the mounting structure that will support the Sprint 2.5 equipment deployment. This assessment assumes that the mounting structure(s) has been installed correctly, is free from deterioration, and is maintained properly.

## **SECTION 5**

### **LIMITATIONS**

The recommendations contained within this report were developed using general project information provided by the owner, tower manufacturer, general field observations, reference information and laboratory testing data, as applicable. All recommendations pertain only to the proposed tower construction, location, and loading as described in this report. RAMAKER assumes no responsibility for failures caused by factors beyond our control. These include but are not limited to the following:

1. Missing, corroding, and/or deteriorating members
2. Improper manufacturing and/or construction
3. Improper maintenance

RAMAKER assumes no responsibility for modifications completed prior to or hereafter in which RAMAKER was not directly involved. These modifications include but are not limited to the following:

1. Replacing or strengthening bracing members
2. Reinforcing or extending vertical members
3. Installing or removing antenna mounting gates or side arms
4. Changing loading configurations

Furthermore, RAMAKER hereby states that this document represents the entire report and that it assumes no liability for any factual changes that may occur after the date of this report. All representations, recommendations and conclusions are based on the information contained and set forth herein. If you are aware of any information contrary to that contained herein, or if you are aware of any defects arising from the original design, material, fabrication and erection deficiencies, you should disregard this report and immediately contact RAMAKER. RAMAKER isn't liable for any representation, recommendation or conclusion not expressly stated herein.

The tower owner is responsible for verifying that the existing loading on the tower is consistent with the loading applied to the tower within this report.

**SECTION 6**  
**REFERENCES**

1. 2003 International Building Code.
2. Telecommunications Industries Association, Structural Standards for Steel Antenna Towers and Antenna Supporting Structures, TIA Standard TIA/EIA-222-F 1996, Washington, D.C.


**APPENDIX A**  
**TOWER FIGURES**



TIA/EIA-222-F - 80 mph/69 mph 1.2500 in Ice

Leg Capacity ———

Leg Compression (lb)



 <p><b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	Job: <b>Avon Mountain (CT03XC053)</b>		
	Project: <b>22984</b>		
	Client: <b>Sprint</b>	Drawn by: <b>JDS</b>	App'd:
	Code: <b>TIA/EIA-222-F</b>	Date: <b>07/03/14</b>	Scale: <b>NTS</b>
Path: <small>I:\22900\22984\Structural\Ris\22984_Rev2.eri</small>		Dwg No. <b>E-3</b>	


Vx

Vz


Mx

Mz




Global Mast Shear (lb)



Global Mast Moment (lb-ft)



	<b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999		Job: <b>Avon Mountain (CT03XC053)</b>	
	Project: <b>22984</b>		Drawn by: JDS App'd:	
	Client: <b>Sprint</b>		Date: 07/03/14 Scale: NTS	
	Code: TIA/EIA-222-F		Path: I:\22900\22984\Structural\Ris\22984_Rev2.eri	
	Dwg No. E-4			




 <p><b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	<b>Job: Avon Mountain (CT03XC053)</b>		
	Project: 22984		
	Client: Sprint	Drawn by: JDS	App'd:
	Code: TIA/EIA-222-F	Date: 07/03/14	Scale: NTS
	Path: I:\22984\22984\Structural\Ris\22984_Rev2.eri		Dwg No. E-5



# Feed Line Distribution Chart 0' - 150'

— Round   
 — Flat   
 — App In Face   
 — App Out Face   
 — Truss Leg




	<b>Ramaker &amp; Associates</b>		<b>Job: Avon Mountain (CT03XC053)</b>		
	1120 Dallas St.		Project: <b>22984</b>		
	Sauk City, WI 53583		Client: <b>Sprint</b>	Drawn by: <b>JDS</b>	App'd:
	Phone: (608) 643-4100		Code: <b>TIA/EIA-222-F</b>	Date: <b>07/03/14</b>	Scale: <b>NTS</b>
	FAX: (608) 643-7999		Path: <small>I:\22984\22984\Structural\Ris\22984 Rev2.eri</small>	Dwg No. <b>E-7</b>	

# Stress Distribution Chart

0' - 150'

■ > 100% 
 ■ 90%-100% 
 ■ 75%-90% 
 ■ 50%-75% 
 ■ < 50% Overstress



	<b>Ramaker &amp; Associates</b>		Job: <b>Avon Mountain (CT03XC053)</b>		
	1120 Dallas St.		Project: <b>22984</b>		
	Sauk City, WI 53583		Client: <b>Sprint</b>	Drawn by: <b>JDS</b>	App'd:
	Phone: (608) 643-4100		Code: <b>TIA/EIA-222-F</b>	Date: <b>07/03/14</b>	Scale: <b>NTS</b>
	FAX: (608) 643-7999		Path: <small>I:\22984\22984\Structural\Ris\22984 Rev2.eri</small>	Dwg No. <b>E-8</b>	

**APPENDIX B**  
**TOWER CALCULATIONS**


<p><b>tnxTower</b></p> <p><b>Ramaker &amp; Associates</b>  1120 Dallas St.  Sauk City, WI 53583  Phone: (608) 643-4100  FAX: (608) 643-7999</p>	<b>Job</b> Avon Mountain (CT03XC053)	<b>Page</b> 1 of 26
	<b>Project</b> 22984	<b>Date</b> 09:40:47 07/03/14
	<b>Client</b> Sprint	<b>Designed by</b> JDS

**Tower Input Data**

The main tower is a 3x free standing tower with an overall height of 150.00 ft above the ground line.  
The base of the tower is set at an elevation of 0.00 ft above the ground line.  
The face width of the tower is 5.00 ft at the top and 14.00 ft at the base.  
This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

- Tower is located in Hartford County, Connecticut.
- Basic wind speed of 80 mph.
- Nominal ice thickness of 1.2500 in.
- Ice density of 56 pcf.
- A wind speed of 69 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 60 mph.
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in tower member design is 1.333.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.



**Triangular Tower**

**Tower Section Geometry**

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	2 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Tower Section	Tower Elevation	Assembly Database	Description	Section Width	Number of Sections	Section Length
	ft			ft		ft
T1	150.00-130.00			5.00	1	20.00
T2	130.00-110.00			5.00	1	20.00
T3	110.00-90.00			5.00	1	20.00
T4	90.00-80.00			5.00	1	10.00
T5	80.00-60.00			6.00	1	20.00
T6	60.00-40.00			8.00	1	20.00
T7	40.00-20.00			10.00	1	20.00
T8	20.00-0.00			12.00	1	20.00

### Tower Section Geometry (cont'd)

Tower Section	Tower Elevation	Diagonal Spacing	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset	Bottom Girt Offset
	ft	ft				in	in
T1	150.00-130.00	2.33	X Brace	No	Steps	8.0000	8.0000
T2	130.00-110.00	2.33	X Brace	No	Steps	8.0000	8.0000
T3	110.00-90.00	2.33	X Brace	No	Steps	8.0000	8.0000
T4	90.00-80.00	10.00	X Brace	No	No	0.0000	0.0000
T5	80.00-60.00	10.00	X Brace	No	No	0.0000	0.0000
T6	60.00-40.00	10.00	X Brace	No	No	0.0000	0.0000
T7	40.00-20.00	10.00	X Brace	No	No	0.0000	0.0000
T8	20.00-0.00	10.00	X Brace	No	No	0.0000	0.0000

### Tower Section Geometry (cont'd)

Tower Elevation	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
ft						
T1 150.00-130.00	Solid Round	1 3/4	A572-50 (50 ksi)	Solid Round	7/8	A572-50 (50 ksi)
T2 130.00-110.00	Solid Round	2	A572-50 (50 ksi)	Solid Round	7/8	A572-50 (50 ksi)
T3 110.00-90.00	Solid Round	2 1/4	A572-50 (50 ksi)	Solid Round	1	A572-50 (50 ksi)
T4 90.00-80.00	Truss Leg	Pirod 216415	A572-50 (50 ksi)	Equal Angle	L3x3x5/16	A36 (36 ksi)
T5 80.00-60.00	Truss Leg	Pirod 216413	A572-50 (50 ksi)	Equal Angle	L3x3x5/16	A36 (36 ksi)
T6 60.00-40.00	Truss Leg	Pirod 195557	A572-50 (50 ksi)	Equal Angle	L3x3x5/16	A36 (36 ksi)
T7 40.00-20.00	Truss Leg	Pirod 195557	A572-50 (50 ksi)	Equal Angle	L3x3x5/16	A36 (36 ksi)
T8 20.00-0.00	Truss Leg	Pirod 195557	A572-50 (50 ksi)	Equal Angle	L3x3x5/16	A36 (36 ksi)

### Tower Section Geometry (cont'd)

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	3 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Tower Elevation ft	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
T1 150.00-130.00	Solid Round	1	A572-50 (50 ksi)	Solid Round	1	A572-50 (50 ksi)
T2 130.00-110.00	Solid Round	1	A572-50 (50 ksi)	Solid Round	1	A572-50 (50 ksi)
T3 110.00-90.00	Solid Round	1 1/4	A572-50 (50 ksi)	Solid Round	1 1/4	A572-50 (50 ksi)

### Tower Section Geometry (cont'd)

Tower Elevation ft	No. of Mid Girts	Mid Girt Type	Mid Girt Size	Mid Girt Grade	Horizontal Type	Horizontal Size	Horizontal Grade
T1 150.00-130.00	1	Solid Round	1	A572-50 (50 ksi)	Solid Round	7/8	A572-50 (50 ksi)
T2 130.00-110.00	1	Solid Round	1	A572-50 (50 ksi)	Solid Round	7/8	A572-50 (50 ksi)
T3 110.00-90.00	1	Solid Round	1 1/4	A572-50 (50 ksi)	Solid Round	7/8	A572-50 (50 ksi)

### Tower Section Geometry (cont'd)

Tower Elevation ft	Gusset Area (per face) ft <sup>2</sup>	Gusset Thickness in	Gusset Grade	Adjust. Factor A <sub>f</sub>	Adjust. Factor A <sub>r</sub>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontal in
T1 150.00-130.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T2 130.00-110.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T3 110.00-90.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T4 90.00-80.00	0.33	0.5000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T5 80.00-60.00	0.77	0.5000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T6 60.00-40.00	0.77	0.5000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T7 40.00-20.00	0.77	0.5000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T8 20.00-0.00	0.77	0.5000	A36 (36 ksi)	1	1	1	36.0000	36.0000

### Tower Section Geometry (cont'd)



<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	5 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Tower Elevation ft	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T8 20.00-0.00	0.0000	1	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75

**Tower Section Geometry (cont'd)**

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.								
T1 150.00-130.00	Sleeve DS	0.6250	5	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T2 130.00-110.00	Sleeve DS	0.7500	5	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T3 110.00-90.00	Flange	1.0000	6	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T4 90.00-80.00	Flange	1.0000	6	1.2500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T5 80.00-60.00	Flange	1.0000	6	1.2500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T6 60.00-40.00	Flange	1.0000	6	1.2500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T7 40.00-20.00	Flange	1.0000	6	1.2500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T8 20.00-0.00	Flange	1.0000	6	1.2500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A687		A325N		A325N									

**Feed Line/Linear Appurtenances - Entered As Round Or Flat**

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
LDF5-50A (7/8 FOAM) (8' Whip)	C	Yes	Ar (CfAe)	150.00 - 0.00	-16.0000	0.4	1	1	1.0900	1.0900		0.33
*****												
LCF158-50J (1 5/8 FOAM) (136' T-Mobile)	C	Yes	Ar (CfAe)	136.00 - 0.00	-8.0000	0.4	6	3	2.0100	2.0100		0.92
*****												
LDF5-50A (7/8 FOAM) (121' Omni)	C	No	Ar (CfAe)	121.00 - 0.00	-20.0000	0.4	1	1	1.0900	1.0900		0.33
LDF6-50A (1-1/4 FOAM) (117' Omni)	C	No	Ar (CfAe)	117.00 - 0.00	-20.0000	0.4	1	1	1.5500	1.5500		0.66
LDF5-50A (7/8 FOAM) (108 Dipole)	A	Yes	Ar (CfAe)	108.00 - 0.00	-18.0000	0.4	1	1	1.0900	1.0900		0.33
LDF6-50A (1-1/4 FOAM) (105' Whip)	C	Yes	Ar (CfAe)	105.00 - 0.00	-16.0000	0.42	1	1	1.5500	1.5500		0.66
LDF4-50A (1/2 FOAM) (102' Leg Mounted)	C	Yes	Ar (CfAe)	102.00 - 0.00	-21.0000	0.4	1	1	0.6300	0.6300		0.15
LDF5-50A (7/8 FOAM)	C	Yes	Ar (CfAe)	98.00 - 0.00	-21.0000	0.4	1	1	1.0900	1.0900		0.33

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	6 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Description	Face Allow or Shield Leg	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	# Per Row	#	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
(98' Omni)											
*****											
1/4 (84' Dish)	C Yes	Ar (CfAe)	84.00 - 0.00	-18.0000	0.42	1	1	0.2900	0.2900		0.07
1/4 (78' Dish)	C Yes	Ar (CfAe)	78.00 - 0.00	-18.0000	0.4	1	1	0.2900	0.2900		0.07
LDF4-50A (1/2 FOAM) (74' GPS)	A Yes	Ar (CfAe)	74.00 - 0.00	-18.0000	0.42	1	1	0.6300	0.6300		0.15
1/4 (72' Dish)	C Yes	Ar (CfAe)	72.00 - 0.00	-19.0000	0.42	1	1	0.2900	0.2900		0.07
1/4 (67' Dish)	C Yes	Ar (CfAe)	66.00 - 0.00	-19.0000	0.4	1	1	0.2900	0.2900		0.07
1/2 (12' GPS)	C Yes	Ar (CfAe)	12.00 - 0.00	0.0000	-0.45	2	2	0.5800	0.5800		0.25
*****											
1-OC-114 Power/Fiber (147' Sprint)	A Yes	Ar (CfAe)	147.00 - 0.00	-10.0000	0.4	3	3	1.5400	1.5400		1.00
1-OC-114 Power/Fiber (147' Sprint - Reserved)	A Yes	Ar (CfAe)	147.00 - 0.00	-7.0000	0.4	3	3	1.5400	1.5400		1.00

### Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight lb
T1	150.00-130.00	A	13.090	0.000	0.000	0.000	102.00
		B	0.000	0.000	0.000	0.000	0.00
		C	4.832	0.000	0.000	0.000	39.72
T2	130.00-110.00	A	15.400	0.000	0.000	0.000	120.00
		B	0.000	0.000	0.000	0.000	0.00
		C	13.770	0.000	0.000	0.000	125.25
T3	110.00-90.00	A	17.035	0.000	0.000	0.000	125.94
		B	0.000	0.000	0.000	0.000	0.00
		C	19.561	0.000	0.000	0.000	151.14
T4	90.00-80.00	A	8.608	0.000	0.000	0.000	63.30
		B	0.000	0.000	0.000	0.000	0.00
		C	10.955	0.000	0.000	0.000	80.08
T5	80.00-60.00	A	17.952	0.000	0.000	0.000	128.70
		B	0.000	0.000	0.000	0.000	0.00
		C	23.070	0.000	0.000	0.000	163.52
T6	60.00-40.00	A	18.267	0.000	0.000	0.000	129.60
		B	0.000	0.000	0.000	0.000	0.00
		C	23.650	0.000	0.000	0.000	165.20
T7	40.00-20.00	A	18.267	0.000	0.000	0.000	129.60
		B	0.000	0.000	0.000	0.000	0.00
		C	23.650	0.000	0.000	0.000	165.20
T8	20.00-0.00	A	18.267	0.000	0.000	0.000	129.60
		B	0.000	0.000	0.000	0.000	0.00
		C	24.810	0.000	0.000	0.000	171.20

### Feed Line/Linear Appurtenances Section Areas - With Ice

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	7 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight lb
T1	150.00-130.00	A	1.250	11.447	17.453	0.000	0.000	526.66
		B		0.000	0.000	0.000	0.000	0.00
		C		8.238	4.020	0.000	0.000	306.37
T2	130.00-110.00	A	1.250	13.467	20.533	0.000	0.000	619.60
		B		0.000	0.000	0.000	0.000	0.00
		C		19.153	13.400	0.000	0.000	916.56
T3	110.00-90.00	A	1.250	18.852	20.533	0.000	0.000	689.87
		B		0.000	0.000	0.000	0.000	0.00
		C		36.819	13.400	0.000	0.000	1157.38
T4	90.00-80.00	A	1.250	9.725	10.267	0.000	0.000	348.84
		B		0.000	0.000	0.000	0.000	0.00
		C		23.022	6.700	0.000	0.000	636.22
T5	80.00-60.00	A	1.250	23.102	20.533	0.000	0.000	739.97
		B		0.000	0.000	0.000	0.000	0.00
		C		57.203	13.400	0.000	0.000	1388.70
T6	60.00-40.00	A	1.250	24.667	20.533	0.000	0.000	758.10
		B		0.000	0.000	0.000	0.000	0.00
		C		62.783	13.400	0.000	0.000	1446.82
T7	40.00-20.00	A	1.250	24.667	20.533	0.000	0.000	758.10
		B		0.000	0.000	0.000	0.000	0.00
		C		62.783	13.400	0.000	0.000	1446.82
T8	20.00-0.00	A	1.250	24.667	20.533	0.000	0.000	758.10
		B		0.000	0.000	0.000	0.000	0.00
		C		65.863	14.560	0.000	0.000	1501.80

### Feed Line Shielding

Section	Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>R</sub> Ice ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	A <sub>F</sub> Ice ft <sup>2</sup>
T1	150.00-130.00	A	1.006	8.440	0.000	0.000
		B	0.000	0.000	0.000	0.000
		C	0.477	4.614	0.000	0.000
T2	130.00-110.00	A	1.184	9.930	0.000	0.000
		B	0.000	0.000	0.000	0.000
		C	1.172	10.126	0.000	0.000
T3	110.00-90.00	A	1.519	11.987	0.000	0.000
		B	0.000	0.000	0.000	0.000
		C	1.684	14.572	0.000	0.000
T4	90.00-80.00	A	0.000	1.727	0.892	2.072
		B	0.000	0.000	0.000	0.000
		C	0.000	2.017	0.907	2.421
T5	80.00-60.00	A	0.000	3.181	1.571	3.818
		B	0.000	0.000	0.000	0.000
		C	0.000	4.219	1.633	5.063
T6	60.00-40.00	A	0.000	2.820	1.368	3.384
		B	0.000	0.000	0.000	0.000
		C	0.000	3.959	1.441	4.751
T7	40.00-20.00	A	0.000	2.548	1.236	3.057
		B	0.000	0.000	0.000	0.000
		C	0.000	3.577	1.302	4.292
T8	20.00-0.00	A	0.000	2.378	1.153	2.853
		B	0.000	0.000	0.000	0.000
		C	0.000	3.561	1.288	4.273

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Avon Mountain (CT03XC053)	<b>Page</b> 8 of 26
	<b>Project</b> 22984	<b>Date</b> 09:40:47 07/03/14
	<b>Client</b> Sprint	<b>Designed by</b> JDS

### Feed Line Center of Pressure

Section	Elevation	CP <sub>x</sub>	CP <sub>z</sub>	CP <sub>x</sub> Ice	CP <sub>z</sub> Ice
	ft	in	in	in	in
T1	150.00-130.00	-0.7485	-4.6273	-0.5128	-1.2426
T2	130.00-110.00	-3.2417	-3.7103	-1.6520	-1.2037
T3	110.00-90.00	-4.0732	-3.6219	-2.8018	-1.5771
T4	90.00-80.00	-3.1133	-2.1945	-2.9070	-1.1507
T5	80.00-60.00	-4.2418	-2.4421	-4.6206	-1.1632
T6	60.00-40.00	-5.5452	-2.6419	-6.4444	-0.9278
T7	40.00-20.00	-6.8279	-2.8621	-7.9444	-0.6581
T8	20.00-0.00	-7.5270	-2.7521	-9.1645	-0.3117

### Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight lb	
8' Whip	B	From Leg	0.00	0.0000	149.00	No Ice	1.36	1.36	43.65
			0.00			1/2" Ice	2.26	2.26	56.01
			4.00			1" Ice	3.20	3.20	74.83
						2" Ice	4.57	4.57	131.26
Lightning Rod 5/8x4'	C	From Leg	0.00	0.0000	149.00	No Ice	0.25	0.25	31.00
			0.00			1/2" Ice	0.66	0.66	33.82
			2.00			1" Ice	0.97	0.97	39.29
						2" Ice	1.49	1.49	58.83
*****									
*****									
Andrew 12'-6" Universal Sector Frame (T-Mobile)	A	From Face	1.00	0.0000	136.00	No Ice	10.80	10.80	525.00
			0.00			1/2" Ice	15.10	15.10	675.00
			0.00			1" Ice	19.40	19.40	825.00
						2" Ice	28.00	28.00	1125.00
(3) APXV18-206516S-C	A	From Face	1.50	0.0000	136.00	No Ice	5.93	4.61	18.70
			0.00			1/2" Ice	6.39	4.99	58.72
			0.00			1" Ice	6.85	5.43	103.97
						2" Ice	7.81	6.36	210.96
*****									
15' Omni	C	From Leg	4.00	0.0000	121.00	No Ice	3.75	3.75	40.00
			0.00			1/2" Ice	5.28	5.28	67.80
			4.00			1" Ice	6.83	6.83	105.17
						2" Ice	9.97	9.97	209.24
6' Standoff	C	From Leg	2.00	0.0000	121.00	No Ice	4.97	4.97	70.00
			0.00			1/2" Ice	6.12	6.12	130.00
			0.00			1" Ice	7.27	7.27	190.00
						2" Ice	9.57	9.57	310.00
20' Omni	A	From Leg	4.00	0.0000	117.00	No Ice	5.00	5.00	55.00
			0.00			1/2" Ice	7.03	7.03	91.96
			10.00			1" Ice	9.07	9.07	141.55
						2" Ice	13.22	13.22	279.21
6' Standoff	A	From Leg	2.00	0.0000	117.00	No Ice	4.97	4.97	70.00
			0.00			1/2" Ice	6.12	6.12	130.00
			0.00			1" Ice	7.27	7.27	190.00

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	9 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub>		Weight
			Horz	Vert			Front	Side	
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	lb
10' Dipole	A	From Leg	4.00	0.0000	108.00	2" Ice	9.57	9.57	310.00
			0.00			No Ice	3.00	3.00	30.00
			4.00			1/2" Ice	4.00	4.00	55.00
						1" Ice	5.00	5.00	85.00
						2" Ice	6.25	6.25	100.00
6' Standoff	A	From Leg	2.00	0.0000	108.00	No Ice	4.97	4.97	70.00
			0.00			1/2" Ice	6.12	6.12	130.00
			0.00			1" Ice	7.27	7.27	190.00
						2" Ice	9.57	9.57	310.00
						No Ice	1.36	1.36	43.65
8' Whip	C	From Leg	4.00	0.0000	105.00	1/2" Ice	2.26	2.26	56.01
			0.00			1" Ice	3.20	3.20	74.83
			4.00			2" Ice	4.57	4.57	131.26
						No Ice	2.72	2.72	50.00
						1/2" Ice	4.91	4.91	89.00
4' Standoff	C	From Leg	2.00	0.0000	105.00	1" Ice	7.10	7.10	128.00
			0.00			2" Ice	11.48	11.48	206.00
			0.00			No Ice	2.20	2.20	30.00
						1/2" Ice	3.03	3.03	46.24
						1" Ice	3.57	3.57	67.80
8' Omni	C	From Leg	0.50	0.0000	102.00	2" Ice	4.56	4.56	127.49
			0.00			No Ice	3.00	3.00	35.00
			0.00			1/2" Ice	4.23	4.23	57.30
						1" Ice	5.47	5.47	87.34
						2" Ice	7.69	7.69	171.25
12' Omni	C	From Leg	4.00	0.0000	98.00	No Ice	4.97	4.97	70.00
			0.00			1/2" Ice	6.12	6.12	130.00
			5.00			1" Ice	7.27	7.27	190.00
						2" Ice	9.57	9.57	310.00
						No Ice	2.00	2.00	38.00
6' Standoff	C	From Leg	2.00	0.0000	98.00	1/2" Ice	3.70	3.70	67.00
			0.00			1" Ice	5.40	5.40	96.00
			0.00			2" Ice	8.80	8.80	154.00
						No Ice	2.00	2.00	38.00
						1/2" Ice	3.70	3.70	67.00
3' Standoff	C	From Leg	2.00	0.0000	78.00	1" Ice	5.40	5.40	96.00
			0.00			2" Ice	8.80	8.80	154.00
			0.00			No Ice	1.00	1.00	10.00
						1/2" Ice	1.50	1.50	15.00
						1" Ice	2.00	2.00	20.00
3' Standoff	C	From Leg	2.00	0.0000	72.00	2" Ice	3.00	3.00	30.00
			0.00			No Ice	2.00	2.00	38.00
			0.00			1/2" Ice	3.70	3.70	67.00
						1" Ice	5.40	5.40	96.00
						2" Ice	8.80	8.80	154.00
GPS	A	From Leg	0.50	0.0000	74.00	No Ice	1.00	1.00	10.00
			0.00			1/2" Ice	1.50	1.50	15.00
			0.00			1" Ice	2.00	2.00	20.00
						2" Ice	3.00	3.00	30.00
						No Ice	1.00	1.00	10.00
GPS	C	From Leg	0.50	0.0000	67.00	1/2" Ice	1.50	1.50	15.00
			0.00			1" Ice	2.00	2.00	20.00
			0.00			2" Ice	3.00	3.00	30.00
						No Ice	1.00	1.00	10.00
						1/2" Ice	1.50	1.50	15.00
GPS	B	From Leg	0.50	0.0000	12.00	1" Ice	2.00	2.00	20.00
			0.00			No Ice	1.00	1.00	10.00
			0.00			1/2" Ice	1.50	1.50	15.00

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	10 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub>		Weight	
			Horz	Vert			Front	Side		
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	lb	
						2" Ice	3.00	3.00	30.00	
*****										
APXVSPP18-C w/Mount Pipe (Sprint)	A	From Leg	0.00 2.00 0.00		0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.26 8.81 9.36 10.50	6.71 7.66 8.49 10.20	78.90 144.31 217.47 390.34
APXVSPP18-C w/Mount Pipe (Sprint)	B	From Leg	0.00 -6.00 0.00		0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.26 8.81 9.36 10.50	6.71 7.66 8.49 10.20	78.90 144.31 217.47 390.34
APXVSPP18-C w/Mount Pipe (Sprint)	B	From Leg	0.00 6.00 0.00		0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.26 8.81 9.36 10.50	6.71 7.66 8.49 10.20	78.90 144.31 217.47 390.34
1900MHz 4x40W RRH (Sprint)	A	From Leg	0.00 1.00 0.00		0.0000	145.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.71 2.95 3.20 3.72	2.61 2.84 3.09 3.61	60.00 83.12 109.48 172.67
1900MHz 4x40W RRH (Sprint)	B	From Leg	0.00 1.00 0.00		0.0000	145.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.71 2.95 3.20 3.72	2.61 2.84 3.09 3.61	60.00 83.12 109.48 172.67
1900MHz 4x40W RRH (Sprint)	C	From Leg	0.00 1.00 0.00		0.0000	145.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.71 2.95 3.20 3.72	2.61 2.84 3.09 3.61	60.00 83.12 109.48 172.67
800MHz 2x50W RRH (Sprint)	A	From Leg	0.00 -1.00 0.00		0.0000	145.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.40 2.61 2.83 3.30	2.25 2.46 2.68 3.13	64.00 86.12 111.30 171.62
800MHz 2x50W RRH (Sprint)	B	From Leg	0.00 -1.00 0.00		0.0000	145.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.40 2.61 2.83 3.30	2.25 2.46 2.68 3.13	64.00 86.12 111.30 171.62
800MHz 2x50W RRH (Sprint)	C	From Leg	0.00 -1.00 0.00		0.0000	145.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.40 2.61 2.83 3.30	2.25 2.46 2.68 3.13	64.00 86.12 111.30 171.62
Pirod 12' PCS T-Frame (1) 104569 (Sprint)	A	From Leg	0.00 0.00 0.00		0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice	9.80 14.80 19.80 29.80	9.80 14.80 19.80 29.80	260.00 360.00 460.00 660.00
Pirod 12' PCS T-Frame (1) 104569 (Sprint)	B	From Leg	0.00 0.00 0.00		0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice	9.80 14.80 19.80 29.80	9.80 14.80 19.80 29.80	260.00 360.00 460.00 660.00
2' Standoff (Sprint)	C	From Leg	2.00 0.00 0.00		0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.80 3.30 4.80 7.80	1.80 3.30 4.80 7.80	33.00 59.00 85.00 137.00
APXV9TM14-ALU-120 w/ 3.5" mount pipe (Sprint)	A	From Leg	0.00 -2.00 0.00		0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.20 8.85 9.51 10.87	6.75 7.59 8.45 10.26	128.00 201.91 285.73 471.85
APXV9TM14-ALU-120 w/ 3.5" mount pipe (Sprint)	B	From Leg	0.00 0.00 0.00		0.0000	147.00	No Ice 1/2" Ice 1" Ice	8.20 8.85 9.51	6.75 7.59 8.45	128.00 201.91 285.73

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	11 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub>		Weight
			Horz Lateral	Vert			Front	Side	
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	lb
APXV9TM14-ALU-120 w/ 3.5" mount pipe (Sprint)	C	From Leg	2.00	0.0000	147.00	2" Ice	10.87	10.26	471.85
			0.00	0.0000		No Ice	8.20	6.75	128.00
			0.00	0.0000		1/2" Ice	8.85	7.59	201.91
			0.00	0.0000		1" Ice	9.51	8.45	285.73
TD-RRH 8x20 (Sprint)	A	From Leg	1.00	0.0000	147.00	2" Ice	10.87	10.26	471.85
			-0.50	0.0000		No Ice	4.32	1.41	66.13
			1.00	0.0000		1/2" Ice	4.60	1.61	90.06
			1.00	0.0000		1" Ice	4.89	1.83	117.33
TD-RRH 8x20 (Sprint)	B	From Leg	1.00	0.0000	147.00	2" Ice	5.50	2.28	182.69
			-0.50	0.0000		No Ice	4.32	1.41	66.13
			1.00	0.0000		1/2" Ice	4.60	1.61	90.06
			1.00	0.0000		1" Ice	4.89	1.83	117.33
TD-RRH 8x20 (Sprint)	C	From Leg	1.00	0.0000	147.00	2" Ice	5.50	2.28	182.69
			-0.50	0.0000		No Ice	4.32	1.41	66.13
			1.00	0.0000		1/2" Ice	4.60	1.61	90.06
			1.00	0.0000		1" Ice	4.89	1.83	117.33
						2" Ice	5.50	2.28	182.69

### Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight	
				Horz Lateral	Vert							
				ft	ft	°	°	ft	ft	ft <sup>2</sup>	lb	
3'-6" Dish (84)	C	Paraboloid w/o Radome	From Leg	3.00	0.0000	0.0000		84.00	3.50	No Ice	12.57	150.00
				0.00	0.0000					1/2" Ice	13.10	217.25
				0.00	0.0000					1" Ice	13.62	284.49
				0.00	0.0000					2" Ice	14.68	418.99
4' Dish	C	Paraboloid w/o Radome	From Leg	3.00	0.0000	0.0000		78.00	4.00	No Ice	12.57	150.00
				0.00	0.0000					1/2" Ice	13.10	217.25
				0.00	0.0000					1" Ice	13.62	284.49
				0.00	0.0000					2" Ice	14.68	418.99
4' Dish	C	Paraboloid w/o Radome	From Leg	3.00	0.0000	0.0000		72.00	4.00	No Ice	12.57	150.00
				0.00	0.0000					1/2" Ice	13.10	217.25
				0.00	0.0000					1" Ice	13.62	284.49
				0.00	0.0000					2" Ice	14.68	418.99

### Truss-Leg Properties

Section Designation	Area	Area Ice	Self Weight	Ice Weight	Equiv. Diameter	Equiv. Diameter Ice	Leg Area
	in <sup>2</sup>	in <sup>2</sup>	lb	lb	in	in	in <sup>2</sup>
Pirod 216415	1080.4244	2978.7225	625.26	936.87	7.5029	20.6856	5.3014
Pirod 216413	2292.1448	5870.4117	549.31	1861.38	7.9588	20.3834	5.3014
Pirod 195557	2421.2300	5942.4117	678.42	1891.12	8.4070	20.6334	7.2158
Pirod 195557	2421.2300	5942.4117	678.42	1891.12	8.4070	20.6334	7.2158

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	12 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Section Designation	Area	Area Ice	Self Weight	Ice Weight	Equiv. Diameter	Equiv. Diameter Ice	Leg Area
	in <sup>2</sup>	in <sup>2</sup>	lb	lb	in	in	in <sup>2</sup>
Pirod 195557	2421.2300	5942.4117	678.42	1891.12	8.4070	20.6334	7.2158

### Force Totals

Load Case	Vertical Forces	Sum of Forces X	Sum of Forces Z	Sum of Overturning Moments, M <sub>x</sub>	Sum of Overturning Moments, M <sub>z</sub>	Sum of Torques
	lb	lb	lb	lb-ft	lb-ft	lb-ft
Leg Weight	10650.41					
Bracing Weight	6959.05					
Total Member Self-Weight	17609.45			-912.97	8459.82	
Gusset Weight	209.05					
Total Weight	23366.04			-912.97	8459.82	
Wind 0 deg - No Ice		1083.13	-18109.75	-1503764.58	-70714.10	-10221.34
Wind 30 deg - No Ice		9578.34	-15188.65	-1272864.77	-787566.77	-9740.20
Wind 60 deg - No Ice		15659.63	-8963.78	-749619.12	-1306970.05	-8473.47
Wind 90 deg - No Ice		18058.90	-633.80	-44999.93	-1507232.50	-5030.12
Wind 120 deg - No Ice		16358.98	8116.86	681946.21	-1351267.58	1531.15
Wind 150 deg - No Ice		8653.26	14874.94	1251947.44	-724691.49	7839.29
Wind 180 deg - No Ice		-63.63	17247.53	1452760.06	8023.37	12029.68
Wind 210 deg - No Ice		-8784.08	15166.03	1269272.87	742464.66	12739.11
Wind 240 deg - No Ice		-15704.37	8989.61	740735.09	1311664.70	8690.19
Wind 270 deg - No Ice		-17642.18	-42.74	-9655.43	1491611.89	2031.21
Wind 300 deg - No Ice		-15102.53	-8568.66	-728127.46	1285792.13	-3556.21
Wind 330 deg - No Ice		-8671.42	-14864.46	-1252954.45	743029.55	-7839.29
Member Ice	34526.12					
Gusset Ice	140.69					
Total Weight Ice	75020.02			-4323.40	40143.52	
Wind 0 deg - Ice		916.24	-31684.90	-2535514.69	-28220.55	-17607.51
Wind 30 deg - Ice		16138.09	-26772.72	-2145744.90	-1248835.16	-15669.45
Wind 60 deg - Ice		27073.27	-15578.05	-1248854.84	-2128011.35	-11130.81
Wind 90 deg - Ice		31333.95	-543.99	-43619.34	-2469751.27	-3707.08
Wind 120 deg - Ice		27989.33	15048.96	1202067.22	-2198677.65	6251.76
Wind 150 deg - Ice		15338.94	26493.92	2118509.99	-1191944.86	14554.80
Wind 180 deg - Ice		-71.63	30559.98	2443702.58	42553.59	18974.93
Wind 210 deg - Ice		-15480.08	26753.99	2135635.07	1277739.67	18153.92
Wind 240 deg - Ice		-27465.92	15804.75	1255572.10	2234909.72	11355.75
Wind 270 deg - Ice		-30988.72	-16.49	-8794.52	2523080.03	1222.60
Wind 300 deg - Ice		-26592.82	-15217.96	-1226249.20	2173964.42	-7844.12
Wind 330 deg - Ice		-15353.99	-26485.23	-2126478.34	1273407.00	-14554.80
Total Weight	23366.04			-912.97	8459.82	
Wind 0 deg - Service		609.26	-10186.74	-844664.44	-39210.77	-5749.50
Wind 30 deg - Service		5387.81	-8543.62	-714783.29	-442440.40	-5478.86
Wind 60 deg - Service		8808.54	-5042.12	-420457.62	-734604.74	-4766.33
Wind 90 deg - Service		10158.13	-356.51	-24109.32	-847252.37	-2829.44
Wind 120 deg - Service		9201.93	4565.73	384797.88	-759522.10	861.27
Wind 150 deg - Service		4867.46	8367.16	705423.57	-407073.05	4409.60
Wind 180 deg - Service		-35.79	9701.74	818380.67	5079.06	6766.70
Wind 210 deg - Service		-4941.05	8530.89	715169.13	418202.29	7165.75
Wind 240 deg - Service		-8833.71	5056.66	417866.62	738377.31	4888.23
Wind 270 deg - Service		-9923.73	-24.04	-4228.04	839597.60	1142.56
Wind 300 deg - Service		-8495.17	-4819.87	-408368.56	723823.99	-2000.37
Wind 330 deg - Service		-4877.67	-8361.26	-703583.74	418520.04	-4409.60

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Avon Mountain (CT03XC053)	<b>Page</b> 13 of 26
	<b>Project</b> 22984	<b>Date</b> 09:40:47 07/03/14
	<b>Client</b> Sprint	<b>Designed by</b> JDS

## Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 60 deg - No Ice
5	Dead+Wind 90 deg - No Ice
6	Dead+Wind 120 deg - No Ice
7	Dead+Wind 150 deg - No Ice
8	Dead+Wind 180 deg - No Ice
9	Dead+Wind 210 deg - No Ice
10	Dead+Wind 240 deg - No Ice
11	Dead+Wind 270 deg - No Ice
12	Dead+Wind 300 deg - No Ice
13	Dead+Wind 330 deg - No Ice
14	Dead+Ice+Temp
15	Dead+Wind 0 deg+Ice+Temp
16	Dead+Wind 30 deg+Ice+Temp
17	Dead+Wind 60 deg+Ice+Temp
18	Dead+Wind 90 deg+Ice+Temp
19	Dead+Wind 120 deg+Ice+Temp
20	Dead+Wind 150 deg+Ice+Temp
21	Dead+Wind 180 deg+Ice+Temp
22	Dead+Wind 210 deg+Ice+Temp
23	Dead+Wind 240 deg+Ice+Temp
24	Dead+Wind 270 deg+Ice+Temp
25	Dead+Wind 300 deg+Ice+Temp
26	Dead+Wind 330 deg+Ice+Temp
27	Dead+Wind 0 deg - Service
28	Dead+Wind 30 deg - Service
29	Dead+Wind 60 deg - Service
30	Dead+Wind 90 deg - Service
31	Dead+Wind 120 deg - Service
32	Dead+Wind 150 deg - Service
33	Dead+Wind 180 deg - Service
34	Dead+Wind 210 deg - Service
35	Dead+Wind 240 deg - Service
36	Dead+Wind 270 deg - Service
37	Dead+Wind 300 deg - Service
38	Dead+Wind 330 deg - Service

## Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
T1	150 - 130	Leg	Max Tension	25	15309.10	-931.53	-608.42
			Max. Compression	15	-21203.28	-8.39	302.20
			Max. Mx	24	-3574.68	-1093.41	-1.34
			Max. My	15	-21188.10	26.89	-1134.18
			Max. Vy	24	-2035.99	261.95	4.34
			Max. Vx	15	-2157.26	-8.39	302.20
			Max Tension	22	2933.04	0.00	0.00
		Diagonal	Max. Compression	16	-2924.51	0.00	0.00
			Max. Mx	23	433.98	-6.14	-0.37
			Max. My	17	-2503.18	-4.56	-0.99
			Max. Vy	24	-8.86	-6.10	-0.36
			Max. Vx	17	-0.36	0.00	0.00

<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	14 of 26
<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft	
T2	130 - 110	Horizontal	Max Tension	15	336.46	0.00	0.00	
			Max. Compression	21	-281.30	0.00	0.00	
			Max. Mx	15	336.46	16.54	0.00	
			Max. My	23	185.62	0.00	-0.00	
			Max. Vy	15	-13.23	0.00	0.00	
			Max. Vx	23	0.00	0.00	0.00	
		Top Girt	Max Tension	25	225.21	0.00	0.00	
			Max. Compression	23	-279.45	0.00	0.00	
			Max. Mx	14	-26.75	19.09	0.00	
			Max. My	22	-29.68	0.00	0.00	
			Max. Vy	14	15.27	0.00	0.00	
			Max. Vx	22	0.00	0.00	0.00	
		Bottom Girt	Max Tension	25	1421.95	0.00	0.00	
			Max. Compression	19	-1461.19	0.00	0.00	
			Max. Mx	14	32.01	19.09	0.00	
			Max. My	22	146.18	0.00	0.00	
			Max. Vy	14	15.27	0.00	0.00	
			Max. Vx	22	0.00	0.00	0.00	
		Mid Girt	Max Tension	17	216.71	0.00	0.00	
			Max. Compression	19	-180.08	0.00	0.00	
			Max. Mx	14	17.73	19.09	0.00	
			Max. My	22	8.33	0.00	0.00	
			Max. Vy	14	15.27	0.00	0.00	
			Max. Vx	22	0.00	0.00	0.00	
		Leg	Max Tension	25	48846.44	335.60	229.79	
			Max. Compression	15	-58075.87	-38.00	457.90	
			Max. Mx	24	-5917.64	-1663.31	17.03	
			Max. My	15	-58060.64	172.66	-1754.72	
			Max. Vy	24	-3087.35	392.87	4.02	
			Max. Vx	15	-3321.66	-38.00	457.90	
			Diagonal	Max Tension	22	4764.05	0.00	0.00
				Max. Compression	16	-4696.65	0.00	0.00
				Max. Mx	24	2826.21	-6.88	-0.39
				Max. My	22	-4633.96	-3.40	2.17
				Max. Vy	24	-9.14	-6.88	-0.39
				Max. Vx	22	-0.80	-3.40	2.17
			Horizontal	Max Tension	21	877.31	0.00	0.00
				Max. Compression	15	-727.35	0.00	0.00
				Max. Mx	15	102.28	16.54	0.00
		Max. My		23	491.03	0.00	-0.00	
		Max. Vy		15	-13.23	0.00	0.00	
		Max. Vx		23	0.00	0.00	0.00	
		Top Girt		Max Tension	19	1623.37	0.00	0.00
				Max. Compression	25	-1539.09	0.00	0.00
				Max. Mx	14	-4.14	19.09	0.00
Max. My	22			-96.15	0.00	0.00		
Max. Vy	14		15.27	0.00	0.00			
Max. Vx	22		0.00	0.00	0.00			
Bottom Girt	Max Tension	25	2074.27	0.00	0.00			
	Max. Compression	19	-2210.41	0.00	0.00			
	Max. Mx	14	42.04	19.09	0.00			
	Max. My	22	349.66	0.00	0.00			
	Max. Vy	14	15.27	0.00	0.00			
	Max. Vx	22	0.00	0.00	0.00			
Mid Girt	Max Tension	21	508.99	0.00	0.00			
	Max. Compression	15	-334.91	0.00	0.00			
	Max. Mx	14	37.00	19.09	0.00			
	Max. My	22	57.16	0.00	0.00			
	Max. Vy	14	15.27	0.00	0.00			
	Max. Vx	22	0.00	0.00	0.00			
T3	110 - 90	Leg	Max Tension	25	96586.05	2328.51	1324.22	

<p><b>tnxTower</b></p> <p><b>Ramaker &amp; Associates</b>  1120 Dallas St.  Sauk City, WI 53583  Phone: (608) 643-4100  FAX: (608) 643-7999</p>	<b>Job</b> Avon Mountain (CT03XC053)	<b>Page</b> 15 of 26
	<b>Project</b> 22984	<b>Date</b> 09:40:47 07/03/14
	<b>Client</b> Sprint	<b>Designed by</b> JDS

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
			Max. Compression	23	-110147.83	2339.12	-1757.11
			Max. Mx	19	-107084.57	-2543.44	-1455.97
			Max. My	15	-109857.05	-363.11	2912.37
			Max. Vy	19	4521.48	-2543.44	-1455.97
			Max. Vx	15	-5132.45	-363.11	2912.37
		Diagonal	Max Tension	16	5722.00	0.00	0.00
			Max. Compression	22	-5829.32	0.00	0.00
			Max. Mx	15	4893.66	-10.22	-0.00
			Max. My	17	-4890.73	-4.98	-3.72
			Max. Vy	15	11.39	-10.22	-0.00
			Max. Vx	17	-1.36	0.00	0.00
		Horizontal	Max Tension	21	1412.79	0.00	0.00
			Max. Compression	15	-1207.73	0.00	0.00
			Max. Mx	15	-735.85	16.54	0.00
			Max. My	23	785.03	0.00	-0.00
			Max. Vy	15	-13.23	0.00	0.00
			Max. Vx	23	0.00	0.00	0.00
		Top Girt	Max Tension	19	2269.61	0.00	0.00
			Max. Compression	25	-2050.80	0.00	0.00
			Max. Mx	14	7.65	24.98	0.00
			Max. My	22	-275.30	0.00	0.00
			Max. Vy	14	-19.98	0.00	0.00
			Max. Vx	22	-0.00	0.00	0.00
		Bottom Girt	Max Tension	21	2296.17	0.00	0.00
			Max. Compression	15	-2131.83	0.00	0.00
			Max. Mx	14	113.98	24.98	0.00
			Max. My	22	62.30	0.00	0.00
			Max. Vy	14	-19.98	0.00	0.00
			Max. Vx	22	-0.00	0.00	0.00
		Mid Girt	Max Tension	21	1169.99	0.00	0.00
			Max. Compression	15	-937.66	0.00	0.00
			Max. Mx	19	-359.08	24.98	0.00
			Max. My	22	130.97	0.00	0.00
			Max. Vy	19	-19.98	0.00	0.00
			Max. Vx	22	-0.00	0.00	0.00
T4	90 - 80	Leg	Max Tension	25	95713.56	-2678.66	17.29
			Max. Compression	23	-109581.97	4874.28	194.33
			Max. Mx	25	95358.45	-5605.52	192.47
			Max. My	26	-9633.57	-316.80	9496.09
			Max. Vy	17	657.20	-5562.77	162.86
			Max. Vx	26	-1099.85	-316.80	9496.09
		Diagonal	Max Tension	23	6528.01	0.00	0.00
			Max. Compression	26	-7564.84	0.00	0.00
			Max. Mx	25	3999.02	217.35	-28.37
			Max. My	22	-4689.47	-136.38	-78.70
			Max. Vy	25	56.70	217.35	-28.37
			Max. Vx	22	16.19	0.00	0.00
T5	80 - 60	Leg	Max Tension	25	118991.60	-5624.24	164.27
			Max. Compression	23	-143216.53	4886.40	48.39
			Max. Mx	23	-130313.92	5804.44	-7.69
			Max. My	26	-11359.43	-317.06	9496.08
			Max. Vy	17	-448.22	-5562.77	162.84
			Max. Vx	26	902.18	-317.06	9496.08
		Diagonal	Max Tension	15	6667.55	0.00	0.00
			Max. Compression	15	-6939.37	0.00	0.00
			Max. Mx	23	5877.04	246.26	5.48
			Max. My	21	1807.83	195.89	-32.69
			Max. Vy	23	-66.49	246.26	5.48
			Max. Vx	21	7.12	0.00	0.00
T6	60 - 40	Leg	Max Tension	25	140749.32	-5041.44	65.43
			Max. Compression	23	-174993.23	4265.53	46.41

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	16 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
T7	40 - 20	Diagonal	Max. Mx	23	-160158.16	5514.66	33.39
			Max. My	24	-13596.13	-127.33	-5265.80
			Max. Vy	19	240.38	5388.67	-78.48
			Max. Vx	26	246.69	-44.80	5215.60
			Max Tension	22	6239.64	0.00	0.00
			Max. Compression	22	-6518.34	0.00	0.00
			Max. Mx	23	3408.63	175.95	-16.39
			Max. My	22	1088.90	133.80	-22.72
			Max. Vy	23	-58.10	168.53	-12.27
		Leg	Max. Vx	22	5.02	0.00	0.00
			Max Tension	25	159992.05	-3467.24	67.20
			Max. Compression	23	-205081.07	2735.60	23.17
			Max. Mx	25	159022.01	-7456.31	44.20
			Max. My	24	-20457.41	1155.59	-5150.15
			Max. Vy	17	558.69	-7407.31	37.37
			Max. Vx	26	364.30	1209.25	5087.01
			Max Tension	16	6802.00	0.00	0.00
			Max. Compression	16	-6752.86	0.00	0.00
T8	20 - 0	Diagonal	Max. Mx	23	3283.56	174.33	-13.93
			Max. My	21	-5827.71	18.20	-20.15
			Max. Vy	23	-62.56	169.04	-14.04
			Max. Vx	21	4.37	0.00	0.00
			Max Tension	25	175796.89	-1168.93	103.39
			Max. Compression	23	-232924.13	-0.00	1.18
		Leg	Max. Mx	23	-217637.07	7610.81	89.69
			Max. My	24	-25946.50	3157.33	-8723.31
			Max. Vy	19	837.51	7536.52	-216.59
			Max. Vx	26	993.53	3199.19	8596.75
			Max Tension	21	9066.58	0.00	0.00
			Max. Compression	16	-7428.00	0.00	0.00
Diagonal	Max. Mx	25	1794.88	192.42	14.31		
	Max. My	21	-7066.53	67.46	-30.09		
	Max. Vy	25	69.52	192.42	14.31		
	Max. Vx	21	5.51	0.00	0.00		

### Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical lb	Horizontal, X lb	Horizontal, Z lb
Leg C	Max. Vert	23	239215.78	17270.69	-10575.32
	Max. H <sub>x</sub>	23	239215.78	17270.69	-10575.32
	Max. H <sub>z</sub>	17	-181118.16	-18624.00	11248.11
	Min. Vert	17	-181118.16	-18624.00	11248.11
	Min. H <sub>x</sub>	17	-181118.16	-18624.00	11248.11
	Min. H <sub>z</sub>	23	239215.78	17270.69	-10575.32
Leg B	Max. Vert	19	234345.01	-17607.66	-9822.12
	Max. H <sub>x</sub>	25	-183531.59	18780.94	10498.65
	Max. H <sub>z</sub>	25	-183531.59	18780.94	10498.65
	Min. Vert	25	-183531.59	18780.94	10498.65
	Min. H <sub>x</sub>	19	234345.01	-17607.66	-9822.12
	Min. H <sub>z</sub>	19	234345.01	-17607.66	-9822.12
Leg A	Max. Vert	15	236811.71	-821.17	20182.10
	Max. H <sub>x</sub>	21	-179246.44	727.31	-21366.10
	Max. H <sub>z</sub>	15	236811.71	-821.17	20182.10
	Min. Vert	21	-179246.44	727.31	-21366.10
	Min. H <sub>x</sub>	15	236811.71	-821.17	20182.10

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	17 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Location	Condition	Gov. Load Comb.	Vertical lb	Horizontal, X lb	Horizontal, Z lb
	Min. H <sub>z</sub>	21	-179246.44	727.31	-21366.10

## Tower Mast Reaction Summary

Load Combination	Vertical	Shear <sub>x</sub>	Shear <sub>z</sub>	Overtuning Moment, M <sub>x</sub>	Overtuning Moment, M <sub>z</sub>	Torque
	lb	lb	lb	lb-ft	lb-ft	lb-ft
Dead Only	23366.04	0.00	0.00	-655.32	8483.71	0.05
Dead+Wind 0 deg - No Ice	23366.04	1083.13	-18109.75	-1511353.63	-70849.14	-10283.84
Dead+Wind 30 deg - No Ice	23366.04	9578.34	-15188.65	-1279314.46	-791542.70	-9795.75
Dead+Wind 60 deg - No Ice	23366.04	15659.63	-8963.78	-753285.10	-1313759.74	-8512.77
Dead+Wind 90 deg - No Ice	23366.04	18058.90	-633.80	-44882.02	-1515100.09	-5044.42
Dead+Wind 120 deg - No Ice	23366.04	16358.98	8116.86	685925.46	-1358233.93	1551.60
Dead+Wind 150 deg - No Ice	23366.04	8653.26	14874.94	1258880.62	-728520.39	7887.60
Dead+Wind 180 deg - No Ice	23366.04	-63.63	17247.53	1460724.82	8082.62	12090.47
Dead+Wind 210 deg - No Ice	23366.04	-8784.08	15166.03	1276197.97	746408.92	12796.54
Dead+Wind 240 deg - No Ice	23366.04	-15704.37	8989.61	744824.29	1318540.43	8730.11
Dead+Wind 270 deg - No Ice	23366.04	-17642.18	-42.74	-9478.57	1499491.25	2042.84
Dead+Wind 300 deg - No Ice	23366.04	-15102.53	-8568.66	-731749.59	1292633.38	-3578.34
Dead+Wind 330 deg - No Ice	23366.04	-8671.42	-14864.46	-1259343.93	747034.57	-7889.01
Dead+Ice+Temp	75020.02	0.00	0.00	-3749.92	40701.42	0.48
Dead+Wind 0 deg+Ice+Temp	75020.02	916.24	-31684.85	-2567999.55	-28097.76	-17980.33
Dead+Wind 30 deg+Ice+Temp	75020.02	16138.08	-26772.71	-2173238.01	-1264834.14	-15994.74
Dead+Wind 60 deg+Ice+Temp	75020.02	27073.25	-15578.04	-1264573.19	-2155646.00	-11370.33
Dead+Wind 90 deg+Ice+Temp	75020.02	31333.89	-544.03	-43438.99	-2501888.62	-3799.67
Dead+Wind 120 deg+Ice+Temp	75020.02	27989.28	15048.94	1218674.04	-2227134.89	6370.32
Dead+Wind 150 deg+Ice+Temp	75020.02	15338.91	26493.90	2147043.25	-1207431.65	14853.63
Dead+Wind 180 deg+Ice+Temp	75020.02	-71.62	30559.97	2476437.41	43259.32	19334.86
Dead+Wind 210 deg+Ice+Temp	75020.02	-15480.07	26753.98	2164216.61	1294609.62	18480.35
Dead+Wind 240 deg+Ice+Temp	75020.02	-27465.88	15804.73	1272545.73	2264222.87	11602.64
Dead+Wind 270 deg+Ice+Temp	75020.02	-30988.66	-16.53	-8341.14	2556222.73	1312.32
Dead+Wind 300 deg+Ice+Temp	75020.02	-26592.80	-15217.95	-1241732.63	-1241732.63	-7966.71
Dead+Wind 330 deg+Ice+Temp	75020.02	-15353.99	-26485.19	-2153750.24	1290341.48	-14856.84
Dead+Wind 0 deg - Service	23366.04	609.26	-10186.74	-850438.73	-36132.55	-5785.06
Dead+Wind 30 deg - Service	23366.04	5387.81	-8543.62	-719909.72	-441526.42	-5512.94
Dead+Wind 60 deg - Service	23366.04	8808.54	-5042.12	-424009.80	-735275.14	-4788.57
Dead+Wind 90 deg - Service	23366.04	10158.13	-356.51	-25527.62	-848528.93	-2834.76
Dead+Wind 120 deg - Service	23366.04	9201.93	4565.73	385552.06	-760292.09	873.00
Dead+Wind 150 deg - Service	23366.04	4867.46	8367.16	707842.20	-406076.68	4435.29
Dead+Wind 180 deg - Service	23366.04	-35.79	9701.74	821381.46	8265.16	6800.81
Dead+Wind 210 deg - Service	23366.04	-4941.05	8530.89	717589.24	423581.91	7200.51
Dead+Wind 240 deg - Service	23366.04	-8833.71	5056.66	418689.67	745416.87	4910.93
Dead+Wind 270 deg - Service	23366.04	-9923.73	-24.04	-5616.37	847206.55	1147.65
Dead+Wind 300 deg - Service	23366.04	-8495.17	-4819.87	-411905.00	730843.96	-2012.56
Dead+Wind 330 deg - Service	23366.04	-4877.67	-8361.26	-708684.23	423936.28	-4435.94

## Solution Summary

Load Comb.	PX lb	Sum of Applied Forces			Sum of Reactions			% Error
		PY lb	PZ lb	PX lb	PY lb	PZ lb		
1	0.00	-23366.04	0.00	-0.00	23366.04	-0.00	0.000%	
2	1083.13	-23366.04	-18109.75	-1083.13	23366.04	18109.75	0.000%	
3	9578.34	-23366.04	-15188.65	-9578.34	23366.04	15188.65	0.000%	

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	18 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
4	15659.63	-23366.04	-8963.78	-15659.63	23366.04	8963.78	0.000%
5	18058.90	-23366.04	-633.80	-18058.90	23366.04	633.80	0.000%
6	16358.98	-23366.04	8116.86	-16358.98	23366.04	-8116.86	0.000%
7	8653.26	-23366.04	14874.94	-8653.26	23366.04	-14874.94	0.000%
8	-63.63	-23366.04	17247.53	63.63	23366.04	-17247.53	0.000%
9	-8784.08	-23366.04	15166.03	8784.08	23366.04	-15166.03	0.000%
10	-15704.37	-23366.04	8989.61	15704.37	23366.04	-8989.61	0.000%
11	-17642.18	-23366.04	-42.74	17642.18	23366.04	42.74	0.000%
12	-15102.53	-23366.04	-8568.66	15102.53	23366.04	8568.66	0.000%
13	-8671.42	-23366.04	-14864.46	8671.42	23366.04	14864.46	0.000%
14	0.00	-75020.02	0.00	-0.00	75020.02	-0.00	0.000%
15	916.24	-75020.02	-31684.90	-916.24	75020.02	31684.85	0.000%
16	16138.09	-75020.02	-26772.72	-16138.08	75020.02	26772.71	0.000%
17	27073.27	-75020.02	-15578.05	-27073.25	75020.02	15578.04	0.000%
18	31333.95	-75020.02	-543.99	-31333.89	75020.02	544.03	0.000%
19	27989.33	-75020.02	15048.96	-27989.28	75020.02	-15048.94	0.000%
20	15338.94	-75020.02	26493.92	-15338.91	75020.02	-26493.90	0.000%
21	-71.63	-75020.02	30559.98	71.62	75020.02	-30559.97	0.000%
22	-15480.08	-75020.02	26753.99	15480.07	75020.02	-26753.98	0.000%
23	-27465.92	-75020.02	15804.75	27465.88	75020.02	-15804.73	0.000%
24	-30988.72	-75020.02	-16.49	30988.66	75020.02	16.53	0.000%
25	-26592.82	-75020.02	-15217.96	26592.80	75020.02	15217.95	0.000%
26	-15353.99	-75020.02	-26485.23	15353.99	75020.02	26485.19	0.000%
27	609.26	-23366.04	-10186.74	-609.26	23366.04	10186.74	0.000%
28	5387.81	-23366.04	-8543.62	-5387.81	23366.04	8543.62	0.000%
29	8808.54	-23366.04	-5042.12	-8808.54	23366.04	5042.12	0.000%
30	10158.13	-23366.04	-356.51	-10158.13	23366.04	356.51	0.000%
31	9201.93	-23366.04	4565.73	-9201.93	23366.04	-4565.73	0.000%
32	4867.46	-23366.04	8367.16	-4867.46	23366.04	-8367.16	0.000%
33	-35.79	-23366.04	9701.74	35.79	23366.04	-9701.74	0.000%
34	-4941.05	-23366.04	8530.89	4941.05	23366.04	-8530.89	0.000%
35	-8833.71	-23366.04	5056.66	8833.71	23366.04	-5056.66	0.000%
36	-9923.73	-23366.04	-24.04	9923.73	23366.04	24.04	0.000%
37	-8495.17	-23366.04	-4819.87	8495.17	23366.04	4819.87	0.000%
38	-4877.67	-23366.04	-8361.26	4877.67	23366.04	8361.26	0.000%

### Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00000001
3	Yes	4	0.00000001	0.00000001
4	Yes	4	0.00000001	0.00000001
5	Yes	4	0.00000001	0.00000001
6	Yes	4	0.00000001	0.00000001
7	Yes	4	0.00000001	0.00000001
8	Yes	4	0.00000001	0.00000001
9	Yes	4	0.00000001	0.00000001
10	Yes	4	0.00000001	0.00000001
11	Yes	4	0.00000001	0.00000001
12	Yes	4	0.00000001	0.00000001
13	Yes	4	0.00000001	0.00000001
14	Yes	4	0.00000001	0.00000001
15	Yes	4	0.00000001	0.00001065
16	Yes	4	0.00000001	0.00001166

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	19 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

17	Yes	4	0.00000001	0.00001295
18	Yes	4	0.00000001	0.00001199
19	Yes	4	0.00000001	0.00000996
20	Yes	4	0.00000001	0.00001201
21	Yes	4	0.00000001	0.00001287
22	Yes	4	0.00000001	0.00001163
23	Yes	4	0.00000001	0.00001078
24	Yes	4	0.00000001	0.00001175
25	Yes	4	0.00000001	0.00001223
26	Yes	4	0.00000001	0.00001192
27	Yes	4	0.00000001	0.00000001
28	Yes	4	0.00000001	0.00000001
29	Yes	4	0.00000001	0.00000001
30	Yes	4	0.00000001	0.00000001
31	Yes	4	0.00000001	0.00000001
32	Yes	4	0.00000001	0.00000001
33	Yes	4	0.00000001	0.00000001
34	Yes	4	0.00000001	0.00000001
35	Yes	4	0.00000001	0.00000001
36	Yes	4	0.00000001	0.00000001
37	Yes	4	0.00000001	0.00000001
38	Yes	4	0.00000001	0.00000001

### Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	150 - 130	7.804	37	0.4758	0.1217
T2	130 - 110	5.771	37	0.4586	0.1176
T3	110 - 90	3.867	36	0.3944	0.0867
T4	90 - 80	2.352	35	0.2863	0.0485
T5	80 - 60	1.796	35	0.2391	0.0365
T6	60 - 40	0.971	35	0.1547	0.0203
T7	40 - 20	0.430	35	0.0994	0.0109
T8	20 - 0	0.111	31	0.0481	0.0047

### Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
149.00	8' Whip	37	7.702	0.4754	0.1218	252282
147.00	APXVSP18-C w/Mount Pipe	37	7.497	0.4746	0.1220	252282
145.00	1900MHz 4x40W RRH	37	7.293	0.4736	0.1222	252282
136.00	Andrew 12'-6" Universal Sector Frame	37	6.376	0.4670	0.1211	90101
121.00	15' Omni	36	4.885	0.4370	0.1067	20980
117.00	20' Omni	36	4.504	0.4237	0.1001	16153
108.00	10' Dipole	36	3.694	0.3846	0.0826	11045
105.00	8' Whip	36	3.442	0.3690	0.0765	10330
102.00	8' Omni	36	3.200	0.3526	0.0703	9728
98.00	12' Omni	36	2.895	0.3300	0.0623	9027
84.00	3'-6" Dish	35	2.004	0.2574	0.0408	10038
78.00	4' Dish	35	1.698	0.2300	0.0346	12518
74.00	GPS	35	1.513	0.2119	0.0308	13371
72.00	4' Dish	35	1.426	0.2030	0.0291	13783

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	20 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Elevation	Appurtenance	Gov. Load Comb.	Deflection	Tilt	Twist	Radius of Curvature
ft			in	°	°	ft
67.00	GPS	35	1.223	0.1815	0.0251	14937
12.00	GPS	31	0.049	0.0285	0.0027	30152

### Maximum Tower Deflections - Design Wind

Section No.	Elevation	Horz. Deflection	Gov. Load Comb.	Tilt	Twist
	ft	in		°	°
T1	150 - 130	21.634	23	1.2627	0.2704
T2	130 - 110	16.253	23	1.2247	0.2643
T3	110 - 90	11.124	23	1.0751	0.2013
T4	90 - 80	6.923	23	0.8080	0.1155
T5	80 - 60	5.333	23	0.6859	0.0892
T6	60 - 40	2.921	23	0.4564	0.0517
T7	40 - 20	1.306	23	0.2974	0.0286
T8	20 - 0	0.338	23	0.1454	0.0125

### Critical Deflections and Radius of Curvature - Design Wind

Elevation	Appurtenance	Gov. Load Comb.	Deflection	Tilt	Twist	Radius of Curvature
ft			in	°	°	ft
149.00	8' Whip	23	21.364	1.2619	0.2707	128867
147.00	APXVSP18-C w/Mount Pipe	23	20.823	1.2601	0.2714	128867
145.00	1900MHz 4x40W RRH	23	20.283	1.2581	0.2719	128867
136.00	Andrew 12'-6" Universal Sector Frame	23	17.859	1.2435	0.2708	46024
121.00	15' Omni	23	13.878	1.1756	0.2428	9209
117.00	20' Omni	23	12.851	1.1446	0.2293	6990
108.00	10' Dipole	23	10.651	1.0515	0.1925	4659
105.00	8' Whip	23	9.960	1.0135	0.1789	4294
102.00	8' Omni	23	9.295	0.9732	0.1652	3989
98.00	12' Omni	23	8.450	0.9176	0.1472	3644
84.00	3'-6" Dish	23	5.931	0.7336	0.0984	3912
78.00	4' Dish	23	5.050	0.6617	0.0848	4796
74.00	GPS	23	4.513	0.6133	0.0765	5063
72.00	4' Dish	23	4.258	0.5892	0.0725	5179
67.00	GPS	23	3.663	0.5307	0.0631	5492
12.00	GPS	23	0.152	0.0862	0.0073	9993

### Bolt Design Data

Section No.	Elevation	Component Type	Bolt Grade	Bolt Size	Number Of Bolts	Maximum Load per Bolt	Allowable Load	Ratio Load Allowable	Allowable Ratio	Criteria
	ft			in		lb	lb			
T1	150	Leg	A325N	0.6250	5	3061.82	12885.40	0.238	1.333	Bolt DS
T2	130	Leg	A325N	0.7500	5	9769.29	18555.00	0.527	1.333	Bolt DS

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	21 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt lb	Allowable Load lb	Ratio Load Allowable	Allowable Ratio	Criteria
T3	110	Leg	A325N	1.0000	6	16097.70	34517.60	0.466 ✓	1.333	Bolt Tension
T4	90	Leg	A325N	1.0000	6	15952.30	34556.90	0.462 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.2500	1	6528.01	11554.70	0.565 ✓	1.333	Member Block Shear
T5	80	Leg	A325N	1.0000	6	19831.90	34557.40	0.574 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.2500	1	6667.55	11554.70	0.577 ✓	1.333	Member Block Shear
T6	60	Leg	A325N	1.0000	6	23458.20	34557.40	0.679 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.2500	1	6239.64	11554.70	0.540 ✓	1.333	Member Block Shear
T7	40	Leg	A325N	1.0000	6	26665.30	34557.00	0.772 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.2500	1	6802.00	11554.70	0.589 ✓	1.333	Member Block Shear
T8	20	Leg	A687	1.0000	6	29299.50	38877.20	0.754 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.2500	1	9066.58	11554.70	0.785 ✓	1.333	Member Block Shear

### Compression Checks

### Leg Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	150 - 130	1 3/4	20.00	2.33	64.0 K=1.00	22.023	2.4053	-21203.30	52971.60	0.400 ✓
T2	130 - 110	2	20.00	2.33	56.0 K=1.00	23.389	3.1416	-58075.90	73477.20	0.790 ✓
T3	110 - 90	2 1/4	20.00	2.33	49.8 K=1.00	24.385	3.9761	-110148.00	96957.60	1.136 ✓
T4	90 - 80	Pirod 216415	10.02	10.02	37.5 K=1.00	26.178	5.3014	-109582.00	138780.00	0.790 ✓
T5	80 - 60	Pirod 216413	20.03	10.02	37.5 K=1.00	26.178	5.3014	-143217.00	138780.00	1.032 ✓
T6	60 - 40	Pirod 195557	20.03	10.02	32.1 K=1.00	26.884	7.2158	-174993.00	193990.00	0.902 ✓
T7	40 - 20	Pirod 195557	20.03	10.02	32.1 K=1.00	26.884	7.2158	-205081.00	193990.00	1.057 ✓
T8	20 - 0	Pirod 195557	20.03	10.02	32.1 K=1.00	26.884	7.2158	-232924.00	193990.00	1.201 ✓

### Truss-Leg Diagonal Data

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	22 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Section No.	Elevation ft	Diagonal Size	$L_d$ ft	$Kl/r$	$F_a$ ksi	$A$ $in^2$	Actual $V$ lb	Allow. $V_a$ lb	Stress Ratio
T4	90 - 80	0.5	1.46	119.3	10.377	0.1963	1103.12	2292.15	0.481 ✓
T5	80 - 60	0.5	1.46	119.3	10.377	0.1963	910.97	2292.15	0.397 ✓
T6	60 - 40	0.5	1.45	118.3	10.520	0.1963	273.84	2323.87	0.118 ✓
T7	40 - 20	0.5	1.45	118.3	10.520	0.1963	579.71	2323.87	0.249 ✓
T8	20 - 0	0.5	1.45	118.3	10.520	0.1963	1058.24	2323.87	0.455 ✓

### Diagonal Design Data (Compression)

Section No.	Elevation ft	Size	$L$ ft	$L_u$ ft	$Kl/r$	$F_a$ ksi	$A$ $in^2$	Actual $P$ lb	Allow. $P_a$ lb	Ratio $\frac{P}{P_a}$
T1	150 - 130	7/8	5.52	2.68	110.2 K=0.75	12.298	0.6013	-2924.51	7394.87	0.395 ✓
T2	130 - 110	7/8	5.52	2.67	109.7 K=0.75	12.404	0.6013	-4696.65	7458.76	0.630 ✓
T3	110 - 90	1	5.52	2.66	95.6 K=0.75	15.710	0.7854	-5829.32	12338.40	0.472 ✓
T4	90 - 80	L3x3x5/16	11.42	4.99	106.3 K=1.04	12.166	1.7800	-7564.84	21655.10	0.349 ✓
T5	80 - 60	L3x3x5/16	12.50	5.64	116.1 K=1.01	10.829	1.7800	-6939.37	19274.90	0.360 ✓
T6	60 - 40	L3x3x5/16	13.80	6.34	129.1 K=1.00	8.958	1.7800	-6494.39	15944.60	0.407 ✓
T7	40 - 20	L3x3x5/16	14.50	6.74	137.2 K=1.00	7.928	1.7800	-6752.86	14112.20	0.479 ✓
T8	20 - 0	L3x3x5/16	16.01	7.51	152.9 K=1.00	6.387	1.7800	-7428.00	11368.50	0.653 ✓

### Horizontal Design Data (Compression)

Section No.	Elevation ft	Size	$L$ ft	$L_u$ ft	$Kl/r$	$F_a$ ksi	$A$ $in^2$	Actual $P$ lb	Allow. $P_a$ lb	Ratio $\frac{P}{P_a}$
T1	150 - 130	7/8	5.00	4.85	186.4 K=0.70	4.298	0.6013	-281.30	2584.43	0.109 ✓
T2	130 - 110	7/8	5.00	4.83	185.6 K=0.70	4.335	0.6013	-727.35	2606.76	0.279 ✓
T3	110 - 90	7/8	5.00	4.81	184.8 K=0.70	4.373	0.6013	-1207.73	2629.38	0.459 ✓

### Top Girt Design Data (Compression)

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	23 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	150 - 130	1	5.00	4.85	163.1 K=0.70	5.614	0.7854	-279.45	4408.93	0.063
T2	130 - 110	1	5.00	4.83	162.4 K=0.70	5.662	0.7854	-1539.09	4447.02	0.346
T3	110 - 90	1 1/4	5.00	4.81	129.4 K=0.70	8.924	1.2272	-2050.80	10951.20	0.187

**Bottom Girt Design Data (Compression)**

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	150 - 130	1	5.00	4.85	163.1 K=0.70	5.614	0.7854	-1461.19	4408.93	0.331
T2	130 - 110	1	5.00	4.83	162.4 K=0.70	5.662	0.7854	-2210.41	4447.02	0.497
T3	110 - 90	1 1/4	5.00	4.81	129.4 K=0.70	8.924	1.2272	-2131.83	10951.20	0.195

**Mid Girt Design Data (Compression)**

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	150 - 130	1	5.00	4.85	163.1 K=0.70	5.614	0.7854	-180.08	4408.93	0.041
T2	130 - 110	1	5.00	4.83	162.4 K=0.70	5.662	0.7854	-334.91	4447.02	0.075
T3	110 - 90	1 1/4	5.00	4.81	129.4 K=0.70	8.924	1.2272	-937.66	10951.20	0.086

**Tension Checks**

**Leg Design Data (Tension)**

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	150 - 130	1 3/4	20.00	2.33	64.0	32.500	1.2339	15309.10	40100.60	0.382
T2	130 - 110	2	20.00	2.33	56.0	32.500	1.5625	48846.40	50780.20	0.962
T3	110 - 90	2 1/4	20.00	2.33	49.8	30.000	3.9761	96586.10	119282.00	0.810

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Avon Mountain (CT03XC053)	<b>Page</b>	24 of 26
	<b>Project</b>	22984	<b>Date</b>	09:40:47 07/03/14
	<b>Client</b>	Sprint	<b>Designed by</b>	JDS

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio $\frac{P}{P_a}$
T4	90 - 80	Pirod 216415	10.02	10.02	37.5	30.000	5.3014	95713.60	159043.00	0.602
T5	80 - 60	Pirod 216413	20.03	10.02	37.5	30.000	5.3014	118992.00	159043.00	0.748
T6	60 - 40	Pirod 195557	20.03	10.02	32.1	30.000	7.2158	140749.00	216475.00	0.650
T7	40 - 20	Pirod 195557	20.03	10.02	32.1	30.000	7.2158	159992.00	216475.00	0.739
T8	20 - 0	Pirod 195557	20.03	10.02	32.1	30.000	7.2158	175797.00	216475.00	0.812

### Truss-Leg Diagonal Data

Section No.	Elevation ft	Diagonal Size	L <sub>d</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual V lb	Allow. V <sub>a</sub> lb	Stress Ratio
T4	90 - 80	0.5	1.46	119.3	10.377	0.1963	1103.12	2292.15	0.481
T5	80 - 60	0.5	1.46	119.3	10.377	0.1963	910.97	2292.15	0.397
T6	60 - 40	0.5	1.45	118.3	10.520	0.1963	273.84	2323.87	0.118
T7	40 - 20	0.5	1.45	118.3	10.520	0.1963	579.71	2323.87	0.249
T8	20 - 0	0.5	1.45	118.3	10.520	0.1963	1058.24	2323.87	0.455

### Diagonal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio $\frac{P}{P_a}$
T1	150 - 130	7/8	5.52	2.68	146.9	30.000	0.6013	2933.04	18039.60	0.163
T2	130 - 110	7/8	5.52	2.67	146.3	30.000	0.6013	4764.05	18039.60	0.264
T3	110 - 90	1	5.52	2.66	127.5	30.000	0.7854	5722.00	23561.90	0.243
T4	90 - 80	L3x3x5/16	11.42	4.99	67.6	29.000	1.0127	6528.01	29369.30	0.222
T5	80 - 60	L3x3x5/16	11.93	5.39	72.8	29.000	1.0127	6667.55	29369.30	0.227
T6	60 - 40	L3x3x5/16	13.13	6.03	81.0	29.000	1.0127	6239.64	29369.30	0.212
T7	40 - 20	L3x3x5/16	15.24	7.09	94.9	29.000	1.0127	6802.00	29369.30	0.232
T8	20 - 0	L3x3x5/16	16.80	7.89	105.3	29.000	1.0127	9066.58	29369.30	0.309

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Avon Mountain (CT03XC053)	<b>Page</b> 25 of 26
	<b>Project</b> 22984	<b>Date</b> 09:40:47 07/03/14
	<b>Client</b> Sprint	<b>Designed by</b> JDS

### Horizontal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	150 - 130	7/8	5.00	4.85	266.3	30.000	0.6013	336.46	18039.60	0.019
T2	130 - 110	7/8	5.00	4.83	265.1	30.000	0.6013	877.31	18039.60	0.049
T3	110 - 90	7/8	5.00	4.81	264.0	30.000	0.6013	1412.79	18039.60	0.078

### Top Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	150 - 130	1	5.00	4.85	233.0	30.000	0.7854	225.21	23561.90	0.010
T2	130 - 110	1	5.00	4.83	232.0	30.000	0.7854	1623.37	23561.90	0.069
T3	110 - 90	1 1/4	5.00	4.81	184.8	30.000	1.2272	2269.61	36815.50	0.062

### Bottom Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	150 - 130	1	5.00	4.85	233.0	30.000	0.7854	1421.95	23561.90	0.060
T2	130 - 110	1	5.00	4.83	232.0	30.000	0.7854	2074.27	23561.90	0.088
T3	110 - 90	1 1/4	5.00	4.81	184.8	30.000	1.2272	2296.17	36815.50	0.062

### Mid Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	150 - 130	1	5.00	4.85	233.0	30.000	0.7854	216.71	23561.90	0.009
T2	130 - 110	1	5.00	4.83	232.0	30.000	0.7854	508.99	23561.90	0.022

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Avon Mountain (CT03XC053)	<b>Page</b> 26 of 26
	<b>Project</b> 22984	<b>Date</b> 09:40:47 07/03/14
	<b>Client</b> Sprint	<b>Designed by</b> JDS

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P/P <sub>a</sub>
T3	110 - 90	1 1/4	5.00	4.81	184.8	30.000	1.2272	1169.99	36815.50	0.032

### Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	SF*P <sub>allow</sub> lb	% Capacity	Pass Fail	
T1	150 - 130	Leg	1 3/4	3	-21203.30	70611.14	30.0	Pass	
		Diagonal	7/8	17	-2924.51	9857.36	29.7	Pass	
		Horizontal	7/8	60	-281.30	3445.04	8.2	Pass	
		Top Girt	1	5	-279.45	5877.10	4.8	Pass	
		Bottom Girt	1	9	-1461.19	5877.10	24.9	Pass	
T2	130 - 110	Mid Girt	1	12	-180.08	5877.10	3.1	Pass	
		Leg	2	68	48846.40	67690.00	72.2	Pass	
		Diagonal	7/8	83	-4696.65	9942.53	47.2	Pass	
		Horizontal	7/8	126	-727.35	3474.81	20.9	Pass	
		Top Girt	1	72	-1539.09	5927.88	26.0	Pass	
T3	110 - 90	Bottom Girt	1	75	-2210.41	5927.88	37.3	Pass	
		Mid Girt	1	76	-334.91	5927.88	5.6	Pass	
		Leg	2 1/4	133	-110148.00	129244.48	85.2	Pass	
		Diagonal	1	150	-5829.32	16447.09	35.4	Pass	
		Horizontal	7/8	192	-1207.73	3504.96	34.5	Pass	
T4	90 - 80	Top Girt	1 1/4	138	-2050.80	14597.95	14.0	Pass	
		Bottom Girt	1 1/4	139	-2131.83	14597.95	14.6	Pass	
		Mid Girt	1 1/4	142	-937.66	14597.95	6.4	Pass	
T5	80 - 60	Leg	Pirod 216415	199	-109582.00	184993.73	59.2	Pass	
		Diagonal	L3x3x5/16	206	-7564.84	28866.25	26.2	Pass	
T6	60 - 40	Leg	Pirod 216413	208	-143217.00	184993.73	77.4	Pass	
		Diagonal	L3x3x5/16	215	-6939.37	25693.44	27.0	Pass	
T7	40 - 20	Leg	Pirod 195557	223	-174993.00	258588.66	67.7	Pass	
		Diagonal	L3x3x5/16	231	-6494.39	21254.15	30.6	Pass	
T8	20 - 0	Leg	Pirod 195557	238	-205081.00	258588.66	79.3	Pass	
		Diagonal	L3x3x5/16	251	-6752.86	18811.56	35.9	Pass	
		Leg	Pirod 195557	253	-232924.00	258588.66	90.1	Pass	
		Diagonal	L3x3x5/16	266	-7428.00	15154.21	49.0	Pass	
							Summary		
							Leg (T8)	90.1	Pass
							Diagonal (T8)	49.0	Pass
							Horizontal (T3)	34.5	Pass
							Top Girt (T2)	26.0	Pass
							Bottom Girt (T2)	37.3	Pass
							Mid Girt (T3)	6.4	Pass
							Bolt Checks	58.9	Pass
							<b>RATING =</b>	<b>90.1</b>	<b>Pass</b>

**APPENDIX C**  
**MOUNT CALCULATIONS**





1120 Dallas Street  
Sauk City, WI 53583  
Office: (608) 643-4100

Job: 22984  
Project: Avon Mountain (CT03XC053-A)  
By: JMO  
Date: 7/14/2014

**Topographic Effects TIA-222**

**2.6.6.2 Topographic Categories**

The topographic category for a structure shall be assessed as being one of the following:

1. Category 1: No abrupt changes in general topography, e.g. flat or rolling terrain, no wind speed-up consideration shall be required.
2. Category 2: Structures located at or near the crest of an escarpment. Wind speed-up shall be considered to occur in all directions. Structures located vertically on the lower half of an escarpment or horizontally beyond 8 times the height of the escarpment from its crest, shall be permitted to be considered as Topographic Category 1.
3. Category 3: Structures located in the upper half of a hill. Wind speed-up shall be considered to occur in all directions. Structures located vertically on the lower half of a hill shall be permitted to be considered as Topographic Category 1.
4. Category 4: Structures located in the upper half of a ridge. Wind speed-up shall be considered to occur in all directions. Structures located vertically on the lower half of a ridge shall be permitted to be considered as Topographic Category 1.

Topographic Category 4

H = 575 ft height of hill

Exposure Category B

z = 147 ft height of antennas above ground level

Ke = 0.90

Kt = 0.72

f = 1.50

Kh = 1.47

**Kzt = 2.08**



1120 Dallas Street  
 Sauk City, WI 53583  
 Office: (608) 643-4100

Job: 22984  
 Project: Avon Mountain (CT03XC053-A)  
 By: JMO  
 Date: 7/14/2014

**Wind Load on Antennas TIA-222**

**2.6.9.6 Velocity Pressure**

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$

Occupancy:	II	Classification of Structures (Table 2-1)
Exposure:	B	Exposure Category
V:	98 mph	Basic Wind Speed (Annex B)
z:	147 ft	Height above ground level to the center of the antenna
I:	1.00	Importance Factor (Table 2-3)
K <sub>z</sub> :	1.10	Velocity Pressure Coefficient (2.6.5.2)
K <sub>zt</sub> :	2.08	Topographic Factor (2.6.6.4)
K <sub>d</sub> :	0.95	Wind Direction Probability Factor (Table 2-2)

**q<sub>z</sub> = 53.6 psf**

G<sub>h</sub>: 1.00 Appurtenances and their Connections

**Mount & Antenna Wind Loads**

Appurtenance	Height	Depth	h/D	Shape	C <sub>a</sub>	A <sub>f</sub>	F = q <sub>z</sub> G <sub>h</sub> C <sub>a</sub> A <sub>a</sub>	
Pipe2STD x 10.5 ft	126.0 in	2.4 in	52.9	Round	1.200	2.08 sf	<b>133.9 lb</b>	12.8 plf
Pipe1-1/2STD x 7 ft	84.0 in	1.9 in	44.2	Round	1.200	1.11 sf	<b>71.3 lb</b>	10.2 plf
Pipe2STD x 3 ft	36.0 in	2.4 in	15.1	Round	0.981	0.60 sf	<b>31.3 lb</b>	10.4 plf
Pipe1/2STD x 2.5 ft	30.0 in	0.8 in	35.7	Round	1.200	0.18 sf	<b>11.3 lb</b>	4.5 plf
APXV9TM14-ALU-120	56.3 in	6.3 in	8.9	Flat	1.465	2.46 sf	<b>193.3 lb</b>	
TD-RRH8x20	26.1 in	6.7 in	3.9	Flat	1.262	1.21 sf	<b>82.1 lb</b>	
APXVSPP18-C-A20	72.0 in	7.0 in	10.3	Flat	1.509	3.50 sf	<b>283.5 lb</b>	



1120 Dallas Street  
 Sauk City, WI 53583  
 Office: (608) 643-4100

Job: 22984  
 Project: Avon Mountain (CT03XC053-A)  
 By: JMO  
 Date: 7/14/2014

**Wind Load on Antennas TIA-222**

**2.6.9.6 Velocity Pressure**

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$


Occupancy:	II	Classification of Structures (Table 2-1)
Exposure:	B	Exposure Category
V:	98 mph	Basic Wind Speed (Annex B)
z:	147 ft	Height above ground level to the center of the antenna
I:	1.00	Importance Factor (Table 2-3)
K <sub>z</sub> :	1.10	Velocity Pressure Coefficient (2.6.5.2)
K <sub>zt</sub> :	2.08	Topographic Factor (2.6.6.4)
K <sub>d</sub> :	0.95	Wind Direction Probability Factor (Table 2-2)

**q<sub>z</sub> = 53.6 psf**

G<sub>h</sub>: 1.00 Appurtenances and their Connections



**Mount & Antenna Wind Loads**

Appurtenance	Height	Width	h/D	Shape	C <sub>a</sub>	A <sub>f</sub>	F = q <sub>z</sub> G <sub>h</sub> C <sub>a</sub> A <sub>a</sub>	
Pipe2STD x 10.5 ft	126.0 in	2.4 in	52.9	Round	1.200	2.08 sf	<b>133.9 lb</b>	12.8 plf
Pipe1-1/2STD x 7 ft	84.0 in	1.9 in	44.2	Round	1.200	1.11 sf	<b>71.3 lb</b>	10.2 plf
Pipe2STD x 3 ft	36.0 in	2.4 in	15.1	Round	0.981	0.60 sf	<b>31.3 lb</b>	10.4 plf
Pipe1/2STD x 2.5 ft	30.0 in	0.8 in	35.7	Round	1.200	0.18 sf	<b>11.3 lb</b>	4.5 plf
APXV9TM14-ALU-120	56.3 in	12.6 in	4.5	Flat	1.287	4.93 sf	<b>339.9 lb</b>	
TD-RRH8x20	26.1 in	18.6 in	1.4	Flat	1.200	3.37 sf	<b>216.8 lb</b>	
APXVSPP18-C-A20	72.0 in	11.9 in	6.1	Flat	1.358	5.95 sf	<b>432.8 lb</b>	



Envelope Only Solution

Ramaker & Associates	Avon Mountain (CT03XC053-A)	SK - 1
JMO		July 14, 2014 at 11:28 AM
22984		22984 Mount.r3d



Envelope Only Solution

Ramaker & Associates

JMO

22984

Avon Mountain (CT03XC053-A)

SK - 2

July 14, 2014 at 11:29 AM

22984 Mount.r3d



### Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (\1E...	Density[k/ft...	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
2	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	65	1.1
3	A992	29000	11154	.3	.65	.49	50	1.1	65	1.1
4	A500 Gr.42	29000	11154	.3	.65	.49	42	1.4	58	1.3
5	A500 Gr.46	29000	11154	.3	.65	.49	46	1.4	58	1.3
6	A53 Gr. B	29000	11154	.3	.65	.49	35	1.5	60	1.2

### Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design R...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	pipe 2.0	PIPE 2.0	Beam	Pipe	A53 Gr. B	Typical	1.02	.627	.627	1.25
2	pipe 1.5	PIPE 1.5	Beam	Pipe	A53 Gr. B	Typical	.749	.293	.293	.586
3	solid rod	1/2 Rod	Beam	BAR	A36 Gr.36	Typical	.196	.003	.003	.006
4	plate	PL3x3/8	Beam	RECT	A36 Gr.36	Typical	1.125	.013	.844	.049

### Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	M2	N5	N14			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
2	M5	N15	N24		180	pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
3	M13	N34	N29			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
4	M15	N31	N6			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
5	M16	N32	N9			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
6	M6	N22	N22A			RIGID	None	None	RIGID	Typical
7	M7	N21	N23			RIGID	None	None	RIGID	Typical
8	M8	N28	N29A			pipe 1.5	Beam	Pipe	A53 Gr. B	Typical
9	M9	N33	N34A			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
10	M10	N35	N48			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
11	M11	N36	N49			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
12	M12	N39	N40			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
13	M13A	N42	N33			RIGID	None	None	RIGID	Typical
14	M14	N43	N41			RIGID	None	None	RIGID	Typical
15	M15A	N44	N45			solid rod	Beam	BAR	A36 Gr.36	Typical
16	M16A	N46	N47			pipe 1.5	Beam	Pipe	A53 Gr. B	Typical
17	M17	N48	N37		90	plate	Beam	RECT	A36 Gr.36	Typical
18	M18	N49	N38		90	plate	Beam	RECT	A36 Gr.36	Typical
19	M19	N48A	N49A			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical

### Joint Coordinates and Temperatures

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
1	N5	3.455	4.67	-.08	0	
2	N6	3.705	3.295	-.08	0	
3	N9	13.705	3.295	-.08	0	
4	N14	13.955	4.67	-.08	0	
5	N15	3.455	7.92	-.08	0	
6	N16	3.705	7.92	-.08	0	
7	N19	13.705	7.92	-.08	0	
8	N22	8.705	7.92	-.08	0	
9	N24	13.955	7.92	-.08	0	
10	APXV9TM14-ALU-I20-BOT_B	8.205	4.17	-.08	0	
11	APXVSP18-C-A20-BOT_B	13.705	4.17	-.08	0	
12	APXV9TM14-ALU-I20-TOP_B	8.205	8.67	-.08	0	
13	APXVSP18-C-A20-TOP_B	13.705	8.67	-.08	0	



**Joint Coordinates and Temperatures (Continued)**

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
14	N31	3.705	9.295	-0.08	0	
15	N32	13.705	9.295	-0.08	0	
16	N34	8.205	9.295	-0.08	0	
17	N29	8.205	3.295	-0.08	0	
18	N19A	3.705	4.67	-0.08	0	
19	N20	13.705	4.67	-0.08	0	
20	N21	8.705	4.67	-0.08	0	
21	N22A	8.705	7.92	-0.33	0	
22	N23	8.705	4.67	-0.33	0	
23	N24A	8.205	7.92	-0.08	0	
24	N25	8.205	4.67	-0.08	0	
25	APXVSP18-C-A20-BOT_G	3.705	4.17	-0.08	0	
26	APXVSP18-C-A20-TOP_G	3.705	8.67	-0.08	0	
27	N28	3.705	6.17	-0.08	0	
28	N29A	7.146459	6.17	-4.994912	0	
29	APXV9TM14-ALU-I20-BOT_G	17.851447	4.92	0.273553	0	
30	APXV9TM14-ALU-I20-TOP_G	17.851447	9.42	0.273553	0	
31	N33	18.205	9.17	-0.08	0	
32	N34A	18.205	4.17	-0.08	0	
33	N35	18.205	7.92	-0.08	0	
34	N36	18.205	5.42	-0.08	0	
35	N37	18.205	7.92	-3.08	0	
36	N38	18.205	5.42	-3.08	0	
37	N39	17.851447	10.17	0.273553	0	
38	N40	17.851447	4.17	0.273553	0	
39	N41	18.205	5.67	-0.08	0	
40	N42	17.851447	9.17	0.273553	0	
41	N43	17.851447	5.67	0.273553	0	
42	N44	18.205	7.92	-1.83	0	
43	N45	18.205	5.42	-1.83	0	
44	N46	18.205	5.42	-1.58	0	
45	N47	20.599141	5.42	-8.157848	0	
46	N48	18.205	7.92	-2.75	0	
47	N49	18.205	5.42	-2.75	0	
48	N48A	13.705	6.17	-0.08	0	
49	N49A	10.705	6.17	-5.276153	0	

**Joint Boundary Conditions**

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]	Footing
1	APXV9TM14-ALU-...							
2	APXV9TM14-ALU-...							
3	N31							
4	N16							
5	N6							
6	N34							
7	N22							
8	N24							
9	N14							
10	N15							
11	N5							
12	N19							
13	N9							
14	N32							
15	APXVSP18-C-A2...							
16	APXVSP18-C-A2...							

**Joint Boundary Conditions (Continued)**

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]	Footing
17	N29							
18	N19A							
19	N20							
20	N21							
21	N22A	Reaction	Reaction	Reaction				
22	N23	Reaction	Reaction	Reaction				
23	N24A							
24	N25							
25	APXVSPP18-C-A2...							
26	APXVSPP18-C-A2...							
27	N28							
28	N29A	Reaction	Reaction	Reaction				
29	APXV9TM14-ALU-...							
30	APXV9TM14-ALU-...							
31	N33							
32	N34A							
33	N35							
34	N36							
35	N37	Reaction	Reaction	Reaction				
36	N38	Reaction	Reaction	Reaction				
37	N39							
38	N40							
39	N41							
40	N42							
41	N43							
42	N44							
43	N45							
44	N46							
45	N47	Reaction	Reaction	Reaction				
46	N48A							
47	N49A	Reaction	Reaction	Reaction				

**Joint Loads and Enforced Displacements (BLC 1 : DL)**

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*...]
1	APXV9TM14-ALU-I20-TOP B	L	Y	-27.5
2	APXV9TM14-ALU-I20-BOT B	L	Y	-27.5
3	APXVSPP18-C-A20-TOP B	L	Y	-28.5
4	APXVSPP18-C-A20-BOT B	L	Y	-28.5
5	APXVSPP18-C-A20-BOT G	L	Y	-28.5
6	APXVSPP18-C-A20-TOP G	L	Y	-28.5
7	APXV9TM14-ALU-I20-BOT G	L	Y	-27.5
8	APXV9TM14-ALU-I20-TOP G	L	Y	-27.5

**Joint Loads and Enforced Displacements (BLC 2 : WLz)**

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*...]
1	APXV9TM14-ALU-I20-TOP B	L	Z	-170
2	APXV9TM14-ALU-I20-BOT B	L	Z	-170
3	APXVSPP18-C-A20-TOP B	L	Z	-216.4
4	APXVSPP18-C-A20-BOT B	L	Z	-216.4
5	APXVSPP18-C-A20-BOT G	L	Z	-216.4
6	APXVSPP18-C-A20-TOP G	L	Z	-216.4
7	APXV9TM14-ALU-I20-BOT G	L	Z	-96.7
8	APXV9TM14-ALU-I20-TOP G	L	Z	-96.7



**Joint Loads and Enforced Displacements (BLC 3 : WLx)**

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*...
1	APXV9TM14-ALU-I20-TOP B	L	X	-96.7
2	APXV9TM14-ALU-I20-BOT B	L	X	-96.7
3	APXVSP18-C-A20-TOP B	L	X	-141.7
4	APXVSP18-C-A20-BOT B	L	X	-141.7
5	APXVSP18-C-A20-BOT G	L	X	-141.7
6	APXVSP18-C-A20-TOP G	L	X	-141.7
7	APXV9TM14-ALU-I20-BOT G	L	X	-170
8	APXV9TM14-ALU-I20-TOP G	L	X	-170

**Member Distributed Loads (BLC 2 : WLz)**

	Member Label	Direction	Start Magnitude[lb/ft,F]	End Magnitude[lb/ft,F]	Start Location[ft, %]	End Location[ft, %]
1	M2	Z	-12.8	-12.8	0	0
2	M5	Z	-12.8	-12.8	0	0
3	M8	PZ	-10.2	-10.2	0	0
4	M16A	PZ	-10.2	-10.2	0	0
5	M9	Z	-12.8	-12.8	0	0
6	M12	Z	-12.8	-12.8	0	0
7	M19	PZ	-12.8	-12.8	0	0

**Member Distributed Loads (BLC 3 : WLx)**

	Member Label	Direction	Start Magnitude[lb/ft,F]	End Magnitude[lb/ft,F]	Start Location[ft, %]	End Location[ft, %]
1	M13	X	-12.8	-12.8	0	0
2	M15	X	-12.8	-12.8	0	0
3	M16	X	-12.8	-12.8	0	0
4	M8	PX	-10.2	-10.2	0	0
5	M16A	PX	-10.2	-10.2	0	0
6	M10	X	-10.4	-10.4	0	0
7	M11	X	-10.4	-10.4	0	0
8	M15A	X	-4.5	-4.5	0	0
9	M19	PX	-12.8	-12.8	0	0

**Member Area Loads**

Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[psf]
No Data to Print ...						

**Basic Load Cases**

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area(Me...	Surface(P...
1	DL	DL		-1		8			
2	WLz	WLZ				8		7	
3	WLx	WLX				8		9	
4	LL1	LL					2		
5	LL2	None					1		

**Load Combinations**

	Description	Sol..	PDelta	SR..	BLC Fact..						
1	1.4DL	Yes	Y		DL 1.4						
2	1.2DL+1.6WLz	Yes	Y		DL 1.2	WLZ 1.6					
3	1.2DL+1.6WLz	Yes	Y		DL 1.2	WLZ -1.6					
4	1.2DL+1.6WLx	Yes	Y		DL 1.2	W... 1.6					
5	1.2DL-1.6WLx	Yes	Y		DL 1.2	W... -1.6					



**Load Combinations (Continued)**

	Description	Sol.	PDelta	SR	BLC Fact.								
6	1.2DL+1.6(0.75WLz+0.75WLx)	Yes	Y		DL 1.2	WLZ 1.2	W...	1.2					
7	1.2DL+1.6(0.75WLz-0.75WLx)	Yes	Y		DL 1.2	WLZ 1.2	W...	-1.2					
8	1.2DL-1.6(0.75WLz-0.75WLx)	Yes	Y		DL 1.2	WLZ -1.2	W...	1.2					
9	1.2DL-1.6(0.75WLz+0.75WLx)	Yes	Y		DL 1.2	WLZ -1.2	W...	-1.2					
10	1.2DL+1.5LLend	Yes	Y		DL 1.2	LL 1.5							
11	1.2DL+1.5LLmid	Yes	Y		DL 1.2	5 1.5							
12	1.2DL+1.5LL+10%1.6WLz	Yes	Y		DL 1.2	LL 1.5	WLZ	.16					
13	1.2DL+1.5LL-10%1.6WLz	Yes	Y		DL 1.2	LL 1.5	WLZ	-.16					
14	1.2DL+1.5LL+10%1.6WLx	Yes	Y		DL 1.2	LL 1.5	W...	.16					
15	1.2DL+1.5LL-10%1.6WLx	Yes	Y		DL 1.2	LL 1.5	W...	-.16					
16	1.2DL+1.5LL+10%1.6(0.75WLz+...	Yes	Y		DL 1.2	LL 1.5	WLZ	.12	W...	.12			
17	1.2DL+1.5LL+10%1.6(0.75WLz-...	Yes	Y		DL 1.2	LL 1.5	WLZ	.12	W...	-.12			
18	1.2DL+1.5LL-10%1.6(0.75WLz-0...	Yes	Y		DL 1.2	LL 1.5	WLZ	-.12	W...	.12			
19	1.2DL+1.5LL-10%1.6(0.75WLz+...	Yes	Y		DL 1.2	LL 1.5	WLZ	-.12	W...	-.12			
20	1.2DL+1.5LL+10%1.6WLz	Yes	Y		DL 1.2	5 1.5	WLZ	.16					
21	1.2DL+1.5LL-10%1.6WLz	Yes	Y		DL 1.2	5 1.5	WLZ	-.16					
22	1.2DL+1.5LL+10%1.6WLx	Yes	Y		DL 1.2	5 1.5	W...	.16					
23	1.2DL+1.5LL-10%1.6WLx	Yes	Y		DL 1.2	5 1.5	W...	-.16					
24	1.2DL+1.5LL+10%1.6(0.75WLz+...	Yes	Y		DL 1.2	5 1.5	WLZ	.12	W...	.12			
25	1.2DL+1.5LL+10%1.6(0.75WLz-...	Yes	Y		DL 1.2	5 1.5	WLZ	.12	W...	-.12			
26	1.2DL+1.5LL-10%1.6(0.75WLz-0...	Yes	Y		DL 1.2	5 1.5	WLZ	-.12	W...	.12			
27	1.2DL+1.5LL-10%1.6(0.75WLz+...	Yes	Y		DL 1.2	5 1.5	WLZ	-.12	W...	-.12			
28	DL		Y		DL	1							
29	WLz		Y		WLZ	1							
30	WLx		Y		W...	1							

**Envelope Joint Reactions**

Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC	
1	N22A	max	913.667	4	738.791	2	541.46	2	0	1	0	1	0	1
2		min	-895.955	5	-350.815	3	-599.769	3	0	1	0	1	0	1
3	N23	max	819.894	4	735.173	3	339.154	2	0	1	0	1	0	1
4		min	-837.713	5	-349.36	2	-277.56	3	0	1	0	1	0	1
5	N29A	max	559.167	3	10.704	1	825.714	2	0	1	0	1	0	1
6		min	-559.259	2	8.079	2	-827.703	3	0	1	0	1	0	1
7	N37	max	445.878	4	275.774	18	182.042	2	0	1	0	1	0	1
8		min	-424.663	5	66.653	7	-653.996	13	0	1	0	1	0	1
9	N38	max	1081.621	5	254.544	15	3929.272	4	0	1	0	1	0	1
10		min	-1111.101	4	62.047	8	-3587.655	5	0	1	0	1	0	1
11	N47	max	1423.454	4	13.962	4	3747.477	5	0	1	0	1	0	1
12		min	-1415.189	5	7.459	5	-3756.572	4	0	1	0	1	0	1
13	N49A	max	427.248	2	14.577	1	770.317	2	0	1	0	1	0	1
14		min	-427.53	3	11.066	2	-771.613	3	0	1	0	1	0	1
15	Totals:	max	2529.82	4	1319.077	16	3050.438	2						
16		min	-2529.82	5	569.075	5	-3050.438	3						

**Envelope AISC 13th(360-05): LRFD Steel Code Checks**

Member	Shape	Code Ch...	Loc[ft]	LC	Shear ...	Loc[ft]	Dir	LC	phi*Pnc ...	phi*Pnt [...]	phi*Mn ...	phi*Mn ...	Cb	Eqn
1	M2	PIPE 2.0	.365	10.172	13	.152	5.25	3	8922.084	32130	1871.625	1871.625	1.8	H1-1b
2	M5	PIPE 2.0	.349	10.172	16	.149	5.25	2	8922.084	32130	1871.625	1871.625	1.8	H1-1b
3	M13	PIPE 2.0	.205	1.375	3	.057	1.375	19	20866.7...	32130	1871.625	1871.625	1...	H1-1b
4	M15	PIPE 2.0	.444	3.125	2	.090	3.125	3	20866.7...	32130	1871.625	1871.625	1...	H1-1b
5	M16	PIPE 2.0	.401	3.125	2	.087	3.125	3	20866.7...	32130	1871.625	1871.625	1...	H1-1b
6	M8	PIPE 1.5	.083	3	6	.005	6	9	11973.6...	23593.5	1105.125	1105.125	1...	H1-1b
7	M9	PIPE 2.0	.721	3.75	4	.833	3.542	4	29810.2...	32130	1871.625	1871.625	1	H3-6



Company : Ramaker & Associates  
 Designer : JMO  
 Job Number : 22984  
 Model Name : Avon Mountain (CT03XC053-A)

July 14, 2014

Checked By: \_\_\_\_\_

**Envelope AISC 13th(360-05): LRFD Steel Code Checks (Continued)**

Member	Shape	Code Ch...	Loc[ft]	LC	Shear ...	Loc[ft]	Dir	LC	phi*Pnc ...	phi*Pnt [..	phi*Mn ...	phi*Mn ...	Cb	Eqn	
8	M10	PIPE 2.0	.636	0	4	.064	1.724		4	29497.8...	32130	1871.625	1871.625	1...	H1-1b
9	M11	PIPE 2.0	.946	1.502	4	.134	1.502		5	29497.8...	32130	1871.625	1871.625	1...	H1-1b
10	M12	PIPE 2.0	.241	4.5	4	.266	1		4	20866.7...	32130	1871.625	1871.625	1...	H3-6
11	M15A	1/2 Rod	.755	0	4	.314	0		4	1822.745	6361.74	53.015	53.015	2...	H1-1b
12	M16A	PIPE 1.5	.498	3.573	5	.007	7		5	9372.519	23593.5	1105.125	1105.125	1...	H1-1a
13	M17	PL3x3/8	.321	0	14	.030	0	y	4	33970.5...	36450	284.766	2278.125	1...	H1-1b
14	M18	PL3x3/8	.339	0	14	.076	0	y	4	33970.5...	36450	284.766	2278.125	1...	H1-1b
15	M19	PIPE 2.0	.055	3	7	.005	0		5	20866.7...	32130	1871.625	1871.625	1...	H1-1b



PROJECT: 2.5 EQUIPMENT DEPLOYMENT

SITE NAME: AVON MOUNTAIN

SITE CASCADE: CT03XC053-A

SITE ADDRESS: 81 MONTEVIDEO ROAD  
AVON, CT 06001

SITE TYPE: 150'-0"  
SELF SUPPORT TOWER



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com



48 SPRUCE STREET  
OAKLAND, NJ 07346

Certification & Seal:  
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 7/14/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 07/14/2014

PROJECT TITLE:  
**AVON MOUNTAIN  
CT03XC053-A**

PROJECT INFORMATION:  
81 MONTEVIDEO ROAD  
AVON, CT 06001  
HARTFORD COUNTY

SHEET TITLE:  
**TITLE SHEET**

SCALE: NONE

PROJECT NUMBER: 22984  
SHEET NUMBER: T-1

**SITE INFORMATION**

**PROPERTY OWNER:**  
MONTE LLC  
PO BOX 320623  
HARTFORD, CT 06132-0623

**SITE ADDRESS:**  
81 MONTEVIDEO ROAD  
AVON, CT 06001  
HARTFORD COUNTY

**GEOGRAPHIC COORDINATES:**  
LATITUDE: 41° 48' 11.0298" N (41.80306388)  
LONGITUDE: 72° 48' 4.6398" W (-72.80128888)

**ZONING JURISDICTION:**  
TOWN OF AVON

**ZONING DISTRICT:**  
RESIDENTIAL

**POWER COMPANY:**  
NORTHEAST UTILITIES  
PH.: (800) 286-2000


**AAV PROVIDER:**  
AT&T  
PH.: (210) 821-4105

**SPRINT CONSTRUCTION MANAGER:**  
NAME: MIKE DELIA  
PHONE: (781) 316-6348  
E-MAIL: michael.delia@spnnt.com

**EQUIPMENT SUPPLIER:**  
ALCATEL-LUCENT  
600-700 MOUNTAIN AVENUE  
MURRAY HILL, NJ 07974  
PH.: (908) 508-8080

**PLANS PREPARED BY:**  
RAMAKER & ASSOCIATES, INC.  
CONTACT: KEITH BOHNSACK, PROJECT MANAGER  
PH.: (608) 643-4100  
EMAIL: kbohnsack@ramaker.com

**AREA MAP**



**LOCATION MAP**



**PROJECT DESCRIPTION**

- INSTALL NEW 2.5 EQUIPMENT IN EXISTING BTS CABINET  
\*(1) RECTIFIER SHELF AND (3) RECTIFIERS  
\*(1) BASE BAND UNIT
- INSTALL NEW BATTERY STRING(S) IN EXISTING BATTERY CABINET
- INSTALL (3) PANEL ANTENNAS
- INSTALL (3) RRH'S ON TOWER
- INSTALL (1) HYBRID CABLE AND (2) SECTOR JUMPERS
- INSTALL (27) ANTENNA / RRH JUMPERS

**APPLICABLE CODES**

\* ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

- INTERNATIONAL BUILDING CODE
- ANSI/TIA-222 STRUCTURAL STANDARD FOR ANTENNA STRUCTURES
- NFPA 780 - LIGHTNING PROTECTION CODE
- NATIONAL ELECTRIC CODE



**SHEET INDEX**

SHT NO:	SHEET TITLE:	REV:	ENGINEER:
T-1	TITLE SHEET	A	JRS
SP-1	SPRINT SPECIFICATIONS	A	JRS
SP-2	SPRINT SPECIFICATIONS	A	JRS
SP-3	SPRINT SPECIFICATIONS	A	JRS
A-1	SITE PLAN	A	JRS
A-2	EQUIPMENT PLAN	A	JRS
A-3	BUILDING ELEVATION & ANTENNA DETAILS	A	JRS
A-4	RF DATA SHEET	A	JRS
A-5	FIBER PLUMBING DIAGRAM	A	JRS
A-6	CABLE COLOR CODING	A	JRS
A-7	ANTENNA & HYBRID CABLE DETAILS	A	JRS
A-8	EQUIPMENT DETAILS	A	JRS
E-1	EQUIPMENT UTILITY & GROUNDING PLAN	A	JRS
E-2	GROUNDING DETAILS	A	JRS
E-3	DC POWER DETAILS & PANEL SCHEDULES	A	JRS

**SECTION 01 100 - SCOPE OF WORK**

**THE WORK:**  
 THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE CONSTRUCTION DRAWINGS AND ASSOCIATED OUTLINE SPECIFICATIONS AND THE SITE SPECIFIC WORK ORDER, DESCRIBE THE WORK TO BE PERFORMED BY THIS CONSTRUCTION CONTRACTOR (SUPPLIER).

**RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF EACH SECTION OF THIS SPECIFICATION APPLY TO ALL SECTIONS, INDIVIDUALLY AND COLLECTIVELY.
- B. RELATED DOCUMENTS: THE CONTRACTOR SHALL COMPLY WITH THE MOST CURRENT VERSION OF THE FOLLOWING SUPPLEMENTAL REQUIREMENTS FOR INSTALLATION AND TESTING.
  - 1. EN-201 2-001 : (FIBER OPTIC, DC CABLE, AND DC CIRCUIT BREAKER TAGGING STANDARDS)
  - 2. TS-0200 - (TRANSMISSION ANTENNA LINE ACCEPTANCE STANDARDS)
  - 3. EL-0568: (FIBER TESTING POLICY)
  - 4. NP-312-201 : (EXTERIOR GROUNDING SYSTEM TESTING)
  - 5. NP-760-500: ETHERNET, MICROWAVE, TESTING AND ACCEPTANCE

**PRECEDENCE:**

SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

**NATIONALLY RECOGNIZED CODES AND STANDARDS:**

- THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
- A. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
  - B. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
  - C. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
  - D. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
  - E. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
  - F. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
  - G. AMERICAN CONCRETE INSTITUTE (ACI)
  - H. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
  - I. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
  - J. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
  - K. PORTLAND CEMENT ASSOCIATION (PCA)
  - L. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
  - M. BRICK INDUSTRY ASSOCIATION (BIA)
  - N. AMERICAN WELDING SOCIETY (AWS)
  - O. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
  - P. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
  - Q. DOOR AND HARDWARE INSTITUTE (DHI)
  - R. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
  - 5. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

**DEFINITIONS:**

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: "SPRINT"; SPRINT NEXTEL CORPORATION AND ITS OPERATING ENTITIES.
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR, SUPPLIER, CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT.

**SITE FAMILIARITY:**

CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.

**POINT OF CONTACT:**

COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

**ON-SITE SUPERVISION:**

THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.

**DRAWINGS REQUIRED AT JOBSITE:**

- THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
- A. THE JOBSITE DRAWINGS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
  - B. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

**USE OF JOB SITE:**

THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

**UTILITY SERVICES:**

WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:

**PERMITS/FEES:**

WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

**CONTRACTOR:**

CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.

**USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:**

CONTRACTOR WILL UTILIZE ITS BEST EFFORTS TO WORK WITH SPRINT ELECTRONIC PROJECT MANAGEMENT SYSTEMS. CONTRACTOR UNDERSTANDS THAT SUFFICIENT INTERNET ACCESS, EQUIVALENT TO "BROADBAND" OR BETTER, IS REQUIRED TO TIMELY AND EFFECTIVELY UTILIZE SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS AND AGREES TO MAINTAIN APPROPRIATE CONNECTIONS FOR CONTRACTOR'S STAFF AND OFFICES THAT ARE COMPATIBLE WITH SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS

**TEMPORARY UTILITIES AND FACILITIES:**

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSOR'S OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

**ACCESS TO WORK:**

THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

**DIMENSIONS:**

VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

**EXISTING CONDITIONS:**

NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

**SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT**

**FURNISHED MATERIALS:**

COMPANY FURNISHED MATERIALS AND EQUIPMENT TO BE INSTALLED BY THE CONTRACTOR (OFIC) IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.

**RECEIPT OF MATERIAL AND EQUIPMENT:**

A. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:

- 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
- 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
- 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
- B. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
- C. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
- D. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

**DELIVERABLES:**

- A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
- B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.

**SECTION 01 300 - CELL SITE CONSTRUCTION**

**NOTICE TO PROCEED:**

- A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S ISSUANCE OF THE WORK ORDER.
- B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

**GENERAL REQUIREMENTS FOR CONSTRUCTION:**

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
  - 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
  - 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION

**FUNCTIONAL REQUIREMENTS:**

- A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. CONTRACTOR SHALL TAKE ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
- B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
- C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
- D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
  - 1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
  - 2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
  - 3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND BACKHAUL (FIBER, COPPER, OR MICROWAVE).
  - 4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
  - 5. INSTALL ABOVE GROUND GROUNDING SYSTEMS, CONDUIT AND BOXES.
  - 6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
  - 7. INSTALL "H-FRAMES", CABINETS AND PADS AND PLATFORMS AS INDICATED.
  - 8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
  - 9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.

- 10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
- 11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
- 12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
- 13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
- 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.
- 15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
- 16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
- 17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
- 18. CONDUCT ALL REQUIRED TESTS AND INSPECTIONS
- 19. PERFORM, DOCUMENT, AND CLOSE OUT ALL JURISDICTIONAL PERMITTING REQUIREMENTS AND ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
- 20. PERFORM ALL ADDITIONAL WORK AS IDENTIFIED IN SCOPE OF SERVICES ATTACHED TO THE SUPPLIER AGREEMENT FOR THIS PROJECT. THIS WORK MAY INCLUDE COMMISSIONING, INTEGRATION, SPECIAL WAREHOUSING, REVERSE LOGISTICS ACTIVITIES, ETC. PERFORM COMMISSIONING AND INTEGRATION ACTIVITIES PER APPLICABLE MOPS.

**DELIVERABLES:**

- A. THE CONTRACTOR SHALL PROVIDE ALL REQUIRED TEST REPORTS AND DOCUMENTATION INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
  - 1. PRODUCT SPECIFICATIONS FOR MATERIALS OR SPECIAL CONSTRUCTION IF REQUESTED BY SPRINT
  - 2. ACTUALIZE ALL CONSTRUCTION RELATED MILESTONES IN SITERRA AND COMPLETE ALL ON-LINE FORMS AND COMPLETE DOCUMENT UP-LOADS. UPLOAD ALL REQUIRED CLOSEOUT DOCUMENTS AND FINAL SITE PHOTOS
  - 3. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT LEFT ON SITE INSIDE BASE OF MAIN RF CABINET IN A PROTECTIVE POUCH.
  - 4. ALL REQUIRED TEST REPORTS.
  - 5. REQUIRED CLOSEOUT DOCUMENTATION INCLUDING BUT NOT LIMITED TO:
    - a. ALL JURISDICTIONAL PERMITTING AND OCCUPANCY INFORMATION
    - b. PDF SCAN OF REDLINES PRODUCED IN THE FIELD
    - c. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS
    - d. LIEN WAIVERS
    - e. FINAL PAYMENT APPLICATION
    - f. REQUIRED FINAL CONSTRUCTION PHOTOS
    - g. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
    - h. LISTS OF SUBCONTRACTORS
- B. PROVIDE ADDITIONAL DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
  - 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
  - 2. PROJECT PROGRESS REPORTS.
  - 3. PRE-CONSTRUCTION MEETING NOTES.

**SECTION 01 400 - TESTS, INSPECTIONS, SUBMITTALS, AND PROJECT CLOSEOUT**

**TESTS AND INSPECTIONS:**

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
  - 1. COAX SWEEPS AND FIBER TESTS PER TS-0200 (CURRENT VERSION) ANTENNA LINE ACCEPTANCE STANDARDS
  - 2. POST CONSTRUCTION HEIGHT VERIFICATION, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
  - 3. CONCRETE BREAK TESTS
  - 4. SITE RESISTANCE TO EARTH TEST
  - 5. STRUCTURAL BACKFILL COMPACTION TESTS
  - 6. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
  - 7. ADDITIONAL TESTING AS REQUIRED ELSEWHERE IN THIS SPECIFICATION.

**SUBMITTALS:**

- A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
- B. UPLOAD THE FOLLOWING TO SITERRA AS APPLICABLE INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
  - 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
  - 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
  - 3. CHEMICAL GROUNDING SYSTEM .
  - 4. REINFORCEMENT CERTIFICATIONS
  - 5. STRUCTURAL BACKFILL TEST RESULTS
  - 6. SWEEP AND FIBER TESTS
  - 7. ANTENNA AZIMUTH AND DOWN-TILT VERIFICATION
  - 8. POST CONSTRUCTION HEIGHT VERIFICATION
  - 9. ADDITIONAL SUBMITTALS MAY BE REQUIRED FOR SPECIAL CONSTRUCTION OR MINOR MATERIALS
- C. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

**TESTING BY THIRD PARTY AGENCY:**

- A. EMPLOY AN AGENCY OF ENGINEERS AND SCIENTISTS WHO IS REGULARLY ENGAGED IN FIELD AND LABORATORY TESTING AND ANALYSIS. AGENCY SHALL HAVE BEEN IN BUSINESS A MINIMUM OF FIVE YEARS, AND BE LICENSED AS PROFESSIONAL ENGINEERS IN THE STATE WHERE THE PROJECT IS LOCATED. AGENCY IS SUBJECT TO APPROVAL BY COMPANY.
  - 1. AGENCY MUST HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
  - 2. AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
  - 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.
- B. REQUIRED THIRD PARTY TESTS:
  - 1. SITE RESISTANCE TO EARTH TEST PER NP-312-201
  - 2. CONCRETE CYLINDER BREAK TESTS FOR TOWER PIER AND ANCHORS PER NATIONALLY RECOGNIZED STANDARDS
  - 3. STRUCTURAL SOILS COMPACTION TESTS PER NATIONALLY RECOGNIZED STANDARDS
  - 4. REBAR PLACEMENT VERIFICATION WITH REPORT
  - 5. TESTING TENSION STUDY FOR ROCK ANCHORS
  - 6. ALL THIRD PARTY TESTS AS REQUIRED BY LOCAL JURISDICTION
- C. REQUIRED TESTS BY CONTRACTOR
  - 1. COAX SWEEP TESTS PER SPRINT STANDARD TS-0200
  - 2. FIBER TESTS PER SPRINT STANDARD EL-0568
  - 3. MICROWAVE LINK TESTS PER NP-760-500
  - 4. ANTENNA AZIMUTHS AND DOWN TILT USING ELECTRONIC ALIGNMENT TOOL PER ANTENNA INSTALLATION SPECIFICATION HEREIN.



**6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251**



**1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com**



**48 SPRUCE STREET  
 OAKLAND, NJ 07346**

**Certification & Seal:**  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* Signature Date: 7/14/2014


MARK	DATE	DESCRIPTION
ISSUE PHASE	FINAL	DATE ISSUED 07/14/2014

PROJECT TITLE:  
**AVON MOUNTAIN  
 CT03XC053-A**

PROJECT INFORMATION:  
**81 MONTEVIDEO ROAD  
 AVON, CT 06001  
 HARTFORD COUNTY**

SHEET TITLE:  
**SPRINT SPECIFICATIONS**

SCALE: NONE

PROJECT NUMBER	22984
SHEET NUMBER	SP-1



SUPPORTING DEVICES:

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN ACCORDANCE WITH NEC.
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING:
  - 1. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF THE PROOF TEST LOAD.
  - 2. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE SLABS.

ELECTRICAL IDENTIFICATION:

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS OF AC PANEL BOARDS WITH ANY CHANGES MADE TO THE AC SYSTEM.
- B. BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

SECTION 26 200 - ELECTRICAL MATERIALS AND EQUIPMENT

- A. RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR UNDERGROUND RUNS. RIGID CONDUIT AND FITTINGS SHALL BE STEEL, COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS. CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS C80.1, FEDERAL SPECIFICATION WW-C-581 AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES. FITTINGS SHALL BE THREADED - SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED EQUAL.
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP RADIUS ELBOWS.
- D. EMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPECIFICATION C80.3, FEDERAL SPECIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE.
- E. LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCEED 6- FEET. LFMC SHALL BE PROTECTED AND SUPPORTED AS REQUIRED BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (21MM).

HUBS AND BOXES:

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
  - 1. CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-Z/GEDNEY OR EQUAL BY ROXTEC.
  - 2. CABLE TERMINATORS FOR LFMC SHALL BE ETCO - CL2075; OR MADE FOR THE PURPOSE PRODUCTS BY ROXTEC.
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY, HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS, CROUSE-HINDS WAB SERIES OR EQUAL.
- D. CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKET COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM 8 OR EQUAL.
- E. MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER, ADALET, APPLETON, O-Z GEDNEY, RACO, OR APPROVED EQUAL.

SUPPLEMENTAL GROUNDING SYSTEM:

- A. FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM TO THE EXTENT INDICATED ON THE DRAWINGS. SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS EXCEPT AS OTHERWISE NOTED.
- B. SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO-OX.
- C. STOLEN GROUND-BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

EXISTING STRUCTURE:

- A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION.

CONDUIT AND CONDUCTOR INSTALLATION:

- A. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- B. CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

*Certification & Seal:*  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski*  
 Signature: \_\_\_\_\_ Date: 7/14/2014


MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 07/14/2014


PROJECT TITLE:  
**AVON MOUNTAIN  
 CT03XC053-A**

PROJECT INFORMATION:  
 81 MONTEVIDEO ROAD  
 AVON, CT 06001  
 HARTFORD COUNTY

SHEET TITLE:  
**SPRINT SPECIFICATIONS**

SCALE: NONE

PROJECT NUMBER	22984
SHEET NUMBER	SP-3



**SITE PLAN**  
 SCALE: 1" = 12.5'



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

**Certification & Seal:**  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski*  
 Signature: \_\_\_\_\_ Date: 7/14/2014


MARK	DATE	DESCRIPTION

ISSUE PHASE: FINAL DATE ISSUED: 07/14/2014

PROJECT TITLE:  
**AVON MOUNTAIN  
 CT03XC053-A**

PROJECT INFORMATION:  
 81 MONTEVIDEO ROAD  
 AVON, CT 06001  
 HARTFORD COUNTY

SHEET TITLE:  
**SITE PLAN**



PROJECT NUMBER: 22984  
 SHEET NUMBER: A-1



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

**Certification & Seal:**  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski*  
 Signature: \_\_\_\_\_ Date: 7/14/2014


MARK	DATE	DESCRIPTION

ISSUE PHASE	DATE ISSUED	DESCRIPTION
FINAL	07/14/2014	


PROJECT TITLE:  
**AVON MOUNTAIN  
 CT03XC053-A**

PROJECT INFORMATION:  
 81 MONTEVIDEO ROAD  
 AVON, CT 06001  
 HARTFORD COUNTY

SHEET TITLE:  
**EQUIPMENT PLAN**




PROJECT NUMBER	22984
SHEET NUMBER	A-2




**EQUIPMENT PLAN**  
 SCALE: 1" = 2.5'


This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.





ANTENNA & RRH MOUNTING DETAILS  
 SCALE: NTS



EXISTING ANTENNA ARRAY  
 SCALE: NTS



BUILDING ELEVATION  
 SCALE: 1" = 40'



NOTE: THE VALMONT TPF 10372 INCLUDES HARDWARE TO ATTACH TO A ROUND MEMBER VARYING IN SIZE FROM 2 1/2"-4 1/2" OD. THE TOWER LEG AT THE ATTACHMENT LOCATION IS 1 3/4" OD; CONTRACTOR TO ENSURE APPROPRIATE MOUNTING HARDWARE TO ACCOMMODATE TOWER LEG IS ORDERED/INSTALLED.

PROPOSED ANTENNA ARRAY  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 7/14/2014

MARK	DATE	DESCRIPTION

ISSUE PHASE	FINAL	DATE ISSUED	07/14/2014
PROJECT TITLE:			

AVON MOUNTAIN  
 CT03XC053-A

PROJECT INFORMATION:  
 81 MONTEVIDEO ROAD  
 AVON, CT 06001  
 HARTFORD COUNTY

SHEET TITLE:  
 BUILDING ELEVATIONS &  
 ANTENNA DETAILS

SCALE:  
 AS NOTED

PROJECT NUMBER: 22984  
 SHEET NUMBER: A-3



**RFDS Sheet**

**General Site Information**

Site ID	CT03XC053	Equipment Vendor	Alcatel-Lucent
Market	Northern Connecticut	Latitude	41.80278
Region	Northeast	Longitude	-72.80111
MLA	N/A	LL SITE ID	N/A
Structure Type	lattice		
BTS Type			

Solution ID		Siterra SR Equipment type		Incremental Power Draw needed by added Equipment	
		Equipment Vendor	Alcatel-Lucent		N/A

**Base Equipment**

BBU Kit	ALU BBU Kit	Top Hat	None
BBU Kit Qty	1	Top Hat Qty	N/A
Growth Cabinet		Top Hat Dimensions	N/A
	None	Top Hat Weight (lbs)	N/A
Growth Cabinet Qty	N/A		
Growth Cabinet Dimensions	N/A		
Growth Cabinet Weight	N/A		

**RF Path Information**

RRH	TD-RRH8x20-25
RRH Qty	3
RRH Dimensions	26.1"x18.6"x6.7"
RRH Weight. lbs.	70
RRH Mount Weight. Lbs.	10
Power and Fiber Cable	HYBRID CABLE
Cable Qty	1
Weight per foot. Lbs.	1.05
Diameter. Inches.	1.24
Length Ft.	300 (calculated as antenna height plus 20%)
Coax Jumper	1/2"
Coax Jumper Qty	27
Coax Jumper Length. Feet.	8
Coax Jumper Weight	1.7
Coax Jumper Diameter. Inches	0.5
AISG Cable	COMMSCOPE ATCB-B01-006
AISG Cable Qty	3
AISG Diameter. Inches.	0.315
AISG Cable length. Feet.	8
Weight of entire AISG cable. Lbs.	1.3

**Antenna Sector Information**

	Sector 1	Sector 2	Sector 3
Antenna make/model	RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20
Antenna qty	1	1	1
Antenna Dimensions. Inches	56.3"x12.6"x6.3"	56.3"x12.6"x6.3"	56.3"x12.6"x6.3"
Antenna Weight. Lbs	55.12	55.12	55.12
Antenna Mounting Kit Weight. Lbs.	11.5	11.5	11.5
CL Height	147	147	147
Antenna Azimuth	340	200	270
Antenna Mechanical Downtilt	0	0	0
Antenna etilt	-2	-2	-2

\*RFDS SHEET WAS GENERATED BY RAMAKER & ASSOCIATES FROM PLAN OF RECORD (POR) PROVIDED BY SPRINT. CONTRACTOR SHALL VERIFY AND OBTAIN FINAL RFDS FROM SPRINT CONSTRUCTION MANAGER PRIOR TO CONSTRUCTION.

**NOTES:**

- GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND C/L HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT BELOW, HALT ANTENNA WORK FOR ONE HOUR, CALL SPRINT RF ENGINEER (OR MANAGER IF RF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE A MESSAGE TO RF ENGINEER) USING CONTACT INFORMATION ABOVE FOR FURTHER INSTRUCTIONS. IF SPRINT DOES NOT RESPOND WITHIN ONE HOUR, PLACE 2.5GHZ ANTENNA AT SAME C/L HEIGHT AS 1.9GHZ ANTENNA AND EMAIL CORRECT C/L HEIGHT AND AZIMUTH TO SPRINT RF ENGINEER. UPDATE AS-BUILT DRAWING WITH CORRECT C/L HEIGHT. ALSO EMAIL CORRECT 1.9GHZ AND 800MHZ ANTENNA C/L HEIGHT, AZIMUTH AND MECHANICAL DOWNTILT TO RF ENGINEER.
- AISG TESTS TO VERIFY OPERATION IS TO BE PERFORMED AFTER FINAL INSTALLATION OF ANTENNAS AND AISG CABLES HAVE BEEN CONNECTED. VERIFY OPERATION OF ALL EXISTING SPRINT AISG EQUIPMENT INCLUDING 800MHZ, 1.9GHZ AND 2.5GHZ. TEST TO INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX SWEEP TEST SPREADSHEET.
- GENERAL CONTRACTOR MUST ENSURE THAT NO OBJECT IS LOCATED WITHIN 45 DEGREES OF LEFT AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTION. IN ADDITION, 2.5GHZ ANTENNA IS NOT TO BE PLACED IN FRONT OF ANY OTHER ANTENNA USING THE SAME 45 DEGREE RULE. THIS INCLUDES SPRINT AND NON-SPRINT ANTENNAS.
- 2.5GHZ ANTENNA MUST BE AT LEAST 6" FROM 1.9GHZ ANTENNA, 30" FROM 800MHZ ANTENNA AND 30" FROM DUAL BAND 1.9GHZ AND 800MHZ ANTENNA.
- GENERAL CONTRACTOR IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNTILT. AZIMUTH ACCURACY IS TO BE WITHIN 1 DEGREE. DOWNTILT AND ROLL (LEFT TO RIGHT TILT) IS TO BE WITHIN 0.1 DEGREES. IF FOR SOME REASON THIS ACCURACY CANNOT BE ACHIEVED, UPDATE AS-BUILT DRAWINGS AND EMAIL SPRINT RF ENGINEER WITH AS-BUILT SETTINGS. USE 3Z RF ALIGNMENT TOOL OR EQUIVALENT TOOL.



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

**Certification & Seal:**  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* Signature: \_\_\_\_\_ Date: 7/14/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 07/14/2014


PROJECT TITLE:  
**AVON MOUNTAIN  
 CT03XC053-A**

PROJECT INFORMATION:  
 81 MONTEVIDEO ROAD  
 AVON, CT 06001  
 HARTFORD COUNTY


SHEET TITLE:  
**RF DATA SHEET**

SCALE:  
 AS NOTED


PROJECT NUMBER: 22984  
 SHEET NUMBER: A-4




TYPICAL FIBER DISTRIBUTION BOX DETAIL  
 SCALE: NTS




RRH TO DISTRIBUTION BOX POWER CONNECTIVITY DETAIL  
 SCALE: NTS



8T8R DETAIL  
 SCALE: NTS



BTS TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL  
 SCALE: NTS



RRH TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 7/14/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 07/14/2014

PROJECT TITLE:

AVON MOUNTAIN  
 CT03XC053-A

PROJECT INFORMATION:  
 81 MONTEVIDEO ROAD  
 AVON, CT 06001  
 HARTFORD COUNTY

SHEET TITLE:

FIBER PLUMBING DIAGRAM





SCALE:  
 AS NOTED

PROJECT NUMBER: 22984  
 SHEET NUMBER: A-5

2.5 FREQUENCY	INDICATOR		ID
2500 -1	YEL	WHT	GRN
2500 -2	YEL	WHT	RED
2500 -3	YEL	WHT	BRN
2500 -4	YEL	WHT	BLU
2500 -5	YEL	WHT	SLT
2500 -6	YEL	WHT	ORG
2500 -7	YEL	WHT	WHT
2500 -8	YEL	WHT	PPL

NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL

Sector	Cable	First Ring	Second Ring	Third Ring
<b>1 Alpha</b>	<b>1</b>	Green	No Tape	No Tape
<b>1</b>	<b>2</b>	Blue	No Tape	No Tape
<b>1</b>	<b>3</b>	Brown	No Tape	No Tape
<b>1</b>	<b>4</b>	White	No Tape	No Tape
<b>1</b>	<b>5</b>	Red	No Tape	No Tape
<b>1</b>	<b>6</b>	Grey	No Tape	No Tape
<b>1</b>	<b>7</b>	Purple	No Tape	No Tape
<b>1</b>	<b>8</b>	Orange	No Tape	No Tape
<b>2 Beta</b>	<b>1</b>	Green	Green	No Tape
<b>2</b>	<b>2</b>	Blue	Blue	No Tape
<b>2</b>	<b>3</b>	Brown	Brown	No Tape
<b>2</b>	<b>4</b>	White	White	No Tape
<b>2</b>	<b>5</b>	Red	Red	No Tape
<b>2</b>	<b>6</b>	Grey	Grey	No Tape
<b>2</b>	<b>7</b>	Purple	Purple	No Tape
<b>2</b>	<b>8</b>	Orange	Orange	No Tape
<b>3 Gamma</b>	<b>1</b>	Green	Green	Green
<b>3</b>	<b>2</b>	Blue	Blue	Blue
<b>3</b>	<b>3</b>	Brown	Brown	Brown
<b>3</b>	<b>4</b>	White	White	White
<b>3</b>	<b>5</b>	Red	Red	Red
<b>3</b>	<b>6</b>	Grey	Grey	Grey
<b>3</b>	<b>7</b>	Purple	Purple	Purple
<b>3</b>	<b>8</b>	Orange	Orange	Orange



COLOR CODING CHARTS  
SCALE: NTS

CABLE MARKING NOTES

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAKOUT UNIT. THERE SHALL BE 1" SPACE BETWEEN EACH RING.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE SECOND CABLE IDENTIFIED BY BLUE BANDS OF TAPE
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com



48 SPRUCE STREET  
OAKLAND, NJ 07346

Certification & Seal:  
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 7/14/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 07/14/2014

PROJECT TITLE:  
**AVON MOUNTAIN  
CT03XC053-A**

PROJECT INFORMATION:  
81 MONTEVIDEO ROAD  
AVON, CT 06001  
HARTFORD COUNTY

SHEET TITLE:  
**CABLE COLOR CODING**

SCALE:  
AS NOTED

PROJECT NUMBER: 22984  
SHEET NUMBER: A-6

HYBRID CABLE DC CONDUCTOR SIZE GUIDELINE  
 MANUF:RFS

CABLE	LENGTH	DC CONDUCTOR	CABLE DIAMETER
Fiber Only	Varies	Use NV Hybriflex	5/8"
Hybriflex	<200'	8 AWG	1-1/4"
Hybriflex	225-300'	6 AWG	1-1/4"
Hybriflex	325-375'	4 AWG	1-1/4"

RFS HYBRIFLEX RISER CABLE SCHEDULE


FIBER ONLY (EXISTING DC POWER)	Hybrid cable	
MN-HB058-M12-050F	12x multi-mode fiber pairs, Top:Outdoor protected connectors, Bottom:LC Connectors, 5/8 cable, 50 ft	50 ft
MN-HB058-M12-075F		75 ft
MN-HB058-M12-100F		100 ft
MN-HB058-M12-125F		125 ft
MN-HB058-M12-150F		150 ft
MN-HB058-M12-175F		175 ft
MN-HB058-M12-200F		200 ft
8 AWG Power	Hybrid cable	
MN-HB114-08U3M12-050F	3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 50 ft	50 ft
MN-HB114-08U3M12-075F		75 ft
MN-HB114-08U3M12-100F		100 ft
MN-HB114-08U3M12-125F		125 ft
MN-HB114-08U3M12-150F		150 ft
MN-HB114-08U3M12-175F		175 ft
MN-HB114-08U3M12-200F		200 ft
6 AWG Power	Hybrid cable	
MN-HB114-13U3M12-225F	3x 6 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 225 ft	225 ft
MN-HB114-13U3M12-250F		250 ft
MN-HB114-13U3M12-275F		275 ft
MN-HB114-13U3M12-300F		300 ft
4 AWG Power	Hybrid cable	
MN-HB114-21U3M12-325F	3x 4 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 325 ft	325 ft
MN-HB114-21U3M12-350F		350 ft
MN-HB114-21U3M12-375F		375 ft

RFS HYBRIFLEX JUMPER CABLE SCHEDULE

FIBER ONLY	Hybrid Jumper cable	
MN-HBF012-M3-5F1	5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
MN-HBF012-M3-10F1		10 ft
MN-HBF012-M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15' NOTIFY SPRINT CM OF ANY DISCREPANCY		
8 AWG POWER	Hybrid Jumper cable	
MN-HBF058-08U1M3-5F1	5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 5/8 cable	5 ft
MN-HBF058-08U1M3-10F1		10 ft
MN-HBF058-08U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15' NOTIFY SPRINT CM OF ANY DISCREPANCY		
6 AWG POWER	Hybrid Jumper cable	
MN-HBF058-13U1M3-5F1	5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 5/8 cable	5 ft
MN-HBF058-13U1M3-10F1		10 ft
MN-HBF058-13U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15' NOTIFY SPRINT CM OF ANY DISCREPANCY		
4 AWG POWER	Hybrid Jumper cable	
MN-HBF078-21U1M3-5F1	5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 7/8 cable	5 ft
MN-HBF078-21U1M3-10F1		10 ft
MN-HBF078-21U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15' NOTIFY SPRINT CM OF ANY DISCREPANCY		


\*NOTE: SPRINT CM TO CONFIRM HYBRID/FIBER RISER CABLE & HYBRID/FIBER JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.

FIBER CABLE CROSS SECTION & DATA  
 SCALE: NTS




RFS: APXV9TM | 4-ALU-120

DIMENSIONS, HxWxD: 56.3" x 12.6" x 6.3"  
 WEIGHT, WITHOUT PRE-MOUNTED BRACKETS: 55.12 lbs.  
 CONNECTOR: (9) MINI-DIN FEMALE/BOTTOM



2.5 ANTENNA DETAIL  
 SCALE: NTS



ALCATEL-LUCENT: TD-RRH&x20  
 HxWxD = 26.1" x 18.6" x 6.7"  
 WEIGHT = 70 lbs.

2.5 RRH DETAIL  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 7/14/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 07/14/2014


PROJECT TITLE:  
**AVON MOUNTAIN  
 CT03XC053-A**

PROJECT INFORMATION:  
 81 MONTEVIDEO ROAD  
 AVON, CT 06001  
 HARTFORD COUNTY


SHEET TITLE:  
**ANTENNA & HYBRID CABLE  
 DETAILS**

SCALE:  
 AS NOTED

PROJECT NUMBER	22984
SHEET NUMBER	A-7




HYBRID BREAKOUT DETAIL ①  
 SCALE: NTS



CABLE ROUTE FROM CABINET ②  
 SCALE: NTS



EXISTING BBU CABINET ③  
 SCALE: NTS



EXISTING MMBS CABINET ④  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 7/14/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 07/14/2014


PROJECT TITLE:  
**AVON MOUNTAIN  
 CT03XC053-A**

PROJECT INFORMATION:  
 81 MONTEVIDEO ROAD  
 AVON, CT 06001  
 HARTFORD COUNTY


SHEET TITLE:  
**EQUIPMENT DETAILS**

SCALE:  
 AS NOTED

PROJECT NUMBER: 22984  
 SHEET NUMBER: A-8



**EQUIPMENT UTILITY & GROUNDING PLAN**  
 SCALE: NTS



**ANTENNA GROUNDING DETAIL**  
 SCALE: NTS

**GROUNDING NOTES:**

1. CONTRACTOR TO ENSURE PROPER SEQUENCING OF GROUNDING AND UNDERGROUND CONDUIT INSTALLATION TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM AND/OR DAMAGE TO THE CONDUIT.
2. ALL EXTERIOR GROUND CONDUCTORS SHALL BE #2 AWG SOLID TINNED COPPER UNLESS NOTED OTHERWISE.
3. ALL GROUND CONNECTIONS BELOW GRADE SHALL BE EXOTHERMIC (CADWELD).
4. ALL GROUND CONNECTIONS ABOVE GRADE AND/OR INTERIOR SHALL BE COMPRESSION TYPE, TWO-HOLE LUGS OR DOUBLE-CRIMP "C" TAPS.
5. CONTACT AREAS WHERE CONNECTIONS ARE MADE SHALL BE PREPARED TO A BARE BRIGHT FINISH AND COATED WITH AN ANTI-OXIDATION MATERIAL BEFORE CONNECTIONS ARE MADE.
6. MAXIMUM RESISTANCE OF THE COMPLETED GROUND SYSTEM SHALL NOT EXCEED 5 OHMS.
7. WHERE GROUNDING CONNECTIONS ARE MADE TO PAINTED METAL SURFACES, PAINT SHALL BE REMOVED TO BARE METAL TO ENSURE PROPER CONTACT AND RESTORED/PAINTED TO ORIGINAL FINISH.
8. GROUND DEPTH SHALL BE 30" MINIMUM BELOW FINISHED GRADE, OR 6" BELOW FROST LINE, WHICHEVER IS GREATER.

LEGEND:	
---	EXISTING GROUND CABLE
---	PROPOSED GROUND CABLE
▲	MECHANICAL CONNECTION
■	EXOTHERMIC CONNECTION
—E—E—E—E—E—	PROPOSED ELECTRIC



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

**Certification & Seal:**  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* Signature: \_\_\_\_\_ Date: 7/14/2014

MARK	DATE	DESCRIPTION

ISSUE PHASE: FINAL DATE ISSUED: 07/14/2014


PROJECT TITLE:  
**AVON MOUNTAIN  
 CT03XC053-A**

PROJECT INFORMATION:  
 81 MONTEVIDEO ROAD  
 AVON, CT 06001  
 HARTFORD COUNTY


SHEET TITLE:  
**EQUIPMENT UTILITY &  
 GROUNDING PLAN**

SCALE:  
 AS NOTED

PROJECT NUMBER: 22984  
 SHEET NUMBER: E-1




**GROUNDING RISER DIAGRAM**  
 SCALE: NTS



- NOTES:**
1. APPLY NO-OX TO LUG AND GROUND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
  2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

**GROUNDING CONDUCTOR INSTALLATION**  
 SCALE: NTS



**TWO-HOLE LUG**  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

**Certification & Seal:**  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 7/14/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 07/14/2014


PROJECT TITLE:  
**AVON MOUNTAIN  
 CT03XC053-A**

PROJECT INFORMATION:  
 81 MONTEVIDEO ROAD  
 AVON, CT 06001  
 HARTFORD COUNTY

SHEET TITLE:  
**GROUNDING DETAILS**

SCALE:  
 AS NOTED

PROJECT NUMBER	22984
SHEET NUMBER	E-2



### A/C PANEL SCHEDULE

VOLTAGE:	240V/1 20	PANEL STATUS:	EXISTING	N TO GROUND BOND:	YES
MAIN BREAKER:	100 AMP	MODEL NUMBER:	TBD	INTERNAL TVSS:	YES
MOUNT:	GROUND	PHASE:	1	WIRE:	3
ENCLOSURE TYPE:	NEMA 3R	BUSS RATING:	200 AMP	GROUND BAR:	YES
		NEUTRAL BAR:	YES		

CKT	DESCRIPTION	BREAKER AMPS	BREAKER POLES	BREAKER STATUS	PHASE A VA	PHASE B VA	BREAKER STATUS	BREAKER POLES	BREAKER AMPS	DESCRIPTION	CKT
1	MM BTS	100	2	ON			ON	2	60	SURGE PROTECTION	7
2	BLANK (UNUSED)	-	-	-							8
3	BLANK (UNUSED)	-	-	-			ON	2	60	NOT LABELED	9
4	BLANK (UNUSED)	-	-	-			ON	1	20	TELCO GFI	10
5	NOT LABELED	20	1	ON						BLANK (UNUSED)	11
6	FAN	10	1	ON							12

A/C PANEL SCHEDULE  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 7/14/2014

