

Daniel F. Caruso  
Chairman

# STATE OF CONNECTICUT

## CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051


Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: [siting.council@ct.gov](mailto:siting.council@ct.gov)

Internet: [ct.gov/csc](http://ct.gov/csc)

March 30, 2007

TO: Parties and Intervenors

FROM: S. Derek Phelps, Executive Director 

RE: **DOCKET NO. 324** - Sprint Nextel Corporation application for a Certificate of Environmental Compatibility and Public Need for the construction, maintenance and operation of a telecommunications facility located at 150 Willow Street, Hamden, Connecticut.

---

Comments have been received from the Department of Public Health, Drinking Water Section, dated March 26, 2007. A copy of the comments is attached for your review.

SDP/MP/laf

Enclosure

c: Council Members


Date: November 3, 2006

Docket No. 324

Page 1 of 1

**LIST OF PARTIES AND INTERVENORS**  
**SERVICE LIST**

| <b>Status Granted</b> | <b>Status Holder<br/>(name, address &amp; phone number)</b> | <b>Representative<br/>(name, address &amp; phone number)</b>   |
|-----------------------|---|--|
| <b>Applicant</b>      | Sprint Nextel Corporation                                   | Thomas J. Regan, Esq.<br>Brown Rudnick Berlack Israels LLP<br>CityPlace I, 185 Asylum Street<br>Hartford, CT 06103<br>(860) 509-6522<br>(860) 509-6501 fax<br><a href="mailto:tregan@brownrudnick.com">tregan@brownrudnick.com</a> |
|                       |   |  |
|                       |   |  |
|                       |   |  |
|                       |   |  |



# STATE OF CONNECTICUT

## DEPARTMENT OF PUBLIC HEALTH

### MEMORANDUM

RECEIVED  
MAR 28 2007

CONNECTICUT  
SITING COUNCIL

TO: Derek Phelps,  
Executive Director  
Connecticut Siting Council

FROM: <sup>LM</sup>Lori Mathieu, Supervisor  
Drinking Water Section  
Department of Public Health

DATE: 3/26/07

SUBJECT: **Docket No. 324**

DATE RECEIVED: 3/14/07

APPLICANT: Sprint Nextel Corporation

TOWN: Hamden

PROJECT: Application for a Certificate of Environmental Compatibility and Public Need for the construction, maintenance, and operation of a telecommunications facility located at 150 Willow Street, Hamden, CT

\_\_\_\_\_ No Comments.

  X   Other Comments: See attached

Cc: Dave Cooley, DWS  
Mike Guaglianone, RWA  
file

ppb



Phone: (860) 509-7333  
Telephone Device for the Deaf: (860) 509-7191  
410 Capitol Avenue - MS # SIWAT  
P.O. Box 340308 Hartford, CT 06134

*Affirmative Action / An Equal Opportunity Employer*

### Connecticut Siting Council Review

**FROM:** Patricia Bisacky, Environmental Analyst II  
**DATE:** March 26, 2007  
**SUBJECT:** Docket # 324  
**LOCATION:** 150 Willow Street, Hamden, CT

This proposed construction is within the Watershed Area for the Mill River System and the Level A Aquifer Protection Area of the North Sleeping Giant Well Field, sources of drinking water for the South Central Regional Water Authority (RWA). The Department's concern is for the protection of the sources of public drinking water that serves this area. RWA needs to be contacted prior to any construction and the following Best Management Practices should be reviewed and followed to ensure the safety of the drinking water supply.

- **Construction Coordination:** Any construction activities are to be coordinated with RWA, especially due to the sensitivity of the multiple sources of drinking water in this area.
- **Emergency Response Plan:** A response plan should be written for actions to be taken for the containment of accidental fuel or chemical spills that may occur during construction. Spill response equipment should be available on-site at all times along with personnel trained in the proper use of such equipment. A person or persons should be designated by the contractor for emergency response coordination on a 24/7 basis. RWA needs to be contacted immediately in these instances.
- **Vehicles and Machinery:** Avoid the cleaning of equipment on the locations of the future construction due to possible contamination from equipment chemicals. Avoid any storage of fuel and refueling within the watershed and aquifer protection areas. Designate one area for auto parking, vehicle refueling and routine equipment maintenance. The designated area should be well away from exposed surfaces or storm drains. All major equipment repairs must be made off site.
- **General Site Conditions.** Keep pollutants off exposed surfaces. The burying of stumps or construction debris must not be allowed on the job site. Sediment fences and hay bales must be strategically placed, inspected and maintained to prevent sedimentation and erosion. Temporary storm water ponds and basins must be routinely inspected and maintained. If unexpected conditions occur, additional fences and hay bales should be available for use as needed to prevent runoff. Protect exposed stockpiles of soil to prevent runoff. Use as little water as possible for dust control. Clean up leaks, drips and other spills immediately to prevent or minimize soil contamination. Never hose down "dirty" pavement or surfaces where materials have spilled. Use dry cleanup methods whenever possible.
- **Blasting:** Any blasting must be done with careful consideration to impacts to the area, including possible effects to ground water which could affect drinking water quality and quantity.
- **Hazardous Materials Storage.** Paints, paint products and other hazardous materials should be removed from the site during non-work hours or otherwise stored in a secure area to prevent vandalism. Place covered trashcans and recycling receptacles around the site. Cover and maintain dumpsters, check frequently for leaks, and never clean a dumpster by hosing it down on site.
- **Steep Slopes:** Development of slopes at 15 percent or greater should be avoided. Development of these areas is difficult, with a potential to significantly impact water quality within the drinking water supply watershed. If they cannot be avoided in this project, a separate environmental consultant should be on site to ensure proper erosion and sedimentation controls are in place. This consultant would be responsible to report to RWA so water quality issues are avoided.