



FROST BRIDGE TO CAMPVILLE 115-kV PROJECT

BY

THE CONNECTICUT LIGHT AND POWER COMPANY

DOING BUSINESS AS EVERSOURCE ENERGY

**VOLUME 1: DESCRIPTION OF THE PROPOSED PROJECT AND
ALTERNATIVES ANALYSES**

SEPTEMBER 2015

Note: This page intentionally left blank.

Contents

VOLUME 1: DESCRIPTION OF THE PROPOSED PROJECT AND ALTERNATIVES ANALYSES

EXECUTIVE SUMMARY	ES-1
PROPOSED PROJECT PURPOSE AND LOCATION.....	ES-1
PURPOSE OF THE MUNICIPAL CONSULTATION FILING	ES-2
PROPOSED TRANSMISSION FACILITIES	ES-3
CONSTRUCTION AND OPERATION / MAINTENANCE PROCEDURES	ES-4
ENVIRONMENTAL RESOURCES, POTENTIAL EFFECTS, AND MITIGATION MEASURES.....	ES-4
EMF ANALYSES	ES-6
ALTERNATIVES CONSIDERED	ES-7
COST AND SCHEDULE.....	ES-8
1. DESCRIPTION OF THE PROPOSED PROJECT	1-1
1.1 PROJECT BACKGROUND	1-1
1.2 PROPOSED PROJECT FACILITIES.....	1-3
1.2.1 New 115-kV Transmission Line.....	1-3
1.2.2 Double Circuit Separation	1-5
1.2.3 Substation Modifications	1-5
2. PROJECT BACKGROUND AND NEED	2-1
2.1 THE SYSTEM PLANNING PROCESS AND RELIABILITY CRITERIA	2-1
2.1.1 A Brief History of Electric Reliability Planning.....	2-1
2.1.2 Modern Reliability Standards and Criteria	2-2
2.1.3 Simulating Contingencies	2-3
2.1.4 Generation Dispatches in Power-Flow Simulations	2-5
2.1.5 Coordinating Ongoing Studies.....	2-6
2.2 DEVELOPMENT OF THE PROJECT	2-6
2.2.1 The Northwest Connecticut Sub-area	2-8
2.2.2 The Need for Transmission Improvements in NWCT.....	2-10
2.3 THE PROPOSED SOLUTION FOR THE NORTHWEST CONNECTICUT SUB-AREA NEEDS.....	2-12
2.3.1 The Frost Bridge – Campville Line and Its Associated Terminal Equipment Improvements	2-13
2.3.2 Separation of the 1191 and 1921 DCT	2-13
2.3.3 Conformance to Long-Range Plan for Expansion of Electric Power Serving the State and Interconnected Utility Systems	2-14
2.3.4 Identification of Facility in the Forecast of Loads and Resources.....	2-14
2.4 CONCLUSION	2-15
3. TECHNICAL PROJECT SPECIFICATIONS	3-1
3.1 PROPOSED TRANSMISSION LINE FACILITIES	3-1

3.1.1	115-kV Conductor Size and Specifications	3-2
3.1.2	Proposed Line Overhead Design, Appearance, and Heights	3-2
3.1.3	Design Voltage and Capacity	3-5
3.1.4	Proposed Structure Locations	3-5
3.1.5	ROW and Access Road Requirements	3-6
3.1.6	Facilities on ROW Post-Construction (Proposed Line Design).....	3-8
3.2	SUBSTATION CONNECTIONS AND MODIFICATIONS	3-13
3.2.1	Frost Bridge Substation	3-13
3.2.2	Campville Substation.....	3-14
3.3	ESTIMATED PROJECT COSTS.....	3-19
3.3.1	Estimated Capital Cost.....	3-19
3.3.2	Life-Cycle Cost.....	3-19
4.	CONSTRUCTION AND OPERATION / MAINTENANCE PROCEDURES.....	4-1
4.1	STANDARD PROCEDURES FOR OVERHEAD TRANSMISSION LINE CONSTRUCTION.....	4-1
4.1.1	Introduction and Overview of Construction Sequencing.....	4-1
4.1.2	Material Staging Sites.....	4-3
4.1.3	Construction Field Offices.....	4-6
4.1.4	Right-of-Way Preparation.....	4-6
4.1.5	Access Roads	4-13
4.1.6	Structure Installation.....	4-17
4.1.7	1921 and 1191 Line Double-Circuit Structure Removal	4-18
4.1.8	Conductor Work	4-18
4.1.9	Cleanup and Restoration.....	4-19
4.1.10	Traffic Considerations and Control	4-22
4.1.11	Construction and Post-Construction Monitoring: D&M Plans.....	4-22
4.2	CONDITIONS REQUIRING SPECIAL CONSTRUCTION PROCEDURES	4-23
4.2.1	Water Resource Crossings	4-23
4.2.2	Blasting	4-28
4.2.3	Soils and Groundwater Testing and Management	4-28
4.2.4	Groundwater and Construction Site Dewatering	4-30
4.3	CONSTRUCTION PROCEDURES FOR SUBSTATION MODIFICATIONS.....	4-30
4.3.1	Overview of Proposed Construction at Stations	4-30
4.3.2	Site Preparation.....	4-31
4.3.3	Foundations and Equipment Installation	4-31
4.3.4	Testing and Interconnections	4-32
4.3.5	Final Cleanup, Site Security, and Landscaping	4-32
4.4	OPERATION AND MAINTENANCE PROCEDURES	4-32
4.4.1	ROW Vegetation Management.....	4-32
4.4.2	Substation Maintenance.....	4-33
4.4.3	Compliance with Applicable Codes and Standards	4-33
4.4.4	Security of Facilities	4-34
5.	DESCRIPTION OF EXISTING ENVIRONMENT.....	5-1
5.1	PROPOSED ROUTE: FROST BRIDGE SUBSTATION TO CAMPVILLE SUBSTATION	5-2
5.1.1	Topography, Geology and Soils	5-2
5.1.2	Water Resources	5-4

5.1.3	Biological Resources	5-12
5.1.4	Land Uses and Scenic Resources.....	5-27
5.1.5	Transportation Systems and Utility Crossings.....	5-41
5.1.6	Cultural (Archaeological and Historic) Resources	5-43
5.1.7	Air Quality	5-44
5.1.8	Noise	5-45
5.2	SUBSTATIONS	5-47
5.2.1	Frost Bridge Substation	5-48
5.2.2	Campville Substation.....	5-50
6.	POTENTIAL ENVIRONMENTAL EFFECTS AND MITIGATION MEASURES	6-1
6.1	PROPOSED ROUTE: FROST BRIDGE SUBSTATION TO CAMPVILLE SUBSTATION	6-2
6.1.1	Topography, Geology, and Soils	6-2
6.1.2	Water Resources	6-5
6.1.3	Biological Resources	6-14
6.1.4	Land Use, Recreational/Scenic Resources, and Land-Use Plans.....	6-31
6.1.5	Transportation, Access, and Utility Crossings.....	6-35
6.1.6	Cultural (Archaeological and Historic) Resources	6-37
6.1.7	Air Quality	6-377
6.1.8	Noise	6-38
6.2	SUBSTATION MODIFICATIONS	6-40
6.2.1	Geology, Topography, and Soils	6-41
6.2.2	Water Resources	6-42
6.2.3	Flood Zones	6-42
6.2.4	Biological Resources	6-43
6.2.5	Land Use, Recreational / Scenic Resources, and Land-Use Plans.....	6-43
6.2.6	Transportation and Access.....	6-43
6.2.7	Archaeological and Historic (Cultural) Resources	6-44
6.2.8	Noise	6-44
7.	ELECTRIC AND MAGNETIC FIELDS	7-1
7.1	ELECTRIC AND MAGNETIC FIELDS FROM POWER LINES AND OTHER SOURCES	7-1
7.2	EMF REGULATIONS AND GUIDELINES IN CONNECTICUT.....	7-1
7.3	EMF MEASUREMENTS AND CALCULATIONS	7-1
7.4	COMPARISON OF EDGE OF ROW MAGNETIC FIELDS TO INTERNATIONAL GUIDELINES	7-6
8.	PROPOSED PROJECT SCHEDULE	8-1
9.	PERMITS, APPROVALS, AND CONSULTATIONS	9-1
9.1	AGENCY PERMITS AND APPROVALS REQUIRED FOR THE PROJECT.....	9-1
9.2	FEDERAL AND STATE AGENCY CONSULTATIONS.....	9-3
9.3	MUNICIPAL, PUBLIC, AND OTHER CONSULTATIONS	9-3
10.	SYSTEM ALTERNATIVES.....	10-1

10.1	NO ACTION ALTERNATIVE.....	10-1
10.2	TRANSMISSION ALTERNATIVES	10-1
	10.2.1 Process for Developing the NWCT Transmission Alternatives	10-2
	10.2.2 Transmission Alternatives Considered	10-2
	10.2.3 Comparison of the Transmission Alternatives.....	10-4
10.3	NON-TRANSMISSION ALTERNATIVES (NTA)	10-8
11.	TRANSMISSION LINE ROUTE / CONFIGURATION ALTERNATIVES.....	11-1
11.1.	ROUTING OBJECTIVES AND ALTERNATIVE ROUTE ANALYSIS PROCESS ..	11-1
	11.1.1 Routing Objectives	11-1
	11.1.2 Alternative Route Analysis Process: Overview and Summary.....	11-2
11.2	OVERHEAD TRANSMISSION LINE ROUTES: ALTERNATIVES ANALYSIS...	11-4
	11.2.1 Route Evaluation Criteria	11-4
	11.2.2 Alternative Overhead Line Routes Considered but Eliminated.....	11-6
11.3	UNDERGROUND TRANSMISSION LINE-ROUTE ALTERNATIVES.....	11-11
	11.3.1 Cable Technology Considerations and Route Evaluation Criteria	11-12
	11.3.2 Construction Considerations and Procedures	11-17
	11.3.3 Alternative Underground Line Routes Considered but Eliminated	11-17
11.4	JUSTIFICATION FOR THE SELECTION OF THE PROPOSED TRANSMISSION LINE ROUTE AND CONFIGURATION.....	11-31
12.	POTENTIAL TRANSMISSION LINE ROUTE AND CONFIGURATION VARIATIONS	12-1
12.1	ROUTE VARIATIONS: GENERAL	12-1
12.2	FROST BRIDGE SUBSTATION LINE EXIT UNDERGROUND / OVERHEAD ROUTE VARIATIONS.....	12-1
12.3	STRUCTURE CONFIGURATION VARIATIONS	12-4
13.	PROPOSED SUBSTATION MODIFICATIONS: ALTERNATIVES REVIEW	13-1
14.	GLOSSARY AND TERMS	14-1

SUPPORTING VOLUMES

VOLUME 2: WETLANDS AND WATERCOURSES REPORT

VOLUME 3: ENVIRONMENTAL

- EX 1: Inventory and Assessment of Vernal Pools
- EX 2: Inventory and Assessment of Breeding Birds
- EX 3: Agency Correspondence
- EX 4: Visual Resource Analysis
 - Appendix A: Proposed Line Route Map with Visual Sites
 - Appendix B: Photographs of Potential Visual Sites
 - Appendix C: Photo-Simulations
 - Appendix D: Representative Photographs of the Proposed Route: General Visual Setting from Public Road Crossings

VOLUME 4: PLANNING

- EX 1: ISO-NE, “Greater Hartford and Central Connecticut (GHCC) Area Transmission 2022 Needs Assessment,” May 2014, Redacted to secure Confidential Energy Infrastructure Information (CEII)
- EX 2: ISO-NE, “Greater Hartford and Central Connecticut (GHCC) Area Transmission 2022 Solutions Study,” February 2015, Redacted to secure Confidential Energy Infrastructure Information (CEII)
- EX 3: ISO-NE “Transmission Planning Technical Guide,” December 2014
- EX 4: London Economics “Analysis of the Feasibility and Practicality of Non-Transmission Alternatives (“NTAs”) to Transmission Solution in the Northwestern Connecticut Subarea,” July 2015

VOLUME 5: PROJECT DRAWINGS AND MAPPING

- EX 1: 400 Scale Maps
 - Appendix 1A: Overview of Route on USGS Map
 - Appendix 1B: Proposed Route Aerial Maps – 400 Scale
- EX 2: 100 Scale Maps
 - Appendix 2A: Overview of Route on USGS Map
 - Appendix 2B: Proposed Route Aerial Maps – 100 Scale
- EX 3: Substation Drawings
 - Appendix 3A: Proposed Frost Bridge Substation Modifications
 - Appendix 3B: Proposed Campville Substation Modifications
- EX 4: Proposed Route Cross Sections and Plan and Profile Drawings
 - Appendix 4A: Typical Cross Sections
 - Appendix 4B: Plan and Profile Drawings

VOLUME 6: BEST MANAGEMENT PRACTICES MANUAL: CONSTRUCTION AND MAINTENANCE ENVIRONMENTAL REQUIREMENTS FOR CONNECTICUT

Available in hard-copy upon request or at the following link:

http://www.transmission-nu.com/contractors/pdf/MA_BMP.pdf


Note: This page intentionally left blank.

EXECUTIVE SUMMARY

PROPOSED PROJECT PURPOSE AND LOCATION

The Connecticut Light and Power Company doing business as Eversource Energy (Eversource) proposes to construct a new 10.4-mile 115-kilovolt (kV) overhead electric transmission line between its Frost Bridge Substation in the Town of Watertown and its Campville Substation in the Town of Harwinton, to make related improvements to both substations, and to reconfigure a short (0.4-mile) segment of two existing 115-kV transmission lines that are supported on common structures. These proposed electric transmission system improvements, referred to collectively as the Frost Bridge to Campville 115-kV Project (Project), are required to bring the electric supply system in northwest Connecticut into compliance with applicable national and regional reliability standards and criteria by eliminating potential thermal overloads and voltage violations identified in studies conducted by Independent System Operator New England (ISO-NE), the independent regional system planning authority. Figure ES-1 illustrates the location of the proposed Project facilities.

Figure ES-1: Project Location Map



The Proposed Route for the new 115-kV transmission line, which would cross portions of four towns in Litchfield County (Watertown, Thomaston, Litchfield, and Harwinton), would be located entirely within Eversource's existing 250-400-foot-wide transmission line right-of-way (ROW), adjacent to other overhead transmission lines. The ROW has been devoted to utility use for approximately 90 years.

Both Frost Bridge and Campville substations are located on Eversource property. The proposed substation modifications, as required to connect the new 115-kV line to the existing transmission system, would be on these properties, which also have been dedicated to utility use since the 1920s and 1930s.

Similarly, the 0.4-mile segment of the two existing transmission lines that would be reconfigured extends across the Naugatuck River (which forms the border between Litchfield and Harwinton), within the same ROW as the new 115-kV transmission line. Along this segment, Eversource proposes to remove the two lattice steel structures that currently support both of the existing overhead 115-kV transmission lines (designated by Eversource as the 1191 and 1921 Lines) at the river crossing, and to relocate each of the transmission circuits onto new steel monopole structures. With the proposed reconfiguration, each of these existing transmission lines then will be supported on its own set of structures for the entire distance between Frost Bridge and Campville substations (in the case of the 1191 Line) and between Thomaston and Campville substations (in the case of the 1921 Line), thereby further enhancing the reliability of the transmission system.

PURPOSE OF THE MUNICIPAL CONSULTATION FILING

The proposed Project is subject to the regulations of the Connecticut Siting Council (Council) and other state regulatory agencies. In December 2015, Eversource plans to submit an *Application for a Certificate of Environmental Compatibility and Public Need (Application)* to the Council. Prior to the submission of such an application, the Council requires applicants to provide project information, in the form of a Municipal Consultation Filing (MCF), to the potentially affected municipalities.

The MCF is a key mechanism both for informing the public and municipal officials about a potential project and for soliciting comments about the project. To provide the public and municipal officials with currently-available information concerning this Project, the format of this MCF follows the anticipated format of the *Application* and includes 6 Volumes (5 of which are being provided in hard copy form), consisting of the planning studies, siting analyses, engineering evaluations, alternatives assessments, environmental investigations, and mapping completed to date concerning the proposed Project.

PROPOSED TRANSMISSION FACILITIES

New 115-kV Transmission Line. The proposed new 115-kV transmission line (designated by Eversource as the 1304 Line) would be located adjacent to existing Eversource overhead transmission lines, which presently occupy the ROW segments that extend between Frost Bridge and Campville substations.

The proposed line would be supported on steel monopole structures in either a delta or a vertical configuration. The existing ROW is sufficiently wide such that the new monopoles would be installed without affecting the existing transmission lines (i.e., without requiring the relocation or rebuilding of existing structures). The new monopole structures would be weathering steel, with typical structure heights between 80 and 90 feet above ground for delta configurations and between 95 and 105 feet above ground for vertical configuration structures, depending on terrain.

The length that the new line would traverse through each of the four municipalities along the existing Eversource ROW is as follows:

Town	ROW Characteristics	
	Length (Miles)	Width Range (Feet, Typical)
Watertown	4.7	250 - 400
Thomaston	2.6	250
Litchfield	1.8	250
Harwinton	1.3	250
Total	10.4	

Separation of Existing 115-kV Double Circuit. Within Eversource's existing 250-foot-wide ROW at the Naugatuck River crossing between the Towns of Litchfield and Harwinton, the two 155-foot-tall lattice steel towers would be removed and the 1191 and 1921 Lines would be placed on separate vertical steel monopoles, each of which would be approximately 155 feet tall.

Substation Modifications. To interconnect the new 115-kV transmission line to the transmission grid, modifications are required to both Frost Bridge and Campville substations. At Frost Bridge Substation, all of the proposed modifications will be accomplished within the developed portion of the existing station. However, at Campville Substation, the modifications will require the expansion of the developed portion of the substation by approximately 0.4 acre, involving an extension of the existing station fence to the east by approximately 90 feet.

CONSTRUCTION AND OPERATION / MAINTENANCE PROCEDURES

Eversource would construct, operate, and maintain the proposed transmission facilities in accordance with all regulatory approvals and its standard practices. Construction of the proposed facilities would be performed in several stages, some overlapping in time.

Transmission Line: The primary activities involved in the construction of the overhead transmission line would include the following:

- Survey to stake the vegetation clearing boundaries and proposed structure locations.
- Mark the boundaries of previously delineated wetland and watercourse areas, as well as areas to be avoided (e.g., sensitive cultural or environmental resource areas).
- Establish construction field office(s) and material staging sites (e.g., storage, staging and laydown areas) to support the construction effort. The preferred locations for such areas are typically in the vicinity of the ROW.
- Perform vegetation clearing along those portions of the ROW to be used for the construction of the transmission lines.
- Install erosion and sedimentation controls in accordance with best management practices.
- Construct new access roads (and/or improve existing roads) and work pads for structure and conductor installation.
- Construct foundations and erect/assemble new structures. (At the Naugatuck River, remove the existing lattice steel structures and replace with new monopoles.)
- Install conductors and shield wires.
- Restore disturbed sites.

After the installation of the new 115-kV transmission line, Eversource would manage the ROW in accordance with its established vegetation management program.

Substation Modifications: The modifications to the two existing substations would involve standard construction procedures (e.g., site preparation, implementation of erosion and sedimentation controls, installation of foundations and equipment, and site stabilization with crushed stone or equivalent). The operation and maintenance of the substation modifications would not substantially affect or alter existing practices at these stations.

ENVIRONMENTAL RESOURCES, POTENTIAL EFFECTS, AND MITIGATION MEASURES

Eversource conducted comprehensive research to compile existing baseline environmental data concerning the Project region, as well as field surveys to characterize the existing environmental

resources along the ROW. Environmental information for the Project was compiled, mapped, and described in accordance with the Council's *Application Guide for an Electric Transmission and Fuel Transmission Line Facility* (April 2010).

Along the proposed transmission line ROW and at the substations, field investigations were performed to identify and characterize site-specific natural resources (e.g., soils, topography, wetlands, watercourses, vegetative communities, vernal pools and amphibian breeding habitats, breeding bird habitat), cultural resources, and visual resources. As a result of this baseline research and field studies, the Proposed Route is characterized in terms of the following principal environmental conditions, land-use features, and natural resources, among others:

- Existing transmission line ROW, transmission line structures, access roads, and substations
- Locations of Eversource-owned properties
- Vegetative community types
- Areas of steep slopes and rock outcrops
- Land uses, including agricultural, residential, commercial, and industrial areas
- Municipal boundaries and zoning classifications
- Federal and state jurisdictional wetlands, watercourse, and other waterbodies
- Floodplain boundaries
- Public recreational, scenic, open space, and other protected areas, including the Mattatuck State Forest, Black Rock State Park, Northfield Brook Recreation Area, and Thomaston Dam recreational trails along the Naugatuck River, and other designated recreational trails
- Existing infrastructure, including roads and railroads

The environmental characteristics along the Project ROW and in the immediately surrounding region are also illustrated on the aerial-photography-based maps in Volume 5.

Using both the baseline environmental data and the plans for the development of the proposed Project, Eversource identified and analyzed the potential short- and long-term effects that the construction of the Project and operation of the resulting transmission facilities would have on the environment, ecology, and scenic, historic, and recreational values, and also identified possible measures for avoiding, minimizing, or mitigating adverse effects. The avoidance, minimization, and mitigation of adverse effects to environmental resources, land uses, and cultural resources were key considerations in the Project planning

process and will continue to be important during the finalization of Project design and the preparation of Development & Management (D&M) Plans.¹

Based on current Project engineering plans and analyses of the existing environmental data, the proposed Project would have localized and relatively minimal environmental effects. Specifically, the Project would:

- Result in minimal, short-term, and localized soil disturbance as a result of on-ROW construction activities and substation modifications.
- Have minor effects on wetlands and watercourses. Of the total 95 wetlands identified and 104 new structures proposed, only one structure would be located in a wetland. A total of 58 watercourses (including waterbodies) were identified; however, no structures would be located within watercourses or waterbodies and no construction access would be required across larger rivers or streams.
- Avoid the placement of new transmission structures within a Federal Emergency Management Area (FEMA) designated 100-year flood zone or floodway.
- Convert approximately 48.9 acres of forested habitat into shrub land (42.2 acres of forested upland and 6.7 acres of forested wetland).
- Be located near approximately 22 vernal pools.
- Use best management practices to minimize potential adverse effects on vernal pools and other sensitive resource areas.
- Result in incremental and generally localized visual effects associated with the installation of the new 115-kV overhead line along the existing ROW. The replacement of the double-circuit lattice steel structures at the Naugatuck River with steel monopoles could be viewed as a visual benefit.

In general, the proposed Project would minimize adverse environmental effects by collocating the new 115-kV transmission line along Eversource's existing ROW, adjacent to long-established overhead transmission lines and by developing the proposed substation modifications on property that is already designated for utility use. Further, Eversource has identified measures that can be effectively applied to mitigate these effects to the extent practical.

EMF ANALYSES

As required pursuant to the Council's 2014 Electric and Magnetic Fields (EMF) *Best Management Practices for the Construction of Electric Transmission Lines in Connecticut* (EMF BMP), Eversource

¹ The Project D&M Plan would include specifications for Project construction, including environmental mitigation measures. A D&M Plan is a pre-requisite condition of the Council's issuance of an approval to construct the Project.

calculated EMF along the Frost Bridge to Campville ROW associated with the existing transmission facilities, as well as the changes in EMF levels that can be expected once the new line is constructed and in-service. These calculations show that the addition of the new line will not increase either electric or magnetic fields at the edge of the ROW, and will decrease such levels in some locations, compared to existing conditions.

ALTERNATIVES CONSIDERED

The proposed Project is the result of a comprehensive evaluation process conducted by ISO-NE, Eversource, The United Illuminating Company, and others. This process began with a determination of the need for a solution to reliability issues in the northwest Connecticut region, then continued with the identification and analysis of alternative solutions for addressing the need, and concluded with the examination of specific alternative routes and route variations for the proposed transmission facilities. As a result of these analyses, the Proposed Route and proposed transmission line configurations were selected as the proposed Project.

The following types of alternatives were considered:

- **No Action Alternative.** Under this alternative, no action would be taken and the northwestern Connecticut electric transmission system would not be improved. The No Action Alternative was rejected because it would not resolve the identified regional electric reliability problems. Thus, the electric supply system in the region would not comply with national and regional reliability standards and criteria.
- **System Alternatives.** Following the evaluations of the need for the Project, transmission system alternatives that would potentially meet that need were identified and evaluated. The results of these analyses led to the selection of a 115-kV transmission solution that would connect Eversource's Frost Bridge and Campville substations. Although potential non-transmission system alternatives (e.g., generation, demand reduction) that could address the need served by the transmission solution were investigated, no practical non-transmission alternative was identified.
- **Overhead and Underground Transmission Line and Route Alternatives.** After a new 115-kV circuit between the Frost Bridge and Campville substations was selected as the preferred transmission system solution, Eversource identified and evaluated potential routes and configurations for the new line. As part of this process, Eversource evaluated both overhead and underground transmission line designs, with potential alignments along various existing ROWs and "greenfield" corridors. All of the route alternatives were evaluated against standard Eversource criteria and objectives for overhead and underground transmission lines. The Proposed Route within Eversource's existing ROW, using an overhead transmission line design, was determined to be the preferred alternative. This alternative does not require the acquisition of any additional property or ROW, represents the lowest cost solution, and would avoid or minimize environmental and social impacts.

- **Potential Variations to the Proposed Transmission Line Configuration and Route.** Because the proposed 115-kV line can be entirely accommodated within the existing ROW, only two potentially viable route variations were identified. These two route variations were identified during the alternatives analysis process and would involve different alignments and configurations to the portion of the Proposed Route exiting from the Frost Bridge Substation. Both route variations, which are situated entirely on Eversource property or on State road ROWs, would involve a short underground transmission cable component, located within or adjacent to the developed substation site. Eversource is in the process of conducting engineering evaluations of these potential route variations.

COST AND SCHEDULE

The estimated capital cost of the Project is approximately \$51 million. Project construction is anticipated to commence in the second half of 2017 with a scheduled In Service Date (ISD) of year end 2018.

1. DESCRIPTION OF THE PROPOSED PROJECT

1.1 PROJECT BACKGROUND

The Connecticut Light and Power Company doing business as Eversource Energy (Eversource) proposes to construct a new 10.4-mile 115-kilovolt (kV) overhead electric transmission line between its Frost Bridge Substation in the Town of Watertown and its Campville Substation in the Town of Harwinton, and to make related improvements to both substations. In addition, within the same right-of-way (ROW) as the proposed new 115-kV transmission line, Eversource proposes to reconfigure a short (0.4-mile) segment of two 115-kV circuits (i.e., the 1191 and 1921 Lines) that are currently supported by common transmission structures so that each circuit will be supported by its own set of structures for the entire distance between Frost Bridge and Campville substations (in the case of the 1191 Line) and between Thomaston and Campville substations (in the case of the 1921 Line). These proposed electric transmission system improvements, referred to collectively as the Frost Bridge to Campville 115-kV Project (Project), are required to bring the electric supply system in northwest Connecticut into compliance with applicable national and regional reliability standards and criteria by eliminating potential thermal overloads and voltage violations identified in studies conducted by Independent System Operator New England (ISO-NE), the regional system planning authority.

The proposed new 115-kV transmission line would cross portions of four towns in Litchfield County: Watertown, Thomaston, Litchfield, and Harwinton. The new line would be located entirely within Eversource's existing transmission line ROW. In addition, both Frost Bridge and Campville substations are located on Eversource property. The proposed modifications to these substations, as required to connect the new 115-kV line to the existing transmission system, would also be on Eversource property.

Figure 1-1 illustrates the general location of the proposed Project facilities; detailed maps of the Proposed Route and Project are provided in Volume 5.

The facilities proposed for the Project were identified as a result of system planning studies and alternatives analyses performed by ISO-NE. After these studies determined a need for a new 115-kV transmission line in northwest Connecticut to improve system reliability², Eversource developed and analyzed potential alternatives before identifying the Proposed Route and a proposed overhead configuration for the new transmission line.³ The primary objectives of this routing and configuration selection process were to identify Project facilities that could be constructed and operated to:

- Comply with state and federal statutory requirements, regulations, and siting policies
- Minimize adverse effects to natural and human resources
- Achieve a reliable, operable, and cost-effective solution

Based on these objectives, the principal factors considered in selecting the Proposed Route and overhead transmission line structure configurations were:

- Availability of existing ROWs within which the proposed facilities could be developed without the need for additional easement acquisition
- Avoidance or minimization of effects on environmental resources
- Avoidance or minimization of effects on significant cultural resources (archaeological and historical)
- Avoidance or minimization of effects on designated scenic resources
- Consideration of visual effects
- Constructability/engineering considerations
- Cost
- Maintenance of public health and safety
- Minimization of the need to acquire property
- Minimization of conflicts with developed areas

The Proposed Route and overhead transmission line configurations best meet these objectives while representing Eversource's preferred solution for providing reliable, cost-effective, and environmentally sound improvements to the regional electric transmission system.

² In addition to eliminating reliability criteria violations, the proposed new 115-kV line also would have better voltage performance, would not adversely affect existing transfer limits; and would be cost-effective, compared to other system alternatives initially considered. Refer to the discussion of Project Need in Section 2, as well as to the systems alternatives analyses in Section 11.

³ The alternatives analyses conducted for the Project are detailed in Sections 10, 11, and 12.

1.2 PROPOSED PROJECT FACILITIES

1.2.1 New 115-kV Transmission Line

The proposed new 115-kV transmission line between Frost Bridge Substation and Campville Substation (referred to as the 1304 Line) would be constructed overhead⁴, entirely within an existing Eversource ROW that ranges from 250 to 400 feet in width. No additional easements would be required for the Project, with the possible exception of off-ROW access road easements. The new line would be aligned within the ROW adjacent to Eversource's existing 115-kV overhead transmission lines, and, along a portion of the ROW in Watertown, an existing 345-kV overhead transmission line.

The ROW in which the new 115-kV transmission line would be located has been dedicated to utility use for almost 90 years. The existing Eversource transmission lines that presently occupy the Project ROW include:

- Frost Bridge Substation to Purgatory Junction (Town of Watertown): Line 1238 (115 kV), Line 1191 (115 kV), and Line 352 (345 kV);
- Purgatory Junction (Town of Watertown) to Walnut Hill Junction (Town of Thomaston): Line 1191;
- Walnut Hill Junction (Town of Thomaston) to Naugatuck River crossing (Towns of Litchfield and Harwinton): Line 1191 and Line 1921 (115 kV); and
- Naugatuck River crossing (Towns of Litchfield and Harwinton) to Campville Substation (Town of Harwinton): Line 1191 and Line 1921.

These existing overhead transmission lines are supported on various structure types, including delta vertical steel, delta wood laminate, and delta wood monopoles, wood H-frames, and lattice steel towers.

Table 1-1 summarizes the length of the proposed 115-kV transmission line in each of the four towns along the Proposed Route, and the typical width of the existing Eversource ROW within which the proposed line would be located. The table also provides a key to the location of the Proposed Route as depicted on the aerial photograph mapsheets in Volume 5, and identifies the Cross-Section (XS) drawings

⁴ Note: Eversource is currently evaluating the alignment of the new 115-kV line in an underground configuration for the line exit at Frost Bridge Substation. This underground line segment, which is currently being evaluated by Project engineers, would be located entirely within the developed portion of the substation or on adjacent Eversource property or on State road ROWs. The underground configuration would provide a more direct exit for the new line from the substation and would avoid the need for the installation of several new overhead transmission line structures outside of and east of the substation fence line (i.e., closer to the Naugatuck River). This potential underground configuration is discussed in Section 12, as a route variation.

in Section 3, Appendix 3A in this Volume and in Volume 5 that illustrate the proposed alignment and configuration of the new overhead line within each ROW segment.

Table 1-1: Proposed 115-kV Transmission Line ROW Segments: Miles, Width, Cross-Sections, and Configuration (By Town and Volume 5, 400 Scale Mapsheet No. and Cross-Section Reference)

Town	ROW Characteristics		Volume 5, 400 Scale Mapsheet No.	Cross-Section (refer to Section 3, Volume 1, and Volume5)
	Length (Miles)	Width Range (Feet, Typical)		
Watertown	4.7	250 - 400	1 - 4	XS-1, XS-2, XS-3
Thomaston	2.6	250	4-7	XS-3, XS-4
Litchfield	1.8	250	7-8	XS-4, XS-5
Harwinton	1.3	250	8-9	XS-5, XS-6
Total	10.4			

Along most of the Proposed Route, the new overhead 115-kV transmission line would be supported on direct embedded monopole structures in a delta or vertical configuration. In certain locations, such as for angle or deadend structures, monopole structures in a vertical configuration on drilled shaft foundations will be used. The existing ROW is sufficiently wide such that the new 115-kV monopoles would be installed without affecting the existing transmission lines (i.e., without requiring the relocation or rebuilding of existing structures).

Between Frost Bridge Substation and Purgatory Hill Junction, the new 115-kV line structures would be aligned near the middle of the existing ROW, between the existing 345-kV (Line 352) and 115-kV (Line 1191) lines. Along the remainder of the Proposed Route, the new 115-kV line structures would be aligned east of an existing 115-kV line (i.e., east of the 1191 Line from Purgatory Hill Junction to Walnut Hill Junction, and east of the 1921 Line from Walnut Hill Junction to Campville Substation).

The new monopole structures would be weathering steel, with typical structure heights between 80 and 90 feet above ground for delta configuration and between 95 and 105 feet above ground for vertical configuration, depending on terrain. Eversource's preference for structure material is steel, due to superior maintenance and constructability benefits.

1.2.2 Double Circuit Separation

Within Eversource's existing 250-foot-wide ROW at the Naugatuck River crossing, two lattice steel towers (one on each side of the river) support both the existing 115-kV 1191 and 1921 Lines. As part of the Project, the two 155-foot-tall lattice steel towers would be removed and the 1191 and 1921 Lines would be placed on separate vertical monopoles, each of which would typically be approximately 155 feet tall. The 1191 Line (between the Frost Bridge and Campville substations) and the 1921 Line (between the Thomaston and Campville substations) would then each be supported on its own set of structures for its entire length.

1.2.3 Substation Modifications

To interconnect the new 115-kV transmission line to the transmission system, Eversource proposes to modify both Frost Bridge Substation and Campville Substation, as described below.

Frost Bridge Substation

Frost Bridge Substation, which is located in the southeastern portion of the Town of Watertown, occupies approximately 5.7 acres of a 128.5-acre property owned by Eversource. The substation is situated on the central-western portion of the parcel, east of and adjacent to Frost Bridge Road. The Eversource parcel is bordered by Frost Bridge Road and State Route 8 to the west; an inactive railroad and the Naugatuck River to the east; State Route 262 to the north; and open land and transmission line infrastructure to the south.

The Frost Bridge Substation property was acquired for utility use in the late 1920s and the substation has been in operation almost 90 years. Seven 115-kV and two 345-kV transmission lines presently connect to the Frost Bridge Substation.

To interconnect the new 115-kV line to Frost Bridge Substation, Eversource proposes the following modifications to the substation, which will all be located within the existing fenced area:

- Expand the existing one-position 115-kV bay to a two-position bay. The proposed 115-kV line would use an existing, vacant 115-kV transmission line-terminal position. Although a 115-kV line terminal structure exists, there is currently no transmission line exiting the substation in this position. The substation currently has four 115-kV bays, with a total of seven 115-kV lines exiting the substation.
- Install one new 115-kV circuit breaker and connect the new 115-kV transmission line to the existing vacant terminal structure position.

- Install one motor-operated disconnect switch, one ground switch, three lightning arrestors, three capacitor-coupled voltage transformers (CCVTs), and one wave trap. Appropriate junction boxes and yard control boxes would be installed and connected to a pre-existing conduit raceway for control cable.

Campville Substation

Eversource's Campville Substation is located in the southwestern portion of the Town of Harwinton and currently occupies approximately 1.65 acres of a 42.33-acre Eversource property. The Eversource property is bordered by Wildcat Hill Road on the west, Hayden Road on the south, and private property on the north and east. The substation property was acquired for utility use in 1926, with additional lands acquired in 1928 and 1936. The Campville Substation has been in operation for close to 90 years.

To accommodate modifications required to interconnect the new 115-kV transmission line, Eversource proposes to expand the substation's fenced area by approximately 0.4 acre. These modifications would require an extension of the substation fence by approximately 90 feet to the east to enclose the expansion area.

At Campville Substation, Eversource proposes the following Project modifications:

- Expand the existing ring bus to accommodate five new 115-kV breakers and one new transmission line-terminal position. The expansion would require the demolition of one existing breaker and the connection of the new equipment in its place. A new transmission line terminal structure would be required to connect the new 115-kV transmission line from Frost Bridge to the Campville Substation line position. In addition, another existing breaker would be shifted slightly to allow the installation of one new 115-kV circuit breaker adjacent to the relocated breaker.
- Install the new 115-kV line terminal structure, which would be approximately 60 feet tall. Install one motor operated disconnect switch, one ground switch, three lightning arrestors, three CCVTs, and one wave trap. Appropriate junction boxes and yard control boxes would be installed and connected to a new conduit raceway for control cable.
- Install four 115-kV disconnect switches, approximately 60 feet of aluminum tube conductor, six 115-kV breakers, one 60-foot-tall lightning mast, and steel support structures and foundations for all new equipment.
- Extend the existing substation ground grid, grading as necessary to manage stormwater flows, and install an extension of the substation fence.
- Install a new substation enclosure to house additional protection and control equipment. Augment the existing protection and control equipment in the existing substation enclosure to accommodate new substation equipment.

2. PROJECT BACKGROUND AND NEED

This section explains how the Project was developed to upgrade the transmission system serving northwestern Connecticut so that it would comply with applicable mandatory reliability standards. The section first identifies the applicable reliability standards and reviews how they evolved as the North American electric supply system was developed, then summarizes the Greater Hartford Central Connecticut (GHCC) studies that identified the need for a group of projects to resolve reliability problems throughout four contiguous study areas in Connecticut, including in northwestern Connecticut; and finally describes how the improvements proposed in this MCF will address reliability needs in northwestern Connecticut.

2.1 THE SYSTEM PLANNING PROCESS AND RELIABILITY CRITERIA

Maintaining continuity of service to customers has been the primary objective of electric utilities in North America since their very beginning. As electric supply systems have grown and become more complex, more interconnected, and increasingly critical to human welfare and a healthy economy, standards for ensuring continuity of service have become mandatory and more stringent, requiring the use of increasingly sophisticated analytical tools. Today, engineers using detailed and highly sophisticated and accurate computer models are able to evaluate the reliability of the existing interconnected transmission system and to plan modifications or additions needed to comply with those standards by simulating the performance of the existing system, as well as the system with proposed potential improvements to it. The following sections review the development of reliability planning standards and their current application.

2.1.1 A Brief History of Electric Reliability Planning

During the first half of the 20th Century, individual power systems each developed and applied their own planning criteria. By mid-century, however, with the dramatic growth of synchronous interconnections and the increasing use of the electric transmission system to move power over longer distances, utilities began to coordinate their planning activities.

When the Northeast Blackout of 1965 occurred, it became obvious that a more closely coordinated strategy was necessary. Shortly after the blackout, the electric utilities across North America formed regional reliability councils to promote and improve the reliability of the interconnected bulk power system. In northeastern North America, electric utilities formed the Northeast Power Coordinating

Council (NPCC) consisting of the six New England states, New York State, and the Canadian provinces of Ontario, Québec, New Brunswick, and Nova Scotia. The U.S. systems of the NPCC also formed two new power pools: the New England Power Pool, which eventually became ISO-NE, and the New York Power Pool, which evolved into the New York Independent System Operator (NYISO). Each regional reliability council established its own reliability criteria. Each also developed procedures for assessing conformance with these criteria. With time, individual electric utilities and power pools often developed their own more detailed and stringent planning and operating procedures to ensure the reliability of their portions of the interconnected bulk-power electric system; however, those procedures had to continue to comply with the broader regional criteria requirements.

In 1968, the U.S. regional reliability councils formed the National Electric Reliability Council (NERC) to coordinate their activities nationally and developed voluntary reliability guidelines for their collective systems. NERC has evolved over the years. In 1981, its name was changed to the North American Electric Reliability Council, to reflect the addition of Canadian members. But the most dramatic changes occurred in the wake of the August 14, 2003 Midwest/Middle Atlantic blackout. The Energy Policy Act of 2005 (EPAct) directed the Federal Energy Regulatory Commission (FERC) to establish an Electric Reliability Organization (ERO), whose major role would be to develop and enforce mandatory reliability standards for planning and operations. After a period of study, FERC designated NERC as the ERO, and its name was changed to the North American Electric Reliability Corporation, Inc.

2.1.2 Modern Reliability Standards and Criteria

The NERC standards today are subject to approval by FERC and are much more specific than they were in the past. Further, transmission owners' compliance is mandatory under federal law. Violations are punishable by fines as high as \$1 million per day per violation. Regional reliability councils may have their own criteria, but these must conform to all NERC requirements – planning, system design and operations. Similarly, whereas an ISO and individual electric systems may also have their own criteria and procedures, but they all must conform to both NERC standards and the regional criteria. Thus, in conducting planning studies, all transmission owners in New England are required to comply with NERC standards, NPCC criteria, and ISO-NE planning procedures. Copies of particularly relevant standards, criteria and procedures are included in Volume 4.

2.1.3 Simulating Contingencies

A key element of the reliability standards is the consideration of “contingency” events wherein generation and/or transmission facilities are assumed to suddenly and unexpectedly cease operating (trip out of service). Such contingency events could be caused by weather; by generator, transmission line, or substation equipment failures; by contingencies on other transmission systems connected to the New England transmission system; or by some combination of these factors.

NERC, NPCC, and ISO-NE standards, criteria and procedures specify the contingencies that must be considered in planning studies. The NPCC criteria and ISO-NE procedures must be consistent with all NERC standards. Thus, NPCC criteria may be more stringent than, but must as a minimum conform to, the NERC standards. Likewise, ISO-NE procedures may be even more stringent than, but must as a minimum conform to the NPCC criteria and NERC standards.

When a generating unit or a transmission line suddenly and unexpectedly trips out of service, power flows increase instantaneously on the transmission lines that remain in-service. (This is in accordance with the laws of physics as applied to electric power systems.) Consequently, an area’s transmission system must be designed not only to transmit and/or import power required to offset anticipated generation deficits with all transmission facilities in service, but also must be capable of transmitting or importing power reliably following specific contingencies as required by the mandatory national standards and regional criteria. Otherwise, post-contingency power flows could exceed emergency transmission element ratings and/or result in low voltage conditions (below prescribed minimum levels) on portions of the electric system.

Because each transmission line must be able to carry the additional current that would instantaneously flow in the event of the sudden loss of a generating unit, transmission line, or other system element, normal power flows on transmission lines will typically be well below the thermal ratings of the line.

Contingencies, as specified by NERC, NPCC, and ISO-NE standards and criteria, are usually characterized as loss of a single system element – that is, a generator, transmission line, bus section, etc. Sometimes, however, a single contingency can result in the loss of two transmission elements, such as where two electric circuits share a common set of towers, forming a “double-circuit tower” (DCT) transmission line. Both of these types of events are referred to as “N-1” contingency events. Another type of contingency involves the occurrence of two separate and unrelated outages within a short period of time (30 minutes per NPCC criteria and ISO-NE procedures). These are referred to as “N-1-1” events.

When such a contingency event is simulated, reliability standards and criteria require an assumption that there will be sufficient time between contingency events for the system operator to implement specific “manual system adjustments” to the system before the second contingency event occurs.

Thus, the reliability standards and criteria applicable for the New England area (the Applicable Reliability Standards) require that in a planning study, after performing each of the required N-1 contingency analyses with all transmission facilities assumed to be initially in service, planning engineers test the ability of the system to be operated reliably with a key facility out of service. To do this, they apply a contingency; measure and document system performance prior to readjusting or reconfiguring the system (with “manual system adjustments”); then apply a second (unrelated) contingency; and then study the electric system’s response. The criteria governing planning studies for the New England control area provide that, to make the system ready for the next contingency, only those manual adjustments that can be implemented within 30 minutes may be considered. These include adjusting the output of generation units, activating “quick start” generating reserves, and changing phase angle regulator taps.

To evaluate compliance with Applicable Reliability Standards, the specified contingencies are simulated on computer models developed to represent the power grid with expected future modifications and additions, operating with projected future loads. If the simulations show that currents on a transmission element will exceed its thermal ratings (a thermal overload), or that system voltages cannot be maintained within acceptable limits following one or more of the contingencies (a voltage violation), appropriate solutions must be developed and implemented in order to maintain the reliability of the electric grid.

Because years are required for the design, siting, engineering, and construction of major transmission improvements once they are recognized to be needed, transmission reliability studies are conducted by modeling expected future system conditions, including expected future generation resources, other planned transmission improvements, and projected future loads. A study year in the future is selected, and conditions expected for that year are modeled. ISO-NE uses a 10-year planning horizon; therefore, transmission reliability analyses consider system conditions expected 10 years in the future from the date a study is commenced are considered.

Modelling of the specific contingencies prescribed by the NERC standards for power-flow analyses identifies improvements that will protect the transmission system against the actual occurrence of those design contingencies. That is, should one of the specified contingency events occur, the remainder of the system would survive without a transmission element overload, an unacceptably low voltage condition,

instability, cascading outages, system separation, or loss of firm customer load⁵. However, modeling of these specific contingencies does more than demonstrate how the power grid would perform should the specific events being modeled occur. The simulations also represent stresses that could result from multiple other potential events, some of which may not even be foreseeable at present. The objective of the simulations is not just to ensure that the system will withstand the specific contingencies defined by the standards, under the specific conditions modeled, but also to document that the system will be strong and robust enough to survive a wide range of potential events that could impose comparable stresses.

2.1.4 Generation Dispatches in Power-Flow Simulations

In accordance with the reliability criteria and procedures of NPCC and ISO-NE, the regional transmission power grid must be designed for reliable operation during stressed system conditions. Stressed conditions are simulated, in part, by developing generation dispatches. First, a base case that reflects the planners' expectation of likely generation resource availability in the study period is constructed. Resources may be assumed to be unavailable in the base case based on operating experience, announced retirement, or other reasons. Then, to simulate critical system conditions, at least the largest and most critical generating unit or station in an area is assumed to be out of service (OOS), and usually two generation resources are assumed as OOS. Generally, two generation resources are considered OOS in the study area. Assuming generators are out of service in a base case addresses issues such as the following:

- Higher forced outage rates for generators than for other system elements
- Higher generator outages and limitations during stressed operating conditions such as a heat wave or a cold snap
- Past experience with simultaneous unplanned outages of multiple generators
- High cost of Reliability Must Run Generation
- Generator maintenance requirements
- Unanticipated generator retirements
- Fuel shortages

As with modelling contingencies, modeling existing generators as OOS in planning studies is not conducted simply to ensure that the system will be able to do without those generators in specific system conditions. This technique also tests the performance of the system under stresses that it may be required to withstand, whether from the unavailability of those specific generators or for other reasons.

⁵ Firm customer load is also defined as uninterruptable service and is intended to be available at all times.

Generating units assumed to be unavailable or otherwise OOS should not be confused with the loss of a generating unit as a contingency, as described earlier. The former is a base case assumption – the system as represented before any contingency is applied. The latter is one of the many contingencies specified by the NERC, NPCC, and ISO-NE standards, criteria and procedures, which the pre-contingency system must be able to withstand without experiencing a transmission line or substation element overload, a low voltage condition, instability, cascading outages, system separation, or loss of firm customer load.

2.1.5. Coordinating Ongoing Studies

At any point in time there are numerous studies of the New England transmission system underway. The New England planning process requires study teams to communicate with other study teams to ascertain if the different teams have identified issues that may be addressed, in whole or in part, by a common solution, or if changes to the transmission system are being proposed that might impact their study. In order to ensure that needed improvements to the system will be identified and designed efficiently and cost-effectively, studies of area needs are sometimes combined and/or split apart as they proceed. As discussed in Section 2.2, development of the Project was done in coordination with the development of several other projects for the GHCC areas, as part of the GHCC studies; and as discussed in Section 2.2.3, the GHCC studies as a whole were conducted in coordination with studies of the Southwest Connecticut (SWCT) system needs.


2.2 DEVELOPMENT OF THE PROJECT

The Project proposed is the product of more than nine years of planning studies. In 2005, ISO-NE identified potential future criteria violations on the 115-kV system in the Greater Hartford area in the course of early studies that ultimately resulted in the New England East-West Solution (NEEWS) Plan, a comprehensive set of 345-kV improvements to the Southern New England transmission system in Connecticut, Rhode Island, and Massachusetts. Initially, these 115-kV problems were considered as part of the NEEWS studies. However, in early 2010, ISO-NE removed 115-kV issues from the scope of the NEEWS studies and initiated the Greater Hartford Area Reliability Study. The Northwest Connecticut (NWCT) sub-area was initially treated as part of the Greater Hartford area for the purpose of this study. In early 2011, the geographical scope of the Greater Hartford Area Study area was expanded and the study was re-named to the Greater Hartford and Central Connecticut (GHCC) Area Study. In this expanded scope, the NWCT sub-area was considered separately from the Greater Hartford sub-area, and the study was combined with other ongoing studies into an assessment of load serving problems in four contiguous sub-areas:

- Greater Hartford
- Manchester – Barbour Hill
- Middletown
- Northwestern Connecticut

To conduct this study, ISO-NE formed a working group consisting of transmission planners from ISO-NE, from Northeast Utilities Service Company (now Eversource Energy Service Company), and from The United Illuminating Company. The combined study area is illustrated in Figure 2-1.

FIGURE 2-1: GREATER HARTFORD CENTRAL CONNECTICUT STUDY AREA



In addition, an ongoing reassessment of the need for the Central Connecticut Reliability Project (CCRP), one of the four NEEWS 345-kV projects, was folded into the combined study. Periodically, the Working Group reviewed its methods, assumptions, and results with the ISO-NE Planning Advisory Committee (PAC).⁶

The GHCC studies proceeded to consider potential interdependencies in the load serving needs and potential solutions for the four sub-areas and ultimately determined that the solutions for the different sub-areas could be analyzed independently of one another, because the needs in each were largely driven by criteria violations following the loss of critical 115-kV sources into each sub-area. After many presentations to the PAC, ISO-NE published a final Needs Assessment in May, 2014 (the “*GHCC Needs Report*”)⁷. Because the study scope and assumptions were finally determined in 2012, the study considered system needs in the study year of 2022, consistent with ISO-NE’s 10-year planning horizon. After further presentations to the PAC, in early 2015 ISO-NE published a report identifying preferred solutions for the needs of the entire Greater Hartford and Central Connecticut study area, including the improvements in the NWCT sub-area proposed in this filing (the *GHCC Solutions Report*)⁸. After further detailed studies and review, and a positive recommendation by its Reliability Committee, ISO-NE issued a technical approval of the preferred GHCC solutions, including the NWCT improvements proposed in this filing, on April 16, 2015.

2.2.1 The Northwest Connecticut Sub-area

The NWCT electrical sub-area is the portion of the state bounded by the Massachusetts and New York state borders, and roughly by Route 8 to the east and Route 84 to the south. It is bordered on the south by the SWCT sub-area. Specifically, NWCT includes the towns of Barkhamsted, Bethlehem, Bristol, Canaan, Canton, Colebrook, Cornwall, Goshen, Hartland, Harwinton, Kent, Litchfield, Morris, New

⁶ The ISO-NE PAC is an advisory committee open to all parties interested in regional system planning activities in New England. ISO-NE is required by its FERC-approved tariff to conduct an open and transparent planning process. Pursuant to this requirement, ISO-NE presents to the PAC the scope of work, assumptions, and draft results for its annual Regional System Plan and for supporting studies, including Needs Assessments and Solution Studies, and considers the comments of the PAC members in developing its final plans and recommendations.

⁷ ISO New England, *Greater Hartford and Central Connecticut (GHCC) Area Transmission 2022 Needs Assessment* (May, 2014). A copy of this document, redacted to delete Critical Energy Infrastructure Information (CEII) that Eversource is required to keep confidential, is provided as part of Volume 4 of this MCF. A complete copy will be filed with the Connecticut Siting Council pursuant to its CEII filing procedure after Eversource files its application for the GHRP, and will be made available to qualified participants in the proceeding.

⁸ ISO New England, *Greater Hartford and Central Connecticut (GHCC) Area Transmission 2022 Solutions Study*, February 2015. A copy of this document, redacted to delete Critical Energy Infrastructure Information (CEII) that Eversource is required to keep confidential, is provided as part of Volume 4 of this MCF. A complete copy will be filed with the Connecticut Siting Council pursuant to its CEII filing procedure after Eversource files its application for the GHRP.


Hartford, Norfolk, North Canaan, Plymouth, Salisbury, Sharon, Simsbury, Thomaston, Torrington, Warren, Washington, and Winchester. (However, the Frost Bridge Substation in Watertown is electrically within the SWCT sub-area).

The NWCT sub-area net load for 2022 after demand resources are subtracted is about approximately 509 MW. The area has one generator at Forestville, which is classified as a regular unit and a hydro station (Falls Village). The sub-area also has two fast start generators in the City of Torrington at Franklin Drive and Torrington Terminal. NWCT is a net importer of energy and relies on the surrounding areas to serve local load. The major 115-kV lines that feed this sub-area are:

- Three 115-kV lines from the Southington Substation (1810 Line and 1800 Line)
 - 1800: Southington Substation (in Southington) to Forestville Substation (in Bristol)
 - 1810: Southington Substation to Chippen Hill Substation (in Bristol) and to the Bristol Substation
- A 115- kV line from North Bloomfield (1256 Line)
 - 1256: North Bloomfield Substation (in Bloomfield) to Northeast Simsbury Substation (in Simsbury)
- A 115-kV line from Frost Bridge Substation
 - 1191: Frost Bridge Substation in (in Watertown) to Campville Substation (in Harwinton)
- A 69-kV line from New York (690 Line)
 - 690: Smithfield Substation (in Smithfield, NY) to Salisbury Substation (in Salisbury)

Figure 2-2 is a geographic map of the sub-area, which shows the existing transmission facilities within the sub-area and, in some cases, line terminations outside of the sub-area.

FIGURE 2-2: NORTHWEST CONNECTICUT SUB-AREA



2.2.2 The Need for Transmission Improvements in NWCT

The GHCC studies showed that there were criteria violations in the NWCT “load pocket.” A load pocket is an area that has insufficient generation and/or transmission to serve its load. The electric system in the NWCT load pocket is subject to overloads when the system attempts to serve peak load under many contingent conditions.

2.2.2.1 Power-Flow Modeling Assumptions

The assumptions built into the power-flow modeling are set forth in detail in the *GHCC Needs Report*. In summary, the power flow study cases were derived from the ISO-NE model representing the New

England electric system, with selected upgrades to reflect relevant system conditions in 2022. All transmission projects with ISO-NE Proposed Plan Application approvals as of the April 2011 Regional System Plan Project listing were included in the base case. These projects included three NEEWS projects - the Greater Springfield Reliability Project (GSRP), the Rhode Island Reliability Project (RIRP) and the Interstate Reliability Project (Interstate). The CCRP was not included in the case, because the need for it was being reassessed as part of the study. New projects in Connecticut that were relevant to the study area were added to the base case as of the October 2013 project listing.

Both existing generation plants and new projects expected to be in-service during the study years, because they had accepted a Forward Capacity Market (FCM) Capacity Supply Obligation, were included in the study base case. All existing and proposed units that accepted a supply obligation in ISO-NE's Forward Capacity Auction #7 (FCA 7) were included. FCA 7 was held in February, 2013, and resulted in the purchase of resources to meet forecasted demand in 2016 – 2017. Certain generation units that were expected to retire imminently (and which have since retired) were assumed to be out of service. [Units assumed OOS were Bridgeport Harbor 2, AES Thames, Norwalk 1, 2 and 10.] The planned Towantic Generating Station in the Town of Oxford, Connecticut was not included in the study because it was not entered in FCA 7.

In accordance with ISO-NE planning procedures, the modeled load was based on the 90/10 weather forecast for 2022 in ISO's 2013 Capacity, Energy, Loads, and Transmission (CELT) load forecast. The forecast 2022 summer peak 90/10 was 34,105 MW. This load, adjusted to take system losses into account, was distributed across New England based on 2013 load distribution data. The forecast Connecticut load was 8,825 MW. Area loads were then adjusted downwards to reflect the effect of passive and active demand response measures committed in FCA 7 and predicted future energy efficiency measures that were expected to be implemented by 2022. Transfers of power into and out New England were modeled in accordance with applicable reliability criteria and standard practice. Finally, generator dispatch scenarios in each sub-area under study were constructed. In this set of studies, 22 dispatches were set up for the four study areas and for the assessment of the need to transfer power across from east to west. The dispatches were set up by taking out either one or two critical units in each sub-area studied. Four dispatches were designed for testing the NWCT sub-area: one set of cases assumed one area unit to be OOS and the other assumed two units to be OOS. For each case, two dispatches were created based on the dispatch of different fast start units within the area.

ISO-NE planning practice requires an assumption that approximately 20% of fast start generation will be OOS. Accordingly, one of the two fast start units was assumed OOS. In accordance with ISO-NE Planning Procedure #3, the output of generation in the study area and its vicinity was reduced following a first contingency if the re-dispatch would position the system so that a second contingency would not result in a violation.

2.2.2.2 Power-Flow Modeling Results – Thermal and Voltage Criteria Violations

Many thermal criteria violations were found in the GHCC study area for N-1 and N-1-1 contingency events. The detailed results are provided in the *GHCC Needs Analysis*. The NWCT sub-area had three transmission elements with N-1 thermal violations and five PTF⁹ buses with N-1 low-voltage violations. Under N-1-1 conditions, there were ten elements with thermal violations and 12 PTF buses with low voltage violations. Two 115-kV non-PTF buses had N-1-1 voltage violations. There were no N-0 thermal violations, but one 69-kV non-PTF bus had an N-0 base case voltage violation. The worst-case violations observed were for the loss of two or more import paths into the NWCT sub-area. Although the study year modelled in the *Needs Assessment Report* was 2022, the study showed that the improvements required to meet the identified needs should be constructed as soon as possible. ISO-NE calculates a “year of need” for system improvements by estimating when the “critical load level” (CLL) for which improvements are needed will be reached. The CLL is the demand level at which criteria violations begin to occur. Above this load level, the system needs to be expanded to continue to reliably support the demand. The *2012 Needs Assessment Report* found that the year of need for the NWCT sub-area improvements was 2013, because the Connecticut net load forecast for 2013 was 7,776 MW, whereas the modeled thermal overloads and low voltages occurred at load levels that were lower than 7,776 MW. Thermal violations began to occur at a 4,225 MW net load and low voltage violations began to occur at a 5,694 MW net load.

2.3 THE PROPOSED SOLUTION FOR THE NORTHWEST CONNECTICUT SUB-AREA NEEDS

The *GHCC Solutions Report* identified preferred solutions for the load serving problems documented in the *GHCC Needs Report* in each of the four load-serving sub-areas. Some of the solution elements were minor system improvements that have been or are being implemented independently of this application.

⁹ “PTF” stands for “Pool Transmission Facilities,” which are transmission facilities under the authority of ISO-NE. Generally, they are facilities that operate at or above 69 kV and are connected to other transmission lines or systems. The construction of new PTF facilities is generally funded through the ISO on a load ratio share among its member utilities.

The major elements of the solution, together with other improvements that are closely tied to them, are described in this document.

2.3.1 The Frost Bridge – Campville Line and Its Associated Terminal Equipment Improvements

The major element of the solution recommended for the NWCT sub-area was the addition of a new 115-kV overhead line from Frost Bridge Substation to Campville Substation, which also required the installation of associated terminal equipment. Since the worst thermal and voltage violations were observed for the loss of two sources that feed the NWCT load pocket, a new source into the area was needed. The preferred solution is to build this new 115-kV line, thereby bringing in a new source from a substation just outside the load pocket to the closest substation within the load pocket. See Figure 2-2. The addition of this new line into the sub-area both provides an additional system element to share the load that is automatically redistributed upon the failure of other system elements, and provides a source to help maintain continuity of supply to the load from external sources in such an event. With the new 115-kV line in place and with the use of re-dispatch after the first contingency, the flows on most system elements in the sub-area were reduced sufficiently so that they did not overload in the modeled N-1-1 contingencies. The terminal equipment associated with the installation of the new line will include the addition of five new circuit breakers at the Campville Substation, including two pairs in series, in order to eliminate problematic stuck breaker contingencies.

2.3.2 Separation of the 1191 and 1921 DCT

An existing 115-kV line (the 1191 Line) extends along the entire ROW between the Frost Bridge and Campville substations. Another 115-kV Line (the 1921 Line) extends from the Thomaston Substation to Campville Substation. At Walnut Hill Junction (approximately 3.9 miles south of Campville Substation), the 1921 Line enters the Frost Bridge to Campville ROW. From Walnut Hill Junction to the Campville Substation, the 1921 Line is located east of the 1191 Line. Except for a 0.4-mile segment, the two 115-kV lines are supported on separate sets of structures.

However, along the 0.4-mile segment of ROW at the Naugatuck River crossing (which forms the border between the towns of Litchfield and Harwinton), these two 115-kV lines are both supported on a single set of lattice steel structures (one on each side of the river crossing), thus comprising a double-circuit tower (DCT) line. The loss of both lines must therefore be modeled as a single contingency. Modeling of the existing system with the addition of the proposed new Frost Bridge to Campville line shows that, even with the new 115-kV line, certain design contingencies that include the loss of both the 1191 and 1921

lines will cause voltage violations on several area buses. Separation of the 1191/1921 DCT segment, which will result in each line being supported by its own set of structures for its entire length, together with the addition of a circuit breaker at the Campville Substation, eliminates these potential overloads. With the addition of the circuit breaker, each of the former DCT lines will be served by its own breaker. If both lines were served by a single breaker after being separated, they would both still be subject to loss from a single stuck breaker contingency.

2.3.3 Conformance to Long-Range Plan for Expansion of Electric Power Serving the State and Interconnected Utility Systems

FERC has charged ISO-NE with the responsibility for conducting long-term transmission system planning for New England. To discharge that responsibility, the ISO-NE continually assesses the needs of the entire New England bulk power system, through the preparation of annual Regional System Plans and long term studies. As explained in Section 2.2, the proposed Project is an outgrowth of the NEEWS studies, which began in 2006, and of the Greater Hartford area study that began in 2010. Ultimately, the need for the CCRP component of NEEWS and the load serving needs of the Greater Hartford, Manchester-Barbour Hill, Middletown, and NWCT sub-areas were examined together in the GHCC Needs Analysis. The grouping of these needs into a single study was to assure that co-ordinated and cost efficient solutions to the identified needs would be developed.

In parallel, ISO-NE has also been examining transmission needs in SWCT in 2022. The GHCC and SWCT studies have been coordinated so as to avoid redundant solutions. Together, the GHCC and SWCT studies identify solutions for Connecticut's transmission system that will comply with applicable reliability requirements through 2022, and that form a part of the ISO-NE Regional System Plan for all of New England.

2.3.4 Identification of Facility in the Forecast of Loads and Resources

Pursuant to section 16-50r(a) of the General Statutes, concerning forecasts of electric loads and resources, transmission owners are required to file with the Council periodic reports that include, among other things, a list of planned transmission lines on which proposed route reviews are being undertaken or for which certificate applications have already been filed, and a description of the steps taken to upgrade existing facilities. For instance, in its March 1, 2012 report, CL&P advised the Council that the ongoing *GHCC Needs Assessment* was considering needs in NWCT. Eversource announced its intention to build the Frost Bridge to Campville 115-kV line in the first forecast report that it filed after ISO-NE identified the line as a preferred solution in July, 2014. That forecast report was filed on March 2, 2015. In the

report, Eversource included the Frost Bridge to Campville line in its list of “Proposed Transmission Line Projects.

2.4 CONCLUSION

The Project is the product of years of careful study of reliability needs in the NWCT sub-area, coordinated with studies of needs in the Greater Hartford, Manchester-Barbour Hill, and Middletown sub-areas, and with those of SWCT. The Project will address violations of reliability criteria identified in these studies, and will assist Eversource in the discharge of its obligation to maintain the reliability of the Connecticut bulk transmission system in accordance with mandatory federal and regional standards and criteria.

Note: This page intentionally left blank.

3. TECHNICAL PROJECT SPECIFICATIONS

This section describes the technical specifications for the Project, including:

- The new 115-kV overhead transmission line along the Proposed Route between Frost Bridge Substation and Campville Substation;
- Separation of two existing Eversource 115-kV transmission lines at the Naugatuck River crossing by replacing two existing lattice steel transmission structures with new monopole structures; and
- Modifications to Eversource's existing Frost Bridge and Campville substations.

The technical information provided for the Project includes:

- Conductor size and specifications
- Overhead structure design, appearance, and height
- Route length, by municipality, and terminal points
- Initial and design voltages and capacities
- ROW and proposed on- and off-ROW access roads
- Proposed work pad locations (i.e., as needed for structure installation, conductor/OPGW pulling, guard structures)
- Proposed structure locations
- Removal and replacement of the existing 115-kV transmission line facilities at the Naugatuck River crossing
- Substation connections and proposed modifications
- Estimated capital (construction) and life-cycle costs

3.1 PROPOSED TRANSMISSION LINE FACILITIES

The proposed overhead 115-kV transmission line, designated as the 1304 Line, would extend for approximately 10.4 miles, and would be aligned adjacent to other existing 115-kV and / or 345-kV transmission lines, as summarized in Table 3-1. The new 115-kV line would be located such that sufficient space exists between the proposed and existing lines for safe and reliable line operations.

Table 3-1: Existing Transmission Lines Sharing ROW with the Proposed 115-kV Transmission Line

Eversource Existing Transmission Line Number	Line Location Description	Line Voltage / Structure Type
352	Frost Bridge Substation to Purgatory Junction	345 kV (Wood H-Frame)
1238	Frost Bridge Substation to Purgatory Junction	115 kV (Vertical Lattice Tower/Steel Monopole)
1191	Frost Bridge Substation to Campville Substation	115 kV (Lattice Tower/Wood H-Frame)
1921	Walnut Hill Junction to Campville Substation	115 kV (Delta Laminate Monopole)

The majority of the 10.4 miles of the Proposed Route for the new transmission line would be located entirely within an existing Eversource ROW that ranges in width from approximately 250 to 400 feet. The remaining approximately 1.3 miles of the Proposed Route would extend across property that Eversource owns.

3.1.1 115-kV Conductor Size and Specifications

The new overhead 115-kV transmission line would consist of three sets of phase conductors. Each set is comprised of one 1,590,000 circular mil (1,590-kcmil) Aluminum Conductor Steel Supported (ACSS). This selection is a standard Eversource conductor utilized for new 115-kV line construction.

The new line would be protected by two overhead lightning shield wires. One of the overhead shield wires would also contain optical glass fibers for communication purposes (also referred to as Optical Ground Wire or “OPGW”). The other lightning shield wire would be conventional 19 No. 10 Alumoweld.

3.1.2 Proposed Line Overhead Design, Appearance, and Heights

New 115-kV Transmission Line

The new 10.4-mile 115-kV transmission line would be located primarily within an existing Eversource ROW. The ROW is occupied by an existing 115-kV transmission line (i.e., the 1191 Line) and, in locations, other 115-kV lines and a 345-kV line (i.e., the 352 Line, 1238 Line, and 1921 Line; refer to

Table 3-1). The existing structures that support these transmission lines consist of wood H-frames, laminated and steel monopoles, and steel lattice towers.

The existing 115-kV 1191 Line is supported primarily on wood-pole H-frame structures with a typical height of approximately 60 feet. The 345-kV 352 Line, which occupies the ROW between Frost Bridge Substation and Purgatory Junction, is also supported on wood-pole H-frame structures; the 345-kV structures have a typical height of about 80 feet.¹⁰

The existing 115-kV 1238 Line and the 115-kV 1921 Line are supported on steel and wood laminate monopoles, respectively. The 1238 Line is arranged in a vertical configuration with typical structure heights of about 95 feet, whereas the 1921 Line is configured in a delta design and is characterized by typical structure heights of approximately 85 feet.

Steel lattice tower structures support the existing lines along the ROW in two locations:

- Along an approximately 0.3-mile segment of the ROW from Frost Bridge Substation, northwest across State Route 8 (Town of Watertown), the 1238 and 1191 Lines are supported on steel lattice towers that are approximately 100 and 110 feet in height, respectively.
- On each side of the Naugatuck River crossing in the towns of Litchfield and Harwinton, the existing 1921 and 1191 Lines are supported by double circuit steel lattice towers. These towers (one on each side of the river) are approximately 155 feet tall.

As illustrated on the Volume 5 maps, most of the new transmission line structures would generally be placed near or adjacent to existing line structures. However, in certain locations, new structure sites were shifted to avoid sensitive environmental or cultural areas, to address constructability and design issues, or to minimize potential impacts to property owners.

Along 10 miles of the 10.4-mile Proposed Route, the new 115-kV transmission line would be installed on weathering steel monopoles. The proposed structure design and configuration for the new 115-kV line would typically be direct-buried tubular steel monopoles in a delta or vertical configuration, with a typical height of about 90 feet (for delta) and 105 feet (for vertical). Self-supported vertical tubular steel monopoles would be used at angle points and as deadend structures, with a typical height of approximately 105 feet.

¹⁰ Wood H-frame tangent structures, which are the predominant type of structure along the existing 1191 Line and 352 Line, have two poles. However, within the H-frame “family” of structures, three-pole structures are used at angle points (turns in the ROW).

Delta deadend tubular steel structures would be used to support the new 115-kV transmission line crossing of the Naugatuck River. The new 1304 Line structures on each side of the river would be approximately 155 feet in height, the same height as the existing steel lattice tower structures that presently support the double-circuit (1191 / 1921 Lines) crossing of the river.

Along the 0.4-mile segment of the Proposed Route where the new 115-kV line would exit out of Frost Bridge Substation¹¹, Eversource plans to support the new 115-kV transmission line on three-pole structures. This type of structure design and configuration is required to accommodate multiple angles in the Proposed Route around the outside of the substation and to better allow crossings of other transmission lines that also interconnect to the substation.

Cross-sections drawings depicting the typically proposed structure types and general location in relation to the existing structures along each ROW segment are included in Appendix 3A, located at the end of this section.¹² Although the cross-sections illustrate the typical proposed structures, in certain locations along each ROW segment (such as at turns [angles] in the ROW), structures of the same type (e.g., monopole), but with slightly different appearance would be used. Appendix 3B (also found at the end of this section) provides illustrations of the family of structure types that Eversource uses in steel-pole lines with delta or vertical conductor configurations.

Modifications to Existing Facilities: 1191 Line and 1921 Line Circuit Separation at Naugatuck River Crossing

At the Naugatuck River crossing, the 1191 and 1921 Lines are presently supported by 155-foot-tall double circuit steel lattice towers (one on each side of the river)¹³. To maintain the reliability of the electric system, Eversource proposes to separate these two circuits, placing each line on separate monopoles (refer to XS-5 in Appendix 3A).

Four vertical deadend tubular steel structures – two on each side of the river - would be installed to replace the steel lattice tower structures and to support separately the 1191 Line and 1921 Line. Each of these new structures would be approximately 155 feet in height.

¹¹ As noted in Section 1, Eversource is in the process of evaluating two route variations that would involve a combination underground / overhead configuration for the new 115-kV line exit at Frost Bridge Substation. These route variations are discussed in Section 12.

¹² These cross-sections are also included in Volume 5.

¹³ In all locations along the ROW except at the Naugatuck River crossing, the 1191 and 1921 Lines occupy separate structures.

The two existing 155-foot-tall steel lattice towers would be dismantled and removed from the ROW. Temporary line sections and short-term outages of each 115-kV circuit would be required to safely install the new vertical deadend monopole structures, remove the existing conductor and steel lattice towers, and install each 115-kV line on its new vertical monopole structures.

3.1.3 Design Voltage and Capacity

The single 1,590-kcmil ACSS conductors would provide approximately 401 MVA of summer normal line capacity and a summer long-term emergency (LTE) capacity of 525 MVA at 115 kV.

The conductor design choice for the new 115-kV line would generally result in lower conductor corona levels compared to levels on the existing transmission lines, with smaller conductor sizes, that presently occupy the ROW. Thus, the new conductor would also limit the new line's audible noise and radio-frequency noise production in wet weather.

3.1.4 Proposed Structure Locations

Along the overhead line route the preliminary location for each of the proposed transmission line structures was determined using transmission line design software (Power Line System's "PLS-CADD"TM). The proposed structure locations are shown on the Plan and Profile Drawings in Volume 5, as well as on the 400 scale and 100 scale maps in Volume 5.

As a starting point in the Project design process, all proposed new 115-kV line structures were initially aligned adjacent to existing structures. This design approach was based on the assumptions that alignment of the new structures adjacent to the existing structures would maximize the use of existing on-ROW access roads (which are already situated to reach most existing structures), minimize changes to the visual environment, and mimic existing span lengths to minimize potential clearance violations under certain high-wind conditions. Based on these analyses, Eversource determined that 10 of the 104 new 115-kV structure locations, as determined by the initial structure siting (i.e., placement of new structures adjacent to existing structures) would be in wetlands.

Following this preliminary structure siting, each proposed structure location was further evaluated to account for other factors, such as potential environmental effects. Based on the constructability studies that have been performed thus far, nine of the 10 structures initially proposed for location in wetlands were shifted to upland locations.

Structure locations may further change as the Project design process continues. Future changes could occur based on information obtained from more detailed field studies (e.g., subsurface investigations, final engineering and environmental surveys, constructability reviews), as well as input from municipalities, the Council, and other regulatory agencies. After this additional information has been evaluated, final detailed line engineering would be performed to determine the exact locations of the new structures. Typically, the final structure locations are expected to be within 100 feet (longitudinally along the line) of the proposed structure locations, as depicted on the Volume 5, 100 scale maps.

3.1.5 ROW and Access Road Requirements

ROW Requirements and Easement Acquisition

Eversource proposes to construct and operate the new 115-kV transmission line along its existing ROW without the need for any additional easement acquisition. The typical easement widths along different segments of the existing transmission line ROW is summarized in Table 3-2 (located at the end of Section 3.1) and shown on the cross-section drawings (refer to Appendix 3A at the end of this section and to the Volume 5 maps).

As part of the Project design process, Eversource reviewed the existing easement rights and restrictions for its existing ROW along the entire Proposed Route. Eversource has sufficient rights within existing easement agreements to construct the Project. New easements may be required for off-ROW access roads.

Access Road Requirements

Various access roads are already established along and within the Eversource ROW (“on-ROW access roads”), where existing transmission lines have been operated and maintained for almost 90 years. To construct, operate, and maintain the new overhead 115-kV transmission line along the Proposed Route, contiguous access along the ROW is not required and these existing access roads would be used to the extent practical.

However, access to each new transmission structure location, as well as to pulling pads and guard structure sites, would be required. As a result, additional temporary and permanent access roads must be established and most of the existing on-ROW access roads would require improvements to allow the safe movement of the heavy construction equipment needed to install the new 115-kV line.

In addition, other temporary access along the ROW may be required to facilitate vegetation removal during construction. Refer to Section 4.1.4.2 for further information regarding temporary access for vegetation removal.

Further, in some areas, to avoid traversing linearly along the ROW over rugged terrain or through sensitive environmental or cultural resources, access roads to the ROW would be developed or improved across private property or across land owned by Eversource (“off-ROW access roads”). Such off-ROW access roads would typically provide access to the ROW from a public road.

The locations and type of new access roads and access road improvements would depend on the terrain, presence / absence of environmental features, and whether the access road would be temporary (used only during construction) or permanent (retained for long-term maintenance of the line). Access roads must have appropriate grades and sufficient width and capacity to support the large, heavy construction equipment (such as flat-bed tractor-trailers, drilling rigs, cranes, and concrete trucks) required to construct the new 115-kV line. The need for access by flat-bed trailers and concrete trucks (including turning radii) typically determines the scope of access road improvements.

In general, all construction access roads (on- or off-ROW) must have a stable base and grades of 10% or less. Whether restored, improved, or newly constructed for the Project, on- and off-ROW access roads would have a typical 16-to-20-foot-wide travel way and, overall, a 20-to-25-foot-wide footprint (including road shoulders). However, access road widths would vary depending on site-specific conditions (principally slope and presence of water resources) and on factors such as the amount of grading (cutting and filling) required and on whether a particular section of road must accommodate equipment turning radii and/or equipment passing/turn-out locations.

Access roads would be graveled or would consist of temporary construction (timber) mats or equivalent. In general, gravel would most commonly be used in constructing access roads in upland areas. In some locations, particularly on steep slopes and at intersections with public roads, asphalt millings could be used to improve road stability and vehicle traction.

Across wetlands where only temporary (construction) access is required, timber mats would typically be used. These mats would be removed upon the completion of construction. Where permanent access is unavoidably required across wetlands, road construction would be more extensive and would involve the use of gravel. To maintain drainage patterns across the ROW, access road construction would typically

incorporate timber mat (or equivalent) bridges, flumes, or culverts as needed. Refer to Section 4.2.1 for additional information regarding water resource crossings, including permanent access roads in wetlands.

New access roads would have to be constructed to reach certain proposed structure locations where sufficient access does not currently exist. However, permanent access roads would typically not be developed through long expanses of wetlands with deep standing water or unstable soils, or in locations where consecutive line structures are separated by long distances. In such areas, off-ROW access roads that provide ingress and egress to work sites on the ROW may be required to facilitate construction or to avoid crossings of sensitive environmental resources, such as rivers or large wetland complexes.

As part of the Project planning, Eversource evaluated the existing public roads leading to or intersecting with the transmission line ROW. Based on that review, an inventory of public roads that could provide access to the ROW was prepared. Table 4-3 in Section 4 identifies the public roads, or sites, that potentially could be used for access to the transmission line ROW. The Volume 5 maps illustrate locations of these roads with respect to the Proposed Route.

Eversource would conduct a detailed evaluation of the access requirements for the Project as part of final design. Access road information would be included in the Project-specific *Development and Management (D&M) Plans*, which would be required as a condition of the Council's approval.

3.1.6 Facilities on ROW Post-Construction (Proposed Line Design)

The configurations of the proposed 115-kV line are illustrated on the typical cross-sections presented in Appendix 3A, as well as on the maps located in Volume 5. Table 3-2 (located at the end of Section 3.1) summarizes the information presented in the cross-sections, identifying both the existing and proposed transmission line configurations.

Cross-sections are provided for each of the six different segments of the ROW, beginning at Frost Bridge Substation and proceeding to Campville Substation. For each ROW segment, the cross-sections depict the configurations of both the existing transmission lines and the new 115-kV transmission line that Eversource proposes.

The following subsections summarize the typical proposed configurations for the new 115-kV line, by ROW segment. These descriptions correspond to the cross-sections included in Appendix 3A, and Volume 5.

3.1.6.1 Frost Bridge Substation to 0.4-Mile West of Frost Bridge Substation – XS-1

XS-1 illustrates the typical configuration of the proposed 0.4-mile segment of the 115-kV line from Frost Bridge Substation toward Purgatory Junction in the Town of Watertown. This cross-section illustrates the typical configuration along this segment of ROW, as viewed to the northwest. As the cross-section shows, along this segment of ROW, the new transmission line would be installed within either Eversource fee-owned property or Eversource's existing 400-foot-wide ROW. Along this segment, the new 115-kV line would typically be installed on three-pole structures because of multiple line crossings and angles.

3.1.6.2 0.4-Mile West of Frost Bridge Substation to Purgatory Junction – XS-2

XS-2 illustrates the typical proposed transmission line configuration along the 2.3-mile segment of ROW extending from 0.4 mile northwest of Frost Bridge Substation to Purgatory Junction in the Town of Watertown. The proposed steel vertical monopole 115-kV structures would be located between the 352 345-kV Line and 1191 115-kV Line H-frame structures within the existing 400-foot-wide ROW. This cross-section illustrates the proposed layout of the new 115-kV line, presenting a typical view, looking west, along the ROW.

3.1.6.3 Purgatory Junction to Walnut Hill Junction – XS-3

XS-3 illustrates the typical proposed transmission line configuration along this 3.8-mile ROW segment in the towns of Watertown and Thomaston. Along this segment, the proposed 115-kV delta line would be aligned adjacent to the existing 1191 Line's 115-kV H-Frame structures within the existing 250-foot-wide ROW. This cross-section illustrates the proposed layout of the new 115-kV line, presenting a typical view along the ROW to the north.

3.1.6.4 Walnut Hill Junction to Naugatuck River – XS-4

XS-4 illustrates the typical proposed transmission line configuration along this 2.5-mile ROW segment in the towns of Thomaston and Litchfield. Along this segment, the proposed 115-kV delta line would be aligned adjacent to and east of the existing 1921 Line's 115-kV delta structures within the existing 250-foot-wide ROW. The existing 1191 Line (supported on H-frames) is located within the ROW to the west of the 1921 Line. This cross-section illustrates the proposed layout of the new 115-kV line, presenting a typical view to the north along the ROW.

3.1.6.5 Naugatuck River Crossing – XS-5

XS-5 illustrates the typical proposed transmission line configuration along this 0.4-mile ROW segment at the Naugatuck River crossing in the towns of Litchfield and Harwinton. At the river crossing, the new 115-kV line would be installed on delta monopole structures. The lattice steel structures that currently support Eversource's two existing 115-kV lines (the 1191 and 1921 Lines) would be replaced with steel monopoles (both vertical). The new proposed 115-kV delta line would be located adjacent to and east of the rebuilt 115-kV structures.

All of the line structures would be accommodated within Eversource's existing 250-foot-wide ROW. XS-5 depicts both the new 115-kV line and the reconfigured 1921 and 1191 Lines, as viewed to the north, at the river crossing.

3.1.6.6 Naugatuck River Crossing to Campville Substation – XS-6

XS-6 illustrates the typical proposed 115-kV transmission line configuration along this 1.0-mile ROW segment in the Town of Harwinton. Along this segment, the proposed 115-kV delta line would be aligned adjacent to and east of Eversource's existing Line 1921 115-kV delta structure. The existing Line 1191 (H-frame structures) is located on the western portion of the ROW. This cross-section illustrates the proposed layout of the new 115-kV line, presenting a typical view to the north (toward Campville Substation), along the ROW.

Table 3-2: Summary of Existing and Proposed Transmission Line Configurations

Transmission Line By Cross-Section (Municipality)	Approx. ROW Mileage	Existing Line Configurations and Typical ROW Width		Proposed 115-kV Transmission Line Reference Case Configurations and Typical ROW Width	
		Typical Structure Type and Height (above ground)	ROW Width (feet)	Typical Structure Type and Height (above ground)	Typical ROW Width (feet)
XS-1 (Watertown)	0.4	None	N/A	One 115-kV circuit supported on steel 3-pole horizontal structures; heights vary, ranging from 45 to 160 feet, with a typical height of 80 feet.	Entirely within Eversource-owned property.
XS-2 (Watertown)	2.3	One 345-kV circuit supported on wood-pole H-frame structures; heights vary, ranging from 59 to 90 feet, with a typical height of 80 feet. One 115-kV circuit supported on wood pole H-Frame chair structures; heights vary, ranging from 50 to 80 feet, with a typical height of 60 feet. One 115-kV circuit supported on steel double circuit vertical monopole structures; heights vary, ranging from 65 to 110 feet, with a typical height of 90 feet.	400	Install one 115-kV circuit on steel vertical monopole structures between existing 115-kV H-Frame and 345-kV H-Frame structures; heights vary, ranging from 75 to 125 feet, with a typical height of 105 feet.	400 (No additional ROW required)
XS-3 (Watertown & Thomaston)	3.8	One 115-kV circuit supported on wood pole H-Frame structures; heights vary, ranging from 50 to 80 feet, with a typical height of 60 feet.	250	Install one 115-kV circuit on steel delta monopole structures east of existing 115-kV H-Frame structures; heights vary, ranging from 70 to 125 feet, with a typical height of 90 feet.	250 (No additional ROW required)
XS-4 (Thomaston & Litchfield)	2.5	One 115-kV circuit supported on wood pole H-Frame chair structures; heights vary, ranging from 50 to 80 feet, with a typical height of 60 feet. One 115-kV circuit supported on steel delta monopole structure; heights vary, ranging from 55 to 100 feet, with a typical height of 80 feet.	250	Install one 115-kV circuit on steel delta monopole structures east of existing 115-kV delta structures; heights vary, ranging from 70 to 110 feet, with a typical height of 90 feet.	250 (No additional ROW required)
XS-5 (Litchfield & Harwinton)	0.4	Two 115-kV circuits supported on double circuit steel lattice structures, typical height of 155 feet.	250	Remove existing lattice structures and install two pairs of 115-kV single circuit steel vertical monopole structures. Install one pair of single circuit steel delta structures; with a typical height of 155 feet.	250 (No additional ROW required)
XS-6 (Harwinton)	1.0	One 115-kV circuit supported on wood pole H-Frame chair structures; heights vary, ranging from 50 to 80 feet, with a typical height of 60 feet. One 115-kV circuit supported on steel delta monopole structures; heights vary, ranging from 55 to 100 feet, with a typical height of 80 feet.	250	Install one 115-kV circuit on steel delta monopole structures east of existing 115-kV delta structures; heights vary, ranging from 75 to 120 feet, with a typical height of 90 feet.	250 (No additional ROW required)

Note: This page intentionally left blank.

3.2 SUBSTATION CONNECTIONS AND MODIFICATIONS

In order to interconnect the new 115-kV transmission line with the existing transmission system, modifications would be required at two existing Eversource substations (Frost Bridge and Campville). None of these modifications would require the acquisition of any additional property.

The proposed Project modifications at the Frost Bridge Substation would be accomplished within the existing developed (fenced) area of the station. However, the proposed Project modifications to the Campville Substation would require an approximately 0.4-acre expansion beyond the existing developed (fenced) area of the substation. This expansion would be on Eversource property.

Preliminary design drawings of the proposed station modifications are included in Volume 5. The technical specifications regarding these modifications are detailed for each substation, as follows. Detailed designs would be included as part of the D&M Plans.

3.2.1 Frost Bridge Substation

The Frost Bridge Substation is located in eastern Watertown, adjacent to Frost Bridge Road, State Route 8, and the Naugatuck River, on 5.7 developed acres within a 128.5-acre site owned by Eversource as shown in Figure 3-1. The modifications required to interconnect the Frost Bridge Substation to the new 115-KV transmission line would be accomplished within the developed (fenced) portion of the property. No expansion or modification to the existing fence line would be required. Preliminary plan and section views for the substation modifications are illustrated in Volume 5; these preliminary plans will be updated as the substation design process proceeds.

The new facilities proposed at the Frost Bridge Substation include the following:

- Expand the existing one-position 115-kV bay to a two-position bay. This would require use of an existing 115-kV transmission line-terminal position). The physical line terminal structure exists, although no transmission line currently exits the substation in this position. The substation currently has a total of four 115-kV bays with a total of seven 115-kV lines exiting the substation, two lines per bay except where the new line will be positioned.
- Install one new 115-kV circuit breaker and one new 115-kV transmission line to an existing terminal structure, approximately 60 feet in height.
- Install one motor operated disconnect switch, one ground switch, three lightning arrestors, three CCVTs, and one wave trap. Appropriate junction boxes and yard control boxes would be installed and connected to a pre-existing conduit raceway for control cable.
- Install new protection and control equipment within the existing relay/control enclosure.

3.2.2 Campville Substation


Campville Substation is located in the southwest portion of the Town of Harwinton, adjacent to Wildcat Hill Road. The substation occupies approximately 1.7 acres of a 42.3-acre property owned by Eversource as shown in Figure 3-2. The proposed Project expansion would include modifications that would increase the developed substation (fenced area) by approximately 0.4 acre. This expansion would be on Eversource owned land.

A preliminary plan and section views for the substation modifications are illustrated in Volume 5; these preliminary plans will be updated as the substation design process proceeds.

The new Project facilities proposed at Campville Substation include the following:


- Expand the existing ring bus to accommodate four new 115-kV breakers and one new transmission line-terminal position. The expansion would require the demolition of one existing breaker and connection of the new equipment in its place. A new transmission structure is required to connect the new 115-kV transmission line from Frost Bridge to the Campville line position. In addition, another existing breaker would be shifted slightly to allow the installation of a new 115-kV circuit breaker adjacent to the relocated breaker.
- Install one new 115-kV line terminal structure, approximately 60 feet tall. Install one motor operated disconnect switch, one ground switch, three lightning arrestors, three CCVTs, and one wave trap. Appropriate junction boxes and yard control boxes also would be installed and connected to a new conduit raceway for control cable.
- Install four 115-kV disconnect switches, approximately 60 feet of aluminum tube conductor, six 115-kV breakers, one 60-foot-tall lightning mast, as well as steel support structures and foundations for all new equipment.
- Extend the substation's existing ground grid, grading as appropriate to accommodate stormwater management controls, install an extension of the substation fence.
- Install a new substation enclosure to house additional substation batteries and the associated DC panel boards. Modification to the existing substation building is also required for protection and control.

Figure 3-1: Frost Bridge Substation Location Map



Note: This page intentionally left blank.

Figure 3-2: Campville Substation Location Map



Note: This page intentionally left blank.

3.3 ESTIMATED PROJECT COSTS

3.3.1 Estimated Capital Cost

The estimated capital cost for the Project is approximately \$51 million, with the transmission line construction accounting for approximately \$46 million and substation modifications accounting for approximately \$5 million.

3.3.2 Life-Cycle Cost

In accordance with the Council's *Life-Cycle Cost Studies for Overhead and Underground Transmission Lines* (2012), Eversource performed a present-value analysis of capital and operating costs over a 35-year economic life of the Project. The following items were considered:

- Annual carrying charges of the capital cost
- Annual operation and maintenance costs
- Cost of energy losses
- Cost of capacity



Applying these factors, the life-cycle cost for the Project is approximately \$76.4 million.

Note: This page intentionally left blank.

Appendix 3A – Cross-Sections

Note: This page left blank intentionally


G:\GIS\CT\EversourceEnergy\W0915\W0915_43_FrostBridgeToCampville\MapDocuments\HighLevelOverview\FrostBridgeToCampville_HighLevelOverview_XSections_Letter_Portrait_20150903_.mxd



EVERSOURCE
ENERGY

**Cross-Section
Location Map**
**Frost Bridge to Campville
115-kV Project**

Note: This page left blank intentionally




PROPOSED CONFIGURATION
3-POLE DEADEND DESIGN

FROST BRIDGE SUBSTATION
TO
0.4 MILE OUT OF FROSTBRIDGE SUBSTATION

IN THE TOWN OF
WATERTOWN

LOOKING
EAST, NORTH AND WEST
(0.4 MILE)




NOTES:

1. NEW TRANSMISSION LINE ALIGNMENT ON EXISTING EVERSOURCE-OWNED PROPERTY.
2. AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
3. DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL 3-POLE DEADEND STRUCTURES TO BE PLACED ON CONCRETE FOUNDATIONS. TANGENT STRUCTURES WILL UTILIZE DIRECT EMBEDDED FOUNDATIONS, WHILE VERTICAL DEADEND STRUCTURES WILL BE PLACED ON CONCRETE FOUNDATIONS.


TITLE			
FROST BRIDGE TO CAMPVILLE 115-kV PROJECT			
PROPOSED CROSS SECTIONS			
FROST BRIDGE S/S TO 0.4 MILE OUT OF FROST BRIDGE S/S			
BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-1
P.A. #			

Note: This page left blank intentionally



**PROPOSED CONFIGURATION
VERTICAL DESIGN**

0.4 MILE OUT OF FROST BRIDGE SUBSTATION
TO
PURGATORY JUNCTION
IN THE TOWN OF
WATERTOWN
LOOKING
WEST
(2.3 MILES)




NOTES:

1. EXISTING LINES TO REMAIN.
2. PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
3. EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
4. AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
5. DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL TANGENT STRUCTURES UTILIZING DIRECT EMBEDDED FOUNDATIONS. ANGLE AND DEADEND STRUCTURES WILL DIFFER AND BE PLACED ON CONCRETE FOUNDATIONS.

TITLE FROST BRIDGE TO CAMPVILLE 115-kV PROJECT PROPOSED CROSS SECTIONS 0.4 MILE OUT OF FROST BRIDGE S/S TO PURGATORY JCT.			
BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-2
P.A. #			

Note: This page left blank intentionally




**PROPOSED CONFIGURATION
DELTA DESIGN**

PURGATORY JUNCTION
TO
WALNUT HILL JUNCTION

IN THE TOWNS OF
WATERTOWN & THOMASTON

LOOKING
NORTH

(3.8 MILES)




NOTES:

- EXISTING LINES TO REMAIN.
- PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
- EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
- AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
- DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL TANGENT STRUCTURES UTILIZING DIRECT EMBEDDED FOUNDATIONS. ANGLE AND DEADEND STRUCTURES WILL DIFFER AND BE PLACED ON CONCRETE FOUNDATIONS.

TITLE FROST BRIDGE TO CAMPVILLE 115-kV PROJECT PROPOSED CROSS SECTIONS PURGATORY JCT. TO WALNUT HILL JCT.			
BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-3
P.A. #			

Note: This page left blank intentionally




**PROPOSED CONFIGURATION
DELTA DESIGN**

WALNUT HILL JUNCTION
TO
SOUTH BANK OF NAUGATUCK RIVER

IN THE TOWNS OF
THOMASTON & LITCHFIELD

LOOKING
NORTH

(2.5 MILES)



KEY MAP
NOT TO SCALE





NOTES:

- EXISTING LINES TO REMAIN.
- PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
- EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
- AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
- DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL TANGENT STRUCTURES UTILIZING DIRECT EMBEDDED FOUNDATIONS. ANGLE AND DEADEND STRUCTURES WILL DIFFER AND BE PLACED ON CONCRETE FOUNDATIONS.

TITLE FROST BRIDGE TO CAMPVILLE 115-kV PROJECT PROPOSED CROSS SECTIONS WALNUT HILL JCT. TO S. BANK OF NAUGATUCK RIVER			
BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-4
P.A. #			

Note: This page left blank intentionally



KEY MAP
NOT TO SCALE

**PROPOSED CONFIGURATION
DELTA DESIGN**

SOUTH BANK OF NAUGATUCK RIVER
TO
NORTH BANK OF NAUGATUCK RIVER

IN THE TOWNS OF
LITCHFIELD & HARWINTON

LOOKING
NORTH


(0.4 MILE)

NOTES:

- EXISTING LINES TO REMAIN.
- PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
- EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
- AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.

TITLE FROST BRIDGE TO CAMPVILLE 115-kV PROJECT PROPOSED CROSS SECTIONS S. BANK OF NAUGATUCK RIVER. TO N. BANK OF NAUGATUCK RIVER			
BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-5
P.A. #			

Note: This page left blank intentionally




**PROPOSED CONFIGURATION
DELTA DESIGN**

**NORTH BANK OF NAUGATUCK RIVER
TO
CAMPVILLE SUBSTATION**

**IN THE TOWN OF
HARWINTON**

**LOOKING
NORTH**

(1.0 MILES)



NOTES:

1. EXISTING LINES TO REMAIN.
2. PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
3. EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
4. AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
5. DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL TANGENT STRUCTURES UTILIZING DIRECT EMBEDDED FOUNDATIONS. ANGLE AND DEADEND STRUCTURES WILL DIFFER AND BE PLACED ON CONCRETE FOUNDATIONS.

TITLE			
FROST BRIDGE TO CAMPVILLE 115-kV PROJECT			
PROPOSED CROSS SECTIONS			
N. BANK OF NAUGATUCK RIVER TO CAMPVILLE SUBSTATION			
BY	D. LAURSEN	CHKD	V. MONTEMURRO
DATE	8/31/15	DATE	8/31/15
SCALE	NONE	MICROFILM DATE	
P.A. #		DWG. NO.	XS-6

Note: This page left blank intentionally

Appendix 3B – 115kV Transmission Line Structure Types

Note: This page left blank intentionally

115-kV TRANSMISSION LINE STRUCTURE TYPES

Transmission line structures, which are typically the element of an electric transmission system that are most apparent to the public, support the conductors (wires) that are used to transport electric power from generation sources to customer load centers.¹⁴ Three 115-kV transmission line structure families have been identified for use on the proposed Project or as configuration options for certain segments of the proposed Project:

- Delta Steel Pole
- Vertical Steel Pole
- H-Frame (configuration option only)

Each of these structure families includes different functional types of structures. Where and how a particular type of structure is used along a transmission line depends on a variety of factors, such as availability of ROW, load requirements¹⁵, and terrain (topography). In each structure family, the basic types of structures commonly used along a transmission line are described as follows:

- **Tangent structure.** Tangent structures are the type most commonly used on a transmission line and are used on relatively straight portions of the transmission line. Because the conductors are in a relatively straight line passing through them, tangent structures are designed only to handle small line angles (changes in direction) of 0 to 2 degrees. Tangent structures are usually characterized by suspension (vertical) insulators, which support and insulate the conductors and transfer wind and weight loads to the structure.
- **Angle structure.** Angle structures are used where transmission line conductors change direction. These types of structures are designed to withstand the additional forces placed on them by the change in direction. Angle structures may be: (1) similar to tangent structures, using suspension insulators to attach the conductors and transfer wind, weight, and line angle loads to the structure; or (2) similar to strain or dead-end structures, using insulators in series with the conductors to bring wind, weight, and line angle loads directly to the structure.
- **Dead-end structure.** A dead-end structure is typically used where transmission line conductors turn at a wide angle or end. Compared to tangent structures, a dead-end structure is designed to be stronger and often is a larger structure. Typically, insulators on a dead-end structure are in line with the conductors (horizontal) to bring wind, weight, and line angle loads directly to the

¹⁴ The conductors proposed for the Project are aluminum with a steel core for strength; these conductors are connected to the transmission line structures by insulators (typically made of porcelain) that must be strong enough to support tensile forces and the weight of the conductors while preventing electrical contact between the conductors and the structure. Shield wires, which are connected directly to the structures, are installed above the conductors to protect the conductors from direct lightning strikes.

¹⁵ Each structure must be designed for both the loads imposed on it by the weight of the conductors and dynamic loads resulting from factors such as wind and ice accumulation.


structure. A dead-end structure is designed to resist the full unbalanced tension that would occur if all conductors were removed from one face of the structure.

- **Strain structure.** A strain structure is similar in appearance and design strength to a tangent structure. The difference in appearance is the conductor attachment hardware. The conductor attachment hardware is the same as a deadend or large angle, where the insulator bells are in line with the conductor. Whereas a dead-end structure is designed to withstand the full unbalanced tension that would occur from the loss of all conductors from one face of the structure, a strain structure is designed to withstand only unbalanced tensions associated with the loss of a single phase (bundle of two conductors) on one face of the structure.


As illustrated in this appendix, structures are self-supported and may include different insulator configurations (e.g., horizontal, vertical).

Delta Steel Pole Family


Note: This page left blank intentionally



DELTA CONDUCTOR CONFIGURATION TANGENT (0-2 DEGREES)



DELTA CONDUCTOR CONFIGURATION STRAIN (0-30 DEGREES)



VERTICAL CONDUCTOR CONFIGURATION DEADEND

NOTES:

- STRUCTURES SHOWN DEPICT STEEL POLE CONSTRUCTION.
- DRILLED PIER FOUNDATIONS MAY BE UTILIZED FOR TANGENT & STRAIN STRUCTURES.
- STRUCTURE GROUNDING EQUIPMENT NOT SHOWN.

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-



83707

date AUG. 31, 2015 detailed D. LAURSEN
 designed V. MONTEMURRO checked P. WILLIAMS

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

EVERSOURCE ENERGY

FROST BRIDGE TO CAMPVILLE 115-KV PROJECT
 DELTA CONDUCTOR CONFIGURATION
 FAMILY OF STRUCTURES

BY	DATE	CHK	DATE	APP	DATE
BMCD	8/31/2015	-	-	-	-


FIELD BOOK & PAGES
 R.E. DWG
 NUSCO

Z:\Clients\IND\NUSCO\81960_ghoc\Working\STRS\MGF\TYP-STR-TYPE.dwg (DELTA-1) 08-31-2015 10:24 DDL B&MCD


Note: This page left blank intentionally

Vertical Steel Pole Family


Note: This page left blank intentionally



VERTICAL CONDUCTOR CONFIGURATION TANGENT (0-2 DEGREES)



VERTICAL CONDUCTOR CONFIGURATION STRAIN (0-30 DEGREES)



VERTICAL CONDUCTOR CONFIGURATION DEADEND

NOTES:

- STRUCTURES SHOWN DEPICT STEEL POLE CONSTRUCTION.
- STRUCTURE GROUNDING EQUIPMENT NOT SHOWN.
- VERTICAL TANGENT STRUCTURES MAY UTILIZE DIRECT EMBED FOUNDATIONS WHERE FEASIBLE.

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-



83707

date AUG. 31, 2015 detailed D. LAURSEN
 designed V. MONTEMURRO checked P. WILLIAMS

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

EVERSOURCE ENERGY

FROST BRIDGE TO CAMPVILLE 115-kV PROJECT
 VERTICAL CONDUCTOR CONFIGURATION
 FAMILY OF STRUCTURES

BY	DATE	CHK	DATE	APP	DATE
BMcD	8/31/2015	-	-	-	-


FIELD BOOK & PAGES
 R.E. DWG
 NUSCO

Z:\Clients\IND\NUSCO\81960_ghoc\Design\Frost_Bridge-Campville\CADD\Working\STRS\MCF_TYP-STR-TYPE.dwg (VERT-1) 08-31-2015 10:24 DDL BMcD


Note: This page left blank intentionally

H-Frame and Horizontal 3-Pole Structure Family


Note: This page left blank intentionally



HORIZONTAL CONDUCTOR CONFIGURATION
H-FRAME TANGENT
(0-2 DEGREES)



HORIZONTAL CONDUCTOR CONFIGURATION
H-FRAME STRAIN
(0-30 DEGREES)



HORIZONTAL CONDUCTOR CONFIGURATION
3-POLE DEADEND

NOTES:

- STRUCTURES SHOWN DEPICT STEEL POLE CONSTRUCTION.
- A NEED FOR AND NUMBER OF X-BRACES ON A STRUCTURE WILL DEPEND ON SITE-SPECIFIC FACTORS, SUCH AS STRUCTURE LOCATION AND HEIGHT. TYPICALLY, A 75-FOOT H-FRAME TANGENT STRUCTURE WOULD HAVE A SINGLE X-BRACE.
- DRILLED PIER FOUNDATIONS MAY BE UTILIZED FOR TANGENT & STRAIN STRUCTURES.
- STRUCTURE GROUNDING EQUIPMENT NOT SHOWN.

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**BURNS
MEDONNELL**

83707

date AUG. 31, 2015	detailed D. LAURSEN
designed V. MONTEMURRO	checked P. WILLIAMS

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE
ENERGY**

FROST BRIDGE TO CAMPVILLE 115-kV PROJECT
HORIZONTAL CONDUCTOR CONFIGURATION
FAMILY OF STRUCTURES

BY BMcD	DATE 8/31/2015	CHKD -	DATE -	APP -	DATE -
H-SCALE -	V-SCALE -	SIZE D	FIELD BOOK & PAGES -	R.E. DWG -	NUSCO -

SHEET 1 OF 1

Z:\Clients\IND\NUSCO\81960_ghoc\Working\STRS\MCF\TYP-STR-TYPE.dwg (H-FRAME-1) 08-31-2015 10:24 DDL BMcD

Note: This page left blank intentionally

4. CONSTRUCTION AND OPERATION / MAINTENANCE PROCEDURES

The proposed Project would be constructed, operated, and maintained in accordance with established industry practices, as well as pursuant to Eversource's specifications. Construction, operation, and maintenance activities also would conform to any conditions identified in the Council's Decision and Order and in federal and state permits obtained for the Project.

Section 4.1 describes the standard procedures to be used for the installation of the proposed overhead 115-kV transmission line, including construction sequencing, material staging sites, construction field offices, access roads, ROW preparation, structure installation, counterpoise installation, conductor work, ROW cleanup and restoration, and general considerations for traffic control. Procedures for the separation of the 1921 and 1191 Lines at the Naugatuck River crossing (i.e., removal the existing lattice steel towers and replacement with steel monopoles) are also described.

Section 4.2 reviews the special procedures that would be followed when specific conditions are encountered during construction (e.g., procedures for water resource crossings, blasting, soils management, and dewatering). The proposed configurations of the 115-kV transmission line along each ROW segment are depicted on the cross-section drawings, which are included in Section 3 of this volume (refer to Appendix 3A) and in Volume 5. (The Volume 5 cross-sections are full-size, scale drawings and include detailed notes; the cross-sections in Appendix 3A and on the Volume 5, 400 scale maps are reduced-size versions).

Section 4.3 summarizes the construction methods for the proposed modifications to Frost Bridge Substation and Campville Substation. Operation and maintenance procedures applicable to the new 115-kV transmission line and associated substations are detailed in Section 4.4.

4.1 STANDARD PROCEDURES FOR OVERHEAD TRANSMISSION LINE CONSTRUCTION

4.1.1 Introduction and Overview of Construction Sequencing

Eversource would construct the proposed Project in several stages, some overlapping in time. The following summarizes the activities, materials, and equipment generally expected to be involved in the construction of the overhead transmission line facilities:

- Survey and stake the ROW boundaries and monument line (where necessary), vegetation clearing boundaries, and proposed structure locations.
- Mark the boundaries of previously delineated wetland and watercourse areas.
- Identify and mark areas to be avoided (e.g., sensitive cultural or environmental resource areas).
- Establish construction field office area(s), typically including space for office trailer(s), equipment storage and maintenance, sanitary facilities, and parking.
- Prepare material staging sites (e.g., storage, staging and laydown areas) to support the construction effort. The preferred locations for such areas are typically in the immediate vicinity of the ROW.
- Perform vegetation clearing. Vegetation would be removed along those portions of the ROW to be used for the construction of the transmission line facility, as well as areas that contain undesirable, tall-growing, woody species that could reach heights that would interfere with the operation of the transmission line should they not be removed. For example, as part of construction, vegetation would be removed to the designated limits of clearing as required, including at work sites (work pads), as well as along existing or new access roads. Vegetation also would be removed, as necessary, along existing or new access roads that may be on the ROW (but outside the designated limits of clearing) or off the ROW (but required to reach the ROW). In addition, as authorized by its easements or permission from the landowner, hazard trees outside the limits of clearing (on or off the ROW) would be removed as necessary to protect the integrity of the proposed or existing transmission lines. Vegetation removal activities typically require flatbed trucks, brush hogs or other types of mowing equipment, skidders, bucket trucks for canopy trimming, tree shears for larger trees, wood chippers, log trucks, and chip vans. Effects on wetlands, watercourses, or other environmentally sensitive areas would be minimized to the extent practicable (refer to Sections 4.2 and 6 for a discussion of potential mitigation measures). Vehicles with tracks or low-ground-pressure tires may be used to remove vegetation in wetlands. In addition, depending on soil saturation, vegetation removal activities in wetlands may include the use of temporary timber mats or timber riprap to provide a stable base for clearing equipment or hand cutting to avoid any vehicular access.
- Install erosion and sedimentation controls in accordance with best management practices (typically, controls are deployed using pickups and other small trucks, or small track vehicles). After vegetation removal, soil erosion and sedimentation controls typically are installed around work limits (e.g., access roads, work pads) in or near wetlands and streams.
- Construct new access roads or improve existing roads to provide a minimum travel-way of 16 to 20 feet in width (overall a 20-25-foot-wide footprint, including road shoulders). This typically requires bulldozers or front loaders, excavators, dump trucks for crushed stone or gravel, pickups or stake-body trucks for culverts, and/or mat installers for wetland mats. Roads may be temporary (for use during construction only) or permanent (for use during both construction and the subsequent maintenance of the lines). Temporary roads may be constructed of wood (timber) mats or gravel, whereas permanent access roads are generally constructed of gravel only. Roads must have sufficient width and capacity for heavy construction equipment for both over-the-road and off-road vehicles, including oversized tractor trailers. The need for access by flat-bed trailers and concrete trucks often determines the scope of access road improvements. Road grades must be negotiable for over-the-road trucks; acceptable grades are typically 10% maximum, less if wet weather or surface conditions result in traction problems.
- Prepare level work (crane) pads as necessary at new structure sites, conductor pulling sites, and guard structure sites. Work pad installation may involve grading and requires the installation of a

stable base (consisting of gravel, timber mats, or equivalent) for drilling and other structure installation equipment.

- Construct structure foundations and erect/assemble new structures. This requires flat-bed trucks for hauling new structure components, new hardware, and augers, other trucks for hauling reinforcing rods, drill rigs, cranes, concrete trucks for structures that require concrete for foundations, dump trucks for structures that require crushed rock backfill, and bucket trucks. Dump trucks are also needed for foundation work if excess excavated material has to be removed from the ROW. In wet conditions or if groundwater is encountered during excavation, pumping (vacuum) trucks or other suitable equipment would be used to pump water from the excavated areas. The water then would be discharged in accordance with applicable local, state, and federal requirements.
- Install counterpoise, where needed. Depending on site-specific soil conductivity, supplemental grounding will be installed. A ditch witch is typical equipment for this activity.
- Install shield wires, OPGW, and conductors. The equipment required for these activities would include conductor reels, conductor pulling and tensioner rigs, and bucket trucks. Helicopters also may be used to install the initial pulling lines for the conductors or shield wires.
- Demolish and remove from the ROW the existing 115-kV lattice steel structures, as well as the existing shield wires, conductors, and other transmission line materials on and between the structures. The equipment required for these activities would be generally the same as required for installing the new structures, conductors, and OPGW, as described above.
- Remove temporary roads and construction debris and stabilize disturbed sites. Haul construction debris off the ROW for disposal. Vegetative materials cut along the ROW and not otherwise planned for use by the landowner (e.g., brush) may be piled, scattered, or chipped on the ROW, depending on site-specific environmental features. If the ROW to be restored is in an agricultural field, the soil may be de-compacted by disking.
- Maintain temporary erosion and sediment controls until vegetation is re-established or disturbed areas are otherwise stabilized. Steep areas may be stabilized with jute netting or pre-made erosion control fabric containing seed, mulch, and fertilizer. Culverts or crushed stone fords installed along access roads would be either left in place or removed pursuant to regulatory approvals. After site stabilization is achieved, all temporary erosion and sedimentation controls that are not biodegradable (e.g., geotextile material, twine, stakes) would be removed from the ROW and disposed of properly.

4.1.2 Material Staging Sites

To support the construction of the new 115-kV transmission line, temporary contractor yards, storage areas, staging areas, and work pads would be necessary. The preferred locations for contractor yards, as well as temporary storage and staging sites, are in the general vicinity of the ROW. Although the staging areas do not necessarily have to be adjacent to the transmission line ROW, establishing these areas in proximity to construction sites would improve construction efficiency and minimize the potential for inconvenience or nuisance effects to the public (e.g., as a result of the movement of equipment, manpower, and supplies to and from the ROW along public roads). Work pads would be located within the ROW, at individual transmission line structures, conductor pulling sites, and guard structure sites.

If practical, material storage and staging areas would be established on Eversource-owned property. Based on the general acreage requirements for each type of staging location (refer to the discussions in Sections 4.1.2.1 and 4.1.2.2), Eversource performed a preliminary review to identify its properties in the vicinity of the ROW that could potentially serve as storage and staging area locations for the Project. Table 4-1 lists the Eversource-owned sites identified as a result of this preliminary assessment. Because each of the identified sites is more than 2 acres, any of these properties could potentially be used for either material storage or staging in support of Project construction.

Table 4-1: Potential Material Storage or Staging Sites on Eversource-Owned Properties

Town	Eversource Property Location (Volume 5, 400 Scale Mapsheet No.)
Watertown	
	Frost Bridge Substation (Mapsheet 1) North and South of Echo Lake Road (Mapsheet 1) Nova Scotia Hill Road (Mapsheet 2) U.S. Route 6 / Thomaston Road (Mapsheet 3)
Thomaston	
	North of State Route 109 (Mapsheet 5) North of Walnut Hill Road (Mapsheet 6)
Litchfield	
	North of State Route 8 (Mapsheet 8)
Harwinton	
	Campville Substation (Mapsheet 9)

However, it is likely that additional material storage and staging areas would be necessary to support Project construction. If Eversource-owned properties are not available or suitable, previously developed sites (such as parking lots, previously used commercial or industrial properties) or vacant land would be evaluated for use as contractor yards, material storage, or staging areas, taking into consideration parcel size requirements and location in relation to the Proposed Route. At any location not already developed (e.g., paved parking lots) or previously used for such construction support work would likely be required to prepare the site for use as a contractor yard, material storage, or staging area. Such site preparation work may include vegetation removal, grading, adding gravel, installing fencing, and installing crushed stone anti-tracking pads at vehicular access points from public roads.

The actual locations of the contractor yards, staging, and storage sites would be determined by, or with input from, the contractor responsible for constructing the line. The contractor would be responsible for finalizing the locations of yards, staging, and storage areas, and also for making arrangements with property owners regarding the use of the properties. Eversource would review and approve the contractor's proposed construction support sites, and would obtain approval from the Council and, if necessary, from other regulatory agencies.

The development, use, and restoration of any staging sites would conform to conditions of the Council's approval and any other applicable federal, state, and local requirements. Because the locations of the staging sites would not be finalized until after a construction contractor is selected, Eversource would either specify such sites in the D&M Plans for the Project or submit them separately to the Council for approval prior to use.

4.1.2.1 Temporary Storage Areas

Temporary storage areas typically range in size from approximately 2 to 5 acres, but may be larger. These areas would be used to temporarily store construction materials, equipment, and supplies. Storage areas also would be used for mobile construction offices, parking the personal vehicles of construction crew members, parking construction vehicles and equipment, and performing minor maintenance, if needed, on construction equipment.

In addition, storage areas may function as staging areas. For example, components for new transmission line structures may be temporarily stored at these locations prior to delivery to structure sites. Transmission line materials or structures also may be assembled at storage areas prior to delivery to the ROW.

Storage areas for the proposed Project would typically be selected based upon proximity to work locations along the ROW. As the construction of the transmission lines progresses, subsequent storage areas are typically used to keep equipment and materials close to the locations where line construction work is being performed. Once a storage area is no longer used to support construction activities, it would be restored pursuant to the use agreement with the property owner.

4.1.2.2 Staging Areas

Staging areas, which are generally less than 2 acres in size, are typically used for temporarily stockpiling materials for transmission line construction (e.g., erosion and sedimentation control materials, poles and

structure components, insulators and hardware, and construction equipment). In addition, staging areas may be used to temporarily stockpile materials removed from the ROW or used during the construction process, prior to off-site disposal. The number and proposed locations of staging areas required to support the construction effort would be determined by the transmission line construction contractor.

Staging areas would be required in proximity to the transmission line route and may be located on or off the ROW. Eversource-owned property that is presently used for utility purposes would be used for staging areas to the extent practical. Locations along the ROW could also be used, provided sufficient easement rights exist.

As construction progresses, subsequent staging areas would likely be used to coincide with nearby construction work. When a particular staging area is no longer required, the site would be restored pursuant to the use agreements with the property owners.

4.1.3 Construction Field Offices

Field offices for both the contractor and Eversource provide headquarters for construction field representatives, engineers, and other Project field personnel near the areas where work is being performed. Optimally, such construction field offices are located in existing commercial or industrial facilities near the Project, including at Eversource substations. If not practical to locate in existing commercial or industrial facilities, these field office sites typically would consist of trailers, portable sanitary facilities, and associated parking areas.

The field offices also may be co-located with other construction support sites, such as staging or storage areas. At the completion of the Project, the office trailers and other construction support equipment or materials would be removed, and the area would be restored.

For construction office sites located on private property, restoration would be in accordance with landowner agreements. If field office sites are located on Eversource-owned property, restoration would be pursuant to Eversource's requirements.

4.1.4 Right-of-Way Preparation

Along with the development or improvement of access roads (refer to Section 4.1.5), ROW preparation constitutes the first step in the transmission line construction process. ROW preparation activities typically involve vegetation removal and the associated deployment of erosion and sedimentation

controls. In addition, during this phase of construction, exclusion fencing or other types of boundary markings are typically installed to demarcate areas of restricted construction access or environmental sensitivity.

4.1.4.1 Temporary Erosion and Sedimentation Controls

Temporary erosion controls (e.g., silt fence, hay/straw bales, filter socks, mulch, and seeding) would be initially installed as practicable prior to and/or during vegetation clearing operations, in compliance with the 2002 *Connecticut Guidelines for Soil Erosion and Sedimentation Control* and Eversource's 2011 Best Management Practices (BMP) manual entitled, "*Best Management Practices Manual: Construction and Maintenance Environmental Requirements for Connecticut*" (BMP Manual).

Temporary controls, such as silt fence, hay/straw bales, straw waddles, and filter socks, also may be deployed during any of the transmission line construction phases involving soil disturbance. Such controls would be maintained (i.e., repaired and replaced as necessary) throughout the construction period, until disturbed areas are revegetated or otherwise stabilized. After stabilization is achieved, these materials would be removed and disposed of appropriately.

Generally, in areas where soils have been or would be disturbed near sensitive environmental resources (e.g., wetlands, vernal pools, watercourses, threatened and endangered species habitat), temporary controls would be deployed as appropriate to minimize the potential for erosion and sedimentation off ROW or into water resources (on or off the ROW).¹⁶ In addition, temporary erosion and sedimentation controls (e.g., silt fence, straw/hay bales), orange construction fencing, or signage may be deployed after vegetation removal to demarcate the limits of work within sensitive environmental areas (i.e., limits of access roads, work pads).

The need and extent of temporary erosion and sedimentation controls would be a function of considerations such as:

- Slope (steepness, potential for erosion, and presence of environmentally sensitive resources, such as wetlands or streams, at the bottom of the slope).

¹⁶ In some locations, such as areas where vegetation is cleared and water resources are situated nearby but no further earth-disturbing construction activities are required, soils may be stabilized with permanent measures (e.g., final revegetation). Refer to Section 4.1.8.1 for a discussion of final revegetation and permanent erosion control measures.

- Type of vegetation removal method used and the extent of vegetative cover remaining after clearing (e.g., presence/absence of understory or herbaceous vegetation to minimize the potential for erosion and degree of soil disturbance as a result of the clearing equipment movements).
- Type of soil.
- Soil moisture regimes.
- Schedule of future construction activities.
- Proximity of cleared areas to water resources, roads, or other sensitive environmental resources.
- Time of year. The types of erosion and sedimentation control methods utilized along the ROW would depend on the time of year construction work is initiated and completed. For example, re-seeding is typically ineffective during the winter months. In winter, with frozen ground, controls other than re-seeding (such as wood chips, straw and hay, geotextile fabric, erosion control logs) typically would be deployed or maintained to control erosion and sedimentation and thus to stabilize disturbed areas until reseeded can be performed under optimal seasonal conditions.

4.1.4.2 Vegetation Removal, Including Tree Clearing

Vegetation Clearing Requirements and Estimates

Along the majority 10.4-mile Proposed Route, the new 115-kV transmission line would be located adjacent to one or more existing overhead transmission lines, which are situated within Eversource's ROW that varies in width from approximately 250 to 400 feet. Beneath and in the vicinity of the existing transmission lines that occupy this ROW, Eversource routinely manages vegetation pursuant to requirements for the reliable operation of the overhead transmission lines.

Since April 7, 2006, Eversource's ROW vegetation management practices have been required to comply with mandatory standards adopted by the North American Electric Reliability Corporation (NERC) following the August 14, 2003 Northeast blackout.¹⁷ These vegetation management practices are designed to allow the reliable operation of the transmission facilities by preventing the growth of trees or invasive vegetation that would otherwise interfere with the transmission facilities or hinder access along the ROWs. As a result, the vegetation within the managed portions of Eversource's ROWs typically consists of shrubs, herbaceous species, and other low-growing species.

To accommodate the construction and subsequent operation of the new 115-kV line, additional vegetation removal would be required. Vegetation along the ROW would be removed to allow for construction equipment at each structure location, to provide cleared access roads and spurs to structure sites, as needed, and to provide no imminent risk to the new line along the new or existing edge from danger trees.

¹⁷ Transmission line outages triggered by overgrown vegetation in Ohio were substantial factors in causing the blackout.

However, the amount and type of vegetation clearing required would vary and would depend on factors such as the existing width of the managed ROW, vegetation communities present (e.g., forested, herbaceous, scrub-shrub, open field), the type of the new 115-kV transmission structures, configuration and spacing of the transmission line conductors, transmission line span lengths, and terrain.

Along the ROW within which the new 115-kV line would be located, the width of the currently managed portions varies, depending on the number and configuration of the existing transmission lines that occupy each ROW segment. The cross-sections illustrate the location of the proposed transmission line along each ROW segment (refer to Section 3, Appendix 3A of this Volume and in Volume 5).

For example, along the 2.2 miles from the vicinity of Frost Bridge Substation to Purgatory Junction (refer to XS-2), the 400-foot-wide ROW currently includes one 345-kV circuit and two 115-kV circuits. The new 115-kV line is proposed for location near the middle of the ROW, between the 345-kV and one of the existing 115-kV circuits. Because Eversource already manages most of this ROW segment for low-growth vegetative communities, clearing for the construction of the new 115-kV line would predominantly involve the removal of scrub-shrub type vegetation. However, some areas of taller-growing vegetation are predominant within the limits of clearing for the new 115-kV transmission line and thus would have to be removed.

On the other hand, along the majority of the remaining 8.2 miles of the Proposed Route, the new 115-kV line would be located adjacent to and east of one or two existing 115-kV lines, within a typical 250-foot-wide ROW. Along these ROW segments, Eversource presently manages (on average) a 95-to-140-foot-wide area beneath and adjacent to the existing lines. The development of the proposed 115-kV line, supported on delta monopole structures, would require (typically) an additional 40-to-45 feet of new vegetation removal for construction and subsequent management within the ROW. Table 4-2 summarizes the widths of the ROW segments along which the proposed 115-kV line would be located, together with the typical widths of the existing managed portions of the ROW and the anticipated additional widths of vegetation removal required along each ROW segment of the Project.

Table 4-2: Summary (by Cross-Section) of Total ROW Widths, Existing Managed ROW Widths, and Additional New Vegetation Clearing Widths Required for the Proposed 115-kV Transmission Line

Town	Existing Eversource ROW			
	Cross-Section Reference (refer to Vol. 1, Appendix 3A and to Vol. 10)	Total ROW Width (feet)	Width of Current Vegetation Management Area along ROW (feet, typical)	Estimated Width of New Vegetation Clearing* Required for Proposed 115-kV Transmission Line (feet)
Watertown	XS-1	Fee-owned	0	100
Watertown	XS-2	400	400	0
Watertown / Thomaston	XS-3	250	90	45
Thomaston / Litchfield	XS-4	250	140	40
Litchfield / Harwinton	XS-5	250	115	70
Harwinton	XS-6	250	140	40

*Note: The estimated width of new vegetation clearing refers to the additional areas of the ROW, outside of the portions of the ROW that Eversource presently manages, where vegetation (typically forest) would have to be removed for the new 115-kV transmission line. To accommodate the construction of the new transmission line, vegetation (mostly shrub-scrub) would also have to be removed along portions of the existing managed ROW. Along the 2.2-mile segment of ROW represented by XS-2, the new 115-kV line would be aligned near the middle of Eversource's 400-foot-wide ROW, which is presently occupied by three other overhead transmission lines. Eversource performs vegetation management within this ROW segment consistent with the safe and reliable operation of these transmission lines. As a result, whereas the overall width of the managed ROW would not be expanded along this segment, some areas of forested and other vegetation, located in the interior of the Eversource ROW, would have to be removed.

Along the 250-foot-wide ROW north of Purgatory Junction (XS-3 through XS-6), after the installation of the new 115-kV transmission line, portions of the ROW to the east of the line would remain unaffected by construction or vegetation management activities associated with this project. These unused (non-managed) portions of the ROW support taller vegetation, including forested uplands and wetlands. The widths of the un-managed portions along the east side of the ROW range from 65 to 115 feet, as illustrated on the cross-section drawings (refer to Appendix 3A and Volume 5).

As part of the construction of the new transmission lines, undesirable, tall-growing, woody species within the ROW areas proximate to the new line would be removed. Desirable species would be preserved to the extent practical. In selected cases, certain desirable, low-growing trees may be kept on the ROW in specific locations and only trimmed to ensure adequate clearance from wires and structures, pursuant to Eversource's *Right-of-Way Vegetation Initial Clearance Standard for 115-kV and 345-kV Transmission Lines*. Generally, all tall-growing tree species would be removed from the managed portion of the ROW and low-growing tree species and taller shrub species would be retained in the areas outside of the

conductor zones (the area directly under the conductors extending outward a distance of 15 feet from the outermost conductors).

These activities would modify, but not eliminate, vegetation and wildlife habitats along the ROW. In general, the principal long-term effect of vegetation removal along the ROW would be to forested habitat. Specifically, within the additional areas where new vegetation clearing would be required to accommodate the proposed Project, trees would be removed and would not be allowed to regenerate. Over time, these previously forested areas would be recolonized by native shrubs, herbaceous flowering plants, and grasses, creating additional old field and scrub-shrub communities.

Landowner Outreach and Beneficial Use of Forestry Products

The timber resources along the Proposed Route belong to the landowners across whose properties the ROW is aligned. Eversource's policy is to pro-actively coordinate with landowners regarding the disposition and use of the trees to be removed along the ROW. If requested by the landowner, the timber portions of the trees would be left on the landowner's property, in upland areas on the edge of the vegetatively managed portion of the ROW. After the limbs are removed, the wood would be piled in tree lengths for landowners to cut and remove at their convenience.

Timber removed along the ROW on Eversource-owned property or on parcels where the landowners are not interested in retaining the wood would become the property of the Project's land clearing contractor. Eversource would competitively bid the vegetation removal work for the Project and would select a contractor taking into consideration the contractor's plans for the beneficial use of the forest products.

Vegetation Clearing Methods

Vegetation would be typically removed from the proposed transmission line construction workspace (including the areas of managed vegetation in the vicinity of the new line) using mechanical methods. Where necessary, Eversource will encourage the selected vegetation clearing contractor to use low-impact tree clearing means and methods to remove forested vegetation. Low-impact tree clearing incorporates a variety of approaches, techniques, and equipment to minimize site disturbance and to protect wetlands, watercourses, soils, rare species and their habitats, and cultural resources.

During vegetation removal, timber mats or equivalent may be used to provide a stable base for clearing equipment across or within wetlands along the ROW. Such temporary support would minimize rutting in wetlands and would be removed after the clearing activities are completed. The locations where

temporary support would be required would be determined in the field, based on site-specific conditions (e.g., soil saturation) present at the time of construction, and may not be the same as the permanent or temporary access roads illustrated on the Volume 5 maps.

Appropriate erosion and sedimentation controls would be deployed as necessary (refer to Section 4.1.4.1). Where removal of woody vegetation is required, vegetation would typically be cut to within 3” of ground surface to the extent possible. Where practical, trees would be felled parallel to and within the ROW to minimize the potential for damage to residual vegetation.

Eversource would direct the Project contractor to retain lower growing vegetation along stream banks and within wetlands, to the extent possible. In general, Eversource may alter to some degree vegetation management activities in the following areas, provided that the construction and operation of the facilities remains in accordance with national transmission line vegetation management standards and consistent with Project permits and approvals:

- Areas of visual sensitivity where vegetation removal may be limited for aesthetic purposes;
- Steep slopes and valleys spanned by transmission lines;
- Agricultural lands; and
- Residential areas where maintained landscapes do not interfere with the construction, maintenance, or operation of the transmission lines.

Danger and Hazard Trees

During and/or after the initial vegetation removal activities, a licensed arborist will evaluate trees beyond the proposed edge of clearing (i.e., both on and off-ROW) to identify and mark any hazard and danger trees that pose an imminent risk to the new 115-kV transmission line.¹⁸ Individual “danger” or “hazard” trees are typically determined based on factors such as species, soil conditions (including wetland vs. upland, susceptibility to flooding, depth of rock), health of the tree, inclination of trunk and shape of crown, etc.. Hazard or danger trees located in un-managed areas outside of the limits of Project clearing would be removed after identification; prior to the removal of any such trees off-ROW, Eversource would inform the affected landowner.

¹⁸ A danger tree is a tree that, due to its location and height, could cause a flashover or damage to the transmission line structures or conductors, or violate conductor zones, if it were to fall toward the transmission line. A hazard tree is a tree that exhibits some type of defect or damage (e.g., weakness, broken limbs, decay, infestation) that increases the risk of it falling into the transmission line.

4.1.5 Access Roads

As discussed in Section 3.1.5, access roads are required during construction. "On-ROW access roads" would be used to move equipment and material between structure locations. Further, in some areas, to avoid traversing along the ROW through sensitive environmental resources (i.e. wetlands and vernal pools) or rugged topography along the ROW, access roads to the ROW may be developed across private property or across land owned by Eversource ("off-ROW access roads").

Depending on site-specific conditions, grading may be required to develop or to improve access roads. Some access roads would be needed only during construction and thus would be used temporarily, whereas other access roads will be required permanently for the long-term operation and maintenance of the new transmission lines.

Typically, at points of intersection with public roads, Eversource would install signs along the access roads that specify the roads are for construction purposes and are restricted from use by public vehicular traffic. In addition, where on-ROW access roads or off-ROW dirt roads intersect with public roads, rock aprons or equivalent would typically be installed to minimize tracking of dirt from the ROW onto the public road as a result of construction vehicle movements. Public roads in the vicinity of access roads may also be periodically swept to remove dirt that is tracked from construction activities.

4.1.5.1 On-ROW Access Roads

Contiguous access along the existing ROW is generally not necessary for the construction of the proposed 115-kV overhead transmission line; although access to each proposed transmission structure location is required. Along most of the Proposed Route, the existing transmission lines have been in service for approximately 90 years and, as a result of the operation and maintenance of those transmission lines, many access roads are already established. Such existing access roads would be used for the construction of the Project wherever possible. The on-ROW access roads expected to be used for the proposed Project are illustrated on the maps in Volume 5.

However, most of the existing access roads would have to be improved, widened, or otherwise modified in order to be used safely and effectively during construction. For example, to safely support the heavy construction equipment (e.g., flat-bed trailers, cranes, drill rigs, and concrete trucks) required to install 115-kV transmission line structure foundations and structures, access roads must be sufficiently wide, with a stable base and grades that typically must be 10% or less.

Access road improvements typically include clearing adjacent vegetation and widening roads as needed to provide a minimal travel surface approximately 16 to 20 feet wide (additional width would be needed at turning or passing locations). Access roads will be graveled. Where access roads traverse streams or wetlands, culverts and timber mats (or equivalent) may be used. Existing culverted crossings may also be improved. Erosion and sedimentation controls would be installed as necessary before the commencement of any improvements to or development of access roads.

4.1.5.2 Off-ROW Access Roads

Along portions of the Proposed Route, terrain and environmental features (e.g., steep slopes, rock outcrops, wetland complexes, Branch Brook Reservoir Dam, Morton Pond, Northfield Brook Lake, Naugatuck River) make linear construction access along the ROW difficult or impractical. In such locations, to avoid or minimize adverse environmental effects while allowing safe access to the ROW, Eversource proposes to use off-ROW access roads as necessary. Such off-ROW access roads will entail the use of public roads or access roads across private property.

Eversource performed an initial review of existing access roads leading to the transmission line ROW for the Project. Based on this initial review, an inventory of possible access roads was prepared. Table 4-3 lists the public roads that provide access to the transmission line ROW.

Table 4-3: Potential Public Road Access to ROW

Town	1"=400' Aerial Mapsheet No. (Volume5)	Existing Access to ROW via the following Town/City Streets or Sites
Watertown		
	1	Frost Bridge Road (State Route 262)
	1	Echo Lake Road
	2	Park Road
	2	Seemar Road
	2	Nova Scotia Hill Road
	3	Highmeadow Road
Thomaston		
	4	Old Branch Road
	5	Branch Road (State Route 109)
	5	Old Northfield Road
	6	Walnut Hill Road
Litchfield		
	7	Mason Hill Road
	7	Hopkins Road
	7/8	Campville Road
	8	State Route 8
Harwinton		
	8	Valley Road
	9	Wildcat Hill Road

As planning for the Project continues and off-ROW access roads are further defined, some of the in-ROW access roads depicted on the Volume 5 maps may be modified or eliminated to minimize adverse effects on environmental resources (e.g., to avoid or minimize wetland crossings). Conversely, new access roads that optimize ingress and egress to the ROW may be identified. A detailed evaluation of the access roads required for construction would be conducted and included in the D&M Plans to be prepared for the Project.

4.1.5.3 Work Pads

Work pads would be required at each transmission line structure site, as well as at conductor and OPGW pulling sites and at locations where temporary road/rail guard structures are necessary during conductor installation.

At each transmission line structure site, a work pad is required to stage structure components for final on-site assembly and to provide a safe, level work base for the construction equipment used to install foundations and erect the structure. The size and configuration of the work pad at a particular line structure location would vary based on site-specific conditions; however, a typical pad for a tangent structure averages about 100 feet by 100 feet and for a deadend structure averages about 200 feet by 100 feet.

The preliminary location and configuration of the work pads, as determined based on the environmental field studies and constructability reviews conducted to date, are included on the Volume 5 maps. The exact locations and configurations of work pads would be determined during final Project design, based on site-specific conditions (e.g., to avoid or minimize work in wetlands or other environmentally- or culturally-sensitive areas).

A typical (upland) installation of a work pad at a structure location involves several steps, beginning with the removal of vegetation, if necessary. The work pad site then would be graded to create a level work area and, if necessary, the upper 3 to 6 inches of topsoil (which is typically unsuitable to support the necessary construction activities) would be removed. The topsoil would be temporarily stockpiled within the ROW, typically near the work pad. A rock base, which allows drainage, would be layered on top of filter fabric (if used). Additional layers of rock with dirt/rock fines are typically placed over this rock base. Finally, a roller typically is used to flatten and compact the pad.

Pulling work pads, which would be required in certain locations along the ROW for conductor and OPGW installation, typically will be 100 feet by 200 feet, but can be as large as 100 feet by 300 feet. Pulling work pads would be constructed using techniques similar to those for work pads at structure locations.

Guard structure work pads are typically required at road and other crossings to provide locations for guard structures or equipment used during conductor and OPGW installation. Typically, such temporary guard structure work pads are 50 feet by 80 feet, with an associated 16 to 20-foot-wide access road.

In areas where work pads must unavoidably be located in wetlands, timber mats are typically used to construct the pads. Alternatively, a geo fabric layer is overlaid with large rock base layer used to allow water to flow underneath the pad. Smaller rock is layered on top of larger rock, followed by the final layer of gravel intermixed with soil.

Upon completion of the transmission line installation, work pads at structure sites in uplands would remain in place, unless directed to be removed by the landowner. Work pads located in active agricultural lands or within manicured or otherwise improved residential, commercial, or industrial areas would typically be removed unless the landowner requests that they remain in place.

All work pads or portions of work pads in wetlands (typically consisting of timber mats) would be removed and the affected wetlands would be restored, pursuant to Project permits and approvals. Guard structure pads and pulling pads also would be removed.

Where work pads would remain in place, topsoil stripped from beneath the work pad and stockpiled nearby also typically would remain in place or be spread over nearby upland areas of the ROW and re-seeded. In locations where gravel work pads must be removed, the rock base and fabric materials would be excavated and removed for appropriate off-site disposal or re-use.

4.1.6 Structure Installation

4.1.6.1 Foundation Work (Foundation Types and Excavation)

The proposed new 115-kV transmission line structures would be either direct embedded or drilled shaft foundations. The tangent structures would typically be direct embedded. Angle and deadend structures would typically have a drilled shaft foundation. Excavations for line-structure foundations are expected to be accomplished using mechanical excavators (drill rigs) and pneumatic hammers. During non-working hours, fencing or other barricades would be placed around or over open foundation excavations for structures.

If blasting is required, a controlled drilling and blasting plan would be developed by a certified blasting contractor in compliance with state and local regulations. Residents would be contacted in advance of the blasting, and pre-blast surveys would be performed as appropriate. The specific locations where blasting would be required are determined by conducting field studies (borings) at the proposed structure locations.

4.1.6.2 Structure Placement

Structures would be delivered to installation locations in sections, then assembled and installed with a crane. Insulators and connecting hardware would be installed on most structures at this time. Supplemental grounding also would be installed on the new structures. Such grounding consists of a

ground ring and sometimes counterpoise (i.e., buried conductors). The type of grounding required at each structure would depend on the electrical characteristics of the soil.

4.1.6.3 Alternate Foundation and Structure Placement Methodology for Inaccessible Areas

To reach some Project structure locations, constructing access roads may not be practical due severe terrain limitations or other constraints. In such locations, helicopter construction methods may be utilized.

However, helicopters do not have the lift capacity to transport the drill rigs or other heavy equipment required to install the drilled shaft foundation typically expected to be used on the Project. As a result, an alternative foundation design involving micro-piles would be required. Specifically, a group of smaller micro-pile foundations, tied together by a steel or concrete cap, would effectively support the new 115-kV structures. These alternative foundation designs can be installed utilizing smaller and lighter equipment that can be safely transported to remote work sites by a heavy lift helicopter.

In addition, helicopters would also be used to transport the structures and other materials and equipment from staging areas near the ROW to the structure sites. The heavy lift helicopters, also sometimes referred to as sky cranes, that would be used to install the new 115-kV structures in remote locations are larger than the helicopters used for stringing conductor, OPGW, and related activities. Because mobilizing and using heavy lift helicopters would be significantly more expensive than traditional construction techniques, this method would only be used at selected structure sites, if access overland is determined to be impractical.

4.1.7 1921 and 1191 Line Double-Circuit Structure Removal

After removal of the existing conductors, shield wires, and insulators, the existing lattice steel structures that presently support the 1921 and 1191 Lines at the Naugatuck River crossing would be disassembled, by section, using a crane. The structure sections would be placed on the ground and then further taken apart so that the steel pieces fit inside a standard dumpster. Eversource would recycle all steel demolished and would properly dispose of all other miscellaneous hardware.

4.1.8 Conductor Work

The installation of overhead line conductors and shield wires requires the use of special pulling and tensioning equipment, which would be positioned at pre-determined locations at intervals of 1 to 3 miles.

Helicopters also may be used to install the initial pulling lines at the commencement of the conductor / shield wire pulling process.

The wires would be pulled under tension to avoid contacting the ground and other objects. The remaining insulators and hardware would then be installed at angle and deadend structures. Finally, the conductors and shield wires would be pulled to their design tensions and attached to the hardware by linemen in bucket trucks in accordance with industry standards and design specifications.

Various pulling sites would be established along the approximately 10.4-mile transmission line route. These sites, which are typically approximately 100 feet wide and 100 to 300 feet long, are usually located within the ROW. Specific conductor pulling sites would be identified by the Project construction contractor, in consultation with Eversource.

The selection of conductor pulling sites is based upon a variety of factors including: accessibility, terrain, angles within the line sections where the conductors would be pulled, the locations of deadend structures (which keep installed conductors under high tension), the length of conductors and OPGW to be pulled, puller capacity, and snub structure¹⁹ loads. Other considerations include the placement of pullers, tensioners, conductor anchors, and other associated pulling equipment, including the installation of a temporary grounding system. Along the Proposed Route, conductor pulling sites would be determined based on the consideration of these factors, the design load of the structures, and the avoidance or minimization of environmental effects.

Steps would be taken to minimize temporary disturbance to adjacent landowners from noise and activity associated with the pulling operation. In addition, conductor pulling sites would be located outside of wetlands, and would avoid other areas of environmental sensitivity to the extent practical.

4.1.9 Cleanup and Restoration

ROW cleanup and restoration activities would include the removal of construction debris, signs, flagging, and fencing, as well as the removal of temporary access roads and work pads. Areas affected by construction would be re-graded as practical and stabilized using revegetation or other measures before removing temporary erosion and sedimentation controls.

¹⁹ A structure located at one end of a sag section and considered as a zero point for sagging and clipping offset calculations. A snub is a pole stub or log that is set or buried in the ground to serve as a temporary anchor. Snubs are often used at pull and tension sites.

4.1.9.1 Final Grading, Revegetation, and Permanent Erosion and Sedimentation Controls

During final grading, areas of the ROW disturbed by construction and not otherwise occupied by permanent access roads or work pads, generally would be back-bladed to approximate preconstruction contours, where possible. Some areas (e.g., slopes, bluffs) affected by construction activities may not be fully restored to original contours. Such areas would be stabilized as warranted by site-specific conditions.

Permanent controls, such as water diversion bars or crushed stone, would be installed as appropriate to minimize the potential for erosion and sedimentation. Other permanent ROW stabilization measures include revegetation, or the use of erosion control blankets to promote revegetation.

For work sites along the ROW in actively used agricultural fields, the soil may be decompacted by disking or using equivalent methods. Where permanent access is not required across wetlands or streams, temporary crossings (e.g., timber mats, other temporary crossing materials such as rock) would be removed and the affected areas re-graded to match the grade of areas outside of the construction work zone, to the extent practicable.

Temporary erosion and sedimentation controls would be left in place and maintained until final stabilization is achieved. Steep areas would be stabilized with jute netting, pre-made erosion and sedimentation control fabric containing seed, mulch, and fertilizer or the equivalent.

Restoration typically is deemed successful based on the effectiveness of stabilization measures as defined in accordance with applicable permit and certificate requirements. Based on the results of post-construction inspections of ROW stabilization (refer to Section 4.1.11), Eversource would determine the appropriate time frame for removing temporary erosion controls.

Upland areas disturbed by construction activities typically would be seeded with appropriate seed mixes, as needed. Mulch or other erosion controls would be applied as necessary based on slope and land use. Wetland areas disturbed by construction would be reseeded with annual rye, or an equivalent native seed mix, which would serve to provide a temporary vegetative cover until wetland species become reestablished. No fertilizer, lime, or mulch would be applied in wetlands unless specified in regulatory approvals for the Project.

Vegetative species compatible with the use of the ROW for transmission line purposes are expected to regenerate naturally over time. Eversource would promote the re-growth of desirable species by implementing vegetation management practices to control tall-growing trees, and where practicable, undesirable invasive species, thereby enabling native plants to dominate the ROW. Vegetation management practices along the ROW also would conform to Project-specific conditions regarding habitat restoration and enhancement as may be included in approvals from the Council, CT DEEP, and USACE (refer to Section 4.4.1 for additional information regarding Eversource's long-term ROW vegetation management program, including invasive species control).

4.1.9.2 Permanent Access Roads and Work Pads

Access roads in uplands would be left in place to facilitate future transmission line maintenance. Structure work pads in uplands would be left in place, unless directed to be removed by the landowner. Access roads and work pads located in active agricultural lands or within manicured or otherwise improved residential, commercial, or industrial areas would typically be removed unless the landowner requests that they remain in place. No new permanent access roads or work pads would be left in wetlands or streams unless approved by the involved regulatory agencies. The locations where permanent access roads and work pads will remain would be identified either in the D&M Plans or in the end-of-Project report to the Council.

4.1.9.3 Methods to Prevent or Discourage Unauthorized Use of the ROW

Eversource's existing transmission line easements restrict the types of activities that can be conducted within the ROW. Easements typically prohibit the construction of buildings, pools, and other structures within its ROWs. Additionally, Eversource has policies addressing requests from property owners and other parties external to Eversource. These policies outline an evaluation process and provide guidelines for allowing certain uses (such as driveways or parking lots), where appropriate.

In addition, Eversource routinely works with landowners to discourage unwarranted access onto and use of its ROWs, such as by third-party users of off-road vehicles such as all-terrain vehicles (ATVs) and snowmobiles. Where Eversource holds an easement rather than land ownership in fee, Eversource must receive landowner approval prior to installing barriers (such as fences, gates, and access control berms) to discourage such access onto its ROWs.

Pursuant to Connecticut General Statutes Section 14-387, written landowner permission is required for the use of ATVs and snowmobiles on privately-owned property. Eversource does not grant permission

for ATV or snowmobile use on its property or easements (other than for its own purposes), and seeks the cooperation of local police departments in discouraging these off-road vehicular uses along its ROWs. In addition, upon request, Eversource will provide landowners along the ROW with “no trespassing” signs for posting on their property and will install gates²⁰ or other barriers at public road crossings to deter unauthorized vehicular access along the ROW.

4.1.10 Traffic Considerations and Control

During the installation of the new transmission line, construction-related vehicular and equipment movements would occur on roads in the Project area. However, the Project-related traffic is generally expected to be temporary and highly localized in the vicinity of the ROW and staging areas. Due to phasing of construction work, these Project-related traffic movements are not expected to significantly affect transportation patterns or levels of service on public roads.

During the Project construction phase, vehicles and equipment also would enter and exit the ROW from various public roads. To safely move construction vehicles and equipment onto and off the ROW while minimizing disruptions to vehicular traffic along public roads, Eversource or its Project contractor would, as appropriate, work with representatives of the four affected towns or the Connecticut Department of Transportation (ConnDOT). The construction contractor is typically responsible for posting and maintaining construction warning signs along public roads near work sites and for coordinating the use of flaggers or police personnel to direct traffic, as necessary.

4.1.11 Construction and Post-Construction Monitoring: D&M Plans

In accordance with the Council’s requirements, after the certification of the Project, Eversource would prepare and submit for Council approval D&M Plans that would detail the procedures to be used to construct the proposed transmission facilities. The D&M Plans would incorporate the conditions of the Council’s Certificate of Environmental Compatibility and Public Need (Certificate) for the Project, as well as the conditions of the permits received from other regulatory agencies, as appropriate.

Eversource would retain engineering and environmental consultants to monitor the conformance of construction activities to the D&M Plans, the Council’s Certificate, other regulatory requirements, and company standards.

²⁰ Of the possible types of access barriers, Eversource typically prefers to install locking gates, which best allow company access to the ROW when needed. Typically, locked gates are installed along the ROW at public access points (e.g., public road crossings) to deter unauthorized off-road vehicular use.

After the completion of construction activities (including ROW restoration), Eversource would conduct periodic monitoring of the Project ROW pursuant to state and federal permits. The monitoring would continue until ROW revegetation or other forms of stabilization are determined to be successful, as defined by Project permits.

4.2 CONDITIONS REQUIRING SPECIAL CONSTRUCTION PROCEDURES

The Proposed Route extends across various wetlands and waterbodies, as well as areas of bedrock outcrops or where bedrock is close to the surface. In some locations, the water table also is close to the surface, resulting in the potential for encountering groundwater in excavations for structure installations. Furthermore, the Proposed Route may traverse certain areas that may potentially contain contaminated soils or groundwater.

The following subsections describe the general construction procedures that Eversource would use for water resource crossings, blasting, soils / groundwater characterization and management, and construction site dewatering. Additional, site-specific procedures would be provided in the D&M Plans, as applicable, after the completion of a final Project design.

4.2.1 Water Resource Crossings

During the construction of the Project, Eversource proposes, to the extent practical, to avoid or limit work in watercourses (streams, rivers, ponds), and to minimize the placement of structures and permanent access roads in wetlands. In addition, Eversource would implement erosion and sedimentation controls in upland areas near water resources to limit the potential for upland erosion and sedimentation into water bodies or wetlands.

All construction activities involving water resources would be performed in accordance with the conditions of the Council's Certificate, as well as pursuant to the conditions of the Project-specific water resource permits issued by the CT DEEP and the USACE. In addition, construction activities would conform to Eversource's BMP Manual, as well as to the requirements of Project-specific plans (e.g., *Stormwater Pollution Control Plan*; *Wetland Invasive Species Control Plan*; *Spill Prevention and Control Plan*), which would be prepared prior to the commencement of construction.

The water resource permit conditions and related plans would be incorporated into the D&M Plans or similar Project documents. Eversource would require the construction contractor(s) to adhere to such conditions and plans during the construction of the Project facilities.

4.2.1.1 Wetlands

To minimize or avoid adverse effects to wetlands, Eversource has attempted to locate new transmission line structures in upland areas wherever practical. Eversource will avoid access roads across wetlands if there are practical upland alternative access routes available to reach the structure locations. Where new structures must unavoidably be located in wetlands, Eversource would limit the effects to the wetlands to the extent practical. Mitigation measures may include, for example, reducing the structure work pad size or configuring the work pad, if practical, to avoid or minimize the placement of temporary fill in wetlands.

In general, where a new structure must be located in a wetland, temporary construction mats would be used for construction support. In some wetland areas, however, field conditions (such as thickness of organics, depth of water or steep slopes) may require the use of a temporary crushed stone pad to provide a safe working surface. After the completion of structure installation, the temporary fill used for the work pads in wetlands would be removed, to the extent practicable and in accordance with the conditions of the Project-specific water resource permits issued by the CT DEEP and the USACE.

The wetland boundaries along the ROW would be clearly flagged prior to the commencement of work. When working in or traversing wetlands, Eversource would:

- Comply with the conditions of the Council's certificate and of federal and state permits related to wetlands;
- Install, inspect, and maintain erosion and sedimentation controls and other applicable construction best management practices;
- Conduct vegetation clearing in wetlands to minimize adverse effects such as by using low-impact equipment and installing temporary timber mats (or equivalent) to minimize rutting;
- Pile cut woody wetland or upland vegetation in upland areas so as not to block surface water flows within wetlands or otherwise to adversely affect the wetland integrity;
- Cut forested wetland vegetation without removing stumps unless it is determined that intact stumps pose a safety concern for the installation of structures, movement of equipment, or the safety of personnel;
- Limit grading for access roads and structure foundations in wetlands to the amount necessary to provide a safe workspace;
- Install temporary construction matting or geotextile and stone pads for access roads across wetlands or to establish safe and stable construction work pads within wetlands, where necessary. The type of stabilization measures to be used in wetlands would depend on soil saturation;
- Avoid or minimize access through wetlands to the extent practical. Where access roads must be improved or developed, the roads would be designed, where practical, so as not to interfere with surface water flow or the wetland functions;

- Install and maintain temporary erosion controls around work sites in or near wetlands to minimize the potential for erosion and sedimentation;
- Implement procedures for petroleum product management that would avoid or minimize the potential for spills into wetlands. For example, to the extent practical, store petroleum products in upland areas more than 100 feet from wetlands; refuel construction equipment, except for equipment that cannot be practically moved, in upland areas and if refueling must occur within a wetland, provide temporary containment. Similarly, except for equipment that cannot be practically moved (e.g., cranes), equipment would not typically be parked overnight on access roads or work pads in wetlands;
- Restore structure work sites in – and temporary access ways through – wetlands following the completion of line installation activities; and
- Restore wetlands, after transmission facility construction, to pre-construction configurations and contours to the extent practicable, and stabilize such areas by initial re-vegetation with annual ryegrass or native seed equivalent.

To provide new access across wetlands (where no access road currently exists), Eversource would either construct a new gravel and crushed stone access road underlain by geotextile fabric, or install a timber mat road. In wetlands where there is a deep organic layer or the wetlands are prone to extended inundation, the crushed stone access roads would remain in place permanently to provide a firm base for future access to the transmission facilities. The surficial fill materials used to construct the access roads would be removed down to the pre-construction elevation so as to not interfere with the wetland surface hydrology. The underlying material serves as either a firm base for equipment access or for the future placement of temporary timber mats to cross these larger wetland systems. Eversource anticipates this practice of establishing a permanent “access road base” may occur in some wetland systems. All other timber mat or gravel access roads would be removed in their entirety after construction.

4.2.1.2 Waterbodies

Eversource proposes to avoid direct construction work in watercourses to the extent feasible and to limit the potential for effects associated with erosion, sedimentation, or spills into streams, rivers, and ponds from construction activities. The proposed transmission line conductors would span all major watercourses, and no transmission line structures are proposed for location in waterbodies. However, temporary and possibly permanent access would be required (i.e., use of existing access roads or creation of new access roads) across some of the smaller streams along the ROW.

Along the Proposed Route, no access would be required across the Naugatuck River or any lakes. Instead, the ROW would be accessed from either side of these water crossings.

In contrast, temporary and possibly permanent access across smaller streams along the ROW would be required. However, the installation of new access roads for construction equipment crossings would be minimized to the extent practical. Whenever possible, equipment would use existing (permanent) culverted access roads to traverse watercourses. As part of pre-construction planning, Eversource would conduct integrity inspections of the existing culverted access roads. Culvert structures that are deemed to be either in disrepair or unable to support the weights of the construction equipment would be replaced at the same location and designed to maintain the stream flows. At some stream crossings, new access roads may have to be constructed or existing roads, involving fords, may require culverts or temporary bridges. Any proposed new culvert crossings would be designed and installed in accordance with applicable regulatory requirements.

Alternatively, temporary bridges consisting of timber mats, metal bridges, or equivalent may be used for equipment stream crossings. The temporary bridges would be installed and removed to limit or avoid direct effects to banks and stream-bottom sediments.

Where practical at stream crossings, vegetation removal will be limited to that necessary for the safe construction and operation of the transmission facilities. If possible, vegetation removal near streams would be performed selectively, preserving desirable streamside vegetation within a 25-foot-wide riparian zone adjacent to either stream bank for habitat enhancement, shading, bank stabilization, and erosion/sedimentation control.

Eversource would take the following actions for construction activities across or near watercourses:

- Where existing access roads crossing stream bottoms must be improved, clean materials would be used (e.g., clean riprap or equivalent, rock fords). To the extent possible, the improvement of existing access roads across streams supporting fishery resources would be scheduled to avoid conflicts with fish spawning/migration;
- Water flows (if water is present at the time of construction) would be unconstrained throughout construction; and
- Concrete would not be mixed, placed, or disposed of so as to create the potential to enter a watercourse.

4.2.1.3 Vernal Pools

To avoid or minimize adverse effects on amphibians, Eversource would locate new structures, access roads, and work areas, to the extent practicable, outside of wetlands that provide vernal pool habitat.

Based on the current Project design, no new structures would be located within vernal pool depressions or “cryptic” vernal pool habitat.²¹

In addition, Eversource’s consultants have reviewed Calhoun and Klemens’, *Best Development Practices, Conserving Pool-Breeding Amphibians in Residential and Commercial Developments in the Northeastern United States*.²² While a linear overhead transmission line such as the Project is not entirely consistent with the types of development described in this document, there are conservation issues and management recommendations that are applicable.

Eversource has identified the following types of measures that may be applicable to minimize adverse Project effects on vernal pools:

- Where feasible in areas proximate to vernal pools, adhere to the seasonal windows for tree clearing to avoid adverse effects on amphibians during migration periods.
- Install appropriate erosion and sediment controls around distinct work sites and access roads to minimize the potential for sediment deposition into vernal pools, and remove such controls promptly after final site stabilization.
- For Project activities that must occur adjacent to vernal pools during amphibian migration periods, implement measures on a site-specific basis as necessary to facilitate unencumbered amphibian access to and from vernal pools. Mitigation measures will be identified after taking into consideration site-specific conditions, including the type of construction activity in proximity to a vernal pool, the amphibian species known to occur in the vernal pool, and seasonal conditions. Options to allow amphibian access to vernal pools may include, but not be limited to: syncopated silt fencing in the immediate vicinity of vernal pools; elevated construction matting; and aligning erosion and sedimentation controls to avoid bifurcating vernal pool habitat.
- Evaluate the use of temporary timber mat access roads in wetlands in lieu of constructing gravel access roads in the vicinity of vernal pools.
- Minimize the removal of low-growing vegetation surrounding vernal pools.

The specific measures that would be implemented to protect vernal pool amphibians would be defined in consultation with the involved regulatory agencies (e.g., CT DEEP and the CSC) and would be incorporated into the D&M Plans for the Project.

²¹ Cryptic vernal pools are vernal pools that are contained within larger wetland systems.

²² Calhoun, A.J.K. and M.W. Klemens. 2002 *Best development practices: Conserving pool-breeding amphibians in residential and commercial developments in the northeastern United States*. MCA Technical Paper No. 5, Metropolitan Conservation Alliance, Wildlife Conservation Society, Bronx, New York.

4.2.2 Blasting

If blasting is necessary (e.g., for access, word pads, structure foundations), Eversource would take the following steps:

- A certified blasting specialist would develop site-specific blasting procedures, taking into account geologic conditions and nearby structures, and ensuring compliance with state regulations;
- The blasting plan would be provided to the local Fire Marshal for approval. Blasting charges would be designed to loosen only the material that must be removed to provide a stable foundation, and to avoid fracturing other rock;
- Eversource would seek to meet with each property owner in proximity to the blasting to explain where and when the blasting is expected to occur, and why blasting is necessary;
- Pre-blast surveys, to document existing conditions, would be conducted for any property within a specified distance of the area where blasting is to occur. This distance would be determined by Eversource's blasting contractor, in consultation with the Fire Marshal, and with Eversource's approval;
- The areas where blasting is to occur would be covered with heavy blanketing materials and charges would be sized appropriately;
- Seismographs would measure each blast to confirm that levels are within prescribed limits; and
- Excavated material that cannot otherwise be used at the site would be removed and properly disposed of elsewhere, pursuant to Project specifications.

4.2.3 Soils and Groundwater Testing and Management

4.2.3.1 Pre-Construction Studies and Plans

Soils and groundwater will be managed in accordance with applicable state regulations during the construction of the Project. As part of the final Project design, Eversource would implement specific plans for characterizing the soils and groundwater (i.e., presence/absence of contaminants) along the ROW, and subsequently for handling and managing such materials during construction. These plans would be developed based upon the results of a due diligence review of existing data regarding the current and historical uses of areas along the ROW, properties along the ROW, and nearby off-site sources. The scope of the due diligence work would comply with Sections 8.1 and 8.2 of the American Society for Testing and Materials (ASTM) Standard E1527-05. The objective of the work would be to identify known locations of potential past or current contamination sources, such as leaking underground storage tanks, sites designated as hazardous by federal or state government, and locations of reported spills of petroleum products or hazardous material, etc.

For soil and groundwater testing and management, Eversource would conform to the guidance issued by the CT DEEP for Utility Company Excavation. This guidance applies to cases where contaminated soils /

waste are encountered during construction or maintenance activities on property not owned by the utility and the contamination was not created by the utility. The utility may reuse the contaminated soil in the same excavation, within the same area of concern, without prior approval by CT DEEP provided:

- Any condition that would be a significant environmental hazard, as defined in Connecticut General Statutes Section 22a-6(u), is reported by the utility and that the location is identified on a map submitted to the CT DEEP Remediation Division;
- Any excess contaminated material is disposed of appropriately in accordance with solid and hazardous waste regulations; and
- The upper 1 foot of the excavation is filled with clean fill material or paved.

Construction contractors would be required to conform to CT DEEP requirements and to any Project-specific material handling plans.

4.2.3.2 Soils / Groundwater Handling and Management

The approach used to handle and manage soils disturbed by construction activities would depend on whether or not contamination is present, as determined by the due diligence work described in Section 4.2.3.1.

If the results of investigations indicate that contaminants may exceed acceptable concentrations, Eversource typically would prepare a Project-specific *Material Handling Guideline*, or equivalent, to assist the Contractor in properly handling and disposing potentially impacted soils or groundwater. The *Material Handling Guideline* would be implemented in areas where the excavation of potentially contaminated soils or the dewatering of potentially contaminated groundwater may be necessary during Project construction and would detail the procedures that would be followed to properly handle and manage such materials in order to minimize exposure to the general public and environmental receptors.

Excavated materials to be transported from the ROW would be loaded directly onto trucks for off-site disposal at an appropriate facility, or stockpiled temporarily on-site or at a permitted facility before being disposed at a permanent facility. Soil transported from the ROW would be transported under a Bill of Lading or a Hazardous Waste Manifest, as appropriate. These soils would be disposed of in accordance with the applicable federal, state and local regulations.

4.2.4 Groundwater and Construction Site Dewatering

Neither the construction nor the operation of the Project is expected to result in adverse effects on groundwater resources or public water supplies. During construction, care would be taken to avoid effects to municipal water lines that may be located within road ROWs or that otherwise extend across the transmission line ROW.

If groundwater is encountered during excavations for transmission line structure foundations, the water would be pumped from the excavated areas and discharged in accordance with applicable local and state requirements. Depending on regulatory authorizations, the water may be discharged on-site into an appropriate sediment control basin/filter bag or directly into municipal storm water catch basins, if available. Proper catch-basin inlet protection would be installed as needed to prevent disturbed soils excavate and construction debris from entering storm water systems.

Contaminated groundwater; if encountered, may require treatment before being discharged to either the storm water or municipal sanitary sewer system. Contaminated groundwater may also be pumped into a temporary fractionation (frac) tank and then pumped into a tanker truck for disposal at appropriate wastewater treatment facilities. Residual silt/sediment collected at the bottom of the frac tanks would be disposed off-site at an appropriately designated disposal facility.

4.3 CONSTRUCTION PROCEDURES FOR SUBSTATION MODIFICATIONS

4.3.1 Overview of Proposed Construction at Stations

The proposed Project will involve modifications to Eversource's Frost Bridge and Campville substations.

The actual sequence of construction activities and methods of construction will vary for each station, based upon the specific engineering design ultimately developed for the substation modifications and the extent of work required at each site. Furthermore, more detailed construction requirements and, as appropriate, environmental mitigation measures specific to each substation, may be defined during the Council's Project review process.

The following summarizes the general sequential, phased, approach expected to be used in modifying these existing stations.

4.3.2 Site Preparation

The type of site preparation work required at each site would vary, in accordance with the characteristics of each station and the areas proposed for the facility modifications. Site preparation work may include:

- Establishing construction offices and material staging sites (either on or off the existing substation properties)
- Installing and maintaining, as necessary, temporary soil erosion and sedimentation controls (e.g., silt fence, hay/straw bales) around areas of planned soil disturbance
- Removing minimal vegetation (if present) from work areas and equipment staging locations
- Creating temporary access to the sites for heavy construction equipment
- Grading (rough), if necessary, to create level work areas
- Excavating unsuitable soils
- Installing protective fencing around work sites

Site preparation work typically could involve the use of construction equipment such as bulldozers, backhoes, man-lift vehicles, compressors, trucks (various sizes), a large capacity crane (e.g., 100-ton), and flat-bed trailers.

4.3.3 Foundations and Equipment Installation

The foundation installation process generally involves excavation, form work, use of steel reinforcement, and concrete placement. Excavated material would either be reused on-site or disposed of off-site in accordance with applicable requirements.

If groundwater is encountered in excavations, the procedures described in Section 4.2.4 would be followed. Similarly, if contaminated soils are encountered, the procedures summarized in Section 4.2.3.1 would be followed.

After the foundations are installed, construction activities would shift to the erection of structures and equipment as specified for each station modification. Such structures and equipment include steel structures, bus and insulators, circuit breakers, switches, voltage transformers, lightning masts, relay / control enclosures or expansion of existing enclosures, cable trench, ground grid, surge arresters, conduits and cables.

4.3.4 Testing and Interconnections

New structures and associated conductors and wires would be installed, as necessary, to connect the new 115-kV facilities at the substations. All of the substation equipment would be commission-tested prior to final connection to the transmission grid.

4.3.5 Final Cleanup, Site Security, and Landscaping

After the completion of construction, any remaining construction debris would be collected and removed from the station sites. Temporary erosion controls would be maintained until the disturbed areas are satisfactorily stabilized.

Because the proposed Project modifications would be within the developed (fenced) area at Frost Bridge Substation and would require only a minor (0.4-acre) expansion of the Campville Substation, landscaping is not expected to be warranted.

4.4 OPERATION AND MAINTENANCE PROCEDURES

4.4.1 ROW Vegetation Management

Eversource's long-term vegetation management program includes the selective removal of targeted species (e.g., tall growing trees and selected state-listed invasive woody shrubs) within the portions of its ROWs occupied by transmission lines. In addition to tree removal within the ROW, hazard trees adjacent to the managed ROW that could fall onto a conductor will be trimmed or removed. Brush control within Eversource's ROWs is performed every four years, and side trimming (i.e., removal of trees or tree limbs that encroach along the edge of the managed ROW) is performed every 10 years. All work is performed in accordance with Eversource's *Specification for Rights-of-Way Vegetation Management (2015)*.

In addition, based on recent experience in the development of other new transmission line facilities, Eversource anticipates that a *Wetland Invasive Species Control Plan*, or similar documentation of an approach for the control of invasive species in wetlands along the ROW, would be required for the Project. The *Wetland Invasive Species Control Plan* (or equivalent) would be developed after consultations with the USACE, CT DEEP, and other involved agencies regarding the types of wetland invasive species to be targeted for control along the Project ROW and the overall objectives of the control program. Typically, the *Wetland Invasive Species Control Plan* is prepared as part of Eversource's regulatory applications to the USACE and CT DEEP.

4.4.2 Substation Maintenance

The proposed Project modifications to the Frost Bridge and Campville substations would not substantially affect or alter existing maintenance practices at these existing facilities.

4.4.3 Compliance with Applicable Codes and Standards

The proposed Project would be constructed in full compliance with the National Electrical Safety Code (NESC), standards of the Institute of Electrical and Electronic Engineers (IEEE) and the American National Standards Institute (ANSI), good utility practice, and the CT DEEP PURA regulations covering the method and manner of high voltage line construction.

4.4.3.1 Emergency Operations and Shutdown

If a transmission line experiences an insulation or conductor failure, then high-speed protective relaying would immediately remove the line from service, thereby protecting the public and the line. If equipment at the substations experiences a failure, then protective relaying would immediately remove the equipment from service, thereby protecting the public and the equipment within the substations.

Protective relaying equipment would be incorporated into the Project design to automatically detect abnormal system conditions and send a protective trip signal to the respective circuit breaker(s) at each end of a line to isolate the faulted section of the transmission system. The protective relaying schemes include fully redundant primary and backup equipment. This ensures that if a line or station equipment failure were to occur at a time when one of the protective relaying schemes fails or is removed from service for maintenance, the redundant protective relaying scheme would initiate the removal from service of the faulted transmission facility being monitored.

Fiber optic strands will be installed within the lightning shield wires above the overhead line. These strands provide a robust and reliable communications path for the protective relaying systems.

Additionally, the overhead transmission line facilities may also provide for electronic communications between substations using signals impressed upon line conductors ("carrier signal") for protective relaying and operations.

4.4.3.2 Fire Suppression Technology

Fire/smoke detection systems are already in place in the existing relay and control enclosures at Frost Bridge Substation. The existing relay and control enclosure at Campville Substation does not have a fire/smoke detection system. However, as part of the Project, the Campville substation will require a new

control building to house DC battery banks, along with applicable chargers and other miscellaneous equipment. This new building will be equipped with fire suppression systems as specified in Eversource standard SUB022.701 REV 0 4/27/2007 and SUB022.712 REV 0 3/19/2007. The standards detail power supply sources, smoke detector locations, control panel requirements, and wiring requirements for a fire suppression system. In addition, fire extinguisher types, mounting locations, and replacement criteria are outlined. In the event that fire or smoke is detected, these fire/smoke detection systems would automatically activate an alarm at the Connecticut Valley Electric Exchange (CONVEX), and the system operators then would take the appropriate action. The relay/control enclosures at each station are equipped with fire extinguishers.

The new protective relaying and associated equipment within the substations, along with a Supervisory Control and Data Acquisition (SCADA) system for remote control and equipment monitoring, would be installed in the existing relay and control enclosures.

4.4.4 Security of Facilities

Pursuant to Section VI.N.4 of the Council's *Application Guide*, a description of siting security measures for the proposed Project facilities, consistent with the Council's "White Paper on the Security of Siting Energy Facilities", will be prepared. This facilities security description will be included in the Application.

5. DESCRIPTION OF EXISTING ENVIRONMENT

This section describes the existing environment and cultural resources along, and in the vicinity of, the Proposed Route. Section 5.1 discusses the environmental conditions in the vicinity of the proposed new 115-kV transmission line and double-circuit separation. Section 5.2 presents existing environmental conditions at the Frost Bridge and Campville Substations. The information concerning these existing environmental and cultural features reflects the results of baseline data research, as well as field investigations conducted along the Project ROW in 2009 (as part of the initial planning for a new 345-kV line that was not advanced for development) and again in 2015 (for this Project).

Two sets of aerial-photography based maps depicting the environmental and cultural conditions in the Proposed Route were prepared: the Volume 5, 400 scale maps show the proposed Project facilities in relation to environmental features in the surrounding areas, whereas the Volume 5, 100 scale maps provide a closer view of the conditions in the immediate vicinity of the proposed Project facilities. The principal environmental conditions, land use features, and natural resources shown on the Project maps include, but not are limited to:

- Location of the existing ROW, transmission line structures access roads, and work pads, as well as the Frost Bridge and Campville substations and junctions with other Eversource transmission lines;
- Location of Eversource fee-owned properties;
- Vegetative cover types;
- Areas of steep slopes;
- Land uses, including agricultural, residential, commercial, and industrial areas;
- Municipal boundaries;
- Municipal zoning classifications;
- Federal and state jurisdictional wetlands;
- Vernal pools;
- Water resources, including streams, rivers, and ponds;
- Floodplains, as designated by the Federal Emergency Management Agency ([FEMA]; Special Flood Hazard Areas²³)

²³ Special Flood Hazard Areas are defined as the area that will be inundated by the flood event having a 1-% chance of being equaled or exceeded in any given year. The 1-% annual chance flood is also referred to as the 100-year flood.

- Public recreational, scenic, open space, and other protected areas, including forests, parks, water supply areas, hunting/wildlife management areas, and designated recreational trails;
- Schools and community facilities; and
- Existing infrastructure, including roads, utility corridors, and railroads.

5.1 PROPOSED ROUTE: FROST BRIDGE SUBSTATION TO CAMPVILLE SUBSTATION

The Proposed Route traverses approximately 10.4 miles in a general northerly to northeasterly direction, extending between Eversource's existing Frost Bridge and Campville substations following an existing Eversource ROW, through portions of the towns of Watertown, Thomaston, Litchfield, and Harwinton, in Litchfield County. Along a portion of the route in Watertown, the ROW also includes a 345-kV line.

5.1.1 Topography, Geology and Soils

The information presented below is based on analyses of existing published information and – in the case of soils – field investigations conducted as part of wetland surveys. Prior to final engineering design, additional investigations will be performed in some areas along the Proposed Route to further characterize the physical and structural characteristics of the subsurface geologic features. The results of such investigations may be used in the design of structure foundations.

5.1.1.1 Topography

The Proposed Route is situated within the Northwest Hills physiographic region of Connecticut.²⁴ This region is characterized moderately hilly glacial till dominated landscapes of intermediate elevation with narrow glacial outwash valleys and local areas of steep and rugged terrain. Elevations throughout the Proposed Route range from approximately 300 feet in Watertown to 880 feet in Litchfield. The Proposed Route does not traverse any traprock ridge²⁵ or amphibolite ridge²⁶ areas as specified in Connecticut

²⁴ Dowhan, J.J., and R.J. Craig. 1976. *Rare and Endangered Species of Connecticut and Their Habitats*. State Geological and Natural History Survey of Connecticut, Department of Environmental Protection. Report of Investigations No. 6. 137 p.

²⁵ According to definitions provided in the Connecticut General Statutes, Chapter 124, § 8-1aa, "traprock ridge" means Beacon Hill, Saltonstall Mountain, Totoket Mountain, Pistapaug Mountain, Fowler Mountain, Beseck Mountain, Higby Mountain, Chauncey Peak, Lamentation Mountain, Cathole Mountain, South Mountain, East Peak, West Peak, Short Mountain, Ragged Mountain, Bradley Mountain, Pinnacle Rock, Rattlesnake Mountain, Talcott Mountain, Hatchett Hill, Peak Mountain, West Suffield Mountain, Cedar Mountain, East Rock, Mount Sanford, Prospect Ridge, Peck Mountain, West Rock, Sleeping Giant, Pond Ledge Hill, Onion Mountain, The Sugarloaf, The Hedgehog, West Mountains, The Knolls, Barndoor Hills, Stony Hill, Manitook Mountain, Rattlesnake Hill, Durkee Hill, East Hill, Rag Land, Bear Hill, Orenaug Hills.

²⁶ According to definitions provided C.G.S. § 8-1aa, "amphibolite ridge" means Huckleberry Hill, East Hill, Ratlum Hill, Mount Hoar, Sweetheart Mountain.

General Statutes (CGS) § 8-1aa (1) and no such geologic formations are located within the Project area towns. Following Eversource's existing ROW, the Proposed Route generally does not parallel ridgelines.²⁷

5.1.1.2 Geology

Connecticut's bedrock geology has a direct effect on landscape forms due to differing resistances to weathering and erosion. Bedrock geologic mapping²⁸ indicates that the Proposed Route traverses extensive areas of schist bedrock (e.g., Taine Mountain formation), and exhibits north-trending belts and outcrops.

The predominant surficial deposit along the Proposed Route is shallow till in moderate to strongly sloping bedrock-controlled topography. Where these deposits are present, the slopes and outline of the landform generally reflect the form of the underlying bedrock, which is draped by a shallow mantle of till. Till thicknesses overlying the bedrock are generally less than 15 feet and may include frequent bedrock outcrops. Bedrock is frequently exposed or shallow (within four feet of the ground surface) in the following sections of the ROW that are characterized by steeply-sloping terrain:

- From the southern terminus of the Project at Frost Bridge Substation to Park Road in Watertown;
- From Thomaston Road (U.S. Route 6) in Watertown to Mason Hill Road in Litchfield (including through Black Rock Park in Watertown, where bedrock outcrops are common); and
- West of Route 8 in Litchfield and east of the Naugatuck River bottomlands to Wildcat Hill Road in Harwinton.

Deep till deposits occur where glacial ice overriding the land surface pushed up rounded hills oriented along the localized travel direction of the last continental ice sheet. These rounded hills, or drumlins, generally have till depths exceeding 15 feet and depths of 100 feet are not uncommon.²⁹ The ROW traverses deep till deposits along Campville Road in Litchfield.

²⁷ According to definitions provided in C.G.S. § 8-1aa, "ridgeline" means the line on a traprock or amphibolite ridge created by all points at the top of a 50% slope, which is maintained for a distance of 50 horizontal feet perpendicular to the slope and which consists of surficial basalt geology, identified on the map prepared by Stone et al., United States Geological Survey, entitled "Surficial Materials Map of Connecticut".

²⁸ Rodgers, J. 1985. *Bedrock Geologic Map of Connecticut*. Connecticut Geological and Natural History Survey, CT Department of Environmental Protection. Hartford CT. 1:125,000.

²⁹ Melvin, R.L., Stone, B.D., Stone, J.R., and N.J. Trask. 1992. *Hydrogeology of Thick Till Deposits in Connecticut*. U.S. Geological Survey Open-File Report. p. 92-43.

Glacial outwash deposits, typically characterized by stratified sand and gravel, were derived from meltwater streams flowing from retreating glacial ice. Along the Proposed Route, outwash deposits are associated with the Naugatuck River Valley in Watertown, Litchfield, and Harwinton. Bedrock depths generally exceed 30 feet beneath these sand and gravel deposits and are often more than 100 feet below the ground surface. Floodplain deposits are also associated with the Naugatuck River Valley in Watertown, Litchfield, and Harwinton. Bedrock is generally deep (greater than 30 feet) beneath these deposits.

5.1.1.3 Soils

Information regarding the soils along the Proposed Route was obtained from on-line soil surveys and maps published by the U.S. Department of Agriculture (USDA), Natural Resources Conservation Service (NRCS).³⁰ These surveys and maps provide soil classifications and characteristics, including depth to bedrock, slope, drainage, and erosion potential. Table 5-8 (which is located at the end of this Section due to its length) summarizes the principal soil associations, as identified by the NRCS along and in the general vicinity of the Proposed Route. The table also identifies soils classified by the NRCS as “Prime Farmland” soils or “Farmlands of Statewide Importance”.

The baseline soils information obtained from the NRCS maps and surveys is a supplement to the field investigations that are required to identify Connecticut wetlands, which are defined based on the presence of poorly drained, very poorly drained, or floodplain soils. Wetlands along the Proposed Route were delineated by registered professional soil and wetland scientists, working along with biologists, as part of field studies conducted along the ROW in 2009 and again in 2015.

5.1.2 Water Resources

Water resources along the existing Eversource ROW include inland wetlands, watercourses (intermittent and perennial streams and rivers), waterbodies (ponds), and groundwater resources, including public water supplies and floodplains. Eversource commissioned both baseline research to identify Project area water resources, and field investigations to delineate state and federal wetlands and watercourses along the Proposed Route.

In April and May of 2015, Eversource’s consultants delineated water resource areas along the Proposed Route. Consultants delineated water resources along the entire width of the Eversource ROW within which the new 115-kV transmission line would be located. During the delineations, wetlands and

³⁰ Web Soil Survey, accessed 2015.

watercourses were field-demarcated using numbered flagging. These boundary flags were subsequently surveyed using a Trimble Global Positioning System (GPS) survey unit. Resource areas are depicted on the Volume 5 maps, summarized in Table 5-9 (which is provided at the end of this section due to its length), and described in detail in the *Wetlands and Watercourses Report* in Volume 2.

5.1.2.1 Drainage Basins and Waterbodies

Connecticut is divided geographically into eight major drainage basins and 45 regional basins. The Proposed Route is located in portions of the Housatonic (major) drainage basin. This basin is characterized by watercourses that flow into the Housatonic River, which flows in a south to southeasterly direction from western Massachusetts and discharges to Long Island Sound at Milford Point, Connecticut. The Proposed Route is located within the Naugatuck River regional drainage basin.

CT DEEP maintains detailed water resources information concerning the drainage basins in Connecticut and promotes watershed management efforts to improve water quality. As a central element of the state's clean water program, the CT DEEP also has established Water Quality Standards and Classifications, which identify the water quality management objectives for each waterbody.

Overall, Connecticut's water quality policies are established to protect surface and groundwater from degradation; restore degraded surface waters to conditions suitable for fishing and swimming; restore degraded surface and groundwater to protect existing and designated uses; and to provide a framework for establishing priorities for pollution abatement. The use goals that the state has established for surface waters and groundwater are summarized in Table 5-1.

Table 5-1: Summary of Connecticut Water Use Goals

Water resource	Classification use description
Surface Waters	
Class AA	Public water supply, fish and wildlife habitat, recreation.
Class A	Potential public water supply, fish and wildlife habitat, recreation, industrial water supply, agricultural water supply.
Class B	Fish and wildlife habitat, recreation, industrial water supply, agricultural water supply, discharge of treated wastewaters.
Class C, D	Goal is Class B. Impaired water quality affecting one or more Class B uses.
Ground Waters	
Class GAA	Public water supply.
Class GAAs	Existing or potential public supply, stream base flow industrial and miscellaneous, tributary to a public reservoir. Natural quality, or suitable for drinking
Class GA	Existing private water supply and potential public water supply suitable for drinking without treatment.
Class GB	Industrial water supply and miscellaneous non-drinking supply.
Class GC	Assimilation of wastes, such as landfill leachate.

The Proposed Route crosses a total of 58 watercourses (including waterbodies). Of these, 20 are perennial streams, rivers, or ponds and 38 are intermittent watercourses. Table 5-10 (located at the end of this section due to its length) provides a summary of major characteristics, including surface water classifications, of the delineated watercourses and waterbodies along the Proposed Route.

Three of the identified perennial watercourses average greater than 20 feet wide and are named brooks or rivers. These include Branch Brook, Northfield Brook, and the Naugatuck River. At Eversource's existing ROW crossing in Litchfield and Harwinton, the Naugatuck River is an estimated 110 feet wide. None of the watercourses crossed by the Proposed Route met the criteria for federal designation as navigable³¹ pursuant to Section 10 of the Rivers and Harbors Act. All of these watercourses are presently spanned by Eversource's overhead transmission lines that occupy the existing ROW along which the Proposed Route would be located.

Of the 23 perennial water crossings along the Proposed Route, six are ponds, as detailed below.

³¹ The USACE's general definition of navigable waters of the United States is "those waters subject to the ebb and flow of the tide shoreward to the mean high water mark and/or presently used, or have been used in the past, or may be susceptible for use to transport interstate or foreign commerce." Waterways considered to be navigable waters may be subject to regulatory jurisdiction under Section 10 of the Rivers and Harbors Act.

- Town of Watertown: two unnamed ponds (one located east of Nova Scotia Hill Road, and one located east of Thomaston Road/U.S. Route 6).
- Town of Thomaston: Morton Pond located east of Old Northfield Road.
- Town of Litchfield: two unnamed ponds (one located south of Campville Road, and one located south of State Route 8).
- Town of Harwinton: one unnamed pond located south of Wildcat Hill Road.

These unnamed ponds include natural areas of standing water, man-made agricultural and recreational ponds, and beaver ponds. All of these water resources are already spanned by Eversource's overhead transmission lines that occupy the existing ROW along the Proposed Route.

The Proposed Route does not cross any rivers designated as a National Wild and Scenic River under the National Wild and Scenic Rivers Act (16 U.S.C. §§ 1271-1287). The Connecticut Protected Rivers Act (CGS §§ 25-200 through 25-210) requires CT DEEP to adopt a list of rivers in the state considered appropriate for designation as protected river corridors. To date, the CT DEEP has not designated any rivers along the Proposed Route under the Protected Rivers Act.

5.1.2.2 Wetlands

As identified in Table 5-9, a total of 91 wetlands were delineated within Eversource's easements or fee-owned properties in proximity to Project activities. An additional 4 wetlands were delineated along publically accessible (State Park/Forest) off-ROW access roads that are proposed for use. Of the total 95 wetlands delineated, 48 would be within the portions of the ROW traversed by the new transmission line.³² The maps in Volume 5 illustrate the locations of the wetlands along the Proposed Route.

State jurisdictional wetlands were characterized using Connecticut delineation methodology pursuant to the Connecticut Inland Wetlands and Watercourses Act, CGS §§ 22a-36 through 22a-45 (the Act). The Act defines a wetland as land, including submerged land, consisting of poorly drained, very poorly drained, alluvial, and floodplain soils as defined by the USDA Cooperative Soil Survey. Such areas may include filled, graded, or excavated sites possessing an aquic (saturated) moisture regime as defined by the USDA Cooperative Soil Survey. The Act defines watercourses as rivers, streams, brooks, waterways, lakes, ponds, marshes, swamps, bogs, and also other bodies of water, natural or artificial, public or private, contained within, flow through or border upon the state, or any portion thereof.

³² The 48 wetlands are those located within the footprint of the new 115-kV line

As part of the Project field investigations, federal jurisdictional wetlands were delineated in accordance with the USACE's *Wetland Delineation Manual* (Technical Report Y-87-1, "1987 USACE Manual") and *Regional Supplement to the Corps of Engineers Delineation Manual*³³ (Regional Supplement) and *Field Indicators for Identifying Hydric Soils in New England, Version 3*.³⁴ According to the 1987 USACE Manual, areas must exhibit three distinct characteristics to be considered federal jurisdictional wetlands:

1. **Vegetation.** The prevalent vegetation must consist of plants adapted to life in hydric soil conditions. These species, due to morphological, physiological, and/or reproductive adaptations, can and do persist in anaerobic soil conditions.
2. **Hydric Soils.** Soils in wetlands must be classified as hydric or they must possess characteristics associated with reducing soil conditions (typically resulting in redoximorphic features or gleyed soils).
3. **Hydrology.** The soil must be inundated either permanently or periodically at mean water depths less than 6.6 feet (2 meters) or the soil must be saturated at the surface for some time during the growing season of the prevalent vegetation.

Wetlands meeting the above technical criteria and determined to be traditional navigable waters, tributaries to traditional navigable waters, or wetlands exhibiting significant nexus are subject to federal jurisdiction under Section 404 of the Federal Clean Water Act (33CFR 320-332).

For the purpose of documenting and organizing the water resource information on tables and maps for the Project, groups of wetlands occurring along the ROW between selected road crossings were identified by letters of the alphabet A through G³⁵. Wetlands within each segment were then labeled in an alpha-numeric sequence (e.g., W-A1, W-A2, W-A3). Watercourses were numbered independently of the wetlands and prefixed by the letter S.

Wetlands that were considered to be hydrologically connected to, or part of a larger ecological functional unit were typically included within the same alpha-numeric label. Frequently, wetlands that appear to lack direct surface water connectivity (such as those bisected by historic disturbance activities such as

³³ Wetlands Regulatory Assistance Program. (2102). *Regional Supplement to the Corps of Engineers Wetlands Delineation Manual: Northcentral and Northeast*, U.S. Army Engineer Research and Development Center, Vicksburg, MS

³⁴ New England Hydric Soils Technical Committee. 2004. *Field Indicators for Identifying Hydric Soils in New England, 3rd ed.*. New England Interstate Water Pollution Control Commission, Lowell, MA.

³⁵ Wetlands in the vicinity of the Frost Bridge Substation were identified with the letters FB. Wetlands identified along an existing access road in Mattatuck State Forest (off Echo Lake Road) were identified with the letters MSF. Wetlands identified with the letter A, or "A - Series" wetlands begin at Echo Lake Road (Watertown); B - Series at Park Road (Watertown); C - Series at Thomaston Road-Route 6 (Watertown); D - Series at Branch Road-Route 109 (Thomaston); E - Series at Northfield Road-Route 254 (Thomaston); F - Series at Campville Road (Litchfield); and G - Series at Wildcat Hill Road (Harwinton).

road construction) were included under the same wetland label if they were considered to be part of the same hydrologic system. A similar approach was taken for small wetlands arrayed along the length of a connecting watercourse.

Due to differences in state and federal wetland delineation criteria and methodology, the boundaries of state and federal jurisdictional wetlands do not correspond in all cases. For example, in Connecticut, areas of alluvial and floodplain soils, which may not include hydric soils or exhibit evidence of wetland hydrology, are characterized as state, but not federal, jurisdictional wetlands. For the most part, however, the state and federal wetland boundaries along the Proposed Route are comparable. Of the 95 wetlands delineated along the Eversource ROW, portions of only two wetlands located within the Naugatuck River floodplain, in Watertown and Litchfield, were identified as being strictly state jurisdictional (refer to Volume 5 maps).

In accordance with *Classification of Wetlands and Deepwater Habitats of the United States* (Cowardin et al., 1979), wetlands delineated for the proposed Project were classified as palustrine³⁶ forested (PFO), palustrine scrub-shrub (PSS), palustrine emergent (PEM), palustrine open water (POW), and palustrine unconsolidated bottom (PUB).

These wetland classifications are characterized as follows:

- **Palustrine Forested Wetlands (PFO):** Forested wetlands are characterized by woody vegetation that is 6 meters (approximately 20 feet) tall or taller and normally includes an overstory of trees, an understory of young trees or shrubs and an herbaceous layer. These wetland types are located predominantly in the unmanaged areas of the existing ROW or in adjacent off-ROW areas.
- **Palustrine Scrub-Shrub Wetlands (PSS):** Scrub-shrub wetlands are typically dominated by woody vegetation less than 6 meters (approximately 20 feet) tall. Scrub-shrub wetland types may represent a successional stage leading to a forested wetland and include shrubs, saplings, and trees or shrubs that are small and/or stunted due to environmental conditions or human vegetation management practices.
- **Palustrine Emergent Wetlands (PEM):** Emergent wetlands are characterized by erect, rooted, herbaceous hydrophytes not including mosses and lichens. These wetlands maintain the same appearance year after year, are typically dominated by perennial plants, and the vegetation of these wetlands is present for the majority of the growing season.

³⁶ Palustrine wetlands are wetlands occurring in the Palustrine System, one of five systems in the classification of wetlands and deepwater habitats. Palustrine wetlands include all non-tidal wetlands dominated by trees, shrubs, persistent emergent plants, or emergent mosses or lichens, as well as small, shallow open water ponds or potholes. Palustrine wetlands are often referred to as swamps, marshes, potholes, bogs, or fens.

- **Palustrine Open Water (POW):** Areas of permanent open water that border on palustrine systems are referred to as POW. Area of open water may exist as man-made or natural waterbodies.
- **Palustrine Unconsolidated Bottom (PUB):** Areas of open water with unconsolidated bottoms that border on palustrine systems are referred to as PUB.

Some wetlands along the Proposed Route exhibit more than one wetland classification type (i.e., PFO / PSS) or have inclusions of multiple vegetative cover types. In such situations, transitions between wetland types are demarcated on the maps in Volume 5 and cover types are categorized by the most dominant classification type.

The results of the wetland field surveys demonstrate that wetland types within Eversource's existing ROW vary. Many of the wetlands along the ROW have been historically affected by maintenance of the ROW which enables low-growing vegetation to insure the safe operation of the existing overhead transmission lines. The majority of the wetlands in the ROW are well-vegetated and dominated by PSS and shallow PEM communities. The majority of the PSS and PEM wetlands located on the managed portions of the ROW also extend into adjacent areas or in currently unmanaged portions of the ROW, transitioning into PFO wetlands characterized by mixed hardwood deciduous and coniferous forested vegetation.

5.1.2.3 Groundwater Resources, Public Water Supplies, and Aquifer Protection Areas

In the vicinity of the Proposed Route, potable water is derived from groundwater wells and surface water supplies or reservoirs. For the most part, in the vicinity of the Proposed Route, the groundwater quality is classified as "GA" (i.e., existing private water supply and potential public water supply suitable for drinking without treatment).

CT DEEP's Aquifer Protection Area Program identifies Level A and Level B Aquifer Protection Areas by municipality. Aquifer Protection Areas are delineated for active public water supply wells in stratified drift that serve more than 1,000 people, in accordance with C.G.S. § 22a-354c and §22a-354z. Level A mapping delineates the final Aquifer Protection Area, which becomes the regulatory boundary for land use controls designated to protect the well from contamination. Level B mapping delineates a preliminary Aquifer Protection Area, providing an estimate of the land use controls designated to protect the well from contamination.

According to the CT DEEP, the Proposed Route does not traverse any designated Aquifer Protection Areas.³⁷ The closest such area is Reynolds Bridge, a Level A Aquifer Protection Area located approximately 0.48 miles east of the Proposed Route where it crosses Branch Road (Route 109).

The water quality of surface water reservoirs is also protected by the Connecticut Public Health Code (PHC.). PHC Section 25-37c-1 and 2 establishes criteria for classification of water company-owned land and provides definitions for classes of land warranting different levels of protection. Section 25-37d-1 of the PHC establishes a process for permitting changes in ownership or the land use of watershed lands owned by water companies. Review standards require the Commissioner of Public Health to determine that the action would not have a significant adverse impact upon the purity and adequacy of the public drinking water supply before a permit for such an action may be issued.

The following list identifies the drinking water supplies for the towns along the Proposed Route.³⁸

- **Watertown** – Watertown is served by a combination of public wells with a public water supply system in the “downtown” portion of town and by private groundwater wells in the more rural sections of town. Reynolds Bridge, a Level A Aquifer Protection Area, is located approximately 0.48 miles east of the Proposed Route near the Watertown / Thomaston town lines. The groundwater in the vicinity of the route is classified as “GA³⁹” or “GAA⁴⁰”. Portions of the Town of Watertown are mapped as a public water supply watershed (Waterbury Water Department) and located approximately 0.95 mile west of the Proposed Route where it crosses Black Rock State Park north of Thomaston Road (Route 6).
- **Thomaston** – Thomaston is served by a large-scale community well, managed by the Connecticut Water Company for water supply in portions of the town, and private groundwater wells that provide water supply to the remainder of the town. Reynolds Bridge, a Level AA Aquifer Protection Area, is located approximately 0.48 miles east of the Proposed Route near the Watertown / Thomaston town lines. The groundwater in the vicinity of the route is classified as “GA” or “GAA”. Portions of the Town of Thomaston are mapped as a public water supply watershed (Waterbury Water Department) and located approximately 1.25 miles west of the Proposed Route where it crosses Walnut Hill Road.
- **Litchfield** – The “downtown” portion of Litchfield, which is located more than 5 miles to the west/northwest of the Proposed Route, is served by a community well system managed by Aquarion and the remainder of the town is served by private groundwater wells in the more rural sections of the town. The Proposed Route does not cross any mapped Aquifer Protection Areas.

³⁷ CT DEEP Aquifer Protection Area Maps: (Accessed July 2015)

³⁸ Information on groundwater quality and municipal water supplies was obtained from CT DEEP Geographic Information System Ground Water Quality Classifications, Town and State websites accessed July, 2015

³⁹ Designated uses: existing private and potential public or private supplies of water suitable for drinking without treatment; baseflow for hydraulically connected surface water bodies.

⁴⁰ Designated uses: existing or potential public supply of water suitable for drinking without treatment; baseflow for hydraulically connected surface water bodies.

The groundwater in the vicinity of the route is classified as “GA”.⁴¹ Portions of the Town of Litchfield are mapped as a public water supply watershed (Waterbury Water Department) and located approximately 1.50 miles west of the Proposed Route where it crosses Mason Hill Road. However, the Proposed Route is entirely within the Naugatuck River Watershed and does not drain towards a public water supply watershed.

- **Harwinton** – Harwinton is served by a combination of community wells in the more populated areas of town, with private groundwater wells providing water supply to the remainder of the town. The Proposed Route does not cross through a public water supply watershed or mapped Aquifer Protection Area. The groundwater along the preferred line route is rated “GA”.

5.1.2.4 Flood Zones

The FEMA classifies flood zones for insurance and floodplain management purposes and has prepared maps designating certain areas according to the frequency of flooding. An area within the 100-year flood designation has a 1% chance of flooding each year or is expected to flood at least once every 100 years.

A review of FEMA maps indicates that the Proposed Route extends across 100-year flood zones associated with three watercourses, including Branch Brook in Watertown, Northfield Brook in Thomaston, and the Naugatuck River along the Litchfield and Harwinton town lines. These watercourses, as well as their 100-year flood zone boundaries, are depicted on the Volume 5 maps. There are no existing structures located within a 100-year floodplain along the Proposed Route.

5.1.3 Biological Resources

5.1.3.1 Vegetative Communities

Vegetation along the Proposed Route consists of a mix of associations and cover types, providing a variety of wildlife habitats. The width of the ROW along which vegetation is currently managed to ensure consistency with existing transmission line use and clearance requirements ranges from approximately 90 feet to 400 feet. The remaining areas within Eversource’s existing ROW are currently unmanaged and generally comprised of forest land.

⁴¹ Town of Litchfield, Connecticut. Litchfield Plan of Conservation and Development. Adopted by the Litchfield Planning and Zoning Commission June 4, 2007.

Eight habitat types/land uses were documented within 200 feet of the Project ROW within which the proposed 115-kV transmission line would be aligned, as illustrated on the Volume 5 maps⁴² and detailed below.

- **Old Field/Shrub land:** This habitat type includes the existing managed ROW in most areas as well as adjacent abandoned fields, natural shrub lands, and early successional forests.
- **Upland Forest:** This forest type includes mature mixed deciduous/coniferous forests adjacent to the existing ROW in upland areas. Mature mixed forests consist typically of tree species common to the Northeast such as maples, oaks, hickories, spruce, and pine. The ratio of deciduous to coniferous species and age of stands varies.
- **Forested Wetland:** Forested wetlands generally include swamps dominated by a mature canopy including deciduous and coniferous trees.
- **Scrub-Shrub Wetland:** Shrub swamp areas exist either within or adjacent to the existing ROW. These types of wetlands typically include components of emergent marsh, where shrub coverage is substantial.
- **Emergent Wetland:** Emergent marshes are dominated by herbaceous wetland plant species.
- **Open Water:** This includes substantial areas of open water found along the existing ROW such as, ponds and large streams/rivers, with the vegetation found along the shorelines of these areas. Most open water areas would be spanned, with no clearing required.
- **Agricultural Lands:** This includes cultivated fields, croplands, hay fields, pastures, and orchards in active agricultural use.
- **Urban Areas:** Urban areas refer to suburban and urban residential developments, subdivisions, areas developed for industrial or commercial use, recreational areas such as parks and golf courses, maintained lawns, and roadside vegetation.

In accordance with Eversource's ROW vegetation management program, woody vegetation that could interfere with the operation of the overhead transmission lines is periodically removed from the managed portion of the ROW, and trees located along the edges of the managed ROW are periodically trimmed or removed. The vegetation within the ROW is managed on an approximate five-year rotating basis.

As a result of Eversource's vegetation management program, the predominant vegetation types within the managed portions of the transmission line ROW consist of dense shrub and herbaceous species (old field/shrubland). In New England, old field/shrubland areas are often disturbance-dependent and ephemeral. Historically, the occurrence and distribution of shrublands and other early successional cover types were largely influenced by humans. The widespread abandonment of farms in the early 20th

⁴² Note that the habitat types are specifically identified only on the Volume 5, 100 scale maps. However, vegetation can generally be discerned on the Volume 5, 100 scale maps, which provide a more detailed view of the location of the proposed 115-kV line in relation to the managed portions of Eversource's ROW.

Century, along with increases in suburban development and fire suppression, has led to a consistent decline in the area of early successional cover types over the last century and the subsequent decline in several wildlife species dependent on this habitat.⁴³

5.1.3.2 Wildlife and Fisheries Resources

This section describes the general wildlife resources expected to be common in the vicinity of the Proposed Route, and then presents specific location information, including data developed as a result of research and field investigations within the ROW.

5.1.3.2.1 General Wildlife Description

The following summarizes the wildlife habitats and some of the species that commonly occur in the vegetative communities found along and in the vicinity of the Proposed Route

- **Upland Forest:** Forests in Southern New England support a wide array of wildlife and is the dominant cover type in the State. Typically common mammalian species in forested habitats include a variety of rodents (e.g., mice, voles, moles and shrews), coyote (*Canis latrans*), red fox (*Vulpes vulpes*), grey fox (*Urocyon cinereoargenteus*), white-tailed deer (*Odocoileus virginianus*), striped skunk (*Mephitis mephitis*), Virginia opossum (*Didelphis virginiana*), chipmunk (*Tamias striatus*) and grey squirrel (*Sciurus carolinensis*). Less common forest-dwelling species include black bear (*Ursus americanus*), fisher (*Martes pennanti*) and porcupine (*Erithizon dorsatum*). Birds typical of forested areas include raptors (owls, hawks), wild turkey, woodpeckers and migratory songbirds, including a number of species solely associated with forested habitats (i.e., habitat specialists). Reptiles and amphibians likely to occur include vernal pool specialists (e.g., mole salamanders), toads and *hylid* treefrogs.
- **Old Field/Shrublands:** Old field/shrubland habitats are some of the rarest and most critical wildlife habitats in the State. Common mammalian wildlife include small mammals such as meadow voles (*Blarina brevicauda*), shrews, various mice, woodchuck (*Marmota monax*), rabbits, and white-tailed deer. Predatory and scavenging species such as red fox, coyote, weasels, skunk, and raccoon (*Procyon lotor*) often forage or bed in fields. Various species of shrubland-dependent birds including the prairie warbler (*Setophaga discolor*) and blue-winged warbler (*Vermivora cyanoptera*) are common.
- **Wetlands/Open Water:** Freshwater wetlands and other aquatic habitat (e.g., streams, ponds) provide excellent habitat for a wide range of wetland-dependent wildlife. Many of the species using upland forest and shrubland habitats also utilize forested wetland, shrub swamp, shallow marsh, or wet meadow communities. Several common mammalian species are adapted primarily to wetlands or other aquatic habitat including beaver (*Castor canadensis*) and muskrat (*Ondatra zibethicus*). Reptiles and amphibians are particularly adapted to wetlands and aquatic habitats. Typical species include mole salamanders, *Ranid* frogs, toads (*Bufo sp.*), *Hylid* treefrogs, spotted

⁴³ Liviatis, J.A. 1993. *Response of early successional vertebrates to historic changes in land use*. Conservation Biology 7:4, and Liviatis J.A. 2003. *Shrublands and early-successional forests: critical habitats dependent on disturbance in the northeastern United States*. Forest Ecology and Management 185:1-4

turtle (*Clemmys guttata*) and various snakes including the eastern ribbon snake (*Thamnophis sauritus*).

- **Agricultural and Urban Lands:** A variety of wildlife habitats are included in this category. These include hayfields, suburban and urban residential areas, commercial and industrial developments, developed recreational areas (e.g., state and federal parks, municipal parks, playgrounds), maintained lawns, and road corridors. Wildlife in these habitats can be abundant, as animals are attracted to human food sources (e.g., crop fields, orchards, bird feeders, landfills), but the species inhabiting them must be tolerant to some degree of human disturbance. Some of the most recognizable wildlife species can be found in these areas, such as white-tailed deer, raccoon, woodchuck, and birds such as Canada geese (*Branta canadensis*), robin (*Turdus migratorius*), house sparrow (*Passer domesticus*), and other numerous bird species frequenting feeders. Other common but less visible species, such as red fox, coyote and skunk are also common. Nuisance wildlife species such as crows, rats, and other small rodents are also often abundant in these habitats. Some wildlife species are even dependent on human activity to thrive, such as birds nesting almost exclusively in human structures (e.g., chimney swift, barn swallow). Reptiles and amphibians tend to be scarce in these habitats because they are typically less tolerant of human activity than birds or mammals. Common amphibian and reptile species in suburban habitats include green frog (*Rana clamitans*), bullfrog (*Rana catesbeiana*) and garter snake (*Thamnophis sirtalis*).

5.1.3.2.2 Fisheries

As summarized in Table 5-10, the Proposed Route traverses various freshwater watercourses, several of which support fisheries. The CT DEEP's inland fisheries management efforts for rivers and streams are directed primarily toward providing recreational fishing opportunities, particularly trout which have traditionally been an important part of Connecticut's angling activity.

The implementation of CT DEEP's *Trout Management Plan* (1999), developed based upon the compilation of fish population, physical habitat and water chemistry information for approximately 800 Connecticut streams, is designed to improve fishing quality by diversifying angler opportunities. The *Trout Management Plan* designates various special management areas for trout. These include streams where self-sustaining wild trout populations are encouraged through catch-and-release angling, trout management areas, streams where CT DEEP stocks catchable size hatchery trout, trophy trout areas (stocked with larger hatchery trout), and trout parks (offering easy access to the public and stocked more frequently to promote angler success). The CT DEEP also stocks select rivers, including the Naugatuck River, with broodstock Atlantic salmon to provide additional fishing opportunities.

The CT DEEP's *2015 Connecticut Angler's Guide* identifies the following stocked or actively managed fishing areas within the vicinity of the Proposed Route:

- Branch Brook ([Trout Park] within Black Rock State Park, Watertown);
- Black Rock Pond ([Trout Park] Watertown within Black Rock State Park);
- Black Rock Lake (Watertown);
- Northfield Brook (Thomaston);
- Northfield Brook (Thomaston);
- Naugatuck River Trout Management Area (Litchfield/Harwinton/Thomaston - from State Route 118 to the Thomaston Dam); and
- Naugatuck River Broodstock Salmon Area (Litchfield/Harwinton/Thomaston - from State Route 118 to the Thomaston Dam).

The Proposed Route's crossing of the Naugatuck River between Litchfield and Harwinton is designated by CT DEEP as a Trout Management and Broodstock Salmon Area. At this crossing location, Eversource's existing and proposed 115-kV transmission lines span the Naugatuck River at an elevation that is well above the height of the riparian forest and the river.

The CT DEEP also has a Bass Management Plan (1999), which recognizes the importance of warm water species like largemouth and smallmouth bass, chain pickerel, northern pike, walleye, channel fish, panfish, brown bullhead and American eel. The existing Eversource ROW crosses warm-water fisheries, such as Morton Pond in Thomaston, and is in close proximity to Jericho Brook Pond in Watertown; however, these areas are not listed in the Connecticut Bass Management Plan.

5.1.3.2.3 Vernal Pools

During the spring of 2015, vernal pool assessments were performed along Eversource's ROW within which the Proposed Route would be located. A detailed description of the survey methodology and results is presented in the *Inventory and Assessment of Vernal Pools* in Volume 3.

CT DEEP describes vernal pools as “*small bodies of standing fresh water found throughout the spring*” that are “*usually temporary*” and “*result from various combinations of snowmelt, precipitation and high water tables associated with the spring season.*”

Vernal pools are included as one of six types of “Special Wetlands” identified in the General Permit (GP) issued by the U.S. Army Corps of Engineers (USACE) for the State of Connecticut.⁴⁴ USACE defines a vernal pool as an often temporary body of water occurring in a shallow depression of natural or human

⁴⁴ The current Connecticut General Permit is valid for the period of July 2011 to July 2016

origin that fills during spring rains and snow melt and typically dries up during summer months.⁴⁵ Vernal pools also are defined as supporting populations of species specially adapted to reproducing in these habitats, which may include wood frogs, mole salamanders (*Ambystoma* sp.), fairy shrimp, fingernail clams (*Sphaeriidae*), and other amphibians, reptiles, and invertebrates. Vernal pools lack breeding populations of fish.

Best Development Practices, Conserving Pool-Breeding Amphibians in Residential and Commercial Developments in the Northeastern United States (Calhoun and Klemens 2002 [“BDP Manual”])⁴⁶

provides the following operational definition of vernal pools:

*Vernal pools are seasonal bodies of water that attain maximum depths in the spring or fall, and lack permanent surface water connections with other wetlands or water bodies. Pools fill with snowmelt or runoff in the spring, although some may be fed primarily by groundwater sources. The duration of surface flooding, known as hydroperiod, varies depending upon the pool and the year; vernal pool hydroperiods range along a continuum from less than 30 days to more than one year. Pools are generally small in size (<2 acres), with the extent of vegetation varying widely. They lack established fish populations, usually as a result of periodic drying, and support communities dominated by animals adapted to living in temporary, fishless pools. In the region, they provide essential breeding habitat for one or more wildlife species including Ambystomid salamanders (*Ambystoma* spp., called “mole salamanders” because they live in burrows), wood frogs (*Rana sylvatica*), and fairy shrimp (*Eubranchipus* spp.).*

Vernal pool physical characteristics can vary widely while still providing habitat for indicator species. “Classic” vernal pools are natural depressions in a wooded upland with no hydrologic connection to other wetland systems. Manmade depressions such as quarry holes, old farm ponds, and borrow pits can also provide similar habitat. Often, vernal pools are depressions or impoundments within larger wetland systems. These vernal pool habitats are commonly referred to as “cryptic” vernal pools.

Several species of amphibians depend on vernal pools for reproduction and development. These species are referred to as indicator⁴⁷ vernal pool species, and their presence in a temporary wetland during the breeding season helps to identify that area as a vernal pool. Indicator species present in Connecticut include the following:

⁴⁵ Definition as included in the USACE’s General Permit for Connecticut

⁴⁶ Calhoun, A.J.K. and M.W. Klemens. 2002. *Best development practices: Conserving pool-breeding amphibians in residential and commercial developments in the northeastern United States*. MCA Technical Paper No. 5 Metropolitan Conservation Alliance, Wildlife Conservation Society, Bronx, New York. 57 p.

⁴⁷ Calhoun and Klemens (2002) argue that “indicator” species is a better word than the commonly used “obligate” species, as they will occasionally breed in roadside ditches and small ponds that are not vernal pools.

- Blue-spotted Salamander (*Ambystoma laterale*);
- Wood Frog (*Rana sylvatica*);
- Spotted Salamander (*Ambystoma maculatum*);
- Jefferson Salamander (*Ambystoma jeffersonianum*);
- Eastern Spadefoot Toad (*Scaphiopus holbrookii*)
- Marbled Salamander (*Ambystoma opacum*); and
- Fairy Shrimp (*Branchiopoda anostraca*).

Facultative vernal pool species are fauna that utilize, but do not necessarily require, vernal pools for reproductive success. Examples of facultative species include the spotted turtles (*Clemmys guttata*) and four-toed salamander (*Hemidactylium scutatum*). These species may breed or feed in vernal pools, but are also capable of carrying out all phases of their lifecycle in other types of wetlands or waterbodies. Evidence of breeding by facultative species alone is not considered indicative of a vernal pool.

For the purpose of the studies conducted for this Project, a vernal pool is defined as an area that meets the physical characteristics described above and contains evidence of breeding activity for any of the indicator species listed above, including the presence of egg masses and larvae. This vernal pool assessment also makes an important distinction between wetlands in which indicator species may breed and those wetlands where they breed *and* successfully develop. A common phenomena is for breeding (i.e., mating and egg laying) to occur in bodies of water such as road ruts or temporary puddles where development and metamorphosis of larvae is unsuccessful. Such areas are referred to as “decoy vernal pools” as reproductive efforts are unsuccessful. In the BDP Manual, Calhoun and Klemens specifically note the negative impact associated with ruts: “*Site clearing can cause water-filled ruts. These ruts intercept amphibians moving toward the vernal pool and may induce egg deposition. Often these ruts do not hold water long enough to allow development of amphibians and therefore acts as “sinks” that result in population declines.*”

Several examples of decoy pools are present within the Project ROW, most often within existing or historic access roads at wetland crossings. Unlike “classic” or “cryptic” vernal pools, these areas often suffer recurring disturbance and generally contain little vegetation to which egg masses can be attached. Small numbers of vernal pool obligate species such as wood frog and spotted salamander may breed in these ephemeral pools, though there may be little chance for larvae to complete development.

Field Assessments

Field assessments began in April 2015, shortly after vernal pool amphibians had emerged from hibernation and were beginning breeding activity. During this period, chorusing wood frogs and spring peepers were heard, spotted salamander spermatophore (a protein capsule containing a mass of spermatozoa) were observed and adult amphibians were observed in amplexus (the mating position of frogs and toads in which the male clasps the female about the back). A number of pools remained ice covered in early April, particularly those pools that were deeply shaded. At some pools, adult wood frogs were observed hopping across iced covered portions of the pools in search of open water. Surveys continued throughout April and into early May as temperatures began to warm. Multiple visits to each pool were conducted to document breeding productivity via egg mass counts. This was done on sunny days where visual detection of egg masses is optimized. A fine-mesh dipnet was used throughout the survey period to search for larval amphibians, and cover searching (turning of rocks, logs, and debris) around the margins of the pools was conducted to search for adult amphibians.

In order to assess these pools qualitatively, the methodology described in the BDP Manual was used. This assessment methodology utilizes a three-tiered rating system, with the tier designation determined by examining the biological value of the pool in conjunction with the condition of the habitat surrounding the pool, which is the area used by vernal pool amphibians during the non-breeding season. The higher the species diversity and abundance coupled with an undeveloped and forested landscape surrounding the pool, the higher the tier rating. Tier 1 pools are considered the highest quality pools, while Tier 3 are the lowest. For this assessment, the potential tier rating was assessed based on the *biological value* of each pool which considers both species richness and species abundance. Per the BDP Manual, Tier 1 and 2 pools are those pools that meet at least one of the following criteria:

- The presence of a breeding state-listed species;
- Two or more indicator species breeding; or
- 25 or more egg masses of a vernal pool indicator species.

A pools tier rating is based on which of the above *biological* criteria are met coupled with an analysis of the level of development within two landscape management zones surrounding the pools, the Vernal Pool Envelope (VPE, 0-100 feet from the pool) and the Critical Terrestrial Habitat (CTH, 100-750 feet from the pool).

A Tier 1 Pool must meet one of the above *biological* criteria *and* have at least 75% undeveloped land within the Vernal Pool Envelope (VPE, 0-100 feet from the pool) and at least 50% undeveloped land within the Critical Terrestrial Habitat (CTH, 100-750 feet from the pool).

A Tier 2 pool must meet one of the above *biological* criteria along with one of the landscape criteria, either 75% undeveloped land within the VPE *or* 50% undeveloped land within the CTH.

A Tier 3 pool is a pool that either has high *biological* value coupled with a high percentage of developed land within the VPE and CTH *or* low biological value coupled with one of the landscape criteria being met (either 75% undeveloped land within the VPE *or* 50% undeveloped land within the CTH).

Results

Wetlands that have been determined to provide vernal pool habitat are listed in Table 5-9 and are depicted on the Volume 5 maps. Each vernal pool has been assigned a Project-specific numerical identifier that corresponds to the designation presented in Table 5-9. Vernal pools were labeled with an alpha-numeric sequence beginning with VP or DVP (decoy vernal pool) followed by a letter and number corresponding to the associated wetland (e.g., VP B2-1, VP B4-1, DVP F13-1).

A total of 22 vernal pools were identified within the Project ROW and along publically accessible off-ROW access roads, supporting three vernal pool indicator species - wood frog, spotted salamander, and marbled salamander. Fifteen of these pools (68%) are potential Tier I pools due to the fact that they had significant numbers of egg masses (i.e., 25 or more) or they had two or more indicator species breeding.

Pools C4-1, E2-1, E2-2 and F13-1 are all associated with access road activities, which have created small ponded areas associated with rutting, culvert inlets (i.e., backwater pool) or culvert outlets (i.e. scour pool). These pools are of low ecological significance, and can reasonably be classified as decoy pools as defined in the BDP Manual.

Several noteworthy pools were documented including pools MSF-1, C12-1, C15-1, C21-1, D4-1 and D15-1; all of which contained large numbers of both spotted salamander and wood frog. Pool D4-1 was noteworthy as it contained the only record of marbled salamander within the Project area. Marbled salamander are uncommon in Connecticut particularly at higher elevations, and this pool represents the only documented breeding location of the species from the Town of Thomaston.

5.1.3.2.4 Birds

A breeding bird inventory and assessment was conducted along the Proposed Route in the spring of 2015. The results are provided in the Project's *Inventory and Assessment of Breeding Birds (Inventory)*, located in Volume 3. The *Inventory* includes descriptions of the avian habitat types present and an inventory of observed and potential breeding birds in the vicinity of the Proposed Route. Various sources were analyzed in order to develop the inventory of all bird species known to breed in the vicinity of the Project. The primary source utilized was *The Atlas of Breeding Birds of Connecticut*,⁴⁸ which is the result of a five-year study (1982-1986) of all bird species known to breed in the state. The study is the most comprehensive review to date of Connecticut's breeding birds, involving the efforts of more than 500 individuals and covering virtually the entire 5,009-square-mile area of the state.

That inventory was then refined by considering such factors as bio-geographical species distribution, minimum patch size requirements, and the presence or absence of critical habitat features identified within the Project area. The inventory was supplemented with direct observations compiled during field investigations conducted in April and May of 2015. All birds seen or heard within suitable breeding habitat were noted as observed in the inventory and are considered "possible"⁴⁹ breeders within the Project area. Because field work was conducted in April and May, birds observed consisted of those that arrive in Connecticut in the early to mid-spring.

Results

A total of 99 species were identified as potential breeders. Of these, 45 were identified during field observations. All identified species were found within suitable breeding habitat and are considered possible breeders.

In order to evaluate the Project area's value for species of high-conservation priority as opposed to common species and habitat generalists, the inventory of birds was prioritized based on conservation status. Species that are included either on *Connecticut's List of Endangered, Threatened and Special Concern Species* (2010) or classified as *Species of Greatest Conservation Need* (SGCN) by *Connecticut's Wildlife Action Plan*⁵⁰ (WAP, in prep.) were considered to be species of high conservation priority. The

⁴⁸ Bevier, L. R. (Ed.). *Atlas of Breeding Birds of Connecticut*. 1994. Bulletin 113. State Geological and Natural History Survey of Connecticut. 461 p.

⁴⁹ A "possible" breeder as defined by Bevier (1994) includes observation of bird (male, female or singing male) within suitable habitat during the breeding season.

⁵⁰ *Connecticut's Wildlife Action Plan*, formerly known as *Connecticut's Comprehensive Wildlife Conservation Strategy* (2005) is currently under revision by the CT DEEP. Portions of the plan, such as the SGCN list, have been released in draft form and have been used in this report.

WAP was created to establish a framework for proactively conserving Connecticut's fish and wildlife, including their habitats. The WAP designates birds of high-conservation priority as SGCN. SGCN fall into three categories in descending order of significance from *most important* to *very important* and finally *important*.

The inventory includes six State-listed species, one of which, the broad-winged hawk (*Buteo platypterus*) was observed within the ROW in Harwinton. The remaining five species were considered potentially present based on bio-geographical species distribution and the presence or absence of critical habitat features identified within the Project area. These species are discussed in detail in the Inventory and in Section 5.1.3.3, below. A total of 35 species (or 35% of the 99 total species) are SGCN. Of those 35 species, seven are classified as *most important*, 16 as *very important* and 12 as *important*. Of the 35 SGCN identified, 15 are associated with managed early-successional ROW vegetation (e.g., shrubland and PSS wetlands) and 13 are associated with forested habitats (e.g., upland forest and PFO wetlands). The remaining seven SGCN species are associated with edge habitats or agricultural lands. A greater percentage of the seven SGCN classified as *most important* are associated with managed early-successional ROW vegetation (e.g., shrubland) as opposed to forested habitats (five species versus two species).

5.1.3.3 Federal and State Listed or Proposed Threatened, Endangered, or Special Concern Species

Eversource has consulted with the CT DEEP Bureau of Natural Resources – Wildlife Division, Natural Diversity Database (NDDB), and the USFWS Information, Planning, and Conservation System (IPaC) to determine whether there is a potential for the Project to affect species identified by federal or state authorities as threatened, endangered, species of concern, or their critical habitats. The following sections describe the species that may occur in the Project vicinity, whereas Section 6 includes best management practices that Eversource would apply, as appropriate, to protect such species during construction.

Federal-listed Species

Screening using the USFWS IPaC indicated that only one species – the northern long-eared bat (*Myotis septentrionalis*), a federal-threatened⁵¹ species, may be present in proximity to the Proposed Route. The northern long-eared bat was also State-listed endangered in August 2015. The USFWS has recommended that consultations regarding this species be coordinated through CT DEEP. Based on consultation

⁵¹ USFWS listing became effective on May 4, 2015

between Eversource and CT DEEP on July 30, 2015⁵² there are no known records or species occurrences or hibernacula in the vicinity of the Proposed Route. CT DEEP has recommended that an assessment be conducted to document habitat suitability (summer roosting) and potential Project impacts to this habitat if it is found to occur. Based on the results of this assessment (which is anticipated to be completed in the fall of 2015), additional acoustic surveys may be conducted along the Proposed Route in the summer of 2016.

State-listed Species

To assess the potential for the Project facilities to be located in or near habitat of State-listed species, Eversource initially reviewed publically-available maps depicting large “polygon” areas within which listed-species may occur. In addition, because of its state-wide transmission facilities and projects, Eversource has a data-sharing agreement with CT DEEP whereby authorized Eversource personnel and its representatives are allowed to review more specific, confidential information about the potential location of listed species within a polygon. As a part of this data sharing agreement, the CT DEEP Bureau of Natural Resources Wildlife Division provided Eversource with species information associated with the publically-available NDDB polygons in the Project area. Eversource reviewed this information and conducted field studies of the ROW to assess the presence of suitable habitat for the listed species.

Following a review of this information, Eversource submitted written correspondence to the CT NDDB for concurrence regarding the potential presence of State-listed threatened, endangered, or special concern species in the vicinity of the Project area, as well as protection strategies for State-listed species that might be affected by Project activities.

The following species were identified following a review of the CT DEEP –provided NDDB polygon data:

- Wood Turtle (*Glyptemys insculpta*) – State-listed Special Concern
- Smooth Green Snake (*Liochlorophis vernalis*) – State-listed Special Concern
- Northern Spring Salamander (*Gyrinophilus porphyriticus*) – State-listed Threatened
- Frosted Elfin Butterfly (*Callophrys irus*) – State-listed Threatened

The following is a description of each species’ habitat requirements and potential habitat suitability within the Project area.

⁵² Meeting with Jenny Dickson and Kate Moran (CT DEEP), Eversource Energy, and Tighe & Bond

Wood Turtle

Wood turtles (*Glyptemys insculpta*) require riparian habitats bordered by floodplain, woodland, or meadows. They hibernate in deep pools, below undercut banks, or in tangled tree roots along streams and rivers. During late spring and throughout the summer, wood turtles may become quite terrestrial, moving into nearby fields, and woodlands.⁵³ Immediately after emergence from hibernation, activity is confined within and immediately adjacent to the waterway. From late spring (ca. May) and throughout summer, upland terrestrial habitats are utilized, including agricultural lands (e.g. cropland, pasture), early-successional habitats including ROWs, railroad beds, and forest. Nesting occurs from late May through second week of June. Suitable nesting areas consist of more open, scarified or sparsely vegetated areas near the waterway. Nesting could occur within the maintained ROW.

Field investigations confirmed habitat suitability for wood turtle within several larger watercourses and adjacent terrestrial habitat within the Proposed Route.

Smooth Green Snake

Smooth green snakes (*Liochlorophis vernalis*) favor open, unforested habitats including meadows, pastures, fens, coastal grasslands, and mountaintop “balds”, but are also found in transitional and lightly forested habitats such as grassy old fields with scattered shrubs and trees, as well as oak-pitchpine woodland (Klemens 1993). Open grassland habitat often associated with wetlands is considered this species’ favored habitat.⁵⁴ Smooth green snakes are active from May through November.

Because this species utilizes early-successional habitats including shrublands, the maintained ROW in its entirety may not be eliminated from consideration as potential green snake habitat. However, the extent of preferred habitat – open grassland associated with wetlands, is much more confined as the majority of the maintained ROW is occupied by dense woody shrubs as opposed to grasses.

⁵³ Klemens, M.W. 1993. Amphibians and Reptiles of Connecticut and Adjacent Regions. State Geological and Natural History Survey of Connecticut, Bulletin No. 112.

⁵⁴ CT DEEP Webpage: <http://www.ct.gov/deep/cwp/view.asp?a=2723&q=325780> (accessed 3/9/2015)

Northern Spring Salamander

Northern spring salamanders (*Gyrinophilus porphyriticus*) require clean, cold, well-oxygenated water. Steep, rocky and heavily forested hemlock ravines are favored habitats. Habitats include steep, rocky high-gradient ravines, brooks, seepage areas, springs including below ground anthropogenic spring pipes and wells (Klemens 1993).

Several wetlands within the Project area lie within the upper reaches of the watershed known to support this species and contain suitable habitat either within or immediately adjacent to the ROW. All of these wetlands contained streams and/or groundwater seepage and could potentially support spring salamander or drain directly to off-ROW wetlands or streams that may support this species.

Frosted Elfin Butterfly

Frosted elfins (*Callophrys irus*) require open habitats maintained by disturbance in which their host plants grow.⁵⁵ Eggs are laid on their primary host plant, lupine (*Lupinus perennis*), which then provides food for the larvae throughout metamorphosis. Wild indigo (*Baptisia tinctoria*) may also serve as a host plant for this species.⁵⁶ This species has been negatively impacted by the loss of its associated host plant species. As a result, the potential occurrence of the species is based on mapping for the presence of these host plant species.

The locations of host plant communities were identified and mapped along the Project ROW within areas supporting suitable habitat, both in 2009 and again in 2015.

Birds

In addition to the above-referenced species, the following State-listed bird species were considered to be potentially occurring or observed within the Project area during the field studies performed as part of the *Inventory*.

- Broad-winged Hawk (*Buteo platypterus*) – State-listed Special Concern
- Brown Thrasher (*Toxostoma rufum*) – State-listed Special Concern
- Savannah Sparrow (*Passerculus sandwichensis*) – State-listed Special Concern
- Bobolink (*Dolichonyx oryzivorus*) – State-listed Special Concern
- Alder Flycatcher (*Empidonax alnorum*) – State-listed Special Concern

⁵⁵ Albanese, G., P. D. Vickery, and P. R. Seivert. 2007. Habitat Characteristics of Adult Frosted Elfins (*Callophrys irus*) in Sandplain Communities of Southeastern Massachusetts, USA. Biological Conservation, in press.

⁵⁶ Albanese et al. 2007. Ibid.

- American Kestrel (*Falco sparverius*) – State-listed Threatened

Broad-winged Hawk

The Broad-winged Hawk inhabits deciduous or mixed forest types often near a lake, pond or wetland. Bevier (1994:102) noted that “the Broad-winged Hawk exhibits a diversified nest site habitat selection”. A single male broad-winged hawk was observed on May 2, 2015 calling from a perch along the forest edge within the ROW adjacent to a wetland in Harwinton. The area consisted of upland forest edge adjacent to wetlands and represents suitable breeding habitat.

Brown Thrasher

Brown thrashers inhabit thickets, brushy hillsides and woodland edges in suburban and rural areas (Bevier, 1994). Maturation of forest and other factors causing loss of early successional habitat are driving the decline in this species. Shrubland dominated (managed) portions of the Project ROW represent suitable breeding habitat for thrasher.

Savannah Sparrow and Bobolink

The savannah sparrow and bobolink are grassland specialists that inhabit early old field habitat, managed grasslands (e.g., airport runway fields) or hayfields. Generally, larger contiguous fields are favored, with a minimum area requirement of 5-10 acres for bobolink and 20-40 acres for savannah sparrow.⁵⁷ Within the Project area, agricultural fields that extend across the ROW and are located on the east side of Park Road in the Town of Watertown totaling approximately 25 acres, represent the only potentially suitable nesting habitat for these grassland species. Both species are ground nesting birds: therefore, a delayed mowing regime (late June-August) would be required to allow for successful nesting. However, if the subject field is managed solely for the production of forage hay, which is presumably the case, such a management regime would not be compatible with these species’ nesting requirements.

⁵⁷ Comins, P., Hanisek, G, and Oresman, S. 2003. Protecting Connecticut’s Grassland Heritage. A Report of the Connecticut Grasslands Working Group. Audubon, Connecticut.

Alder Flycatcher

The alder flycatcher occurs in habitats with an interspersed low vegetation, including shrubs with trees over eight feet high in the vicinity of streams or other open water.⁵⁸ Suitable nesting habitat occurs in the managed early-successional portions of the ROW that include streams, wetlands, or open water.

American Kestrel

The American kestrel can be found in a wide variety of open to semi-open habitats including meadows, grasslands, deserts, early old field successional communities, open parkland, agricultural fields, and both urban and suburban areas; regardless of dominant vegetation form present. Breeding territories are characterized by either large or small patches covered by short ground vegetation, with taller woody vegetation either sparsely distributed or lacking altogether. Suitable nest trees and perches are required. Typical breeding habitat in the Northeast U.S. is large (>62 acre) pasture or recently fallowed field, with one or few isolated large dead trees for nesting and several potential perches.⁵⁹

There is limited suitable habitat available for American kestrel within the Project area due to the narrow linear configuration of early-successional habitats available and the limited graminoid (grass-like) dominated areas. The agricultural fields located on the east side of Park Road in the Town of Watertown (refer to Volume 5 maps) represent the only area potentially suitable for American kestrel within the Project area.

5.1.3.4 Designated Wildlife Management Areas (WMAs)

The Proposed Route does not cross any national wildlife refuges, forests, or parks, or State-designated Wildlife Management Areas (WMAs). State-designated WMAs are established by use of funding related to the federal Pittman-Robertson Act of 1937, which specifies the use of taxes/fees on hunting for game management.

5.1.4 Land Uses and Scenic Resources

The Proposed Route for the new 115-kV transmission line would be aligned within Eversource's existing transmission line ROW between Frost Bridge Substation and Campville Substation. Lands in the general Project region are characterized by a variety of uses and types. The predominant uses include forest

⁵⁸ Bevier, L. R. (Ed.). 1994. Ibid.

⁵⁹ Smallwood, John A. and David M. Bird. 2002. American Kestrel (*Falco sparverius*), The Birds of North America Online (A. Poole, Ed.). Ithaca: Cornell Lab of Ornithology; Retrieved from the Birds of North America Online: <http://bna.birds.cornell.edu/bna/species/602>

lands, recreational areas, transportation corridors (state and local roadways), and residential, commercial, and industrial developments.

Eversource's ROW encompasses both lands occupied by existing overhead transmission lines and lands within the utility easement, but not presently managed for utility use. Beneath and in the vicinity of the portions of the ROW occupied by existing transmission lines, Eversource conducts vegetation management to promote shrub or similar low-growth vegetation, consistent with utility use. Lands within the unmanaged portions of the ROW are undeveloped and consist of forested, shrub, and agricultural or other open lands. Within the ROW, developed land uses (e.g., buildings) are not permitted, pursuant to Eversource's easement agreements with landowners.

To identify and assess land uses along the ROW, as well as existing and future land use plans and conditions in the Project vicinity, Eversource consulted existing published resources utilizing a geographic information system (GIS); analyzed aerial photography and maps; examined state, local, and regional land-use plans (including data concerning federal- and state-designated recreational areas); and reviewed data concerning public and private recreational resources, including the CT DEEP's Black Rock State Park and Mattatuck State Forest; the USACE's Black Rock Lake, Northfield Brook Lake, and Thomaston Dam recreational areas; Connecticut Forest and Park Association's (CFPA's) blue-blazed trail system, as defined in the CFPA's *Connecticut Walk Book West (The Guide to the Blue-Blazed Hiking Trails of Western Connecticut. 2006, 19th Edition)* and town recreational areas. In addition, Eversource conducted research to identify whether any parcels preserved by land trusts (e.g., Watertown Land Trust, Harwinton Land Trust) are located near the Proposed Route.

Based on this research, Eversource determined that the Project is not located near any Connecticut Heritage Areas, national scenic or historic trails, or state- or federally-designated scenic highways. Two Connecticut State Department of Transportation (ConnDOT) scenic land strips (undeveloped parcels) are located adjacent to State Route 8, approximately 0.25 mile south of the ROW crossing of this highway.⁶⁰ No land trust parcels are located along or in the immediate vicinity of the ROW.

The following subsections describe existing land uses along the Proposed Route, as well as community facilities, and designated protected and scenic resources. Zoning classifications of properties along and in the vicinity of the ROW are identified on the Volume 5 maps.

⁶⁰ ConnDOT scenic lands are roadside properties, located primarily outside of highway ROW, which were purchased at least in part with federal Highway Beautification Act (1965) funds in order to control the proliferation of billboards and other unsightly views along federal highways.

5.1.4.1 Existing Land Uses

Commencing at Eversource's existing Frost Bridge Substation in the Town of Watertown, the Proposed Route for the new 115-kV transmission line would extend first west-northwest and then north-northeast across portions of the Towns of Watertown, Thomaston, Litchfield, and Harwinton before terminating at Campville Substation. The entire route would be aligned within a long-established Eversource ROW that traverses or borders a variety of land uses. The ROW extends across properties that Eversource owns in fee and across private or public lands over which Eversource has easements for utility use.

Table 5-2 summarizes the length of the Proposed Route in each of the four towns, along with the Eversource-owned and the publicly-owned property (length) traversed along the ROW in each town.

Table 5-3 summarizes the land uses along the proposed 115-kV transmission line route within the existing Eversource ROW, by land use type within each town.

Table 5-2: Approximate Distance Traversed by Proposed Route, by Town, and across Eversource-Owned Property or Public Lands

Town	Approximate Distance Traversed (Miles)		
	Total ROW	Eversource-Owned Property	Public Property
Watertown	4.7	0.47	2.5 miles State Route 8; US Route 6 Mattatuck State Forest (CT DEEP) Black Rock State Park (CT DEEP) Veterans Memorial Park (Town)
Thomaston	2.6	0.22	0.43 Mile Mattatuck State Forest (CT DEEP) Black Rock State Park (CT DEEP) Branch Brook Reservoir / Dam (USACE) Northfield Brook Lake Recreation Area (USACE)
Litchfield	1.8	0.09	0.18 Mile State Route 8 (ConnDOT) Thomaston Dam Recreation Area (USACE)
Harwinton	1.3	.16	0.19 mile Thomaston Dam Recreation Area (USACE)
TOTAL	10.4	0.94	3.3

Table 5-3: Approximate Area (Acres) of Each Land Use within the Project ROW, by Town

Land Use Type ¹	Town (Approximate Area by Land Use Type)				Total
	Watertown	Thomaston	Litchfield	Harwinton	
Upland Forest	46.4	35.3	17.3	15.1	114.1
Old Field /Shrubland	91.8	24.3	11.8	13.7	141.6
Agricultural Land	11	1.3	2.3	0.5	15.1
Urban Areas ²	19.7	10.8	8.7	3.6	42.8
Wetlands	22.5	6.3	14.5	7.6	50.9
Open Water	1.1	1.8	0.1	0.4	3.4
TOTAL	192.5	79.8	54.7	40.9	368

¹ Land use types are depicted on the Volume 5, 400 scale maps. Land use type boundaries were determined using aerial mapping and field reconnaissance in some places.

² Includes Commercial/Industrial, House/Yard and Other as depicted on the Volume 5, 400 scale maps.

The following summarizes the primary land-use patterns, by town, along and in the vicinity of the Proposed Route.

Town of Watertown

From Frost Bridge Substation, the Proposed Route would extend for approximately 4.7 miles through the eastern portion of the Town of Watertown. For approximately 2.6 miles of the 4.7 miles in Watertown (between Frost Bridge Substation and Purgatory Junction), the new 115-kV transmission line would be aligned either on Eversource property (i.e., near the Frost Bridge Substation) or near the middle of Eversource's existing 400-foot-wide ROW, between the existing 345-kV line (352 Line) and 115-kV line (1191 Line; refer to XS-1 and XS-2 in Section 3, Appendix A of this Volume, as well as to the maps in Volume 5). Along this 2.6-mile segment of the route, Eversource currently manages most of the land within the ROW for utility use (i.e., the ROW segment is characterized by lower-growing vegetation consistent with required clearances from overhead transmission line conductors, except in isolated areas along the Proposed Route where taller-growing vegetation has become established). As a result, although there are areas of forest and taller-growing shrub vegetation, most of the land within this ROW segment consists of scrub-shrub land or grassland.

This 2.6-mile segment of the ROW crosses State Route 8 and U.S Route 6, as well as various local roads; Mattatuck State Forest; and undeveloped portion of the Town of Watertown Veteran's Memorial Park; commercial / industrial areas; and residential developments. Within Mattatuck State Forest, the ROW crosses the CFPA's Whitestone-Jericho Connector Trail and the Jericho Trail, which connects to the CFPA's Mattatuck Trail. Across the ROW, the Jericho Trail is asphalted. The Whitestone-Jericho Connector Trail extends, in part, along Echo Valley Road before traversing northwest along the 400-foot-wide ROW for a short distance before diverging north into the forest.

Along the remaining approximately 2 miles of the Proposed Route in Watertown (i.e., from Purgatory Junction to the Town of Thomaston border), the new 115-kV line would be aligned within Eversource's 250-foot-wide ROW, east of the existing 1191 Line (refer to XS-3 in Section 3, Appendix 3A of this Volume). Predominant land uses along or near this portion of the ROW include single-family residences, Mattatuck State Forest, Crestbrook Park and Golf Club, and Black Rock State Park. Within Black Rock State Park, the ROW crosses the CFPA's Mattatuck Trail and the park's Red Trail Loop. Branch Brook / Branch Brook Reservoir (Black Rock Lake) Dam, which is managed by the USACE and the CT DEEP, forms the boundary between Watertown and Thomaston.

Town of Thomaston

The Proposed Route traverses approximately 2.6 miles through the Town of Thomaston. Land uses in the vicinity of the Proposed Route consist of a mix of forestland, residences, open land, and public and

private recreational areas (including Mattatuck State Forest, the USACE's Branch Brook Reservoir (Black Rock Lake) / Dam and North Brook Recreational Area, Thomaston Fish and Game Club property, and town open space).

Land uses within the existing 250-foot-wide Eversource ROW include principally scrub-shrub land with forest along the uncleared portion of the ROW. The proposed 115-kV line would be aligned within this ROW, east of the existing 1191 Line south of Walnut Hill Junction and east of both the 1191 Line and the 1921 Line north of Walnut Hill Junction (refer to XS-3 and XS-4 in Appendix 3A and to the Volume 5 maps).

Town of Litchfield

Extending northeast from Thomaston, the Proposed Route for the new 115-kV line would cross approximately 1.8 miles through the southeastern portion of the Town of Litchfield. In Litchfield, the new 115-kV transmission line would be aligned east of the existing 1191 and 1921 Lines, within the Eversource's 250-foot-wide ROW (refer to XS-4 in Appendix 3A of this Volume).

Lands in the vicinity of the ROW in Litchfield consist predominantly of residences, agricultural land, and forest land. Land uses within the existing ROW include forest, undeveloped shrub land, and agricultural land. Residences are located near the ROW at road crossings, such as Mason Hill Road, Hopkins Road, and Campville Road.

The Proposed Route also would extend across State Route 8, the former Conrail railroad tracks (now owned by ConnDOT), and lands along the Naugatuck River that are part of the USACE's Thomaston Dam Recreational Area. The Naugatuck River is bordered by recreational trails (hiking, ATV, snowmobile) and is designated by CT DEEP as a trout fishery.

In addition to the proposed new 115-kV line, within the existing ROW at the Naugatuck River crossing, Eversource proposes to replace the existing lattice steel tower (located west of the river) that presently supports the river crossing for both the 1191 and 1921 Lines, with new monopole structures, placing each of these two existing 115-kV lines on a separate structure (refer to XS-5 in Appendix 3A of this Volume). At and in the vicinity of the Naugatuck River crossing, the ROW is bordered by forest land. Portions of the ROW that are not maintained with low-growth vegetation also are forested. The existing 1191 and 1921 Lines are currently elevated 155 feet above the Naugatuck River, spanning the area such that no forested vegetation has had to be cut to maintain appropriate clearances from the conductors.

Portions of the USACE's Thomaston Dam Recreational Area extend linearly along both sides of the Naugatuck River. Along the west side of the river in the Litchfield, an extensive system of hiking, snowmobiling, and ATV trails traverse adjacent to the river.

Town of Harwinton

From the Litchfield border at the Naugatuck River crossing, the Proposed Route traverses approximately 1.3 miles through the southwestern portion of the Town of Harwinton before terminating at Campville Substation. Lands in the vicinity of the route consist primarily of undeveloped forest, with some residences located along Wildcat Hill Road. At the Naugatuck River crossing, the ROW extends across undeveloped USACE-owned property that is part of the Thomaston Dam Recreational Area. In addition, a sand and gravel mining operation is located adjacent to the Naugatuck River, along Valley Road, directly south of the ROW. The existing ROW is characterized principally by forest and open field / shrub lands. Forested areas dominate land use-patterns near the ROW.

East of the Naugatuck River in Harwinton, Eversource also proposes to replace the existing lattice steel tower that presently supports both the 1191 and 1921 Lines. As described above for the proposed lattice steel tower replacement on the west side of the river in Litchfield, Eversource proposes to install two new monopoles to separately support the 1191 and 1921 lines. These two new structures, as well as the new 115-kV line structure, will be located within Eversource's existing ROW east of Valley Road. In this area, existing land uses consist of forest land and shrubland.

5.1.4.2 Federal, State, and Local Use Plans/Future Land-Use Development

To assess the relationship of the proposed Project with respect to established land use plans and policies, Eversource compiled and reviewed federal, state, regional, and local land use plans, including Connecticut's *Conservation and Development Policies Plan* (C&D Plan, 2013). Eversource also consulted with representatives of the four municipalities along the Proposed Route. Each municipality along the Proposed Route has established municipal land use plans, all having goals and objectives consistent with the operation of transmission lines within Eversource's existing ROW, where the new 115-kV line would be located.

5.1.4.2.1 Federal Plans

There are no specific federal land use plans that pertain to the Project. The only federal lands along the Proposed Route are the USACE properties associated with the various projects to control flooding on the Naugatuck River (i.e., Branch Brook / Black Rock Lake and Dam; Northfield Brook Dam, and

Thomaston Dam). The USACE actively manages these flood control projects and maintains its surrounding properties for public recreational uses. All of the USACE flood control projects were implemented in the 1960s, decades after the Eversource transmission line ROW was established. Eversource's existing 115-kV transmission lines span Branch Brook, Northfield Brook, and the Naugatuck River, and are compatible with the USACE's flood control programs. The Eversource ROW also does not affect any of the public recreational uses of these USACE properties.

In addition, the U.S. Department of the Interior, National Park Service (NPS), through its Rivers, Trails, and Conservation Assistance Program (Northeast Region), is assisting in the planning of a greenway along the Naugatuck River. Under this program, the NPS provides technical assistance to community groups and local, state, and federal agencies seeking to protect natural areas and water resources and to enhance "close-to-home" outdoor recreational opportunities. The NPS is assisting the Towns of Watertown and Thomaston, among others, to develop a 44-mile greenway trail along the Naugatuck River from Torrington to Derby.

5.1.4.2.2 State and Regional Plans

Eversource reviewed the C&D Plan prepared by the Connecticut Office of Policy and Management. The objective of the C&D Plan is to guide and balance response to human, environmental, and economic needs in a manner that best suits Connecticut's future. Based on the general planning information provided in the C&D Plan, the Project is consistent with the overall goals and objectives of the C&D Plan and is particularly relevant to the Plan's Growth Management Principle #1: Redevelop and Revitalize Regional Centers and Currently Planned Infrastructure. The Project would serve a public need by providing an environmentally-sound approach to the reliable transmission of electricity, which, as the C&D Plan (p. 8) notes is needed, along with other physical infrastructure, to "...take full advantage of Connecticut's strategic location within the Northeast Megaregion, while also proactively addressing the needs and desires of a changing demographic base."

In addition, there are several regional planning agencies that serve the municipalities along the Project, including Council of Governments of Central Naugatuck Valley (COGCNV) (including Watertown and Thomaston) and the Northwest Hills Council of Governments ([NHCOG⁶¹]: including Litchfield and Harwinton). The regional planning agencies establish land use, conservation, and development policies to assist in coordinating regional growth patterns, with the objective of maximizing efficiencies in shared environmental, economic, and infrastructure facilities. The Project, which is located entirely on Eversource's fee-owned properties and long-established ROW, will improve the reliability of the regional electric system and thus will be consistent with these regional planning agencies' overall goals.

5.1.4.2.3 Local Land-Use Plans

All four of the towns traversed by the Proposed Route have published plans of conservation and development:

- Watertown: Plan of Conservation and Development (December 2007)
- Thomaston: Plan of Conservation and Development (2014)
- Litchfield: Plan of Conservation and Development (Adopted June 2007, revised January 2010)
- Harwinton: Plan of Conservation and Development (January 2010)

In general, these plans identify the areas traversed by the Proposed Route as continuing to maintain current land use patterns in the future (e.g., public recreational or protected lands, low-density residential development). None of the plans identify local land use policies that would be inconsistent with the development of the new 115-kV transmission line within Eversource's existing ROW.

5.1.4.3 Community Facilities

The Council's *Application Guide for Electric and Fuel Transmission Facilities* (April 2010; Section VI.G) specifies that the proximity of the proposed Project to certain community facilities, as identified below, must be identified. These facilities are, in particular:

- Public and private schools, licensed daycare centers, licensed youth camps, and public playgrounds;

⁶¹ NHCOG was formed January 1, 2014 and is a consolidation of the Litchfield Hills Council of Elected Officials (LHCOE) and the Northwestern Connecticut Council of Governments. The NHCOG is a coordinating body for 21 towns, including Litchfield and Harwinton. A combined Plan of Conservation and Development has not yet been prepared for the 21 municipalities. As a result, the *Plan of Conservation and Development* (2009) prepared by the LHCOE remains in effect for Litchfield and Harwinton.

- Hospitals;
- Group homes; and
- Recreational areas.

Recreational areas, including public playgrounds, are discussed in Section 5.1.4.4.

A review of public records indicates the Proposed Route is not located within 500 feet of any schools, licensed residential child day-care facilities, youth camps, hospitals, or group homes.⁶² The only public schools located in the general vicinity of the Project are Thomaston High School and Black Rock Elementary School (pre-K to Grade 3), which are both located approximately 0.5 mile southwest of the Proposed Route south of State Route 109 (Branch Road).

Two group day-care facilities, both in the Town of Watertown, are located within 0.5 mile of the Proposed Route: Kidz Child Care Center, 169 Callender Road, which is located approximately 0.19 mile southwest of the Proposed Route, south of Park Road, and Ledgewood Private Pre-School, 720 Thomaston Road (US Route 6), which is located approximately 0.07 mile southwest of the Proposed Route.

5.1.4.4 Public Forests, Parks, Open Space, Recreational / Public Trust Lands, and Trails

The Proposed Route traverses or is located near various forests, parks, open space lands, and recreational areas (including trails), including Mattatuck State Forest, Veterans Memorial Park, Black Rock State Park and Black Rock Lake, Northfield Brook Lake Recreation Area, and areas along the Naugatuck River in Litchfield and Harwinton that are part of Thomaston Dam Recreation Area. The Black Rock Lake, Northfield Brook Lake, and Thomaston Dam areas are owned by the USACE and were created when the USACE developed dams to control flooding within the Naugatuck River basin. These flood control projects, which were completed in the 1960s, were prompted by the significant damage and loss of life caused by severe flooding on the Naugatuck River during Hurricane Diane in 1955.

The recreational areas crossed by or near the Proposed Route are described below and are summarized in Table 5-11 (located at the end of this subsection), and depicted on the maps located in Volume 5.

⁶² http://www.dir.ct.gov/DCF/Licensed_Facilities/listing_CCF.asp;
<https://www.elicense.ct.gov/Lookup/DownloadRoster.aspx>

- **Mattatuck State Forest.** The Mattatuck State Forest, which is owned and managed by CT DEEP, encompasses approximately 4,673 acres and is comprised of a variety of parcels located in six towns, including all four of the Project towns. The Proposed Route traverses approximately 1.77 miles through portions of the forest in the towns of Watertown (1.50 miles) and Thomaston (0.27 mile). In Thomaston, the ROW extends across the forest's largest single parcel (1,327 acres), which adjoins Black Rock State Park. CT DEEP manages the forest for a wide variety of recreational uses (e.g., hunting, hiking, mountain biking, etc.), as well as for forest products and wildlife habitat. The CFPA's Mattatuck Trail passes through several portions of the forest.
- **Jericho-Whitestone Connector Trail, Jericho Trail, Mattatuck Trail.** The Mattatuck Trail, which is managed by the CFPA, is a 36-mile hiking trail that stretches across nine towns in central-northwestern Connecticut, extending from the Town of Wolcott northwest to the Town of Cornwall. The Jericho-Whitestone Connector Trail extends along Echo Valley Road and from there crosses onto the 400-foot-wide ROW for a short distance before diverging north into Mattatuck State Forest and eventually joining the Jericho Trail, north of the Project ROW. In the vicinity of the ROW, views from this trail are presently influenced by Echo Valley Road and developments along it, as well as by the existing transmission lines within the ROW. The Jericho Trail, which connects to the Mattatuck Trail, originates at Echo Lake Road in Watertown and extends north, across the Eversource ROW, to connect to the Mattatuck Trail in the Mattatuck State Forest. In addition to crossing the Jericho Trail, the Proposed Route crosses the Mattatuck Trail within Black Rock State Park in the Town of Thomaston.
- **Veterans Memorial Park.** This Town of Watertown park, which encompasses approximately 100 acres, provides year-round multi-use recreational opportunities. The park includes baseball fields, soccer fields, basketball courts, walking trails, a playground, gazebo, covered pavilion, Jericho Brook Pond (fishing), horseshoe pits, bocce courts, and picnic areas. The Eversource ROW extends across the northern boundary of the park land. In this area, the ROW is 400 feet wide. The proposed 115-kV transmission line would be aligned near the middle of the ROW, away from the park and north of the existing 1191 Line. Mature trees screen virtually all of the developed portion of the Park from the ROW.
- **Black Rock State Park and Black Rock Lake.** CT DEEP's Black Rock State Park, a multi-use outdoor recreational area, encompasses 439 acres in Watertown. The park includes Black Rock Pond (used for swimming and fishing), various hiking trails (including the CFPA's Mattatuck Trail and the park's Red Trail), a campground with 78 sites, picnic areas, and a nature center. The park abuts the Mattatuck State Forest on the south, and Branch Brook and Black Rock Lake, which forms the boundary between the towns of Watertown and Thomaston, to the north.

In 1970, the USACE completed the construction of Black Rock Dam, damming the upstream portion of Branch Brook and creating the 21-acre Black Rock (Conservation) Lake as well as Wigwam Reservoir. The dam is part of a network of USACE flood control projects within the Naugatuck River basin. The USACE and CT DEEP cooperatively manage approximately 341 acres⁶³ of land and water resources in the Black Rock Lake area for recreation, wildlife, and forestry resources. Recreational opportunities include fishing and hiking, as well as nature viewing. An overlook on top of the dam is accessible from State Route 109, and a portion of the CFPA's Mattatuck Trail extends west along the south side of the lake and reservoir. The Black Rock Lake recreational area is located in both Watertown and Thomaston, spanning the border between the two towns.

⁶³ The 314 acres includes approximately 173 acres of USACE land and 141 acres of CT DEEP land.

The Proposed Route follows Eversource's existing 250-foot-wide ROW across approximately 1.06 mile of Black Rock State Park lands within the Town of Watertown, and approximately 0.10 mile of Black Rock State Park property in the Town of Thomaston.

- **Thomaston Fish & Game Club.** The Proposed Route would be located within Eversource's existing 250 foot ROW across approximately 0.24 mile of the privately-owned Thomaston Fish and Game Club lands in the Town of Thomaston. The club's property is located off Old Northfield Road.
- **Northfield Brook Lake and Recreation Area.** Northfield Brook Lake Recreation Area is a 208-acre day use park, owned by the USACE and located north of State Route 254. The area includes an 8-acre lake (which CT DEEP stocks with trout), a small beach and swimming area, picnic areas (with picnic shelters and grills), and a 1.7-mile self-guided hiking trail. This area is also a CT DEEP-designated deer and turkey bow hunting area. The Eversource ROW crosses approximately 0.07 mile through the northern portion of the recreation area, near the entrance off State Route 254. The self-guided trail crosses the ROW near Northfield Brook, as well as in an upland area east of the park access road.
- **Thomaston Dam and Naugatuck River Greenway.** This USACE-owned area encompasses approximately 850 acres along both sides of the Naugatuck River in the towns of Thomaston, Litchfield, Harwinton, and Plymouth. The area includes Thomaston Dam, which is part of the USACE's network of dams built to control flooding in the Naugatuck River Basin. The area is managed for a variety of recreational uses including hiking, snowmobiling, trail biking, fishing, picnicking, model airplane flying, and upland hunting (pheasant, small game, waterfowl, deer bow hunting and turkey). The U.S. Department of the Interior, National Park Service ([NPS]; Rivers, Trails and Conservation Assistance Program⁶⁴) is working with towns along the Naugatuck River to create a Naugatuck River Greenway, which would extend for 44 miles along the river between the cities of Torrington and Derby. In the Project area, this trail would extend along the USACE-owned land along the river. The Proposed Route would include an approximately 0.4-mile span of the Naugatuck River and associated USACE recreational areas (refer to XS-5 in Appendix 3A).

In addition, the Proposed Route traverses two state-designated greenways: the CFPA's Mattatuck Trail in the Town of Watertown and the Naugatuck River, which forms the border between the towns of Litchfield and Harwinton.⁶⁵ According to C.G.S. § 23-100, a "greenway" means a corridor of open space that may protect natural resources, preserve scenic landscapes and historical resources or offer opportunities for recreation or non-motorized transportation; may connect existing protected areas and provide access to the outdoors; may be located along a defining natural feature, such as a waterway, along a man-made corridor, including an unused ROW, traditional trail routes or historic barge canals; or may be a greenspace along a highway or around a village.

⁶⁴ The NPS's Rivers, Trails, and Conservation Assistance program provides technical assistance to community groups and government agencies that are planning projects to protect natural areas and water resources and to enhance outdoor recreational opportunities.

⁶⁵ CT DEEP, *Connecticut Greenways Council: Officially Designated Greenways 2015*.
<http://www.ct.gov/deep/lib/deep/greenways/greenwaysmap2015.pdf>

Table 5-4: Public Forest, Parks, Open Space, Land-Trust Parcels, and Trails along and in the vicinity of the Proposed Route

Town	Proximity to Route	Recreational/Scenic/Open Space Feature (Refer to Volume 5 maps for parcel location)
Watertown		
	Crosses	Mattatuck State Forest
	Extends along ROW	Jericho-Whitestone Connector Trail
	Crosses	CFPA Jericho Trail
	Crosses	Veterans Memorial Park
	Adjacent	Crestbrook Park and Golf Club
	Crosses	Black Rock State Park
	Crosses	CFPA Mattatuck Trail
	Crosses	Black Rock State Park Red Trail Loop (two crossings)
	Crosses	Black Rock Lake Dam (USACE)
Thomaston		
	Crosses	Black Rock Lake Dam (USACE)
	Crosses	Mattatuck State Forest
	Crosses	Thomaston Fish and Game Club
	Adjacent	Town Open Space (Dug Road)
	Crosses	Northfield Brook Recreation Area (USACE)
	0.07 mile to west	Mattatuck State Forest
Litchfield		
	0.28 mile to west	Humaston Brook State Park Scenic Reserve
	Crosses	Thomaston Dam Recreation Area / Naugatuck River Greenway (USACE)
Harwinton		
	Crosses	Thomaston Dam Recreation Area / Naugatuck River Greenway (USACE)

5.1.5 Designated Protected and Scenic Resources

As summarized in in this section, described in more detail in the *Visual Resources Analysis* (Volume 3), and depicted on the Volume 5, 400 scale maps, the proposed 115-kV transmission line would be located within Eversource's existing ROW across or near several areas that have scenic attributes, such as established recreational trails (e.g., the CFPA's Jericho-Whitestone Connector Trail, Jericho Trail and Mattatuck Trail; the Red Trail Loop within Black Rock State Park); Veteran's Memorial Park; Black Rock State Park; Black Rock Lake and Dam; Northfield Brook Recreational Area; and the Naugatuck River greenway. Through all of these areas, the proposed 115-kV line would be located adjacent to one

or more of Eversource's existing overhead 115-kV lines and, in portions of Watertown, also located adjacent to a 345-kV overhead transmission line.

The ROW also traverses near one locally-designated scenic road: Hayden Road in the Town of Harwinton. The ROW extends west of the intersection of Hayden Road with Wildcat Hill Road. In addition, Hayden Road forms the southern boundary of the 42.33-acre Eversource property on which the Campville Substation is located.

The Project area does not encompass any state heritage corridors, as designated in July 2009 pursuant to Connecticut Public Act No. 09-221, codified at C.G.S. § 23-81. As set out in C.G.S. § 23-81, a heritage area is defined as a place within Connecticut that has historic, recreational, cultural, natural, and scenic resources that form an important part of the state's heritage. State agencies must take the resources of the national heritage areas into consideration in planning and project decision-making.

On December 23, 2009, the Council issued a memorandum to routine applicants / participants concerning, among other issues, the consideration of scenic quality and the aesthetic attributes of land that might be affected by projects under the Council's jurisdiction. In the same memorandum, the Council advised applicants to use photographs of aesthetic areas, particularly for use in photo-simulations that depict "leaf off" conditions. In the absence of deciduous vegetative screening, such "leaf off" conditions would tend to represent "worst case" (or maximum) views of potential project facilities.

Pursuant to the Council's specifications for visual resource analyses, Eversource conducted research to identify designated scenic, recreational, open space, and historic properties (collectively referred to herein as the "visual sites") crossed by or in the vicinity of the Proposed Route. These sites were identified based on the review of Project mapping, data contained in land use sections of town plans, Internet research, and other published information such as the CFPA's *Walk Book West* and data concerning ConnDOT's scenic land strips. In general, designated scenic, recreation, open space, and historic sites crossed by or within approximately 0.5 - 1 mile of the Proposed Route were identified for further evaluation. Field inspections were conducted of each of the identified potential visual sites. The objectives of the field inspections were to:

- Assess the relationship of each potential visual site to the existing Eversource ROW within which the Project is planned;
- Determine whether Eversource's existing overhead transmission line(s) are currently visible from each potential visual resource site; and

- Photo-document views, as applicable, of the existing transmission line(s) from the visual sites. Sites that were determined to be too geographically remote from the ROW or from which views of the overhead transmission lines were blocked by intervening topography, vegetation, or land uses, were not photographed.

Initial field reviews to document visual conditions under “leaf off” conditions (when the existing overhead transmission lines would be most visible) were conducted in April 2015.

In May 2015, Eversource conducted follow-up field visits to assess and photo-document conditions at the same sites when deciduous forest vegetation was leafed out. In general, such “leaves on” conditions are representative of the spring through fall seasons when public use of most of the designated recreational or scenic areas near the ROW can be expected to be highest.

Table 5-11 at the end of this section identifies the sites from which the existing Eversource transmission line(s) are visible during “leaf off” and “leaf on” conditions, based on the field inspections. In most cases, long views of the existing transmission lines from sites remote from the ROW were found to be precluded by intervening topography, vegetation, and land uses. Overall, the rugged topography along the Proposed Route limited most long views of the ROW and overhead transmission lines.

For each site with views of the existing transmission line, the table identifies its location in relation to the existing Eversource ROW and summarizes its known aesthetic, recreational, or cultural attributes.

Overall, the primary scenic areas from which the existing transmission lines are visible include the Jericho-Whitestone Connector Trail, Jericho Trail, Mattatuck Trail, Black Rock State Park Red Loop Trail, Black Rock Lake / Dam, Northfield Brook Lake Recreation area (trail, picnic area, and access road), and the Naugatuck River.

5.1.5 Transportation Systems and Utility Crossings

As listed in Table 5-5 and shown on the maps in Volume 5, the road transportation network in the vicinity of the Proposed Route is well developed and consists of a variety of federal, state, and local roads.

Principal roads include U.S. Route 6; State Routes 8 (James H. Darcey Memorial Highway), 109, 262, and 254. The Federal Aviation Administration (FAA) has the following notification requirements associated with the construction or alteration of an electric transmission line:

- Any construction or alteration exceeding 200 feet above ground level

- Within 20,000 feet of a public use or military airport which exceeds a 100:1 surface from any point on the runway of each airport with its longest runway more than 3,200 feet
- Within 10,000 feet of a public use or military airport which exceeds a 50:1 surface from any point on the runway of each airport with its longest runway no more than 3,200 feet
- Within 5,000 feet of a public use heliport which exceeds a 25:1 surface

Waterbury Airport is a privately-owned airport, open for public use located approximately 7,000 feet northeast of the Proposed Route in the Town of Plymouth. The airport has a two grass runways, 1,600 feet and 2,005 feet in length and operates using visual flight rules (VFR) with no established instrument procedures. The runway elevation is 850 feet above mean sea level (AMSL) and based on analysis of the transmission line structures along the Proposed Route, none of the structures would exceed the FAA notification criteria for this airport.

Northfield Heliport is a privately-owned heliport, open for public use located approximately 7,100 feet west of the Proposed Route in the Town of Litchfield. The helipad is grass and operates using visual flight rules with no established instrument procedures. The helipad elevation is 903 feet AMSL and based on analysis of the transmission line structures along the Proposed Route, none of the structures would exceed the FAA notification criteria for this heliport.

Waterbury-Oxford Airport is the nearest publicly-owned airport, located approximately 9.5 miles south of the Proposed Route in the Town of Oxford. The airport has one, 5,800-foot asphalt runway and operates using VFR and instrument flight rules (IFR) with established instrument procedures. The runway elevation is 726 feet AMSL and based on analysis of the transmission line structures along the Proposed Route, none of the structures would exceed the FAA notification criteria for this airport.

ConnDOT owns a railroad track that extends along the Naugatuck River within the Project area, from Waterbury to Torrington. This rail line is located east of the Frost Bridge Substation and is traversed by the Proposed Route along the west side of the river in Litchfield.

The Railroad Museum of New England (RMNE) operates heritage railroad, referred to as the Naugatuck Railroad, over portions of these tracks. The RMNE offers scenic excursions, typically from the Waterville neighborhood of Waterbury to Thomaston.

Table 5-5: Road Crossings – Proposed Route

Town	Road Name	Road Type
Watertown		
	Frost Bridge Road (State Route 262)	State Highway
	State Route 8	Major State Highway
	Echo Lake Road	Local Road
	Park Road	Local Road
	Seemar Road	Local Road
	Nova Scotia Hill Road	Local Road
	Thomaston Road (US Route 6)	Federal Highway
Thomaston		
	Old Branch Road	Local Road
	Branch Road (State Route 109)	State Highway
	Walnut Hill Road	Local Road
	Northfield Road (State Route 254)	State Highway
	Northfield Dam Access Road	Local Road
Litchfield		
	Mason Hill Road	Local Road
	Hopkins Road	Local Road
	Thomaston-Campville Road	Local Road
	State Route 8	Major State Highway
Harwinton		
	Valley Road	Local Road
	Wildcat Hill Road	Local Road

5.1.6 Cultural (Archaeological and Historic) Resources

Cultural resources include buried archaeological sites, standing historic structures, or thematically-related groups of structures. To be considered significant and eligible for listing on the National or State Registers of Historic Places (NRHP/SRHP), a cultural resource must exhibit physical integrity and contribute to American history, architecture, archaeology, technology, or culture; and must possess at least one of the following four criteria:

- Association with important historic events;
- Association with important persons;
- Distinctive design or physical characteristics; and
- Potential to provide important new information about prehistory or history.

The State Historic Preservation Office (SHPO) is responsible for reviewing proposed projects to ensure that significant cultural resources will be protected or otherwise preserved. In Connecticut, the SHPO's office is part of the Connecticut Commission on Arts, Tourism, Culture, History, and Film.

As part of the Project planning effort, Eversource's cultural resources consultant conducted a preliminary archaeological and historical resources assessment (Phase 1A) along the Proposed Route and at each substation. This assessment is anticipated to be submitted to the SHPO, subsequently finalized in the fall of 2015 and will be included in the Application to the Council. The objectives of this assessment were: 1) to gather and present data regarding previously identified cultural resources situated within the vicinity of the Proposed Route; 2) to investigate the Project area's natural and historical characteristics; 3) to complete a visual survey of the Area of Potential Effect, and 4) to identify culturally sensitive areas in proximity to the Proposed Route. This review verified there are no previously identified historic structures, archaeological sites or National Register of Historic Places properties on file with the Connecticut State Historic Preservation Office that are situated within 152 m (500 ft) of the proposed project corridor or in the general vicinity.

Eversource will coordinate with the SHPO regarding the need for any additional studies that may be required to identify and/or further evaluate known or potentially significant cultural resources in the vicinity of the Project.

5.1.7 Air Quality

Ambient air quality is affected by pollutants emitted from both mobile sources (e.g., automobiles, trucks) and stationary sources (e.g., manufacturing facilities, power plants, and gasoline stations). Naturally occurring pollutants, such as radon gas or emissions from forest fires, also affect air quality.

In addition to emissions from sources within the state, Connecticut's air quality is significantly affected by pollutants emitted in states located to the south and west, and then transported into Connecticut by prevailing winds. Ambient air quality in the state is monitored and evaluated by the CT DEEP. Air quality conditions are assessed in terms of compliance with the National Ambient Air Quality Standards (NAAQS) for selected "criteria" pollutants, as well as conformance with regulations governing the release of toxic or hazardous air pollutants. Litchfield County is in conformance with all National Ambient Air Quality Standards established by the Federal Clean Air Act Amendment standards except for the 8-hour ozone criterion. The U.S. Environmental Protection Agency (EPA) has determined that carbon dioxide

(CO₂) is a pollutant and has included CO₂ in its list of criteria pollutants. Areas of non-attainment have not yet been established for CO₂ or other greenhouse gases.

In an effort to reduce particulate emissions, the CT DEEP has promulgated a regulation (RCSA§ 22a-174-18), that prohibits unnecessary idling for more than 3 minutes. Exceptions are made for weather extremes, certain service vehicles, and health-related conditions.

5.1.8 Noise

Existing noise levels in the vicinity of the Proposed Route vary as a function of land use, and can be expected to range from sound levels typical of an urban environment to those typical of quiet, rural areas. Noise levels are also variable throughout the day, and are influenced by diverse factors such as vehicular traffic, commercial and industrial activities and outdoor activities typical of suburban environments. Table 5-6 below lists typical sound levels associated with different types of environments and activities.

The State of Connecticut has noise regulations (RCSA §§ 22a-69-1 to 22a-69-7.4) identifying the sound limits that can be emitted by certain types of land uses. The state regulations define daytime vs. nighttime noise periods; classify noise zones based on land use; and identify noise standards for each zone. Table 5-7 summarizes Connecticut's noise zone standards, by emitter (source) and receptor (receiver) noise classification. In general, the regulations specify that noise emitters must not cause the emission of excessive noise beyond the boundaries of their noise zone so as to exceed the allowable noise levels on a receptor's land.

As illustrated in Table 5-7, the allowable noise levels vary by type of noise emitter and type of noise receptor. For example, an industrial noise emitter is allowed a 70 dBA (decibel, on the A-weighted scale) level on another industrial receptor's property, but only a 61 dBA (daytime) level on a residential receptor's property. Where multiple noise emitter/noise receptor types exist on the same property, the least restrictive limits apply.

Table 5-6: Typical Noise Levels Associated with Different Indoor and Outdoor Activities

Outdoor Noise Levels	A-Weighted Sound Level (dBA)	Indoor Noise Levels
Jet aircraft take-off at 100 feet	+120	
Riveting machine at operator's position	+110	
Cut-off saw at operator's position	+100	
Elevated subway at 50 feet		
		Newspaper press
Automobile horn at 10 feet		
	+90	Industrial boiler room
Diesel truck at 50 feet		Food blender at 3 feet
Noisy urban daytime	+80	Garbage disposal at 3 feet
Diesel bus at 50 feet		
		Shouting at 3 feet
	+70	
Gas lawn mower at 100 feet		Vacuum cleaner at 10 feet
Quiet urban daytime	+60	Normal conversation at 5 - 10 feet
		Large business office
Quiet urban nighttime	+50	Open office area background level
Substation (transformer)	+43	
Quiet suburban nighttime		
	+40	Large conference room
		Small theater (background)
Quiet rural nighttime	+30	Soft whisper at 2 feet
		Bedroom at nighttime
	+20	Concert hall

Table 5-7: State of Connecticut Noise-Control Regulations by Emitter and Receptor Land-Use Classification

Noise Emitter Class	Noise Receptor Class			
	C: Industrial	B: Generally Commercial	A: Residential Day	A: Residential Night
C: Industrial	70 dBA	66 dBA	61 dBA	51 dBA
B: Generally Commercial	62 dBA	62 dBA	55 dBA	45 dBA
A: Residential	62 dBA	55 dBA	55 dBA	45 dBA

Definitions:

Day = 7:00 AM to 9:00 PM Monday – Saturday; 9:00 AM to 9:00 PM Sunday

Night = 9:00 PM to 7:00 AM Monday – Saturday; 9:00 PM to 9:00 AM Sunday

The regulation also prohibits the production of prominent, audible discrete tones. If a facility produces such sounds, the applicable limits in Table 5-7 are reduced by 5 dBA to offset the undesirable nature of tonal sound in the environment. The regulation defines prominent discrete tones on the basis of one-third octave band sound levels.

Construction noise is exempted under RCSA § 22a-69-1.8(h); therefore, the noise limits presented in Table 5-7 do not apply to construction of this Project.

In accordance with the Connecticut General Statutes § 22a-73, municipalities also may adopt noise-control ordinances. Such ordinances must be approved by the Commissioner of CT DEEP and be consistent with the state noise regulations. Of the four towns traversed by the Project, only Watertown has an established noise ordinance (Chapter 12, Article 2). The ordinance does not reference acceptable noise levels for construction activities. It does, however, prevent (without special permit) the operation of heavy equipment between the hours of from 8:00 p.m. through 6 a.m. Monday through Saturday, and 6:00 p.m. through 9:00 a.m. on Sundays.

5.2 SUBSTATIONS

To interconnect the new 115-kV transmission line to the transmission system, Eversource proposes to modify both Frost Bridge Substation and Campville Substation. Characteristics of the existing environment and cultural resources that are unique to these locations are described below. Air quality characteristics at each substation are similar to the Proposed Route (refer to Section 5.1.7) and therefore, not described in this section.

5.2.1 Frost Bridge Substation

Frost Bridge Substation, which is located in the southeastern portion of the Town of Watertown, occupies approximately 5.7 acres of a 128.5-acre site owned by Eversource. The modifications required to interconnect Frost Bridge Substation to the new 115-KV transmission line would be accomplished within the developed (fenced) portion of the property. No expansion or modification to the existing fence line would be required.

5.2.1.1 Geology, Topography, and Soils

Frost Bridge Substation is located in the Naugatuck River Valley at the base of a hillside perched above the Naugatuck River. Elevations in the vicinity range approximately 350 feet at Frost Bridge Road to approximately 300 feet along the Naugatuck River. Slopes above the valley rise steeply to elevations in excess of 700 feet. Three bedrock formations interface near the Eversource property, all predominately composed of schists. Soils at the highest elevations along Frost Bridge Road are formed in shallow till deposits over bedrock. The northern portion of the substation consists of an undulating outwash terrace with a steep escarpment to the east, facing the river. Below approximately elevation 310 feet, alluvial soils associated with the Naugatuck River are encountered. Till soils are mostly well or somewhat excessively drained, outwash soils excessively drained across much of the site and very poorly drained in wetland depressions, and floodplain soils well to poorly drained.

5.2.1.2 Water Resources

Six wetland systems were identified in the vicinity of the developed substation on Eversource's property (refer to Volume 5 maps). Portions of two of these wetlands (W-FB1 and W-FB6) are characterized by non-hydric alluvial soils and as such, are Connecticut wetlands only. The surface water quality of the Naugatuck River is rated use Class B. Groundwater at the site is rated as GA.

5.2.1.3 Flood Zones

A review of FEMA maps indicates that the Frost Bridge Substation is beyond the limits of both the 100-year and 500-year flood zones associated with the Naugatuck River to the east.

5.2.1.4 Biological Resources

The most notable biological resource present in the vicinity of the substation is the Naugatuck River, which is located approximately 260 feet east of the fence line. The substation property is separated from the river by a railroad grade. No open water habitats are present within the property. Terrestrial habitats present within the property include upland forest, upland shrubland, forested wetland, and shrub wetland.

A discussion of these habitats and the associated wildlife species is provided in Section 5.1.3.2. Larger wildlife species are mostly excluded from the property by significant barriers to movement, including State Route 8 to the west, the railroad, industrial development, and the Naugatuck River to the east and north.

5.2.1.5 Existing and Future Land Uses, Recreational Areas, and Visual Resources

The substation property is bounded by the Naugatuck Railroad and Naugatuck River to the east, Frost Bridge Road and State Route 8 to the west, and undeveloped property to the north and south. The Naugatuck River forms the boundary between the towns of Watertown and Thomaston.

The substation property is classified as within a “growth area” in Connecticut’s C&D Plan and is zoned by the Town of Watertown as general industrial land (IG 80). Lands in the immediate vicinity of Frost Bridge Substation also are zoned for general industrial uses. The Town of Watertown *Plan of Conservation and Development* (2007) calls for future land use on and in the vicinity of the substation to be for industrial park purposes.

Frost Bridge Substation is isolated from other land uses by the Naugatuck River, Frost Bridge Road and State Route 8, and steep topography. There are no residential areas in the vicinity. The closest residence is located on Echo Lake Road, approximately 1,200 feet to the southwest. A portion of the Mattatuck State Forest is located east of the substation, across the Naugatuck River, and east of State Route 262, in the Town of Thomaston. The substation is not in the vicinity of any designated scenic or recreational resources.

The existing substation and the various overhead transmission line structures that extend into and out of the substation are partially visible from State Routes 8 and 262, the railroad, and Frost Bridge Road.

5.2.1.6 Transportation and Access

Frost Bridge Substation is readily accessible via Frost Bridge Road and existing ROW access roads. The existing access roads are depicted on the maps in Volume 5.

5.2.1.7 Noise

Frost Bridge Substation is located within an area zoned for industrial use and generally isolated from other land uses by the Naugatuck River, Frost Bridge Road and State Route 8, and steep topography. The ambient sound environment is predominantly influenced by vehicular traffic along State Route 8,

followed by the operation of Frost Bridge Substation, and occasional train movement along the railroad tracks located to the east of the substation.

5.2.2 Campville Substation

Eversource's Campville Substation is located in the southwestern portion of the Town of Harwinton and currently occupies approximately 1.65 acres of a 42.33-acre property owned by Eversource. The property is bordered by Wildcat Hill Road to the west, Hayden Road to the south, and private property to the north and east.

To accommodate modifications required to interconnect the new 115-kV transmission line, Eversource proposes to expand the developed portion of the substation by approximately 0.4 acre. These modifications would require an expansion of the substation fence line by approximately 90 feet to the east.

5.2.2.1 Geology, Topography, and Soils

Campville Substation is located on a west-facing hillside above the Naugatuck River Valley. Elevations in the vicinity range approximately 760 feet at Wildcat Hill Road to 840 feet to the north of Campville Substation. Bedrock geologic formations near the substation are predominately composed of schists. Soils are formed in shallow till deposits over bedrock. Till soils are mostly well or somewhat excessively drained across much of the site and poorly and very poorly drained in wetland depressions.

5.2.2.2 Water Resources

Three wetland systems were identified in the vicinity of the developed substation on the Eversource property. Wetlands W-G1 and W-G2 are located south and north of the substation, respectively. Each wetland receives stormwater inputs from the fenced portions of the substation via overland flow and/or culvert outfall. Wetland W-G3 is a red maple swamp located to the east of the substation. Groundwater at the site is rated as GA.

5.2.2.3 Biological Resources

The vegetative communities in the vicinity of the substation consist principally of upland forest (mixed deciduous and coniferous forest) and open field-shrub land. A discussion of these habitats and the associated wildlife species is provided in Section 5.1.3.2.

5.2.2.4 Existing and Future Land Uses, Recreational Areas, and Visual Resources

The substation is within an area zoned by the Town of Harwinton for Country Residential Use. This zoning classification characterizes all of the land in southern Harwinton. Lands in the vicinity of the substation consist of a mix of undeveloped, mostly forested land, along with single-family residential uses. The entrance to the substation is off Wildcat Hill Road, along which single-family residential land uses predominate.

There are no designated scenic or public recreational areas in the vicinity of the Campville Substation. Hayden Road, which borders the Eversource property to the south, is a town-listed scenic road. However, due to topography and intervening vegetation, the substation is not visible from this road.

5.2.2.5 Transportation and Access

Campville Substation is readily accessible via Wildcat Hill Road and existing access roads.

5.2.2.6 Noise

Campville Substation is located in a rural / suburban area dominated by forest. The ambient noise levels are low which is typical of such areas.

Note: This page left blank intentionally

**Table 5-8
Soils and Soil Characteristics
along the Proposed Route**

Table 5-8: Soils and Soil Characteristics along the Proposed Route

Soil Map Unit		Parent Material	Hydric Soil	Depth to Restrictive Feature (inches)	Depth to Water Table (inches)	Hazard of –Off-Road or Off-Trail Erosion
Symbol	Name					
3	Ridgebury, Leicester, and Whitman soils, extremely stony	Coarse-loamy lodgment till derived from granite and/or schist and/or gneiss; or coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	Yes	12-30 to Dense material	0-18	Slight
5	Wilbraham silt loam ²	Coarse-loamy lodgment till derived from basalt and/or sandstone and shale.	Yes	20-36 to Dense material	0-18	Slight
6	Wilbraham and Menlo soils, extremely stony	Coarse-loamy lodgment till derived from basalt and/or sandstone and shale.	Yes	20-36 to Dense material	0-18	Slight
12	Raypol silt loam ²	Coarse-loamy eolian deposits over sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss.	Yes	—	0-12	Slight
13	Walpole sandy loam ²	Sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss.	Yes	—	0-12	Slight
15	Scarboro muck	Sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss.	Yes	—	0-6	Slight
17	Timakwa and Natchaug soils	Woody organic material over sandy and gravelly glaciofluvial deposits; Woody organic material over loamy alluvium and/or loamy glaciofluvial deposits and/or loamy till.	Yes	—	0-12	Very Severe
18	Catden and Freetown soils	Woody organic material; organic material.	Yes	—	0-12	Very Severe
21A	Ninigret and Tisbury soils, 0 to 5 % slopes ¹	Coarse-loamy eolian deposits over sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss; Coarse-silty eolian deposits over sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss.	No	—	18-30	Slight
23A	Sudbury sandy loam, 0 to 5 % slopes ¹	Sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss.	No	—	18-36	Slight
29A	Agawam fine sandy loam, 0 to 3 % slopes ¹	Coarse-loamy eolian deposits over sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss.	No	—	—	Slight
29B	Agawam fine	Coarse-loamy eolian deposits over	No	—	—	Slight

Table 5-8: Soils and Soil Characteristics along the Proposed Route

Soil Map Unit		Parent Material	Hydric Soil	Depth to Restrictive Feature (inches)	Depth to Water Table (inches)	Hazard of –Off-Road or Off-Trail Erosion
Symbol	Name					
	sandy loam, 3 to 8 % slopes ¹	sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss.				
32A	Haven and Enfield soils, 0 to 3 % slopes ¹	Coarse-loamy eolian deposits over sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss; Coarse-silty eolian deposits over sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss.	No	—	—	Slight
32B	Haven and Enfield soils, 3 to 8 % slopes ¹	Coarse-loamy eolian deposits over sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss; Coarse-silty eolian deposits over sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss.	No	—	—	Slight
34A	Merrimac sandy loam, 0 to 3 % slopes ¹	Sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss.	No	—	—	Slight
34B	Merrimac sandy loam, 3 to 8 % slopes ¹	Sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss.	No	—	—	Slight
36A	Windsor loamy sand, 0 to 3 % slopes ²	Eolian sands over sandy glaciofluvial deposits derived from granite and/or schist and/or gneiss.	No	—	—	Slight
36B	Windsor loamy sand, 3 to 8 % slopes ²	Eolian sands over sandy glaciofluvial deposits derived from granite and/or schist and/or gneiss.	No	—	—	Slight
36C	Windsor loamy sand, 8 to 15 % slopes ²	Eolian sands over sandy glaciofluvial deposits derived from granite and/or schist and/or gneiss.	No	—	—	Slight
37C	Manchester gravelly sandy loam, 3 to 15 % slopes ²	Sandy and gravelly glaciofluvial deposits derived from sandstone and shale and/or basalt.	No	—	—	Slight
38A	Hinckley gravelly sandy loam, 0 to 3 % slopes ²	Sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss.	No	—	—	Slight
38C	Hinckley gravelly sandy	Sandy and gravelly glaciofluvial deposits derived from granite	No	—	—	Slight

Table 5-8: Soils and Soil Characteristics along the Proposed Route

Soil Map Unit		Parent Material	Hydric Soil	Depth to Restrictive Feature (inches)	Depth to Water Table (inches)	Hazard of -Off-Road or Off-Trail Erosion
Symbol	Name					
	loam, 3 to 15 % slopes ²	and/or schist and/or gneiss.				
38E	Hinckley gravelly sandy loam, 15 to 45 % slopes	Sandy and gravelly glaciofluvial deposits derived from granite and/or schist and/or gneiss.	No	—	—	Moderate
41B	Ludlow silt loam, 2 to 8 % slopes, very stony	Coarse-loamy lodgment till derived from basalt and/or sandstone and shale.	No	20-40 to Dense material	18-30	Slight
43A	Rainbow silt loam, 0 to 3 % slopes ¹	Eolian deposits over coarse-loamy lodgment till derived from gneiss and/or schist and/or sandstone and/or basalt.	No	20-40 to Dense material	18-30	Slight
43B	Rainbow silt loam, 3 to 8 % slopes ¹	Eolian deposits over coarse-loamy lodgment till derived from gneiss and/or schist and/or sandstone and/or basalt.	No	20-40 to Dense material	18-30	Slight
44B	Rainbow silt loam, 2 to 8 % slopes, very stony	Eolian deposits over coarse-loamy lodgment till derived from gneiss and/or schist and/or sandstone and/or basalt.	No	20-40 to Dense material	18-30	Slight
45A	Woodbridge fine sandy loam, 0 to 3 % slopes ¹	Coarse-loamy lodgment till derived from granite and/or schist and/or gneiss.	No	20-40 to Dense material	18-30	Slight
45B	Woodbridge fine sandy loam, 3 to 8 % slopes ¹	Coarse-loamy lodgment till derived from granite and/or schist and/or gneiss.	No	20-40 to Dense material	18-30	Slight
45C	Woodbridge fine sandy loam, 8 to 15 % slopes ²	Coarse-loamy lodgment till derived from granite and/or schist and/or gneiss.	No	20-40 to Dense material	18-30	Slight
46B	Woodbridge fine sandy loam, 2 to 8 % slopes, very stony	Coarse-loamy lodgment till derived from granite and/or schist and/or gneiss.	No	20-40 to Dense material	18-30	Slight
47C	Woodbridge fine sandy loam, 2 to 15 % slopes, extremely stony	Coarse-loamy lodgment till derived from granite and/or schist and/or gneiss.	No	20-40 to Dense material	18-30	Slight
50A	Sutton fine sandy loam, 0	Coarse-loamy melt-out till derived from granite and/or schist and/or	No	—	18-30	Slight

Table 5-8: Soils and Soil Characteristics along the Proposed Route

Soil Map Unit		Parent Material	Hydric Soil	Depth to Restrictive Feature (inches)	Depth to Water Table (inches)	Hazard of -Off-Road or Off-Trail Erosion
Symbol	Name					
	to 3 % slopes ¹	gneiss.				
50B	Sutton fine sandy loam, 3 to 8 % slopes ¹	Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	No	—	18-30	Slight
51B	Sutton fine sandy loam, 2 to 8 % slopes, very stony	Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	No	—	18-30	Slight
52C	Sutton fine sandy loam, 2 to 15 % slopes, extremely stony	Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	No	—	18-30	Slight
58C	Gloucester gravelly sandy loam, 8 to 15 % slopes, very stony	Sandy and gravelly melt-out till derived from granite and/or schist and/or gneiss.	No	—	—	Slight
59C	Gloucester gravelly sandy loam, 3 to 15 % slopes, extremely stony	Sandy and gravelly melt-out till derived from granite and/or schist and/or gneiss.	No	—	—	Slight
59D	Gloucester gravelly sandy loam, 15 to 35 % slopes, extremely stony	Sandy and gravelly melt-out till derived from granite and/or schist and/or gneiss.	No	—	—	Moderate
60B	Canton and Charlton soils, 3 to 8 % slopes ¹	Coarse-loamy over sandy and gravelly melt-out till derived from granite and/or schist and/or gneiss; Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	No	—	—	Slight
60C	Canton and Charlton soils, 8 to 15 % slopes ²	Coarse-loamy over sandy and gravelly melt-out till derived from granite and/or schist and/or gneiss; Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	No	—	—	Slight
60D	Canton and Charlton soils, 15 to 25 % slopes	Coarse-loamy over sandy and gravelly melt-out till derived from granite and/or schist and/or gneiss; Coarse-loamy melt-out till derived	No	—	—	Moderate

Table 5-8: Soils and Soil Characteristics along the Proposed Route

Soil Map Unit		Parent Material	Hydric Soil	Depth to Restrictive Feature (inches)	Depth to Water Table (inches)	Hazard of -Off-Road or Off-Trail Erosion
Symbol	Name					
		from granite and/or schist and/or gneiss.				
61B	Canton and Charlton soils, 3 to 8 % slopes, very stony	Coarse-loamy over sandy and gravelly melt-out till derived from granite and/or schist and/or gneiss; Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	No	—	—	Slight
61C	Canton and Charlton soils, 8 to 15 % slopes, very stony	Coarse-loamy over sandy and gravelly melt-out till derived from granite and/or schist and/or gneiss; Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	No	—	—	Slight
62C	Canton and Charlton soils, 3 to 15 % slopes, extremely stony	Coarse-loamy over sandy and gravelly melt-out till derived from granite and/or schist and/or gneiss; Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	No	—	—	Slight
62D	Canton and Charlton soils, 15 to 35 % slopes, extremely stony	Coarse-loamy over sandy and gravelly melt-out till derived from granite and/or schist and/or gneiss; Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	No	—	—	Moderate
67B	Narragansett silt loam, 3 to 8 % slopes, very stony	Coarse-loamy eolian deposits over sandy and gravelly melt-out till derived from gneiss and/or schist and/or sandstone and shale.	No	—	—	Slight
67C	Narragansett silt loam, 8 to 15 % slopes, very stony	Coarse-loamy eolian deposits over sandy and gravelly melt-out till derived from gneiss and/or schist and/or sandstone and shale.	No	—	—	Slight
73C	Charlton-Chatfield complex, 3 to 15 % slopes, very rocky	Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	No	20-40 to Lithic bedrock	—	Slight
73E	Charlton-Chatfield complex, 15 to 45 % slopes, very rocky	Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	No	20-40 to Lithic bedrock	—	Moderate

Table 5-8: Soils and Soil Characteristics along the Proposed Route

Soil Map Unit		Parent Material	Hydric Soil	Depth to Restrictive Feature (inches)	Depth to Water Table (inches)	Hazard of -Off-Road or Off-Trail Erosion
Symbol	Name					
75C	Hollis-Chatfield-Rock outcrop complex, 3 to 15 % slopes	Loamy melt-out till derived from granite and/or schist and/or gneiss; Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	No	0-40 to Lithic bedrock	—	Slight
75E	Hollis-Chatfield-Rock outcrop complex, 15 to 45 % slopes	Loamy melt-out till derived from granite and/or schist and/or gneiss; Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss.	No	0-40 to Lithic bedrock	—	Moderate
76E	Rock outcrop-Hollis complex, 3 to 45 % slopes	Loamy melt-out till derived from granite and/or schist and/or gneiss.	No	0-20 to Lithic bedrock	—	Moderate
76F	Rock outcrop-Hollis complex, 45 to 60 % slopes	Loamy melt-out till derived from granite and/or schist and/or gneiss.	No	0-20 to Lithic bedrock	—	Very Severe
78C	Holyoke-Rock outcrop complex, 3 to 15 % slopes	Loamy eolian deposits over melt-out till derived from basalt and/or sandstone and shale.	No	0-20 to Lithic bedrock	—	Slight
78E	Holyoke-Rock outcrop complex, 15 to 45 % slopes	Loamy eolian deposits over melt-out till derived from basalt and/or sandstone and shale.	No	0-20 to Lithic bedrock	—	Slight
79E	Rock outcrop-Holyoke complex, 3 to 45 % slopes	Loamy eolian deposits over melt-out till derived from basalt and/or sandstone and shale.	No	0-20 to Lithic bedrock	—	Moderate
82B	Broadbrook silt loam, 3 to 8 % slopes ¹	Eolian deposits over coarse-loamy lodgment till derived from gneiss and/or schist and/or sandstone and/or basalt.	No	20-40 to Dense material	18-30	Slight
82C	Broadbrook silt loam, 8 to 15 % slopes ²	Eolian deposits over coarse-loamy lodgment till derived from gneiss and/or schist and/or sandstone and/or basalt.	No	20-40 to Dense material	18-30	Moderate
83B	Broadbrook silt loam, 3 to 8 % slopes, very stony	Eolian deposits over coarse-loamy lodgment till derived from gneiss and/or schist and/or sandstone and/or basalt.	No	20-40 to Dense material	18-30	Slight
84B	Paxton and	Coarse-loamy lodgment till derived	No	20-40 to	18-30	Slight

Table 5-8: Soils and Soil Characteristics along the Proposed Route

Soil Map Unit		Parent Material	Hydric Soil	Depth to Restrictive Feature (inches)	Depth to Water Table (inches)	Hazard of -Off-Road or Off-Trail Erosion
Symbol	Name					
	Montauk fine sandy loams, 3 to 8 % slopes ¹	from granite and/or schist and/or gneiss; Coarse-loamy lodgment till derived from granite and/or coarse-loamy lodgment till derived from gneiss and/or coarse-loamy lodgment till derived from granite.		Dense material		
84C	Paxton and Montauk fine sandy loams, 8 to 15 % slopes ²	Coarse-loamy lodgment till derived from granite and/or schist and/or gneiss; Coarse-loamy lodgment till derived from granite and/or coarse-loamy lodgment till derived from gneiss and/or coarse-loamy lodgment till derived from granite.	No	20-40 to Dense material	18-30	Slight
84D	Paxton and Montauk fine sandy loams, 15 to 25 % slopes	Coarse-loamy lodgment till derived from granite and/or schist and/or gneiss; Coarse-loamy lodgment till derived from granite and/or coarse-loamy lodgment till derived from gneiss and/or coarse-loamy lodgment till derived from granite.	No	20-40 to Dense material	18-30	Moderate
85B	Paxton and Montauk fine sandy loams, 3 to 8 % slopes, very stony	Coarse-loamy lodgment till derived from granite and/or schist and/or gneiss; Coarse-loamy lodgment till derived from granite and/or coarse-loamy lodgment till derived from gneiss and/or coarse-loamy lodgment till derived from granite.	No	20-40 to Dense material	18-30	Slight
85C	Paxton and Montauk fine sandy loams, 8 to 15 % slopes, very stony	Coarse-loamy lodgment till derived from granite and/or schist and/or gneiss; Coarse-loamy lodgment till derived from granite and/or coarse-loamy lodgment till derived from gneiss and/or coarse-loamy lodgment till derived from granite.	No	20-40 to Dense material	18-30	Slight
86C	Paxton and Montauk fine sandy loams,	Coarse-loamy lodgment till derived from granite and/or schist and/or gneiss; Coarse-loamy lodgment till	No	20-40 to Dense material	18-30	Slight

Table 5-8: Soils and Soil Characteristics along the Proposed Route

Soil Map Unit		Parent Material	Hydric Soil	Depth to Restrictive Feature (inches)	Depth to Water Table (inches)	Hazard of -Off-Road or Off-Trail Erosion
Symbol	Name					
	3 to 15 % slopes, extremely stony	derived from granite and/or coarse-loamy lodgment till derived from gneiss and/or coarse-loamy lodgment till derived from gneiss and/or coarse-loamy lodgment till derived from granite.				
86D	Paxton and Montauk fine sandy loams, 15 to 35 % slopes, extremely stony	Coarse-loamy lodgment till derived from granite and/or schist and/or gneiss; Coarse-loamy lodgment till derived from granite and/or coarse-loamy lodgment till derived from gneiss and/or coarse-loamy lodgment till derived from granite.	No	20-40 to Dense material	18-30	Moderate
87B	Wethersfield loam, 3 to 8 % slopes ¹	Coarse-loamy lodgment till derived from basalt and/or sandstone and shale.	No	20-40 to Dense material	18-30	Slight
87C	Wethersfield loam, 8 to 15 % slopes ²	Coarse-loamy lodgment till derived from basalt and/or sandstone and shale.	No	20-40 to Dense material	18-30	Slight
88B	Wethersfield loam, 3 to 8 % slopes, very stony	Coarse-loamy lodgment till derived from basalt and/or sandstone and shale.	No	20-40 to Dense material	18-30	Slight
100	Suncook loamy fine sand ²	Sandy alluvium.	No	—	60-72	Slight
105	Hadley silt loam ¹	Coarse-silty alluvium.	No	—	60-72	Slight
106	Winooski silt loam ¹	Coarse-silty alluvium.	No	—	18-36	Slight
107	Limerick and Lim soils ²	Coarse-silty alluvium; Coarse-loamy alluvium.	Yes	—	0-18	Slight
108	Saco silt loam	Coarse-silty alluvium.	Yes	—	0-6	Slight
109	Fluvaquents-Udifluvents complex, frequently flooded	Alluvium.	Yes	—	0-12	Slight
243B	Rainbow-Urban land complex, 0 to 8 % slopes	Eolian deposits over coarse-loamy lodgment till derived from gneiss and/or schist and/or sandstone and/or basalt; Drift.	No	20-40 to Dense material	18-54	Slight
302	Dumps	Miscellaneous area.	No	—	—	Slight
305	Udorthents-Pits complex,	Gravelly outwash.	No	—	24-54	Moderate/Severe

Table 5-8: Soils and Soil Characteristics along the Proposed Route

Soil Map Unit		Parent Material	Hydric Soil	Depth to Restrictive Feature (inches)	Depth to Water Table (inches)	Hazard of -Off-Road or Off-Trail Erosion
Symbol	Name					
	gravelly					
306	Udorthents-Urban land complex	Drift.	No	—	54-72	Moderate
307	Urban land	Miscellaneous area.	No	—	--	Moderate
308	Udorthents, smoothed	Drift.	No	—	24-54	Moderate
309	Udorthents, flood control	Drift.	No	—	24-54	Moderate
W	Water	Miscellaneous area.	Yes	—	0	Not Rated

Source: USDA Natural Resources Conservation Service, Online Soil Surveys, Geographic Data and Soil Data Mart information of Hartford and Litchfield Counties, accessed July 2009.

¹ Soils classified as Prime Farmland Soils.

² Soils classified as Farmland Soils of Statewide Importance.

— No Data Given. No restrictive features or water encountered to survey depth.

**Table 5-9
Delineated Wetlands and Vernal Pools
along the Proposed Route**

Table 5-9: Delineated Wetlands and Vernal Pools along the Proposed Route

Municipality; Vol. 9/Vol. 11 Mapsheet Nos.	Wetland No.¹	Dominant NWI Class²	Other NWI Classes	Water Regime	Associated Vernal Pool(s)³
Watertown					
1/1	W-FB1	PFO	PSS	Seasonally saturated	
1/1	W-FB2	PFO	PSS	Saturated	
1/1	W-FB3	PEM	PSS	Seasonally saturated	
1/1	W-FB4	PEM	PSS	Seasonally saturated	
1	W-FB5	PFO	PSS	Saturated	
1	W-FB6	PEM		Seasonally saturated	
1/3A	W-MSF1	PFO		Seasonally saturated	VP MSF-1
1/3	W-MSF2	PFO		Seasonally saturated	VP MSF-2
1/3A	W-MSF3	PFO	PSS	Seasonally saturated	
1/1	W-A1	PSS	PEM	Saturated	
1/1	W-A2	PSS	PEM	Seasonally saturated	
1/2	W-A3	PFO	PSS	Seasonally saturated	
1/2	W-A4	PFO	PEM	Saturated	
1/3	W-A5	PSS	PEM	Temporarily flooded	
1/3	W-A6	PEM		Temporarily flooded	
1/4	W-A7	PFO	PEM	Seasonally saturated	
1/4	W-A8	PSS		Temporarily flooded	
1-2/4-5	W-A9	PSS	PEM	Saturated	
1/4	W-A10	PEM		Seasonally saturated	
2/5	W-A11	PSS		Saturated	
2/6	W-A12	PSS	PEM	Seasonally saturated	
2/6	W-B1	PSS	PEM	Saturated	
2/6	W-B2	PSS	PEM	Saturated	VP B2-1
2/6	W-B3	PSS	PEM	Intermittently flooded	
2/6	W-B4	PFO		Saturated	VP B4-1
2/6-7	W-B5	PSS	PEM	Seasonally saturated	
2/6-7	W-B6	PSS	PEM	Saturated	
2/8	W-B7	PSS	PEM	Saturated	
2/8	W-B8	POW	PEM	Temporarily flooded	
2/8	W-B9	POW	PSS, PEM	Saturated	

Table 5-9: Delineated Wetlands and Vernal Pools along the Proposed Route

Municipality; Vol. 9/Vol. 11 Mapsheet Nos.	Wetland No.¹	Dominant NWI Class²	Other NWI Classes	Water Regime	Associated Vernal Pool(s)³
3/9	W-B11	PSS	POW	Saturated	
3/10A/10B	W-C1A	PSS	PFO	Saturated	
3/10A/10B	W-C2A	PSS	PEM	Saturated	
3/10	W-C1	PFO	PSS	Seasonally saturated	
3/10	W-C2	PFO		Seasonally saturated	
3/10	W-C3	PSS	PEM	Seasonally saturated	
3/11	W-C4	PFO	PSS	Seasonally saturated	DVP C4-1
3/11	W-C6	PSS		Seasonally saturated	
3/11	W-C7	PFO		Seasonally saturated	
3/11	W-C8	PFO		Saturated	
3/11	W-C10	PFO		Seasonally flooded	VP C10-1
3/12	W-C12	PFO	PSS, PEM	Saturated	VP C12-1
3/12	W-C14	PSS	PEM	Seasonally saturated	
3-4/12-13	W-C15	PFO	PSS, PEM	Saturated	VP C15-1
3/11	W-C16	PSS	PEM, PFO (off-ROW)	Saturated	
3-4/13	W-C18	PFO		Seasonally saturated	
4/14	W-C20	PFO	PSS	Saturated	VP C20-1
4/15	W-C21	PFO	POW	Semi-permanently flooded	VP C21-1
4/16	W-C22	PEM	PFO	Saturated	
4/17	W-C23	PSS	PEM	Saturated	
Thomaston					
5/18	W-D1	PUB		Temporarily flooded	
5/18	W-D2	PEM		Seasonally saturated	
5/18-19	W-D3	PFO	PSS	Seasonally saturated	
5/19	W-D4	PFO		Seasonally saturated	VP D4-1
5/20	W-D5	PEM		Seasonally saturated	VP D5-1
5/20	W-D6	POW	PEM	Permanently flooded	
6/21	W-D7	PFO	PEM	Seasonally saturated	
6/21	W-D8	PFO		Seasonally saturated	
6/22	W-D10	PFO	PFO	Seasonally saturated	

Table 5-9: Delineated Wetlands and Vernal Pools along the Proposed Route

Municipality; Vol. 9/Vol. 11 Mapsheet Nos.	Wetland No.¹	Dominant NWI Class²	Other NWI Classes	Water Regime	Associated Vernal Pool(s)³
6/22	W-D11	PFO	PSS	Seasonally saturated	
6/22-23	W-D12	PSS	PFO, PEM	Seasonally saturated	VP D12-1
6/23	W-D13	PFO	PSS	Seasonally saturated	
6/24	W-D14	PFO		Saturated	
5/21	W-D15	PSS	PEM	Semi-permanently flooded	VP D15-1
6/24	W-E1	PFO	PSS	Permanently flooded	
7/25-26	W-E2	PSS	PFO	Saturated	
Litchfield					
7/25-26	W-E2	PSS	PFO	Saturated	DVP E2-1, DVP E2-2
7/26	W-E3	PEM		Saturated	
7/26	W-E4	PFO	PSS, PEM	Seasonally saturated	
7/26	W-E5	PEM		Seasonally saturated	
7/26	W-E6	PEM		Seasonally saturated	
7/26-27	W-E7	PSS		Seasonally saturated	
7/27	W-E8	PSS	PFO	Seasonally saturated	
7/27-28	W-E9	PFO	PSS	Saturated	VP E9-1
7/28	W-E10	PSS	PFO	Saturated	
7/28	W-E11	PSS	POW	Saturated	
7/29	W-E12	PEM		Seasonally saturated	
7/28	W-E13	PFO		Seasonally saturated	
8/29	W-F1	PEM		Seasonally saturated	
8/29	W-F2	PEM		Seasonally saturated	
8/29	W-F3	PFO		Seasonally saturated	
8/29	W-F4	PFO		Seasonally saturated	
8/29	W-F5	PSS	PEM	Seasonally saturated	
8/29	W-F6	PFO		Seasonally saturated	
8/29-30	W-F7	PSS	PFO, PEM, POW	Seasonally saturated	
8/30	W-F8	PEM	PSS	Seasonally saturated	
8/31	W-F9	PFO	POW	Intermittently flooded	

Table 5-9: Delineated Wetlands and Vernal Pools along the Proposed Route

Municipality; Vol. 9/Vol. 11 Mapsheet Nos.	Wetland No. ¹	Dominant NWI Class ²	Other NWI Classes	Water Regime	Associated Vernal Pool(s) ³
Harwinton					
8/31	W-F9	PFO	POW	Intermittently flooded	VP F9-1
8/31	W-F10	PFO		Temporarily flooded	VP F10-1
8/32	W-F11	PFO	PSS	Seasonally saturated	
8/32	W-F12	PSS	PEM	Seasonally saturated	
8-9/33	W-F13	PFO	PSS, PEM	Saturated	DVP F13-1
9/34	W-F14	PSS	PFO	Seasonally saturated	VP F14-1
9/34-35	W-F15	PEM	PFO, PSS, POW	Seasonally saturated	VP F15-1
9/35	W-G1	PFO	PSS	Seasonally saturated	
9/35	W-G2	PSS	PFO	Saturated	
9/35	W-G3	PSS	PEM	Seasonally saturated	

¹Wetland No. refers to the number generated during the 2015 field surveys to identify wetlands in and adjacent to the Project ROW. This Wetland No. is keyed to those depicted in Volume 5.

²Wetlands classified according to Cowardin et al 1979; PEM = Palustrine Emergent Wetland; PFO = Palustrine Forested Wetland; PSS = Palustrine Scrub-Shrub Wetland; POW = Palustrine Open Water.

³Associated Vernal Pool refers to the identification number generated during the 2015 field surveys to identify vernal pools within the Project ROW or along publically accessible off-ROW access. This vernal pool identification number is keyed to those depicted in the Volume 5, 100 scale maps.

Note: This page intentionally left blank.

Table 5-10
Watercourses and Waterbodies along
the Proposed Route

Municipality; Vol. 9/Vol. 11 Mapsheet Nos.	Watercourse No. ¹	Watercourse /Waterbody Name	Flow Regime	Water Quality Classification	Approximate Width	Associated Wetland
Watertown						
1/1	S-FB1		Intermittent	A	1 - 2'	W-FB2
1	S-FB2	Tributary to Naugatuck River	Perennial	B/A	3 - 6'	W-FB6
1	S-FB3	Tributary to Naugatuck River	Intermittent	B/A	1'	W-FB6
1/1	S-A1	Tributary to Naugatuck River	Perennial	B/A	3 - 4'	W-A1
1/1	S-A2	Tributary to Naugatuck River	Intermittent	B/A	1 - 3'	W-A2
1/2	S-A3	Tributary to Naugatuck River	Perennial	B/A	2 - 5'	W-A3
1/3	S-A4	—	Intermittent	A	1 - 2'	W-A6
1/4	S-A5	Tributary to Turkey Brook	Perennial	A	4 - 8'	W-A8
1/4	S-A6	Turkey Brook	Perennial	A	3 - 7'	W-A9
1-2/4-5	S-A7	Turkey Brook	Perennial	A	3 - 7'	W-A9
2/8		Unnamed Pond	Perennial	A		W-B9
3/9		Unnamed Pond	Perennial	A		W-B11
3/9	S-B1	Tributary to Hannon Pond/Purgatory Brook	Intermittent	A	2 - 3'	W-B11
3/9	S-B2	Tributary to Hannon Pond/Purgatory Brook	Intermittent	A	2 - 3'	W-B11
3/9	S-B3	Tributary to Hannon Pond/ Purgatory Brook	Intermittent	A	2 - 3'	W-B11
3/10	S-C1	—	Intermittent	A	2 - 3'	W-C1, W- C2
3/10	S-C2	Tributary to Hannon Pond/ Purgatory Brook	Intermittent	A	2 - 3'	W-C1, W- C2
3/12	S-C3	—	Intermittent	A	3 - 4'	W-C12
3/12	S-C4	Tributary to Lockwood Pond	Perennial	A	3 - 4'	W-C15
3/12	S-C5	Tributary to Lockwood Pond	Intermittent	A	1'	W-C15
4/14	S-C6	—	Intermittent	A	2'	W-C20
4/16	S-C7	—	Intermittent	A	3'	W-C22

Municipality; Vol. 9/Vol. 11 Mapsheet Nos.	Watercourse No. ¹	Watercourse /Waterbody Name	Flow Regime	Water Quality Classification	Approximate Width	Associated Wetland
4/17	S-C8	Branch Brook	Perennial	A	20 - 30'	W-C23
4/17	S-C9	Tributary to Branch Brook	Intermittent	A	3'	W-C23
Thomaston						
5/18	S-D1	—	Intermittent	A	< 1'	
5/18	S-D2	Tributary to Branch Brook	Intermittent	A	2 - 3'	W-D2
5/18-19	S-D3	Tributary to Branch Brook	Intermittent	A	2 - 8'	W-D3
5/20		Morton Pond	Perennial	A		W-D6
6/21	S-D5	Tributary to Northfield Brook	Perennial	A	3 - 8'	W-D7
6/22	S-D8	—	Intermittent	A	< 1'	W-D11
6/22	S-D9	Tributary to Northfield Brook	Intermittent	A	5 - 10'	W-D12
6/22	S-D10	Tributary to Northfield Brook	Intermittent	A	2 - 4'	W-D12
6/23	S-D11	Tributary to Northfield Brook	Intermittent	A	2 - 8'	W-D13
6/24	S-E2	Northfield Brook	Perennial	A	20 - 30'	W-E1
7/25	S-E3	Tributary to Northfield Brook	Intermittent	A	3 - 4'	W-E2
Litchfield						
7/26	S-E4	—	Intermittent	A	< 1'	W-E2
7/26	S-E5	—	Intermittent	A	2'	W-E4
7/27	S-E7	—	Intermittent	A	1'	W-E9
7/28		Unnamed Pond	Perennial	A		W-E11
8/29	S-F1	—	Intermittent	A	4 - 6'	W-F4, W-F5
8/29	S-F2	—	Intermittent	A	< 1'	W-F2
8/29	S-F1/S-F3	—	Intermittent	A	3'	W-F2, W- F4, W-F5
8/30		Unnamed Pond	Perennial	A		W-F7
8/30	S-F4	—	Intermittent	A	1 - 2'	W-F7
8/30	S-F5	—	Intermittent	A	< 1'	W-F8
8/30-31	S-F6	Tributary to Naugatuck River	Perennial	A	5-15'	

Municipality; Vol. 9/Vol. 11 Mapsheet Nos.	Watercourse No. ¹	Watercourse /Waterbody Name	Flow Regime	Water Quality Classification	Approximate Width	Associated Wetland
8/31	S-F7	Naugatuck River	Perennial	B	70 - 110'	W-F9
Harwinton						
8/31	S-F7	Naugatuck River	Perennial	B	70 - 110'	W-F9
8/30	S-F8	Tributary to Naugatuck River	Perennial	A	4 - 7'	W-F9
8/31	S-F9	Tributary to Naugatuck River	Intermittent	A	1 - 2'	W-F10
8/32	S-F10	Tributary to Naugatuck River	Intermittent	A	1 - 3'	W-F12
8/32	S-F11	Tributary to Naugatuck River	Perennial	A	6 - 9'	W-F11
8/33	S-F12	Tributary to Naugatuck River	Intermittent	A	4 - 8'	W-F13, W- F15
9/34	S-F13	Tributary to Naugatuck River	Intermittent	A	1 - 3'	W-F15
9/35	S-F14	Tributary to Naugatuck River	Intermittent	A	1 - 2'	
9/35		Unnamed Pond	Perennial	A		W-F15
9/35	S-G1	—	Intermittent	A	1 - 2'	W-G1
9/35	S-G2	—	Intermittent	A	1 - 2'	W-G1
9/35	S-G3	—	Intermittent	A	1 - 2'	W-G1

¹ Watercourse No. refers to the number generated during the 2015 field surveys to identify watercourses within the Project area. This Wetland No. is keyed to those depicted in the Volumes 5 maps.

Table 5-11
Summary of Potential Visual Sites Traversed by
or in the Vicinity of the Proposed Route with Views
of the existing Eversource Transmission Lines

Table 5-11: Summary of Potential Visual Sites Traversed by or in the Vicinity of the Proposed Route with Views of the existing Eversource Transmission Lines

Town / Potential Visual Site / Photo-Simulation	Volume 5, 400 Scale Mapsheet No./ Relation to ROW	Feature Information	Summary Results of Field Review
Watertown			
Jericho-Whitestone Connector Trail	1 Follows	The Jericho-Whitestone Connector Trail is a CFPA “blue blaze” trail that connects to the Jericho Trail.	This trail extends from State Route 8 along Echo Valley Road and then turns onto the ROW, following the ROW for approximately 600 feet before diverging north into forested areas and then into Mattatuck State Forest.
Jericho Trail / Mattatuck State Forest	1 Crosses	The Jericho Trail is a CFPA “blue-blaze” trail that connects to the CFPA’s Mattatuck Trail. The Jericho Trail is accessible from Echo Lake Road, through the Mattatuck State Forest.	The Jericho Trail crosses the 400-foot-wide ROW, most of which Eversource presently manages in low-growth vegetation consistent with overhead transmission line use. At the ROW crossing, the Jericho Trail is a relatively wide, asphalt pathway. A steep slope extends to the northwest, limiting views along the ROW in that direction. However, views to the east are unobstructed, with the existing transmission lines and Frost Bridge Substation clearly visible. Due to topography and forest vegetation adjacent to the ROW, views of the transmission lines / ROW from other portions of the trail are precluded or limited.
Veterans Memorial Park	2 Crosses	Town of Watertown park that provides year-round recreational opportunities	Eversource ROW crosses the northeastern boundary of the park. The new 115-kV line will be located toward the center of the existing 400-foot-wide ROW. The existing transmission lines are slightly visible above the tree line from the park’s ball fields that border the ROW, as well as from the park’s entrance road, across Jericho Brook Pond.
Black Rock State Park / Mattatuck Trail, Park Red Trail	4 Crosses	CFPA Trail that extends through Black Rock State Park, also connecting to the Park’s “Red Trail”	The 250-foot-wide Eversource ROW extends along the western portion of the park, crossing both the Mattatuck Trail and the Red Trail in rugged locations. Views of the ROW are limited to the immediate vicinity of the crossings, due to the topography, dense vegetation, and bends in the trails.

Town / Potential Visual Site / Photo-Simulation	Volume 5, 400 Scale Mapsheet No./ Relation to ROW	Feature Information	Summary Results of Field Review
Watertown/Thomaston			
Black Rock Lake Dam Overlook	4 Crosses	Public access on top of dam that offers views of the lake, and to the hills to the east and north	From portions of this overlook, the existing and proposed 115-kV transmission structures are visible on a wooded slope that extends north-northeast from State Route 109.
Thomaston			
Northfield Brook Recreation Area	6 Crosses	“Yellow” trail located north of the recreation areas’s access road	The “Yellow Trail”, a narrow hiking trail, crosses the Eversource ROW, which is occupied by two 115-kV lines. At the trail crossing, the ROW is visible along the hillside to the south of State Route 254, toward Walnut Hill Junction.
Litchfield / Harwinton			
Naugatuck River / Thomaston Dam Trails	8 Crosses	ATV / Snowmobile / hiking trails / fishing area along Naugatuck River greenway	Eversource ROW spans the river and river valley, limiting views of the transmission lines from most areas due to dense vegetation. ROW and transmission line structures are visible from Valley Road in Harwinton.

Note: This page intentionally left blank.

6. POTENTIAL ENVIRONMENTAL EFFECTS AND MITIGATION MEASURES

This section identifies and analyzes the potential short- and long-term effects that the construction and operation of the proposed facilities would have on the environment, ecology, scenic, historic, and recreational values. Furthermore, this section describes the measures that Eversource proposes to implement to avoid, minimize, or mitigate adverse effects. This analysis is based on the currently available information concerning the Project, as well as Eversource's past experience with the installation of overhead transmission facilities and substations throughout New England. The impact and mitigation analysis may be refined after Eversource addresses input from the municipal consultation process.

Section 6.1 discusses the potential effects, and measures to mitigate such effects, associated with the construction and operation of the new 115-kV transmission line and double-circuit separation. Section 6.2 discusses the potential environmental effects and mitigation measures related to the proposed modifications at the Frost Bridge and Campville Substations.

Overall, the proposed Project would minimize adverse environmental effects by locating the new 115-kV transmission line within an existing Eversource ROW, adjacent to existing overhead transmission lines and by developing the proposed substation modifications within uplands on Eversource property that are already designated for utility use. Although the construction and operation of the Project would result in unavoidable short- and long-term effects on certain environmental, cultural, and recreational / scenic resources, Eversource has identified measures that can be applied to mitigate these effects to the extent practical. The identified mitigation measures are based on Eversource's historical experience in the construction, operation, and maintenance of the existing transmission lines along the Project ROW; on the results of the field investigations and agency consultations conducted for the Project; and on recent, directly relevant expertise in siting and constructing 115-kV and other transmission facilities elsewhere in New England.

For example, as part of the Project planning process, Eversource modified the new 115-kV transmission line design to place new structures outside of wetlands wherever possible. Of the total 104 new structures proposed, only one structure would be located in a wetland. Similarly, as has been the case on other recent transmission line projects, Eversource would commit to prepare Project-specific construction plans related to erosion and sediment control; spill prevention; and ROW revegetation. Eversource would also

preserve riparian vegetation near streams to the extent practical, and would make every effort to align new permanent access roads in upland (rather than wetland) areas where possible.

Furthermore, along with the mitigation methods identified in this section, additional measures to avoid or minimize adverse effects on the environment may be identified during the course of the Council proceedings and during the process of acquiring Project-specific permits and approvals from other state and federal agencies, including the CT DEEP and the USACE. Mitigation measures, as described herein or as included as conditions of regulatory approvals, would be reflected in the final Project design and incorporated into Development and Management Plans (D&M) or other Project specifications, as appropriate. During construction, Eversource or its consultants would regularly monitor the Project construction contractors' compliance with the D&M Plans and applicable regulatory approvals.

6.1 PROPOSED ROUTE: FROST BRIDGE SUBSTATION TO CAMPVILLE SUBSTATION

6.1.1 Topography, Geology, and Soils

The construction and operation of the new 115-kV transmission line would have negligible effects on topography and geology, and only minor, short-term, and highly localized effects on soils. These effects would be concentrated in the vicinity of work sites along the ROW, or where earth-moving activities, if any, are required at off-ROW Project support areas (e.g., off-ROW access roads, staging areas).

6.1.1.1 Topography and Geology

Generally, the construction of the Project would result in minor, localized changes in elevation only at locations where grading and filling are required, such as at certain structure sites, pulling pads, and guard structure areas where level work pads must be established, or along access roads that must be improved or developed to safely support the ingress and egress of construction equipment. Grading would not be required in instances where the terrain along the ROW is relatively level, where little or no access road improvements or new access roads are needed, or where the conductors span the underlying terrain.

At structure locations, work pads must be established to accommodate the equipment needed to safely install the structure foundation, structure, and associated conductors / hardware. The size of the work pad needed, as well as the changes in grades (e.g., cut or fill) required, will depend on the type of structure and the nearby terrain in the vicinity of each structure. Cut and fill activities typically are localized to the

work pad⁶⁶ and the immediately adjacent areas. Grading (cut and fill) similarly would be required as necessary at conductor / OPGW pulling work pads and at guard structure work pads. In addition, grading will be required along certain on-ROW and possibly off-ROW access roads to provide safe travel ways for heavy construction equipment.

The Volume 5, 400 scale maps identify the general locations of access roads along the ROW, whereas the Volume 5, 100 scale maps provide more detail regarding the locations of existing and potential new access roads along the Proposed Route.

6.1.1.2 Soils

Soils would be disturbed by the same types of Project construction activities that would cause localized alterations to grades, such as the creation or expansion of on- or off-ROW access roads; the establishment of staging areas and contractor yards; leveling (cut or fill) as required to create work pads; and earth-disturbing activities required to install the transmission line structures. Soils also could be disturbed as a result of vegetation removal activities along the ROW. However, the soil disturbance would be short-term, lasting only for the duration of the construction at a particular location, until revegetation or other forms of soil stabilization are achieved.

At locations where earth-disturbing activities are required, temporary erosion and sediment control measures (e.g., silt fence, hay/straw bales, filter socks, mulching, temporary reseeding) and / or BMPs would be used to minimize the potential for soil erosion and sedimentation off the ROW, and particularly into watercourses or wetlands (either on or off the ROW). These temporary erosion controls would be deployed as necessary after vegetation removal or after / in conjunction with grading. Typically, the erosion and sediment control measures, which would be installed based on the judgment of Eversource's in-field representatives, would be inspected and maintained throughout the construction period, until final stabilization of disturbed areas is achieved, or until permanent controls (if required) are established.

The need for and extent of temporary and permanent erosion and sedimentation controls would be a function of site-specific field considerations such as:

⁶⁶ The typical construction work area for a tangent structure is 100 feet x 100 feet and the typical construction work area for a deadend structure is 200 feet x 100 feet; however, the specific size and shape of an individual work pad can vary due to site or environmental constraints.

- Slope (steepness, potential for erosion, and presence of environmentally sensitive resources, such as wetlands or streams at the bottom of the slope);
- Type of vegetation removal method used and the extent of vegetative cover remaining after removal (e.g., presence/absence of understory or herbaceous vegetation that would minimize the potential for erosion and degree of soil disturbance as a result of clearing equipment movements);
- Type of soil and erodibility factor (K value);
- Soil moisture regimes;
- Schedule of pending construction activities in particular ROW areas;
- Proximity to water resources (e.g., wetlands, watercourses), public roads, or other sensitive environmental resources; and
- Time of year. The types of erosion and sedimentation control methods used along the ROW would depend on the time of year construction work is initiated and completed. For example, re-seeding is typically ineffective during the winter months. In winter, with frozen ground, controls other than re-seeding (such as wood chips, straw, hay, geotextile fabric, erosion control logs, etc.) typically would be deployed or maintained to control erosion and sedimentation and thus to stabilize disturbed areas until reseeded can be performed under optimal seasonal conditions.

The measures selected would be appropriate to minimize the potential for erosion and sedimentation in particular areas of soil disturbance. Eversource would adhere to its BMP Manual and would prepare a Project-specific *Erosion and Sedimentation Control Plan*, which would be included in the D&M Plans. The *Erosion and Sedimentation Control Plan* would conform to the requirements of CT DEEP's *General Permit for the Discharge of Stormwater and Dewatering Wastewaters from Construction Activities* and with the 2002 *Connecticut Guidelines for Soil Erosion and Sedimentation Control*.

After the completion of earth-disturbing activities, permanent soil stabilization measures (e.g., seeding, mulching, permanent work pad / access road stabilization) would be performed. Temporary erosion controls would be maintained, as necessary, throughout the period of active construction until restoration has been deemed successful, as determined by field inspections and adherence to BMPs for storm water pollution control/prevention and erosion control. The decision to remove temporary erosion controls would be made based on the effectiveness of restoration measures, such as percent vegetative cover achieved, in accordance with applicable permit and certificate requirements.

Rock Removal and Blasting

As currently designed, the proposed structures are steel monopoles. Some of these structures would require foundations with anchor bolts. The preferred technique for removing rock, when encountered, would be to use mechanical methods (e.g., mechanical excavators and pneumatic hammers). In the

unlikely event that access roads and/or structures cannot be installed via mechanical methods alone; Eversource would supplement with controlled blasting. Potential effects from rock removal may include dust, vibration, and noise. If blasting is required, Eversource would develop a *Blasting Control Plan* in compliance with state, industry, and Eversource standards. This plan would be provided to the state and local Fire Marshals.

Furthermore, if blasting is necessary, Eversource would require its construction contractor(s) to employ methods to minimize potential adverse effects (refer to Section 4.2.2). For example, blasting charges, if required, would be designed to loosen only the material that must be removed to provide a stable foundation, and to avoid fracturing other rock. Excavated material that cannot otherwise be used at the site would be removed and properly disposed of elsewhere, pursuant to Project specifications.

6.1.2 Water Resources

The Proposed Route follows an existing Eversource ROW across and adjacent to multiple wetlands and watercourses (collectively referred to as water resources), most of which are traversed by the existing overhead transmission lines that currently occupy the ROW. Through Project design and construction planning, Eversource has attempted to avoid or minimize the potential for adverse direct and indirect effects to water resources to the extent practical. For example, only one new structure is proposed within a wetland in Harwinton. For effects that are unavoidable, Eversource would implement mitigation measures, including construction BMPs, such as temporary erosion and sedimentation controls, restoration, and wetland mitigation. Specific water resource mitigation measures would be designed and implemented in accordance with the Project-specific regulatory approvals received from the USACE, CT DEEP, and the Council.

Most potential effects to water resources, associated with the development of the new 115-kV transmission line, would be short-term and highly localized with the exceptions of tree removal within forested wetlands, unavoidable placement of one structure within a wetland, and permanent access road improvements across wetlands and streams. Tree removal within forested wetlands (as required to allow construction and thereafter to maintain safe distances between vegetation and the transmission line conductors) would not represent any loss of wetland habitat, but would constitute a long-term effect by converting wetland habitat type from forested to scrub-shrub and emergent. In contrast, both the unavoidable placement of one new transmission line and / guy anchors structure within a wetland and the permanent improvement of historic access roads across certain wetlands and streams would involve fill, resulting in a highly localized, but permanent effect to wetlands. During the Project planning, Eversource

has attempted to avoid permanent fill in watercourses and wetlands and wetland conversion effects to the maximum extent possible.

The operation and maintenance of the proposed facilities would not have long-term, adverse effects on water quality, watercourses, or waterbodies. The limited, localized, permanent effects on wetlands would be largely the result of expanding the width of the managed ROW within Eversource's existing easement. The ROW would be managed in accordance with Eversource's established vegetation management program, the objective of which is to maintain a climax vegetative community of low scrub-shrub growth that does not interfere with the overhead transmission line facilities and allows for inspection and access along the ROW.

Potential direct short-term effects on water resources could stem from erosion and sedimentation into watercourses or wetlands as a result of soil disturbance and vegetation removal along the ROW; fill or sedimentation associated with the installation and use of temporary access roads across wetlands and small watercourses; temporary fill required along existing access roads near wetlands; work pads in wetlands; and disturbance to wetland plant communities located along the ROW. In addition, the movement of construction equipment and vehicles along the ROW would increase the potential for inadvertent spills of fuels, lubricants or hydraulic oil, which could potentially enter water resources.

In designing and planning the construction of the transmission lines Eversource has incorporated, or would implement during construction, measures to avoid or limit adverse effects to water resources to the extent practical. For example, where practical, Eversource proposes to avoid direct work in watercourses (with the exception of in-water activities required for the replacement of culverted watercourse crossings), install temporary construction mats for work pads around structure locations in wetlands, and employ best management practices to limit the potential for erosion/sedimentation or for inadvertent spills of fuels and lubricants into water resources.

Eversource would prepare, and would require its construction contractor to implement, a Project-specific *Stormwater Pollution Prevention and Control Plan*, in accordance with CT DEEP requirements as specified in the *General Permit for the Discharge of Stormwater and Dewatering Wastewaters from Construction Activities*. In addition, Eversource would prepare, and its construction contractor would be required to follow, a Project-specific spill prevention and control plan. Both plans would be developed in conjunction with the preparation of the D&M Plans.

Moreover, any construction work potentially affecting water resources would be performed in accordance with the conditions of Project-specific regulatory approvals required from the USACE, the CT DEEP, and the Council.

Adherence to the conditions of Project permits issued by the CT DEEP and USACE would serve to further avoid, minimize, or mitigate potential adverse effects to water resources during the construction and operation of Eversource's proposed facilities. Eversource would incorporate the conditions of the environmental regulatory approvals into Project documents, and would require the Project construction contractor(s) to adhere to such conditions.

6.1.2.1 Waterbodies

A total of 58 waterbodies were delineated along the Proposed Route (20 perennial and 38 intermittent streams), some of which are traversed by existing Eversource access roads. However, temporary and, in some areas, permanent access (i.e., improvement to existing historic access roads) would be required across smaller streams along the ROW. No access would be required across the larger watercourses, such as the Branch Brook, Northfield Brook, and the Naugatuck River.

The development of the proposed transmission line would not create a new ROW across any waterbodies, but would increase the width of the managed portion of the existing ROW in some sections and would add another overhead transmission line span at each crossing. In-stream work would be limited to smaller streams where access road crossings must be installed or improved along the ROW, and two watercourses (one intermittent and one unnamed perennial) where culvert replacements are proposed along historic access roads where pre-existing culverts have been displaced. These locations, north of Walnut Hill Road in Thomaston and north of Valley Road in Harwinton, are depicted on the Volume 5 maps.

Eversource would direct its contractors to cross streams by using, where possible, existing on-ROW access roads. In areas where new access road crossings must be installed, or where existing roads must be improved or expanded across streams, temporary and localized effects to water resources, consisting of short-term increases in turbidity, removal of stream shading vegetation at the crossing, and temporary disturbance to riparian zones, would likely occur.

Potential effects on watercourses may occur from the selective removal of vegetation within riparian zones/buffers (as necessary to allow safe construction or to maintain appropriate clearance from conductors) and the movement of construction equipment across watercourses via either temporary

equipment bridges or permanent access roads. Where alternative means of access are not available, temporary bridges (consisting of timber mats, metal bridges, timber mats or metal bridges with culverts, or equivalent) may be used for equipment crossings; erosion and sedimentation controls also would be installed as appropriate. Use of such materials would minimize or avoid direct effects to banks and stream bottom sediments, and would minimize sedimentation to the extent practical.

To maintain the existing transmission lines that occupy the ROW along which the new 115-kV line would be located, Eversource currently utilizes existing access road crossings at various watercourses along the ROW, including culverted and hard-bottomed crossings.⁶⁷ Prior to submitting permit applications to the CT DEEP and USACE, Eversource would conduct integrity inspections of these existing crossings and would identify the crossings (if any) that would have to be replaced.

Where two culvert replacements are proposed along historic access roads, it is anticipated that approvals from the USACE and CT DEEP would be required. These culverts would be designed and installed in accordance with USACE and CT DEEP stream crossing guidelines, which specify that culvert design should allow for the maintenance of ambient stream flows, the continuous flow of the 50-year frequency storm, and fish passage.

Eversource would implement the following mitigation measures to minimize the potential effects of construction activities in or near watercourses:

- Where existing access roads across streams must be improved, clean materials would be used (e.g., riprap or equivalent and rock fords).
- At streams that support fisheries resources, improvements to or the development of access road crossings involving in-water work would be scheduled, to the extent possible, to avoid conflicts with fish spawning or migration. The CT DEEP *Stream Crossing Guidelines* indicate that in inland waters, unconfined⁶⁸ in-stream construction activities should only be performed between June 1 and September 30.
- Water flows in streams (if water is present at the time of construction) would be unconfined throughout construction.
- Concrete (used for structure foundations) would be mixed, placed, and disposed of so as to avoid or minimize the risk of concrete materials entering a watercourse.

⁶⁷ Hard-bottomed or rock ford stream crossings are characterized by well-graded coarse stone placed at-grade within the stream bed at road crossings. They are intended to promote substrate stability while also providing unobstructed conveyance of stream flows.

⁶⁸ Unconfined is defined as work not contained within a cofferdam or similar water exclusion structure.

- Installation of new culverts at locations where culverts presently do not exist would be avoided to the extent possible and, where culverts must be installed, the measures recommended in the CT DEEP *Stream Crossing Guidelines* would be implemented as appropriate.
- Existing riparian vegetation within 25 feet of watercourse banks would be maintained or cut selectively, to the extent practical and consistent with ROW vegetation management requirements.
- Temporary access roads (e.g., consisting of timber mats, metal bridges, or equivalent) across streams will be removed as part of the restoration phase of the Project.
- The D&M Plans and other construction specifications would incorporate the conditions of permits received from the USACE and the CT DEEP relating to the protection of water resources.

6.1.2.2 Wetlands

As identified in Table 5-9, a total of 91 wetlands were delineated within Eversource's ROW (easements or fee-owned properties) in proximity to the proposed Project activities. An additional four wetlands were delineated along publically accessible (Black Rock State Park/Mattatuck State Forest) off-ROW access roads that are proposed for use during Project construction. Of the total 95 wetlands delineated, 48 would be within the portions of the ROW traversed by the new transmission line.⁶⁹ The development of the Project would unavoidably affect some of these wetlands. However, Eversource has designed, and proposes to construct, the Project to avoid or minimize adverse effects to wetlands to the extent practical.

Most of the wetlands within Eversource's ROW have historically been affected, to some degree, by the vegetation management practices or other procedures associated with Eversource's operation of the existing overhead transmission lines between Frost Bridge Substation and Campville Substation. The principal effects associated with these existing lines is the ongoing maintenance of scrub-shrub and emergent wetland cover types that presently characterize the managed portions of the ROW, as well as the establishment of certain structures and access roads in wetlands.

The construction and operation of the new 115-kV transmission line along the presently un-managed portions of the ROW would result in similar, but incremental, effects to wetlands. Temporary effects to wetlands would occur from the development and use of temporary construction access roads (e.g., using timber mats or gravel placed over geotextile fabric) through wetlands; the placement of temporary work

⁶⁹ The 48 wetlands are those located within the footprint of the new 115-kV line and therefore potentially affected by the proposed Project construction and maintenance activities.

pads and – if required, temporary guard structure work pads or structure support poles⁷⁰ in wetlands; the removal of scrub-shrub or emergent wetland vegetation; and incidental sedimentation due to erosion.

Long-term effects on wetlands will result from the following activities:

- The removal of vegetation within forested wetlands (as necessary) along the ROW as required for the construction and operation of the new transmission line.⁷¹ Within these areas, forested wetlands would be converted to scrub-shrub or emergent marsh wetland habitats, resulting in a long-term cover type change in wetland communities, but not in an overall net wetland loss.
- The improvement of historic access roads with gravel (up to 16 feet wide) through wetlands, in order to provide permanent access. Permanent access roads would only be required if no alternative upland access is available.

As summarized in Table 6-1, as a result of the proposed Project, approximately 6,142 square feet (0.14 acre) of wetlands would be permanently filled, primarily for improvements to historic access roads.

Approximately 2.56 acres of wetlands would be temporarily affected by construction work areas, such as work pads or timber mat (or equivalent) access roads; these areas will be restored following the completion of the 115-kV transmission line installation.

⁷⁰ To install the new transmission line, temporary guard structure work pads (on which a bucket-type truck is positioned) or poles may have to be installed in wetlands that are located along the ROW adjacent to public road crossings. These temporary facilities are used during conductor / OPGW stringing to prevent the wires from sagging onto the public road. These temporary facilities (poles and/or work pads) would be removed following the completion of the conductor / OPGW stringing operation.

⁷¹ The width of vegetation removal is a function of the type of transmission line structure and existing maintained ROW width. Refer to the cross-sections in Section 3 (Appendix 3A) and the Volume 5, 100 scale maps for details.

Table 6-1: Estimated Surface Area of Waters of the United States Potentially Affected by the Proposed Transmission Lines (Temporary and Permanent Effects)

Project Activity	Estimated Temporary Effect (Acres)	Estimated Permanent Effect (Acres)
Access Roads ¹	1.66	0.14 ³
Work Pads	0.90	N/A
Structure Foundation	N/A	0.001
Total Primary Wetland Effects (Fill)	2.56	0.14
Total Secondary Wetland Effects (Tree Removal in Forested Wetlands)	N/A	6.7²

¹The majority of temporary access road impacts are associated with temporary access for tree clearing.

²Area assumes tree clearing will be required over all forested areas. In some areas, such as over the Naugatuck River, tree clearing may not be required where suitable clearance between the proposed new line and tree canopy already exists.

³Estimated Permanent Access Road impacts are associated with improvements to existing historic access roads.

Notes:

This table provides estimates of (1) permanent effects (e.g., permanent fill at one structure site and for permanent improvements to access roads) and (2) temporary effects (e.g., work pads, temporary access roads, and temporary access for tree clearing). Temporary effects associated with the widening of existing roads to facilitate access during construction were not included at this time.

Vegetation removal is a secondary effect and all of the permanent and temporary effects, previously noted, were excluded to determine the estimated acres of forested wetland clearing.

Assumptions for Estimating Wetland Effects:

Structure work pad dimensions are assumed to be typically 100 feet by 100 feet for tangent structures and 100 feet by 200 feet for deadend structures.

Permanent access roads through wetlands are assumed to be approximately 16 feet wide.

Temporary access roads through wetlands to structures are assumed to be approximately to be approximately 20 feet wide.

Temporary access roads for tree clearing are assumed to be approximately 16 feet wide.

Approximately 6.7 acres of forested wetland vegetation along the ROW would be removed during Project construction. These forested wetlands would be permanently converted to scrub-shrub or emergent wetlands, representing a long-term cover type change to wetland habitat, but not a net loss of wetlands (refer to Table 6-5, located at the end of this section). The amount of and type of vegetation clearing required along the ROW would vary and would depend on factors such as the existing width of the managed ROW, vegetation communities present, the type of the new 115-kV transmission structures, configuration and spacing of the transmission line conductors, transmission line span lengths, and terrain. The cross-sections illustrate the location of the existing and proposed transmission lines along each ROW

segment and the existing and proposed managed ROW widths (refer to Section 3, Appendix 3A and Section 4, Table 4-2 of this volume, and Volume 5).

Best management practices, as detailed in Eversource's *Best Management Practices Manual Connecticut Construction & Maintenance Environmental Requirements* (2011), would be used to minimize disturbances to wetlands during Project construction, as applicable. The wetland boundaries along the ROW would be clearly demarcated (e.g., re-flagged by a registered soil or wetland scientist) prior to the commencement of work. Construction personnel would be provided mapping (e.g., D&M Plans) that depict wetland boundaries in relation to work areas. When working in or traversing such wetlands, Eversource would also employ the construction procedures detailed in Section 4.2.1.1 and summarized below for ease of reference:

- Comply with the conditions of federal and state permits and certificates related to wetlands;
- Install, inspect, and maintain erosion and sediment controls and other applicable construction best management practices around work sites in or near wetlands to minimize the potential for erosion and sedimentation;
- Limit grading and filling for access roads and work pads in wetlands to the amount necessary to provide a safe workspace;
- Install temporary construction matting or geotextile and crushed stone pads for access roads across wetlands or to establish safe and stable construction work areas/ work pads within wetlands, where necessary. The type of stabilization measures to be used in wetlands would depend on soil saturation;
- Cut forested wetland vegetation without removing stumps unless it is determined intact stumps pose a safety concern for the installation of structures, movement of equipment, or the safety of personnel;
- Avoid or minimize access through wetlands to the extent practical. Where access roads must be improved or developed, the roads would be designed, not to interfere with surface water flow and to minimize adverse effects on the wetland functions;
- Implement procedures for petroleum product management that would avoid or minimize the potential for spills into wetlands (e.g., to the extent possible, store petroleum products in upland areas more than 25 feet from wetlands; refuel construction equipment, except for equipment that cannot be practically moved, in upland areas only);
- Restore structure work sites in – and temporary access ways through – wetlands following the completion of line installation activities unless permanent fill is authorized in advance by the USACE and CT DEEP; and
- Restore wetlands temporarily affected by construction activities. As the final phase of transmission line construction, restore wetlands to approximate pre-construction contours and configurations to the extent practicable; replace topsoil and/or organic soils disturbed by construction (as appropriate); stabilize with temporary seeding (if necessary); and allow native vegetation to recolonize.

To compensate for the effects to wetlands that would occur as a result of the Project, Eversource would consult with the USACE and CT DEEP to assess mitigation options. The extent of compensatory wetland mitigation required would depend on the final Project design and the amount of direct permanent and temporary impacts and secondary and cumulative wetland impacts. Compensatory wetland mitigation options for the Project, which would be specifically evaluated as part of the USACE and CT DEEP regulatory review processes, may consist of wetlands restoration and/or enhancement (on or off the ROW), including invasive species control, in-lieu fee payment wetland preservation, and/or conservation restrictions.

6.1.2.3 Groundwater Resources and Public and Private Water Supplies

The construction and operation of the 115-kV transmission lines would not adversely affect groundwater resources, including Aquifer Protection Areas, public water supplies, or private groundwater wells. As identified in Section 5.1.2.3, no public wells would be traversed by, or are located in the vicinity of the Project. Private wells provide drinking water to the majority of the Project region. The Proposed Route does not cross any Aquifer Protection Areas. The closest such area is Reynolds Bridge, a Level A Aquifer Protection Area located approximately 0.48 mile east of the Proposed Route where it crosses Branch Road (Route 109).

During construction, Eversource would require its contractors to adhere to its best management practices and any Project-specific regulatory requirements regarding the storage and handling of any hazardous materials used during the work. Proper storage, secondary containment, and handling of potentially hazardous materials such as diesel fuel, motor oil, grease and other lubricants, would be required.

Construction staging areas and contractor yards, which would be identified during the preparation of the D&M Plans or thereafter by the Project contractor(s), would typically be located at existing developed areas (parking lots, existing storage yards, warehouses, sand/gravel mining areas, etc.). At such yards, contractors may store fuels and lubricants and conduct refueling activities.

6.1.2.4 Flood Zones

The Proposed Route extends across FEMA-designated 100-year flood zones associated with Branch Brook in Watertown, Northfield Brook in Thomaston, and the Naugatuck River in Litchfield and Harwinton. However, no transmission line structures are proposed within a 100-year flood zone. The only work proposed within a designated 100-year flood zone is associated with improvements to approximately 575 linear feet of historic access road north of Valley Road in Harwinton, and replacement

of a culvert within an unnamed perennial tributary of the Naugatuck River at the same location. As a part of the Project application to CT DEEP for a 401 Water Quality Certificate, Eversource would commission hydrologic/hydraulic modeling analyses, as required, to assess the potential effects of these proposed Project activities on floodplains. If necessary, compensatory flood storage volume would be designed to mitigate permanent effects on 100-year floodplains, and therefore no adverse effects to flood zones would occur.

6.1.3 Biological Resources

The construction and operation of the new 115-kV transmission line would result in generally minor effects on vegetative communities and wildlife. The potential effects will be concentrated primarily within and near the existing ROW within which the proposed facilities would be aligned. With the exception of the conversion of existing forested habitat to scrub-shrub habitat, these effects would typically be short-term lasting one to two seasons post-construction.

6.1.3.1 Vegetation

6.1.3.1.1 Vegetation Communities Affected, including Upland and Wetland Forest Clearing

The construction and operation of the Project facilities would affect portions of the various vegetative communities that presently characterize the Eversource ROW along which the new 115-kV transmission line would be located. In general, the construction of the new 115-kV line, adjacent to Eversource's existing transmission lines, would necessitate removal of trees and shrubs within the construction footprint.

Subsequently, the operation of the Project facilities would require the management of vegetation beneath and in the vicinity of the new transmission line to maintain low-growth communities, consistent with utility industry standards. Along the majority of the existing ROW, this would increase the width of the vegetation that Eversource would manage in herbaceous, shrub-scrub, or other low-growth vegetative types. In currently forested wetlands, tree removal would result in a permanent cover type change and the conversion to scrub-shrub and/or emergent wetlands, such as are characteristic of the wetlands within the presently managed portions of the ROW.

Along the ROW within which the new 115-kV line would be located, the width of the currently managed portions varies, depending on the number and configuration of the existing transmission lines that occupy each ROW segment. Along the 2.2 miles from the vicinity of Frost Bridge Substation to Purgatory Junction (refer to XS-1 and XS-2), much of the 400-foot-wide ROW is currently managed for low growth

vegetative communities.⁷² Along the majority of the remaining 8.2 miles of the Proposed Route (XS-3 through XS-6), the new 115-kV line would be located within a typical 250-foot-wide ROW. Along these ROW segments, Eversource presently manages (on average) a 95- to 140-foot-wide area beneath and adjacent to the existing lines. For the new 115-kV transmission line, an additional 40-to-70-foot-wide area, located within the ROW to the east of the existing lines, would be cleared of forest and shrub-scrub vegetation for construction and subsequently managed on a long-term basis in low-growth vegetation.

The existing Eversource transmission line ROW within which the Proposed Route would be located encompasses approximately 370 acres. Of this, 114 acres (31%) are deciduous and coniferous forested upland and approximately 18 acres (5%) are palustrine forested wetland (consisting predominantly of deciduous forest cover with some areas of mixed deciduous / coniferous forest).

Approximately 48.9 acres of forested habitat would be affected by the Project (42.2 acres of forested upland and 6.7 acres of forested wetland). Refer to Table 6-2 below. This figure assumes tree clearing will be required over virtually all forested areas, regardless of clearance. In some areas, such as over the Naugatuck River, tree clearing may not be required where clearance between the proposed new line and the existing tree canopy is adequate. Virtually all of the acres of affected forested habitat is within Eversource's existing ROW, the only exception being minimal expansion or side trimming required along existing off-ROW access roads.

⁷² Some tree clearing is required to the rear (east) of Frost Bridge Substation, to forested areas to the east and west of Echo Lake Road (XS-1), and within portions of the ROW interior between Echo Lake Road and Purgatory Junction (XS-2).

Table 6-2: Approximate Acres of Forest Land¹ to be Converted² to Scrub-Shrub Land, by Town

Town	Areas within the Vegetation Removal Limits of the Proposed Route (Estimated Acres, all within Existing Eversource ROW)	
	Forested Wetlands	Forested Upland
Watertown	1	16.2
Thomaston	1.6	12.8
Litchfield	2.7	7
Harwinton	1.2	6.2
TOTAL³	6.7	42.2

¹ Forest land refers to mixed hardwood and deciduous tree species in both wetlands and uplands.

² Many areas of forest were previously agricultural or shrubland associated with post-agricultural abandonment and succession.

³ Totals include tree removal required along the Proposed Route pursuant to 115-kV conductor clearance specifications and represent the estimated acreage that would subsequently be managed in shrubland vegetation, consistent with the operation of the 115-kV overhead transmission lines. Additional forested vegetation removal may be required along access roads and construction work areas located outside of the identified “limits of vegetation removal” for conductor clearance purposes.

Based on the results of field investigations, and analyses of aerial photography / vegetative cover types, Eversource estimates that most of the forest vegetation to be removed consists of trees with an average diameter at breast height (dbh) greater than 5 to 6 inches. The predominant forested communities that would be affected by the Project are mixed deciduous upland forest. In the areas where tall-growing trees must be removed during construction, the ROW subsequently would be managed in shrubland or old field habitat.

Converting forest to shrubland, open field, or old field vegetation along the transmission line ROW would modify habitat, representing a long-term, but not a necessarily adverse, affect. In fact, the creation of additional shrubland and early successional habitat (and the preservation of such existing habitat) along the ROW would represent a long-term benefit for many species because shrubland habitat is otherwise declining in New England. This decline is a result of various factors (e.g., conversion of farms, suburban / urban development, ecological succession, absence of fires).

In Connecticut, transmission line ROWs are a major source of shrubland habitat. The ROWs are managed to promote early successional habitats, dominated by scrub-shrub vegetation and open areas with dense grasses and other herbaceous vegetation. Scrub-shrub communities within ROWs provide a variety of wildlife habitat functions (e.g., food, cover and nesting habitat for birds and small mammals,

and cover and browse for whitetail deer; Ballard et al., 2004).⁷³ These plant communities also tend to offer habitats preferred by certain rare and other invertebrate species, including moths, butterflies, and bees, for certain stages of their annual life-cycles.

Other vegetative cover types within the ROW that would be affected by the construction of the Project include existing open field / shrubland, agricultural land, and lawn / landscaped areas associated with developed areas (e.g., houses with yards, commercial / industrial uses, road shoulders). However, the effects on these cover types and land uses would be mostly short-term. After the completion of Project construction, these community types and land uses, which are compatible and/or coexisting with the existing transmission lines, would continue to coexist with the operation and maintenance of the proposed transmission facilities.

6.1.3.1.2 Vegetation Management and Preservation Goals and Methods

The objective of Eversource's well-established vegetation management program is to maintain safe access to its transmission facilities and promote the growth of vegetative communities along its ROWs that are compatible with transmission line operation and in accordance with federal and state standards. The vegetation along the new transmission line would be managed in accordance with these standards.

Eversource has historically conducted ROW vegetation maintenance as a matter of good utility practice. However, since April 7, 2006, all public utilities have been required to comply with mandatory reliability standards adopted by the NERC following the August 14, 2003 Northeast blackout; an event which was triggered by line outages caused by overgrown vegetation. Eversource's vegetation management practices are designed to allow for the safe operation of transmission lines by preventing the growth of trees or invasive vegetation that interfere with the transmission facilities or access along the ROW. As a result, the vegetation within the managed portions of Eversource's ROW typically consists of shrubs, herbaceous species, and other low-growing species. Following construction, Eversource would restore disturbed areas with appropriate herbaceous seed mixes, and mulch with hay/straw or wood chips as appropriate. Vegetative species compatible with the use of the ROW for transmission line purposes are expected to regenerate naturally, over time. Eversource promotes the re-growth of desirable species by implementing ROW vegetation management practices to control tall-growing trees and promote native plant colonization.

⁷³ Ballard, B.D., H.L. Whittier, and C.A. Nowak. 2004. *Northeastern Shrubs and Short Tree Identification, A Guide for Right-of-Way Vegetation Management*, State University of New York-College of Environmental Science and Forestry.

When performing ROW management, Eversource would take particular care to preserve vegetation along watercourses and within wetlands to the extent possible. In general, Eversource may alter, to some degree, its vegetation management activities in the following areas:

- Areas of visual sensitivity where vegetation removal may be limited for aesthetic purposes;
- Steep slopes and valleys spanned by transmission lines;
- Agricultural lands;
- Near homes where owner-maintained ornamental vegetation does not interfere with the construction or operation of the facilities;
- Within wetlands, vernal pool habitats, or along streams to preserve shrub cover;
- Within the 25-foot vegetated riparian zone adjacent to watercourses and waterbodies; and
- In areas documented to support rare animal species or host plant species that support rare invertebrates.

While undesirable tall-growing woody species within the ROW and proximate to the new line would be removed during construction, desirable species are preserved to the extent practical. In selected locations, certain desirable low-growing trees or tall growing shrubs, due to their growth characteristics and locations relative to the new lines, may be allowed to remain on the ROW. These species would be trimmed to ensure that adequate clearance from wires and structures is maintained, pursuant to Eversource's *Rights-of-Way Vegetation Initial Clearance Standard for 115-kV and 345-kV Transmission Lines*. However, any vegetation preserved during construction activities may be removed in the future in accordance with Eversource's *Specification for Rights-of-Way Vegetation Management*. Generally, all tall-growing tree species would be removed from the ROW, whereas low-growing tree species and taller shrub species would be retained in the areas outside of the wire zones. The wire zone is defined as the area directly beneath the conductors extending outward a distance of 15 feet from the outermost conductors.

6.1.3.1.3 Landowner Outreach and Beneficial Use of Forestry Products

The timber and firewood resources along the Proposed Route belong to the landowners across whose property the ROW is aligned. Eversource's policy is to proactively coordinate with landowners regarding the disposition and use of the trees to be removed along the ROW. If requested by the landowner, the firewood and timber portions of the trees would be left on the landowner's property on the edge of the ROW. After the limbs are removed, the boles of the trees would be piled in tree-lengths for landowners to cut and remove at their convenience.

Timber and firewood removed along the ROW on Eversource fee-owned property or on parcels where the landowners are not interested in retaining the wood would become the property of the Project's land clearing contractor. Eversource would competitively bid the land clearing work for the Project and would select a contractor taking into considering the contractor's plans for the beneficial use of the forest products that are not otherwise left for landowner use.

6.1.3.2 Wildlife and Fishery Resources

6.1.3.2.1 Wildlife

The development of the new 115-kV transmission line would result in both temporary and permanent alteration of wildlife habitat along the ROW, as well as direct effects on wildlife such as disturbance, displacement, or mortality. However, these effects will be localized on and in the vicinity of the ROW, and would be generally short-term (for the duration of the construction phase of the Project) and minor due to the availability of undisturbed habitat types, similar to those found on the ROW, in adjacent areas and in the Project region as a whole. Furthermore, the Project would have a long-term beneficial effect on certain wildlife species that utilize shrubland habitats.

During construction, the removal of vegetation within the construction footprint would displace wildlife and would reduce cover, nesting, and foraging habitat for some species. Other construction activities (e.g., the development of access roads and work pads; general construction equipment movements; and construction-related noise) would similarly disturb or displace mobile wildlife species, such as large mammals and birds. These species would likely move to comparable nearby habitats. Eversource would minimize adverse effects to wildlife by adhering to mitigation measures, including Project-specific procedures expected to be developed in consultation with CT DEEP and the USACE.

Within the ROW, the removal of existing forest vegetation and the conversion to low-growing vegetative communities would have a long-term beneficial effect on early-successional wildlife by providing additional habitat for species that utilize shrubland, old field and other non-forested habitats. The wildlife species that would benefit from the additional shrubland habitat include various bird species such as Prairie Warbler, Brown Thrasher, Field Sparrow, Eastern Towhee and Indigo Bunting, among others), as well as other taxa and species that favor this habitat. While early-successional habitat specialists will benefit from the creation of additional habitat resulting from this project, total habitat for forest-dwelling species would be reduced as a result of the project.

Overall, although the species of wildlife utilizing the ROW would be expected to change slightly, the ROW would continue to provide diverse wildlife habitat. The exchange of forested habitats for shrublands is often interpreted as a net gain for regional biodiversity (Confer and Pascoe, 2003⁷⁴). A study conducted by Nickerson and Thibodeau (1984) indicated an increase in wildlife utilization, especially in avian species, following clearing of ROWs.⁷⁵ The study attributed this increase in wildlife usage to the conversion of forested areas into both wetland and upland shrub and emergent plant communities. The management of ROW vegetation provided edge-effect feeding, nesting, and cover habitat for various species. ROWs also serve as open corridors connecting non-contiguous natural areas.

6.1.3.2.2 Fisheries

The construction and operation of the Project is not anticipated to have an effect on fishery resources. The proposed 115-kV transmission line would span all major waterbodies containing fisheries (e.g., Branch Brook, Morton Pond, Northfield Brook, and the Naugatuck River). With the exception of temporary equipment access and the installation of permanent access roads across smaller watercourses, no new facilities are proposed for installation in any waterbodies, and no access roads will be installed across larger watercourses. Access roads across streams would be designed to avoid or minimize direct disturbance to stream banks and substrates to the extent practical, and would conform to USACE and CT DEEP permit requirements.

Eversource recognizes that streambank vegetation provides important cover and shading for fish. Within a 25-foot-wide area adjacent to watercourses, lower-growing riparian vegetation along the ROW would be maintained, where possible. Vegetation would be cut only if required to maintain safe clearances from conductors and access to and from the transmission facilities. Above Branch Brook, Northfield Brook, and Naugatuck River, the conductors would be installed at such heights that no vegetation removal or tree-trimming would be required. Thus, all of the existing riparian vegetation would remain.

Temporary soil erosion and sedimentation controls would be installed around areas of disturbed soils at work sites up-gradient from streams. These temporary erosion controls would remain in place until the disturbed areas are revegetated or otherwise stabilized.

⁷⁴ United States Department of Agriculture (USDA), 2001, Trends in Connecticut's Forests: A Half-Century of Change, USDA Forest Service, Northeastern Research Station and Connecticut Department of Environmental Protection, Division of Forestry, Hartford, CT.

⁷⁵ Nickerson, N.H. and F.R. Thibodeau. 1984. *Wetlands and Rights-of-Way. Final Report Submitted to the new England Power Company*, 25 Research Drive, Westboro, MA.

6.1.3.2.3 Vernal Pools

Based on the results of ROW field surveys conducted in both 2009 and 2015, the Proposed Route would traverse or be located near 22 vernal pools. The construction of the new transmission line would result in both direct and indirect adverse effects to vernal pools. A summary of potential effects to vernal pools is provided in Table 6-6, at the end of this section. The principal construction activities that could affect vernal pools include:

- The removal of vegetation within and / or the tree canopy over vernal pools;
- The work within vernal pool envelopes and / or critical terrestrial habitat;⁷⁶
- The movement of vehicles and equipment use on access roads in the vicinity of amphibian migratory routes;
- The potential for erosion and sedimentation into vernal pools;
- The modification of structural habitat features such as pit and mound micro-topography; and
- The development and use of distinct construction areas (work pads constructed from fill material and/or timber mats) in vernal pools during breeding periods, as well as at other times throughout the year.

The potential for adverse effects on vernal pools could increase if construction activities cannot be scheduled to avoid critical amphibian breeding or migration periods in areas proximate to confirmed vernal pools. Three vernal pool indicator species were observed within the Project area, wood frog, spotted salamander and marbled salamander. While wood frog and spotted salamander were observed throughout the Project area, marbled salamander was observed at only one location – vernal pool D4-1 in Thomaston. Adult migration of wood frog and spotted salamander to and from the vernal pools typically occurs between March and May. For the marbled salamander, adult migration occurs in the late summer and early fall. Overland movement of amphibians most often occurs during rain events.

To avoid or minimize adverse effects on amphibians, Eversource would locate new structures, access roads, and work areas, to the extent practicable, outside of wetlands that provide vernal pool habitat. Based on the current Project design, no new structures would be located within vernal pool depressions or “cryptic” vernal pool habitat. One temporary work pad is currently shown over a portion of vernal pool C20-1. This pool is located along an existing access road within the maintained ROW, and its hydrology the result of the surface-water impoundment along the existing access road. Access road improvements are proposed through vernal pool F13-1. This pool is located within road ruts within a historic access

⁷⁶ Vernal pool envelope is the area extending from the vernal pool edge to 100 feet, and critical terrestrial habitat includes areas between 100 and 750 feet from the vernal pool edge. (Calhoun, A.J.K. and M.W. Klemens. 2002).

road that is bisected by an intermittent watercourse. This pool, which is anthropogenic in origin, was determined to be of low ecological significance and can reasonably be classified as a decoy pool as defined by the BDP Manual. Decoy pools often lack the hydroperiod for successful larval development, and may act as “sinks,” which may draw from more viable vernal pool habitats nearby.

Eversource has identified the following types of measures that may be applicable to minimize adverse Project effects on vernal pools:

- Where feasible in areas proximate to vernal pools, adhere to the seasonal windows for tree clearing to avoid adverse effects on amphibians during migration periods;
- Install appropriate erosion and sediment controls around distinct work sites and access roads to minimize the potential for sediment deposition into vernal pools, and remove such controls promptly after final site stabilization;
- For Project activities that must occur adjacent to vernal pools during amphibian migration periods, implement measures on a site-specific basis as necessary to facilitate unencumbered amphibian access to and from vernal pools. Mitigation measures will be identified after considering site-specific conditions, including the type of construction activity in proximity to a vernal pool, the amphibian species known to occur in the vernal pool, and seasonal conditions. Options to allow amphibian access to vernal pools may include, but not be limited to: syncopated silt fencing in the immediate vicinity of vernal pools; elevated construction matting; and aligning erosion and sedimentation controls to avoid bifurcating vernal pool habitat;
- Evaluate the use of temporary timber mat access roads in wetlands in lieu of constructing gravel access roads in the vicinity of vernal pools; and
- Minimize the removal of low-growing vegetation surrounding vernal pools.

The specific measures that would be implemented to protect vernal pool amphibians would be defined in consultation with the applicable regulatory agencies (CSC, CT DEEP, and USACE) and would be incorporated into the D&M Plans for the Project.

6.1.3.2.4 Birds

The proposed Project would result in both long-term benefits and short-term, but minor, effects on bird species that inhabit the ROW and nearby areas. Temporary effects are associated with construction activities (due to direct disturbance and noise), and localized and short-term displacement as a result of periodic vegetation management activities during operation of Eversource’s facilities. These disturbances may drive birds from the work areas or generally disrupt nesting, feeding or other activities. If conducted during the breeding season, such activities may result in inadvertent takings of nests and young. Once construction is complete, avian utilization of the Project area is anticipated to resume to pre-construction levels.

Permanent effects associated with the proposed Project are associated with the conversion of forested habitats to shrubland or scrub-shrub wetland. The greatest potential for negative effects on high-conservation priority species are on those birds that are considered forest-interior birds (e.g., scarlet tanager, wood thrush). Forest-interior birds favor the interior of the forest or “forest core” away from non-forested “edge” habitat. In particular, forest interior birds may find edge habitat detrimental as it creates conditions favorable to predators such as raccoons and nest parasites such as brown-headed cowbird. Forest interior birds have become the focus of conservation efforts region-wide due to long-term population declines of many of these species due to forest fragmentation.

The Proposed Route would utilize an existing ROW and therefore would not contribute to the new fragmentation of forest interior habitats, thus minimizing the potential impact to forest-interior birds. Given that the Proposed Route is characterized in part by managed ROW, the forest bordering the managed ROW is categorized as edge forest as opposed to interior forest. Edge forest is favored by ecotone specialists or forest generalists, and is not optimal breeding habitat for forest-interior birds. Although the Project will not directly impact core forest, it may indirectly impact core forest as the additional clearing along the edge of the ROW may result in reduced core forest within the overall forest patch.

The width of the edge forest effect can vary by region or species. In order to evaluate potential Project effects to forest-interior birds as a result of expansion of the maintained ROW, the methodology described in the *Center for Land Use Education and Research’s (CLEAR) Forest Fragmentation Study (2006)*⁷⁷ was used. The CLEAR study designates a forest as core if it is greater than 300 feet away from non-forested areas with the 300-foot zone representing edge forest that is considered sub-optimal breeding habitat for forest-interior birds.

The CLEAR study, along with many other studies, has suggested that forest patch size is a critical factor for successful breeding by forest-interior birds.⁷⁸ The CLEAR study suggests that 250 acres should be considered the *absolute minimum* forest patch size needed to support area-sensitive forest-interior birds, with a recommended minimum forest patch size of 500 acres. At that scale, a forest is presumed to provide enough suitable habitat to support more diversity of interior forest species. Therefore, not all of

⁷⁷ 2006 *CLEAR Forest Fragmentation Study*

http://clear.uconn.edu/projects/landscape/forestfrag/forestfrag_public%20summary.pdf

⁷⁸ Environment Canada. 2004. *How Much Habitat is Enough? (Second Edition) A Framework for Guiding Habitat Rehabilitation in the Great Lakes Areas of Concern* AND Lee, M., L. Fahrig, K. Freemark and D.J. Currie. 2002. *Importance of patch scale vs. landscape scale on selected forest birds*. *Oikos*, Vol. 96, No. 1, pp. 110-118.

the forest areas impacted by the Project will constitute high-value forest. This data identifies three categories to indicate the viability of the core patches with respect to the size of the patch, including; small (< 250 acres), medium (250-500 acres), and large (>500 acres).

As shown in the *Inventory and Assessment of Breeding Birds* (Volume 3), the Project area is dominated by small core (<250 acres) forest, non-forest, or forest fragments (patch or perforated forests) as opposed to large forest patches. These small core forests and forest fragments may provide some breeding habitat for forest-interior species but are generally considered sub-optimal, and may serve as population sinks. Significant core forest patches are not abundant within the Project area. Only one medium core forest patch (Black Rock State Park in Watertown) and one large core forest patch (Mattatuck State Forest in Watertown) occur. Furthermore, the single large core forest patch is located within a segment of Project area where the ROW is 400 feet wide and minimal tree clearing will be required within the interior of the managed ROW.

Shrubland and other early-successional bird species will benefit from the conversion of forest to shrubland. These include a number of species of high-conservation priority, including the prairie warbler, blue-winged warbler and field sparrow. Shrublands in the northeastern United States are primarily disturbance-dependent and are typically ephemeral. Left unmanaged, these areas would naturally revert to forest. Despite the transient nature of shrublands and other early successional habitats, many species of birds and other wildlife require these habitats.

The decline of shrublands and other early-successional cover types in the Northeast has had considerable impacts on the populations of associated wildlife. In particular, many bird species have experienced statistically significant population declines due to the loss of suitable breeding habitat.⁷⁹ By some estimates, at least 45% of all shrubland birds in the Northeast have experienced statistically significant population declines between 1966 and 2000.⁸⁰

Because transmission line corridors are one of the few sources of persistent early-successional habitat in the Northeast, they play an important role in supporting a variety of bird and wildlife species. This

⁷⁹ Witham, J. W., and M. L. Hunter, Jr. 1992. *Population Trends of Neotropical Migrant Landbirds in Northern Coastal New England*. In: J. M. Hagan and D. W. Johnston (Eds.), *Ecology and Conservation of Neotropical Migrant Landbirds*. Smithsonian Institution Press, Washington, D.C.

⁸⁰ Dettmers, R. 2003. *Status and Conservation of Shrubland Birds in the Northeastern U.S.* *Forest Ecology and Management* 185:81-93.

important role in maintaining essential habitat and wildlife biodiversity has been widely acknowledged, not only for bird species but also for a number of reptile and invertebrate species.

Statewide, transmission corridors remain critical habitat for shrubland and other early-successional birds. Vegetation management of transmission line corridors is recommended as part of the regional and national conservation strategy to reverse declines of priority shrubland birds in the eastern region. Askins notes that shrubland birds today are largely dependent on clearcuts and transmission line corridors, and that the latter typically supports a rich diversity of shrubland birds.⁸¹ In the Connecticut Audubon Society's 2009 *State of the Birds* report (p.44), it was noted that "...shrubland birds are benefitting from maintenance of powerline corridors by utility companies which remove tall-growing trees from the vicinity of wires, creating a habitat dominated by shrubs, grass and herbs."

Six state-listed species were identified within the Project area as potential or confirmed breeders (five potential, one confirmed). All six of these species are associated within open or early-successional habitats or forest edge habitats as opposed to forest-interior. In addition, a total of 35 species identified as potentially occurring within the Project area are designated as *Species of Greatest Conservation Need* (SGCN) by *Connecticut's Wildlife Action Plan*⁸² (WAP, in prep.). Of those 35 species, seven are classified as *most important*, 16 as *very important* and 12 as *important*. Of the 35 SGCN identified, 15 are associated with managed early-successional ROW vegetation (i.e., shrubland and scrub-shrub wetlands) and seven SGCN species are associated with edge habitats or agricultural lands. Five of the seven (71%) SGCN classified as *most important* are associated with managed early-successional ROW vegetation.

6.1.3.3 Federal and State Listed or Proposed Threatened, Endangered, or Special Concern Species

Eversource is working with both the USFWS and the CT DEEP to identify general measures to avoid or minimize adverse effects on federal and state-listed species that may inhabit the ROW. Eversource expects to consult in more detail with these agencies as the planning for the Project continues. As a result of the implementation of the measures discussed below, or similar or additional measures that may be identified during future agency consultations, Eversource anticipates that no significant adverse effects would occur to any known listed species.

⁸¹ Askins, R. A. 2000. Ibid.

⁸² *Connecticut's Wildlife Action Plan*, formerly known as *Connecticut's Comprehensive Wildlife Conservation Strategy* (2005) is currently under revision by the CT DEEP. Portions of the plan, such as the SGCN list, have been released in draft form and have been used in this report.

6.1.3.3.1 Federally-Listed Species

Screening using the USFWS IPaC indicated that northern long-eared bat (*Myotis septentrionalis*), a federally-threatened and State-endangered species, may be present in proximity to the Project area. The USFWS has recommended that consultations regarding this species be coordinated through CT DEEP. Based on consultation between Eversource and CT DEEP on July 30, 2015⁸³ there are no known records of this species or hibernacula in the vicinity of the Proposed Route. CT DEEP has recommended that an assessment be conducted to document habitat suitability (summer roosting) and potential Project impacts to this habitat if it is found to occur. Based on the results of this assessment additional acoustic surveys may be conducted along the Proposed Route in the summer of 2016.

6.1.3.3.2 State-Listed Species

Based on an initial consultations with the CT NDDDB, followed by wildlife habitat field surveys, ten state-listed species have been identified as potentially occurring in the vicinity of the Proposed Route, one state-listed species (broad-winged hawk) was observed. Table 6-3 lists these animal species, provides the listing status of individual species, summarizes each species' ecological/habitat preference, and provides a general location of each species' habitat in relation to the ROW.

⁸³ Meeting with Jenny Dickson and Kate Moran (CT DEEP), Eversource Energy, and Tighe & Bond

Table 6-3: Summary of State-Listed Threatened, Endangered, or Special Concern Species Potentially Occurring in the Vicinity of Proposed Route

Scientific (Latin) Name	Common Name	Town / Area	State Status*	Habitat (Nesting/Breeding/Active Periods)
Birds				
<i>Buteo platypterus</i> **	Broad-winged Hawk	Harwinton	SSC	Deciduous or mixed forest types often near a lake, pond or wetland April-August
<i>Toxostoma rufum</i>	Brown Thrasher	Project ROW	SSC	Thickets, brushy hillsides and woodland edges in suburban and rural areas April-August
<i>Dolichonyx oryzivorus</i>	Bobolink	Watertown	SSC	Early old field habitat, managed grasslands or hayfields May-June
<i>Passerculus sandwichensis</i>	Savannah Sparrow	Watertown	SSC	Early old field habitat, managed grasslands or hayfields May-August
<i>Empidonax alnorum</i>	Alder Flycatcher	Project ROW	SSC	Low vegetation including shrubs with trees over eight feet high near streams or other open water June-August
<i>Falco sparverius</i>	American Kestrel	Watertown	ST	Grassland or shrubland at the edge of forest; requires cavities for nesting April-June
Reptiles				
<i>Liochlorophis vernalis</i>	Smooth Green Snake	Project ROW	SSC	Open, unforested habitats including meadows, pastures, fens, coastal grasslands, and mountaintop “balds”, transitional and lightly forested habitats such as grassy old fields with scattered shrubs and trees April 1-October 31
<i>Glyptemys insculpta</i>	Wood Turtle	Branch Brook, Northfield Brook, Naugatuck River	SSC	Riparian habitats bordered by floodplain, woodland, or meadows April 1-October 31
Amphibians				
<i>Gyrinophilus porphyriticus</i>	Northern Spring Salamander	Watertown	ST	Steep, rocky high-gradient ravines, brooks, seepage areas, springs April 1 through October 31
Lepidoptera				
<i>Callophrys irus</i>	Frosted elfin	Litchfield, Harwinton	ST	Xeric and open disturbance-dependent habitats on sandy soil; hosts include wild indigo or lupine
Mammal				
<i>Myotis septentrionalis</i> ***	Long Eared Bat	Project Area	FT/SE	Hibernates in caves and mines - swarming in surrounding wooded areas in autumn. During late spring and summer roosts and forages in upland forests.

*SSC=State Species of Special Concern, ST=State Threatened, SE=State Endangered, FT=Federal Threatened

**Observed species

***No NDDB polygons over Proposed Route

The following summarizes the potential effects and proposed protection measures that Eversource has identified to date with respect to these species. The protection measures outlined below were provided to CT DEEP for concurrence that they are adequately protective. In a response letter dated May 19, 2015 (provided in Volume 3), CT DEEP indicated that if these protection strategies are followed the Project will not have an adverse impact on these species. This determination is valid for one year. As the planning for the Project proceeds, Eversource will continue to consult with the USFWS, ACOE, and CT DEEP regarding species-appropriate mitigation strategies. Such mitigation would be incorporated into the D&M Plans and other Project specifications.

Bird Species

Eversource's consultants performed a breeding bird assessment along the Proposed Route in the spring of 2015. The results of this assessment indicate that portions of the Project ROW provide suitable habitat for the six state-listed species; therefore, it is possible that these species may periodically utilize the ROW (refer to the *Inventory and Assessment of Breeding Birds*, Volume 3). One state-listed Special Concern species, broad-winged hawk, was observed May 2, 2015 calling from a perch along the forest edge adjacent to a wetland in Harwinton. CT DEEP indicated during a meeting on July 30, 2015⁸⁴ that the State-listed bird species identified as potentially occurring or observed would not be adversely affected by the Project and therefore, no additional surveys or protection measures are warranted.

Wood turtle (*Glyptemys insculpta*)

Eversource does not anticipate any in-water work associated with the construction of the new transmission lines. Therefore, the Project would not be expected to result in any negative effects on this important habitat component. When active, this species uses woodlands, meadows, and linear ROWs bordering riparian habitats. These terrestrial habitats exist within the Proposed Route in proximity to the above-referenced riparian habitats.

Although the construction of the proposed Project is unlikely to affect turtles during the hibernating period, it is possible that activities (e.g., vegetation removal and grading) performed in terrestrial habitats along the ROW during the turtles active period (April through October) could adversely affect individual turtles. For example, turtles could be killed or temporarily displaced as a result of construction activities. However, when construction is complete, the turtles would once again utilize these habitats.

⁸⁴ Meeting with Jenny Dickson and Kate Moran (CT DEEP), Eversource Energy, and Tighe & Bond

In order to minimize the potential for adverse effects to wood turtles, protection strategies and techniques have been incorporated from similar Eversource transmission line projects previously approved by the CT DEEP. In locations along the ROW where suitable wood turtle habitat was identified (including summer terrestrial habitat), the following CT DEEP approved measures are proposed for the protection of this species during Project construction activities:

General:

- A contractor awareness program will be developed and implemented to ensure that contractors working in the area have been instructed on the proper response in the event that a wood turtle is observed in the work area.

For construction activities during the inactive season (November 1 to April 1):

- The removal of low-growth vegetation and tree stumps adjacent to the banks of identified suitable riparian habitat will be avoided and minimized to the greatest extent possible.
- To the extent practicable, mowing in preparation of Project construction activities will be limited to work areas and conducted in the inactive season, between November 1 and April 1.

For construction activities during the active season (April 1 to November 1):

- A sweep of the work area shall be conducted prior to heavy machinery access, construction, and/or mowing to look for basking turtles.
- If mowing during the active season is required, vegetation will be mowed to no lower than 7". Flail type mowers will not be used for mowing in the active season.
- Any turtle encountered during construction will be moved, unharmed, to an area immediately outside of the work area, and positioned in the same direction that it was heading when discovered. Workers will be informed that turtles should never be moved off site.
- All silt fencing will be removed after work is completed and soils are stable so that reptile and amphibian movement is not restricted.
- Any confirmed sightings of this species will be reported to the CT DEEP NDDB.

Smooth Green Snake (*Liochlorophis vernalis*)

Two main factors have influenced the conservation status and current distribution of smooth green snakes: the long-term change in land use patterns (loss of fields and early successional habitat), and historic use of pesticides such as DDT (Klemens 1993). The proposed expansion of the existing managed ROW will expand the amount of suitable (early successional) habitat for this species. Mortality as a result of construction is not anticipated to have an adverse impact on local populations because smooth green snakes are highly mobile, and thus individuals are likely to avoid interaction with construction equipment. The following measures are proposed for the protection of this species during construction activities:

- A contractor awareness program will be developed and implemented to ensure that contractors working in the area have been instructed on the proper response in the event that a smooth green snake is observed in the work area.
- If any snakes are observed, construction personnel will safely relocate them to an area immediately outside of the construction footprint.
- Any silt fence utilized will be removed after construction is complete and soils are stabilized.
- Any confirmed smooth green snake sightings will be reported to the CT DEEP NDDDB.

Northern Spring Salamander (*Gyrinophilus porphyriticus*)

Potential Project effects are largely associated with the possible transport of sediment into viable downstream habitat during construction. The following measures are proposed for the protection of this species during construction activities:

- Implement erosion and sedimentation controls that incorporate best management practices to minimize or avoid sediment deposition into wetlands draining to the spring salamander's stream habitat, and/or;
- Conduct construction-phase stormwater monitoring to document the condition and, as necessary, the maintenance of erosion and sedimentation controls and best management practices. Prompt contractor response to repair / maintain these controls, as required pursuant to regulatory approvals, will avoid or minimize the potential for discharge of sediment to wetlands and watercourses, or degradation of water quality, which might adversely affect this species.

Frosted Elfin Butterfly (*Callophrys irus*)

Potential effects to frosted elfin relate to the reduction and/or destruction of the identified host plant communities (*Baptisia tinctoria*) as a result of construction activities, as well as direct impacts to larval stages of these species, if present in areas of impacted host plant communities. Such activities include but are not limited to the establishment of staging areas, access road construction or improvements, work pad construction, construction activities related to structure locations, and pulling pad locations for stringing lines.

The following conservation measures are proposed to avoid and minimize impacts to host plants and potential indirect effects on frosted elfin:

- Prior to commencement of construction in the host plant areas, the boundaries of host plant communities will be flagged in the field;
- A contractor awareness program will be developed and implemented to ensure that contractors have knowledge of the presence of the host plant communities near work areas;

- Temporary impacts to identified host plant communities will be reduced to the extent practicable by minimizing mowing and ground disturbance outside of the areas required to safely complete the necessary construction activities;
- Construction-phase environmental monitoring by qualified personnel will be provided during construction; and
- Where stabilized vegetation replacing bare soil is necessary following construction, only annual seed mixtures shall be used to prevent the introduction and establishment of non-native species.

After the completion of construction, the wider managed portions of the ROW would likely promote additional habitat for the moths and butterflies that utilize shrubland communities, creating a long-term benefit for this species.

6.1.4 Land Use, Recreational/Scenic Resources, and Land-Use Plans

The proposed 115-kV transmission line would be located adjacent to one or more existing Eversource 115-kV overhead transmission lines (as well as a 345-kV line for part of the route), within a ROW that has long been established for utility purposes. Similarly, the separation of the existing 1191 and 1921 Lines onto separate structures at the Naugatuck River crossing between Litchfield and Harwinton will be accomplished within Eversource's existing ROW. Consequently, the overall development of the proposed new 115-kV transmission line and the separation of the two existing 115-kV lines at the Naugatuck River crossing would be consistent with existing and future land use plans and would typically result in incremental effects on land uses, recreational resources, and scenic views.

6.1.4.1 Land Use

The Project would result in both short-term and long-term effects on land uses. Because the new 115-kV transmission line would be aligned within an existing Eversource ROW that has been dedicated to utility use for decades, the overall effects on land uses will be minor and localized. The new 115-kV transmission line would be located on property subject to existing Eversource easements or within Eversource-owned properties. Overall, more than 41% of the new transmission line would be aligned across Eversource-owned properties or publicly-owned properties across which Eversource has existing easements; specifically, approximately 0.94 miles (9%) of the 10.4-mile-long transmission line route would extend across Eversource-owned land, while an additional 3.3 miles (32%) would be across federal, state, or local properties subject to Eversource easements. The construction of the proposed transmission line would convert approximately 6.7 acres of forested wetlands and approximately 42.2 acres of forested uplands to scrub/shrub lands (refer to Table 6-2).

The upland forest land use type would be converted to open field – shrubland, whereas the forested wetland land-use type would be converted to emergent or scrub-shrub wetlands. Construction would also temporarily affect a few agricultural areas, open fields, residential areas (house/yard), and commercial and industrial properties within Eversource’s existing ROW. However, the operation of the Project would not cause long-term adverse effects on these land uses, which are required to conform to Eversource’s existing easement requirements.

6.1.4.2 Consistency with Existing and Future Land-Use Plans

Based on a review of Connecticut’s C&D Plan, town *Plans of Conservation and Development*, and regional planning agency land use documents, the construction and operation of the Project facilities would not conflict with local land use plans, because the proposed transmission line would be located within an existing, long-established ROW already dedicated to energy use. Moreover, within the ROW, Eversource’s existing easements already specify land uses that are consistent with the safe operation of overhead transmission lines, precluding permanent non-utility structures. Further, the state C&D Plan (Growth Management Principle #1) advocates the development of utility infrastructure to continue to support the state’s economic growth and revitalization of regional centers.

6.1.4.3 Public Forests, Parks, Open Space, Recreational / Public Trust Lands, and Trails

The new 115-kV transmission line would be aligned within Eversource’s existing ROW across portions of various designated recreational areas, including Mattatuck State Forest, Veterans Memorial Park, Black Rock State Park, Northfield Brook Recreation Area, Thomaston Dam properties along the Naugatuck River, and recreational trails (e.g., Jericho Trail, Mattatuck Trail, Black Rock State Park Red Trail, Northfield Brook Recreation Area trail). Most of these areas offer year-round recreational opportunities, although peak uses in most areas are in the spring, summer, and fall.

Transmission line construction activities may temporarily affect recreational uses by causing traffic congestion or delays on local roads leading to recreational areas, or by requiring temporary closures of recreational trails. The ROW crosses hiking trails in Mattatuck State Forest, Black Rock State Park, and Northfield Brook Recreation Area.

The ROW traverses the northern boundary of Veterans Memorial Park, outside of the Park’s developed recreational areas; as a result, no recreational activities in the Park would be affected by the project. Similarly, at the Naugatuck River crossing between Litchfield and Harwinton, the new 115-kV transmission line conductors, as well as the separated 1191 and 1921 Line conductors, would be aligned

high above the river and the recreational trails along it. Due to the height of the conductor spans, no tree clearing or trimming is expected to be required in the riparian corridor. As a result, recreational activities associated with the Naugatuck River / Thomaston Dam (e.g., fishing, ATV / snowmobile use, hiking) would not be affected.

The proposed transmission line would be consistent with the existing utility use of the ROW that already extend across the recreational areas and thus would not result in significant adverse effects on the public uses of such areas. In general, adverse effects on recreational uses would be short-term, lasting only for the duration of construction.

The operation and maintenance of the new transmission line would not alter the use of the recreational areas traversed by the ROW. Further, the expansion of shrubland habitat could benefit some recreational activities, such as hunting within the Mattatuck State Forest, Black Rock State Park, and other recreational areas where hunting is allowed.

Consistent with its typical project planning process, Eversource would coordinate with the owners or managers of the public recreational areas to develop measures to maintain public safety during construction, while also avoiding or minimizing short-term impacts to recreational users. In addition, Eversource would typically provide an anticipated construction schedule to representatives of each recreational use area. The schedule would define Eversource's proposed plans for minimizing disruptions to recreational uses during construction, such as proposed road closures, detours/re-routes, signs along trails and public use areas identifying work zones, etc.

6.1.4.4 Designated Protected and Scenic Resources

The proposed 115-kV transmission line would be aligned adjacent to one or more of Eversource's existing overhead transmission lines across or near certain designated public open space and potential scenic areas. Eversource carefully evaluated the proposed Project facilities in relation to these areas and has attempted to minimize incremental visual effects to the extent practical by aligning new structures generally parallel to existing structures.

In addition, as described in Section 5.1.4.5, Eversource conducted field reconnaissance of all known scenic and protected open space areas in the vicinity of the ROW to assess viewpoints from these areas to the existing overhead transmission lines within the ROW and, based on these analyses, to identify areas from which to perform photo-simulations to further evaluate the potential changes that the new overhead

transmission line would have on the viewscape. At each location where views of the transmission line were identified as a potentially dominant component of the local viewscape, Eversource prepared photo-simulations depicting views of the ROW (illustrating the new and existing transmission lines) under two conditions:

- (1) During early April 2015, when no deciduous vegetation was present (i.e., “leaf off” conditions); and
- (2) During May 2015, when deciduous vegetation had leafed out (i.e., “leaf on” conditions). While the “leaf off” conditions represent the time periods when the ROW and transmission lines would be most visible, the “leaf on” conditions are more representative of the seasons when the public is most apt to use the public recreational facilities in the vicinity of the Proposed Route.

The results of the visual resource surveys, along with the photo-simulations, are provided in Volume 3. The following briefly summarizes potential views of the existing and proposed transmission lines, based on the field studies conducted.

- **Jericho Trail, Watertown.** The Jericho Trail, which is located within Mattatuck State Forest, extends perpendicularly across Eversource’s existing 400-foot-wide ROW, which is occupied by two 115-kV and one 345-kV transmission line. The proposed 115-kV line would be located near the center of this ROW, between the existing lines. At the crossing, the trail is asphalted. Long views of the ROW to the west are blocked by a steep slope. However, from the trail, hikers have extended views to the east, where the Frost Bridge Substation and various existing overhead transmission lines are visible within the generally forested Naugatuck River Valley and adjacent hillsides. On both sides of the ROW, the Jericho Trail reverts back to a narrow trail and bends into the densely wooded Mattatuck State Forest. Consequently, the new 115-kV structures would be visible only at or in the immediate vicinity of the trail crossing
- **Jericho-Whitestone Connector Trail, Watertown.** In the Project area, this trail extends along Echo Valley Road and from there crosses onto the 400-foot-wide ROW for a short distance before diverging north into Mattatuck State Forest and eventually joining the Jericho Trail, north of the Project ROW. In the vicinity of the ROW, views from this trail are presently influenced by Echo Valley Road and developments along it, as well as by the existing transmission lines within the ROW. As a result, the development of the new 115-kV line would have only an incremental visual effect.
- **Mattatuck Trail, Black Rock State Park, and Park Red Trail, Watertown.** The ROW crosses the CFPA’s Mattatuck Trail approximately 0.5 mile from the park’s main gate and primary recreational areas (e.g., lake, fields, camping area). The ROW is not visible from the scenic overlook along the Trail, which offers views to the east toward the main park entrance and beyond. At the crossing of the Trail, the new 115-kV line would be located east of the existing 1191 Line. In this area, views are limited by the rugged terrain (rock outcrops, steep topography) and dense forested vegetation (coniferous and deciduous). The existing ROW and overhead transmission line are prominently visible to trail users at and in the immediate vicinity of the trail crossing during either “leaf off” or “leaf on” conditions. However, the ROW crosses the trail

perpendicularly, and bends in the trail both northwest and southeast of the ROW generally prohibit long views of the transmission line structures except at and close to the ROW crossing. The ROW also crosses the Park's Red Trail, which is located to the north of the Mattatuck Trail. Visual conditions along this trail are similar to those described for the Mattatuck Trail.

- **Interpretive (Yellow) Trail, Northfield Brook Recreation Area.** The existing ROW crosses this trail twice, perpendicularly. At the first crossing, the existing 115-kV transmission lines (the 1191 and 1921 Lines) extend high above the trail near Northfield Brook; as a result, no vegetation is managed at this crossing. The proposed 115-kV line would similarly span this trail crossing. The second crossing of the trail is located on a slope above the recreation area's main access road. The managed vegetation within the ROW affords hikers long views to the south, toward State Route 254, where the ROW and transmission line structures also are visible. The new 115-kV transmission line will be similarly visible from this trail crossing. However, due to both topography and dense vegetation, views of the ROW and transmission line structures are limited, except at the actual ROW crossing.

6.1.4.5 Methods to Prevent and Discourage Unauthorized Use of ROW

Eversource's existing transmission line easements restrict the types of activities that can be conducted within the ROW. Easements typically prohibit the construction of buildings, pools, and other structures within the ROW. Additionally, Eversource has policies addressing requests from property owners and other parties external to Eversource. These policies outline an evaluation process and provide guidelines for allowing certain uses (such as driveways or parking lots), where appropriate. Requests prohibited by the easement agreements, or otherwise posing safety, engineering, environmental, or other concerns are rejected.

Where Eversource holds an easement as opposed to land ownership in fee, Eversource must receive landowner approval prior to installing fences, gates, etc. Eversource seeks to work with landowners and agencies to discourage unwarranted access onto and use of its ROWs, and typically installs signs warning the general public of the overhead hazards posed by contact with the high voltage transmission lines and, with landowner approval, installs fences, gates, barricades, or berms to discourage access onto the ROWs.

In addition, Connecticut law prohibits the operation of ATVs on private land without the written permission of the landowner (C.G.S. § 14-387). Eversource does not allow ATV use on its properties or properties subject to its easements.

6.1.5 Transportation, Access, and Utility Crossings

The construction of the new transmission line would have minor, short-term, and localized effects on transportation patterns in the immediate vicinity of the Project. These effects would stem primarily from additional traffic on local roads associated with the movement of construction vehicles and equipment to

and from contractor yards, staging areas, and work sites along the ROW. The proposed 115-kV transmission line would span all roads that it crosses.

The construction of the 115-kV transmission facilities would not affect railroads or other utilities (e.g., water lines, stormwater or sanitary sewers), all of which would be spanned by the proposed overhead line. Similarly, the operation of the Project, which would not generate traffic other than that associated with periodic ROW management, would not affect transportation systems or local traffic patterns.

During construction, the well-established public road network in the Project area would afford ready access to the ROW for vehicles and equipment. Along the ROW, construction equipment, materials, and support vehicles would use existing or improved access roads to reach work sites. In certain areas, Eversource proposes to use off-ROW access roads to reach on-ROW work sites.

During construction, personnel traveling to and from work sites, as well as the movement of construction equipment, may cause temporary localized increases in traffic. When heavy equipment and large structure components must be transported along public roads for delivery to the ROW, temporary disruptions in local traffic patterns, delays, or detours could occur. Activities involving the installation of the conductors at or near road crossings also could result in minor, short-term, and localized traffic congestion, delays, or detours. However, any such traffic volume increases would be short-term, as would any detours.

Eversource would employ personnel to direct traffic at construction work sites along public roads, as needed, and would erect appropriate traffic signs to indicate the presence of construction work zones. In addition, to minimize the potential for transportation issues, Eversource would work with representatives of the affected towns as appropriate. Such plan(s), which would be implemented by Eversource's construction contractor(s) would define traffic control requirements and identify measures for safe ingress and egress to the ROW for construction equipment and other vehicles.

Based on analysis of the transmission line structures along the Proposed Route, none of the structures would exceed the FAA notification criteria for airports or heliports located in the vicinity of the Proposed Route; including Waterbury Airport (located approximately 7,000 feet to the northeast in the Town of Plymouth), Northfield Heliport (located approximately 7,100 feet west in the Town of Litchfield), and Waterbury-Oxford Airport (located approximately 9.5 miles south in the Town of Oxford).

6.1.6 Cultural (Archaeological and Historic) Resources

As part of the Project planning effort, Eversource's cultural resources consultant compiled baseline information about the history and prehistory of the Project area, including identifying any known cultural resources in the vicinity of the Proposed Route and substations. This review verified there are no previously identified historic structures, archaeological sites or National Register of Historic Places properties on file with the Connecticut State Historic Preservation Office that are situated within 152 m (500 ft) of the proposed project corridor or in the general vicinity.

As planning for the proposed Project continues, Eversource expects to conduct additional archaeological reconnaissance field investigations and thereafter to develop appropriate intensive survey testing and other research measures needed to determine the eligibility of any discovered sites to the NRHP/SRHP. This additional work would be performed based on consultations with the Connecticut SHPO and involved Native American tribes.

Any sites determined eligible for the NRHP/SRHP would be avoided if possible, using methods such as the adjustment of construction pad or construction road locations, low-impact forest vegetation removal with no subsurface disturbance, use of protection measures such as fill or timber mats, etc. Avoidance methods can also include placement of fill material sufficient to resist all effects of construction equipment, but marked with geotextile fabric wherever fill is removed following construction to preclude subsurface disturbance during fill removal. Eversource is sensitive to Connecticut's cultural heritage and is committed to working with the SHPO in protecting and mitigating potential effects to these resources, if applicable.

If avoidance of eligible resources is not possible, mitigation strategies would be developed for review and approval by the SHPO, in consultation with interested Native American tribes. Mitigation would include data recovery sufficient to document significant information which may be lost to adverse Project effects.

6.1.7 Air Quality

The construction of the proposed Project facilities would result in short-term, minor, highly localized effects on air quality, primarily from fugitive dust (as a result of soil disturbance at work sites and from vehicular movements on access roads along the ROW) and from vehicular emissions associated with the construction equipment operation. No long-term effects on air quality would result from the operation of the proposed 115-kV transmission line.

To minimize short-term adverse effects to air quality during construction, as necessary, access roads and other sites would be watered to suppress fugitive dust emissions. Additionally, crushed stone aprons would be installed at all access road entrances to public roadways, minimizing tracking of soil onto the road pavement. Vehicular emissions would be limited by requiring contractors to properly maintain construction equipment and vehicles, as well as to conform to Connecticut's vehicular anti-idling regulations (RCSA§ 22a-174-18).

Unlike other criteria pollutants, greenhouse gas (GHG) impacts are global in nature, not local or regional. Consumption of fuel from construction equipment or vehicles is only a part of the global GHG emission sources. The global consumption of fuel would remain the same whether it is combusted during this Project or elsewhere in the world. Since the construction of the proposed Project facilities will be short-term, actual emissions of GHGs would be very small when compared to the carbon footprint of vehicles or permanent emission sources such as a refinery.

6.1.8 Noise

The construction of the new 115-kV transmission line would cause localized, short-term, and generally minor increases in ambient noise levels in the immediate vicinity of work sites. The operation of the transmission line would not affect the noise environment, except under certain weather conditions when sound from the conductors may be audible on or in the immediate vicinity of the ROW.

Construction-related noise would generally stem from construction equipment operation, truck traffic, earth-moving vehicles and equipment, jackhammers, and structure erection equipment (cranes), etc. Overall, these sound levels would be typical of construction projects.

The temporary increase in construction-related noise could potentially raise ambient sound levels at certain receptor locations near work sites, including residences, schools, and designated recreational areas. The extent of a noise effect to humans at a sensitive receptor is dependent upon a number of factors, including the change in noise level from the ambient; the duration and character of the noise; the presence of other, non-Project sources of noise; people's attitudes concerning the Project; the number of people exposed to the noise; and the type of activity affected by the noise (e.g., sleep, recreation, conversation). The effect of construction-generated noise would also depend on the noise source location relative to the receptor's location because sound attenuates with distance and with the presence of vegetative buffers or other barriers.

Noise levels diminish at a rate of approximately 6 dBA per doubling of distance from a noise source. For example, a noise level of 84 dBA measured at 50 feet from the noise source to the receptor would reduce to 78 dBA at 100 feet from the source to the receptor, and reduce to 72 dBA at 200 feet from the source to the receptor.

Table 6-4 summarizes noise level data compiled for various types of construction equipment and measured at 50 feet from the source. Such construction-generated noise would be localized to the vicinity of construction work sites along the ROW. In general, construction activities would typically occur during the daytime Monday through Saturday (between 7:00 A.M. to 7:00 P.M.), when human sensitivity to noise is lower.

Table 6-4: Noise Ranges of Typical Construction Equipment

Equipment	Noise Levels (Leq, dBA) at 50 feet ¹
Backhoe	73-95
Compressors	75-87
Concrete Mixers	75-88
Concrete Pumps	81-85
Cranes (moveable)	75-88
Cranes (derrick)	86-89
Front Loader	73-86
Generators	71-83
Jackhammers	81-98
Paver	85-88
Pile Driving (peaks)	95-107
Pneumatic Impact Equipment	83-88
Pumps	68-72
Saws	72-82
Scraper/Grader	80-93
Tractor	77-98
Trucks	82-95
Vibrator	68-82

¹ Modern machinery equipped with noise control devices or other noise-reducing design features do not generate the same level of noise emissions as shown in this table. Source: USEPA Office of Noise Abatement and Control, 1971 and U.S. Department of Transportation, Federal Highway Administration (http://www.fhwa.dot.gov/environment/noise/construction_noise/special_report/hcn06.cfm, updated 7/06/2011)

6.2 SUBSTATION MODIFICATIONS

To interconnect the new 115-kV transmission line to the transmission system, Eversource proposes to modify both Frost Bridge Substation and Campville Substation. Potential environmental effects that are unique to these locations are described below. Potential effects to air quality at each substation are similar to the Proposed Route (refer to Section 6.1.7 for a description) and therefore, not described in this section.

The proposed modifications at Frost Bridge Substation would all occur within the fence lines (i.e., the already developed portions). As a result, most environmental effects would be minor, localized on-site, and short-term (lasting only for the duration of construction).

To accommodate modifications required to interconnect the new 115-kV transmission line at Campville Substation, Eversource proposes to expand the developed portion of the substation by approximately 0.4 acre (the fence line by would extend approximately 90 feet farther to the east). The expansion would occur over generally level topography in an area that has been subject to historic disturbance associated with the substation and ROW access road.

The proposed modifications would result in a long-term, but incremental, change in the appearance of each station. However, these effects would be negligible because each site is already developed for electric utility use.

The following subsections review the potential environmental effects associated with the construction and operation of the substation modifications, as well as the mitigation measures that Eversource has identified to date. These effects and associated mitigation measures would be similar for each substation and thus are discussed jointly. The planned modifications to each substation, along with the proposed construction procedures expected to be used at each site are discussed in detail in Sections 3 and 4.

6.2.1 Geology, Topography, and Soils

The modifications to each substation would require site preparation work, including grading and other soil disturbance (e.g., excavations) to install the new 115-kV transmission line facilities. Mechanical methods would be used to install foundations into bedrock, if encountered. As a result, no blasting is anticipated. Grading and filling, if required, may result in minor alterations to the topography and soils on the substation sites.

To avoid or minimize the potential for erosion and sediment transport beyond the limits of work, construction work would be performed in accordance with an *Erosion and Sediment Control Plan*, in conformance with the 2002 *Connecticut Guidelines for Soil Erosion and Sediment Control* and CT DEEP stormwater regulatory requirements. Typically, excess soil resulting from the construction of the substation modifications would be removed from the substation property, rather than stockpiled on site. In addition, construction activities typically would be sequenced to the extent possible, thereby minimizing the amount of time that soils are exposed. Further, after the installation of the new 115-kV facilities, disturbed areas at each substation would be stabilized with trap rock or another type of crushed stone.

6.2.2 Water Resources

The proposed substation modifications would occur in upland areas. Therefore, no direct adverse effects on water resources are anticipated.

Six wetlands were identified on undeveloped portions of Everource's fee-owned property in the vicinity of Frost Bridge Substation. The closest resource areas to the existing fenced development include wetlands W-FB1 (a PFO wetland), W-FB2 (a PFO wetland); and W-FB3 (a PEM wetland).

Three wetlands were identified on undeveloped portions of Everource's fee-owned property in the vicinity of Campville Substation. As a result of the proposed expansion of the substation and fence line by approximately 70 feet to the east, the new fence line would be located approximately 75 feet to the west of wetland W-G3 (a PFO wetland) which is located on undeveloped portions of Everource's fee-owned property.

During the construction of the station modifications, appropriate temporary soil erosion and sedimentation controls would be installed and maintained, pursuant to Eversource's regulatory approvals and best management practices. These erosion and sedimentation control measures would minimize the potential for off-site sedimentation into nearby water resources. Similarly, appropriate spill prevention, control, and countermeasure procedures would be implemented during construction to minimize the potential for inadvertent spills or leaks from construction equipment. Such procedures would be specified in the D&M Plans governing the substation modification work.

The operation of the modified substations would not affect water resources. Eversource would apply standard operation and maintenance procedures to avoid or minimize the potential for off-site erosion and sedimentation. During facility operation, Eversource also would conform to standards for minimizing the potential for spills or leaks from electrical equipment.

6.2.3 Flood Zones

A review of FEMA maps indicates that both the Frost Bridge and Campville Substations (including the proposed expansion area) are located beyond the limits of both the 100-year and 500-year flood zones. As a result of the proposed substation modifications. Therefore, no impact to flood zones would occur

6.2.4 Biological Resources

Because the proposed Frost Bridge modifications would occur within the existing station fence lines, no vegetation or wildlife resources would be affected. The proposed Campville Substation expansion would result in a loss of approximately 0.4 acre of mixed deciduous forest adjacent to the existing substation. This area has been subjected to historic disturbance associated with the existing substation and a ROW access road. Given the relatively small loss of forest habitat, and abundance of similar contiguous habitat, the expansion is not anticipated to have a long-term adverse impact on biological resources.

In addition, neither of the proposed substation modifications has the potential to affect any known state-listed special concern, threatened or endangered wildlife species.

6.2.5 Land Use, Recreational / Scenic Resources, and Land-Use Plans

The proposed modifications to the existing Frost Bridge and Campville substations would be located on Eversource property; would be consistent with the existing uses of each site for utility purposes; and would not conflict with any land use plans. Although the proposed modifications would slightly alter the appearance of each station, the changes would be minimal and would generally be similar in appearance to the existing facilities at each site.

The expansion of the Campville Substation (by approximately 0.4 acre) would convert undeveloped Eversource-owned land to developed utility use. However, this minor change in land use is consistent with Eversource's ownership of the property.

The proposed substation modifications would not be visible from any designated scenic sites or public recreational areas. Hayden Road, a Harwinton-designated scenic road, is located south of Campville Substation, and borders Eversource's property. However, views of the substation from the road are screened by vegetation and topography.

6.2.6 Transportation and Access

The proposed substation modifications would not adversely affect long-term transportation or access patterns. During construction, minor and short-term effects on vehicular traffic may occur as construction vehicles use local public roads leading to the sites. The operation of the modified stations would have no effect on transportation patterns or traffic.

Frost Bridge Road provides primary access to the Frost Bridge Substation and would be the principal public road used for ingress / egress to the site during construction. Similarly, Wildcat Hill Road is the principal local road in the vicinity of the Campville Substation and would be the primary access route to and from the substation during construction.

At times during construction, localized traffic congestion may occur when heavy construction equipment or electric components are transported to the substation. The movement of construction workers and equipment in general also would temporarily cause minor increased traffic on local public roads leading to the sites. However, such effects would be minor, localized, and limited to only certain periods during the construction of the substation modifications. Construction activities would be staged on Eversource property, within the fenced stations or on other previously disturbed Eversource fee-owned property.

Traffic on local roads would typically occur during normal work hours. However, some work will depend on the scheduling of allowable line outages and thus may have to be performed at other times.

6.2.7 Archaeological and Historic (Cultural) Resources

Because all construction activities associated with the modifications to the Frost Bridge Substation would be within the existing fenced areas, where soils have been disturbed by past activities, the potential for encountering intact, previously unrecorded, significant archaeological resources is negligible. As a result, no adverse effects to cultural resources would occur from the proposed Frost Bridge Substation modifications.

Most of the proposed modification to Campville Substation would occur within the fenced substation where soils have been previously disturbed and potential for locating intact cultural artifacts is negligible. Eversource will conduct appropriate investigations of the substation expansion area in order to identify potential cultural artifacts, and if found, identify appropriate protection or mitigation measures.

6.2.8 Noise

The substation modifications would result in short-term increases in noise, which would emanate from the on-site work activities and from construction-related vehicular traffic on local roads. The operation of the modified station facilities would not cause a long-term change in the ambient noise environment.

The Frost Bridge Substation is located within an area zoned for industrial use where there are no nearby noise receptors and where the ambient sound environment is influenced by the surrounding land uses and

by other activities, such as traffic on State Route 8. The Campville Substation is located in a rural / suburban area. The existing environment is typical of such areas. The ambient noise levels, albeit low, are presently influenced by the operation of the substation and vehicular movement along Wildcat Hill Road.

During construction, noise-generating activities would be generally short-term and would emanate from activities such as the operation of equipment, truck traffic, earth excavation and moving operations, and installation of electric components (refer to Table 6-4 for a summary of noise emissions from typical construction equipment). Such construction-generated noise would be localized to the vicinity of each of the stations and would typically occur during the daytime Monday through Saturday (between 7:00 A.M. to 7:00 P.M.), when human sensitivity to noise is lower. At the Campville Substation, existing forested vegetation around the developed portion of the station would assist in attenuating construction-related noise.

Under certain circumstances, especially when circuit outages are required, night work and weekend work could be necessary at the stations. Night construction would require lighting and may result in localized, temporary increases in noise levels.

Note: This page intentionally left blank.

Table 6-5
Summary of Wetland Effects along Proposed
115-kV Transmission Line ROW

Table 6-5: Summary of Wetland Effects along Proposed 115-kV Transmission Line ROW

Town/Wetland Number	Dominant Wetland Classification*	Type of Wetland Effect
Watertown		
W-A1	PSS	Vegetation Removal Outside of Managed ROW
W-A9	PSS	Work Pad
W-B1	PSS	Work Pad
W-B2	PSS	Work Pad
W-B6	PSS	Work Pad
W-B11	PSS	Work Pad
W-C1	PFO	Vegetation Removal Outside of Managed ROW
W-C3	PSS	Work Pad
W-C4	PFO	Vegetation Removal Outside of Managed ROW
W-C12	PFO	Vegetation Removal Outside of Managed ROW
W-C15	PFO	Vegetation Removal Outside of Managed ROW
W-C20	PFO	Vegetation Removal Outside of Managed ROW, Work Pad
W-C21	PFO	Vegetation Removal Outside of Managed ROW
Thomaston		
W-D3	PFO	Vegetation Removal Outside of Managed ROW, Work Pad
W-D4	PFO	Vegetation Removal Outside of Managed ROW
W-D5	PEM	Vegetation Removal Outside of Managed ROW
W-D6	POW	Vegetation Removal Outside of Managed ROW
W-D7	PFO	Vegetation Removal Outside of Managed ROW
W-D10	PFO	Vegetation Removal Outside of Managed ROW
W-D11	PFO	Vegetation Removal Outside of Managed ROW
W-D12	PSS	Vegetation Removal Outside of Managed ROW, Work Pad, Access Road Improvements
W-D13	PFO	Vegetation Removal Outside of Managed ROW
W-E2	PSS	Vegetation Removal Outside of Managed ROW, access Road Improvements
Litchfield		
W-E2	PSS	Vegetation Removal Outside of Managed ROW, Access Road Improvements
W-E4	PFO	Vegetation Removal Outside of Managed ROW
W-E6	PFO	Vegetation Removal Outside of Managed ROW, Work Pad
W-E8	PFO	Vegetation Removal Outside of Managed ROW, Work Pad, Proposed Access Road
W-E9	PFO	Vegetation Removal Outside of Managed ROW, Work Pad
W-E10	PSS	Vegetation Removal Outside of Managed ROW, Work Pad, Proposed Access Road
W-E12	PEM	Vegetation Removal Outside of Managed ROW
W-E13	PFO	Vegetation Removal Outside of Managed ROW
W-F2	PEM	Access Road Improvements
W-F3	PFO	Vegetation Removal Outside of Managed ROW
W-F4	PFO	Vegetation Removal Outside of Managed ROW
W-F7	PSS	Vegetation Removal Outside of Managed ROW
Harwinton		
W-F10	PFO	Vegetation Removal Outside of Managed ROW
W-F11	PFO	Vegetation Removal Outside of Managed ROW

Table 6-5: Summary of Wetland Effects along Proposed 115-kV Transmission Line ROW

Town/Wetland Number	Dominant Wetland Classification*	Type of Wetland Effect
W-F13	PFO	Vegetation Removal Outside of Managed ROW
W-F14	PSS	Vegetation Removal Outside of Managed ROW, Work Pad
W-F15	PEM	Vegetation Removal Outside of Managed ROW, Work Pad
W-G1	PFO	Vegetation Removal Outside of Managed ROW

* Wetlands were classified according to Cowardin et al. PEM = palustrine emergent wetland; PSS = palustrine scrub-shrub wetland; PFO = palustrine forested wetland; POW = palustrine open water; PUB = palustrine unconsolidated bottom.

“Vegetation Removal Outside of Managed ROW” refers to the vegetation that would have to be cleared from wetlands located within the construction footprint of the proposed 115-kV lines, along the presently un-managed portions of Eversource’s ROW.

Note: This page intentionally left blank.

Table 6-6
Potential Effects to Vernal Pools

Municipality / Volume 5, 100 Scale Mapsheet #	Wetland Number	Vernal Pool No.	Proposed Project Facilities and Vegetation Removal				
			Structures Located in Wetland Providing Habitat	Structures Located Directly in Habitat	Work Proposed in Vernal Pool Envelope (from vernal pool edge to 100 feet)	Work in Vernal Pool Depression	New Vegetation Removal Required in Vernal Pool Depression (acres)
Watertown							
3	W-MSF2	VP MSF-2			Access Road Improvements		
3A	W-MSF1	VP MSF-1			Access Road Improvements		
6	W-B2	VP B2-1			Work Pad		
7	W-B4	VP B4-1			Access Road Improvements		
11	W-C4	DVP C4-1			Access Road Improvements		
11	W-C10	VP C10-1			Tree Clearing		
12	W-C12	VP C12-1			Access Road Improvements		
13	W-C15	VP C15-1			Access Road Improvements		
14	W-C20	VP C20-1			Access Road Improvements	Work Pad	
15	W-C21	VP C21-1			Tree Clearing	Tree Clearing	.054
Thomaston							
19	W-D4	VP D4-1			Work Pad, Access Road Improvements	Tree Clearing	.021
20	W-D5	VP D5-1			Access Road Improvements		
22	W-D12	VP D12-1			Work Pad		
21	W-D15	VP D15-1					
Litchfield							
26	W-E2	DVP E2-1/E2-2			Access Road Improvements		
28	W-E9	VP E9-1			Work Pad	Tree Clearing	.17

Municipality / Volume 5, 100 Scale Mapsheet #	Wetland Number	Vernal Pool No.	Proposed Project Facilities and Vegetation Removal				
			Structures Located in Wetland Providing Habitat	Structures Located Directly in Habitat	Work Proposed in Vernal Pool Envelope (from vernal pool edge to 100 feet)	Work in Vernal Pool Depression	New Vegetation Removal Required in Vernal Pool Depression (acres)
Harwinton							
31	W-F9	VP F9-1					
31	W-F10	VP F10-1			Tree Clearing	Tree Clearing	.002
33	W-F13	DVD F13-1				Access Road Improvements	
34	W-F14	VP F14-1					
34	W-F15	VP F15-1					

7. ELECTRIC AND MAGNETIC FIELDS

7.1 ELECTRIC AND MAGNETIC FIELDS FROM POWER LINES AND OTHER SOURCES

Electric fields (“EF”) and magnetic fields (“MF”) (collectively “EMF”) are forms of energy that surround an electrical device.

EF are produced within the surrounding area of a conducting object (e.g., a wire) when a voltage is applied to it. EF are measured in units of kilovolts per meter (“kV/m”). The level of an EF near to energized power line depends on the applied voltage, the distance between the conductors, and the distance to the measurement location.

MF are produced within the surrounding area of a conductor or device that is carrying an electric current. MF are measured in units of milliGauss (“mG”). The level of a MF near to line conductors carrying current depends on the magnitude of the current, the distance between conductors, and the distance from the conductors to the measurement location.

Both electric and magnetic fields decrease rapidly as the distance from the source increases, and even more rapidly from electric equipment in comparison to line conductors. EF levels are further weakened by obstructions, such as trees and building walls, while MF pass through most obstructions.

7.2 EMF REGULATIONS AND GUIDELINES IN CONNECTICUT

Transmission lines are common sources of EMF, as are other components of electric power infrastructure, ranging from transformers and distribution lines, to the wiring and appliances in a home. There are no state or federal laws or regulations concerning transmission line electric and magnetic fields. However, to address concerns regarding potential health risks from exposure to EMF, the Council, after a nearly two year long proceeding, developed a policy document entitled *Electric and Magnetic Fields Best Management Practices for the Construction of Electric Transmission Lines in Connecticut* (EMF BMP), a copy of which is provided is provided as Appendix 7A.

The EMF BMP Document summarizes the latest information regarding scientific knowledge and consensus on EMF and health concerns and recommends best practices concerning the design of new

transmission lines with respect to EMF. The Council most recently revised the EMF BMP on February 20, 2014.

In the EMF BMP, the Council recognized “that a causal link between power-line MF exposure and demonstrated health effects has not been established, even after much scientific investigation in the U.S. and abroad,” and “that timely additional research is unlikely to prove the safety of power-line MF to the satisfaction of all.” Accordingly, the Council decided to “continue its cautious approach to transmission line siting that has guided its Best Management Practices since 1993.” As the Council states in the EMF BMP:

This continuing policy is based on the Council’s recognition of an agreement with conclusions shared by a wide range of public health consensus groups, and also, in part, on a review which the Council commissioned as to the weight of scientific evidence regarding possible links between power-line MF and adverse health effects. Under this policy, the Council will continue to advocate the use of effective no-cost and low-cost technologies and management techniques on a project-specific basis to reduce MF exposure to the public while allowing for the development of efficient and cost-effective electrical transmission projects.

Pursuant to this policy, the Council requires an applicant proposing to build an overhead electric transmission line to develop and present a Field Management Design Plan (“FMDP”) that identifies design features to mitigate MF that would otherwise occur along an electric transmission ROW. In accordance with the BMP guidelines, the proposed new line has been designed so that it will have very little effect on magnetic field levels with and along the ROW.

The magnitude of edge of ROW magnetic fields vary greatly according to the placement and configuration of the conductors on transmission lines, and the spatial relationship and current loading of multiple lines within a single ROW. For instance, one of the EMF BMP recommended by the Connecticut Siting Council is “optimum phasing,” which refers to an engineering design technique that applies in situations where more than one circuit exists within a ROW. Electric transmission circuits utilize a three-phase system with each phase carried by one conductor, or a bundle of conductors. Optimum phasing reduces MF through partial cancellation. For a ROW with two or more circuits, the phasing arrangement of the conductors of each circuit can be arranged to reduce MF levels under typical conditions. This design is the prime example of a low-cost method of reducing MF.

The relative current loading of multiple circuits on a ROW will also influence edge of ROW magnetic fields. For instance, where a circuit that is normally loaded relatively lightly is placed parallel to a much more highly loaded line, the fields associated with the high current line will be dominant, such that the edge of ROW fields from the combination of the two lines may not be measurably greater than those produced by the high current line by itself. On the other hand, where two parallel circuits are constructed between the same terminal points, the two circuits will share the load being transmitted between those points, with the effect that the edge of ROW magnetic fields will be lower than they would be if the same load were transmitted on a single circuit.

Both of the situations described above will exist on the Frost Bridge to Campville ROW after the proposed new line is constructed. On the segment of the ROW from the Frost Bridge Substation to Purgatory Junction., the proposed new line will be adjacent to the existing No. 352 345-kV line, a heavily loaded circuit that is now and will remain the dominant magnetic field source on the ROW. In addition, the new line will be built adjacent to the existing No. 1191 115-kV line, and will share with that line the load transmitted between Purgatory Junction and Campville Substation . As a result, the addition of the proposed new line to the Frost Bridge to Campville ROW will have very little effect on the pre-existing edge of ROW magnetic fields.

7.3 EMF MEASUREMENTS AND CALCULATIONS

The EMF BMP requires transmission line applicants to present calculations of MF under pre-project and post-project conditions, assuming the use of different transmission line design alternatives. The purpose of this requirement is to “allow for an evaluation of how MF levels differ between alternative power line configurations,” in order to “achieve reduced MF levels when possible through practical design changes.” However, the reduction of MF is only one of the factors that the Council will consider in approving particular line designs. Other factors include “cost, system reliability, aesthetics, and environmental quality.”

Eversource has prepared initial calculations of the existing and predicted MF from the transmission lines along the Proposed Route. The calculations most representative of typical conditions are based on projected average annual loading conditions, which were assumed in these calculations. As required by the BMP, loads projected for the year 2019 (the first summer when the new line would be in service) were used for the existing transmission lines and loads projected for 2024 (5 years after the line will have been placed in service) were used for the proposed transmission line. The calculations are made relative to the centerline of the proposed transmission line. As provided by standard protocols, the calculations apply at

1 meter (3.28 feet) above grade, and assume that the lowest conductor for each 115-kV circuit is 30 feet above grade and that the 345-kV circuit (which is within the ROW only between Frost Bridge Substation and Purgatory Junction) is 35 feet above grade. These calculations confirm that the addition of the new line will not substantially increase electric and magnetic fields at the edge of the ROW, and will decrease them in some locations, as compared to current conditions. Table 7-1 summarizes the calculated magnetic fields at the ROW edges before and after the construction of the new line. Each of the three figures relates to a segment of the ROW where the number and/or configuration of the lines on the ROW is different.

Table 7-1 - Summary of Magnetic Field Calculations

Magnetic Field Calculation Summary (Average Annual Loads, field in mG)				
Section	Left Edge of ROW		Right Edge of ROW	
	Pre	Post	Pre	Post
Frost Bridge S/S to Purgatory Junction	23.9	23.4	41.3	41.0
Purgatory Junction to Walnut Hill Junction	7.3	4.2	6.1	3.9
Walnut Hill Junction to Campville S/S	20.5	13.3	0.6	1.5

***Left and right edges of ROW are defined by looking from Frost Bridge Substation to Campville Substation**

Eversource also prepared calculations of EF from the transmission lines along the Proposed Route which is summarized in Table 7-2. The calculations assume that the voltages on all transmission lines are at 1.05 per unit value (the maximum permissible voltage per ISO-NE planning criteria). The conductor heights are assumed to be the same as for the magnetic field calculations discussed above. The calculations show minimal increases and decreases in the edge of ROW electric fields after the construction of the new line.

Table 7-2 –Summary of Electric Field Calculations

Electric Field Calculation Summary (Field in kV/m)				
Section	Left Edge of ROW		Right Edge of ROW	
	Pre	Post	Pre	Post
Frost Bridge S/S to Purgatory Junction	0.23	0.22	0.98	0.96
Purgatory Junction to Walnut Hill Junction	0.23	0.20	0.02	0.08
Walnut Hill Junction to Campville S/S	1.18	1.16	0.04	0.08

The MF associated with the existing and new conditions on the ROW are graphically depicted in Figures 7-1 through 7-3. These figures represent the MF levels across the entire width of the ROW and for 100 feet beyond each edge. Each graph includes one line for the “before” condition and another line for the “after” conditions. The “after” line is nearly on top of the “before” line because there is so little change in the levels represented. Figures 7-1 through 7-3 represents the “before” and “after” MF levels.

Figure 7-1: Calculated Magnetic Fields between Frost Bridge Substation and Purgatory Junction




Figure 7-2: Calculated Magnetic Fields between Purgatory Junction and Walnut Hill Junction





Figure 7-3: Calculated Magnetic Fields between Walnut Hill Junction and Campville S/S



Figures 7-3 through 7-6 illustrate the calculated “before” and “after” electric fields within the ROW and to a hundred feet beyond each of its edges. As with MF, there is very little change in the levels within and beyond the ROW.

Figure 7-4: Calculated Electric Fields between Frost Bridge Substation and Purgatory Junction




Figure 7-5: Calculated Electric Fields between Purgatory Junction and Walnut Hill Junction





Figure 7-6: Calculated Electric Fields between Walnut Hill Junction and Campville Substation



7.4 COMPARISON OF EDGE OF ROW MAGNETIC FIELDS TO INTERNATIONAL GUIDELINES

Although there are no binding regulations limiting EMF exposures, there are guidelines that have been developed by the international scientific community, in particular the International Committee on Electromagnetic Safety (“ICES”), a committee of the Institute of Electrical and Electronics Engineers) and the International Council on Non-Ionizing Radiation Protection (“ICNIRP”), a specially chartered independent scientific organization. Under all projected operating conditions after the proposed line is placed in service, the calculated electric and magnetic fields will be a small fraction of the ICNIRP and ICES guidelines, which are summarized Table 7-3.

Table 7-3: International Restrictions for Electric and Magnetic Fields

	EF (Kv/M)	MF (Mg)
ICES	26.8	9,150
ICNIRP	36.4	12,400

The calculations presented in section 7.3 projects that after the new line is constructed, under typical (annual average) operating conditions, edge of ROW magnetic fields will range from 1.5 mG to 41.0 mG and electric fields will range from 0.08 to 1.16 kV/m.

Appendix 7A
CSC, “Electric and Magnetic Fields Best Management Practices
for the Construction of Electric Transmission Lines in
Connecticut,” February 2014.

Note: This page left blank intentionally

Electric and Magnetic Fields Best Management Practices For the Construction of Electric Transmission Lines in Connecticut

Revised on February 20, 2014

I. Introduction

To address a range of concerns regarding potential health risks from exposure to transmission line electric and magnetic fields (EMF), whether from electric transmission facilities or other sources, the Connecticut Siting Council (Council) (in accordance with Public Act 04-246) issues this policy document "*Electric and Magnetic Fields Best Management Practices for the Construction of Electric Transmission Lines in Connecticut.*" It references the latest information regarding scientific knowledge and consensus on EMF health concerns; it also discusses advances in transmission- facility siting and design that can affect public exposure to EMF.

Electric and magnetic fields (EMF) are two forms of energy that surround an electrical device. The strength of an electric field (EF) is proportional to the amount of electric voltage at the source, and decreases rapidly with distance from the source, diminishing even faster when interrupted by conductive materials, such as buildings and vegetation. The level of a magnetic field (MF) is proportional to the amount of electric current (not voltage) at the source, and it, too, decreases rapidly with distance from the source; but magnetic fields are not easily interrupted, as they pass through most materials. EF is often measured in units of kilovolts per meter (kV/m). MF is often measured in units of milligauss (mG).

Transmission lines are common sources of EMF, as are other substantial components of electric power infrastructure, ranging from transformers at substations to the wiring in a home. However, any piece of machinery run by electricity can be a source of EMF: household objects as familiar as electric tools, hair dryers, televisions, computers, refrigerators, and electric ovens.

In the U.S., EMF associated with electric power have a frequency of 60 cycles per second (or 60 Hz). Estimated average background levels of 60-Hz MF in most homes, away from appliances and electrical panels, range from 0.5 to 5.0 mG (NIEHS, 2002). MF near operating appliances such as an oven, fan, hair dryer, television, etc. can range from 10's to 100's of mG. Many passenger trains, trolleys, and subways run on electricity, producing MF: for instance, MF in a Metro-North Railroad car averages about 40-60 mG, increasing to 90-145 mG with acceleration (Bennett Jr., W. 1994). As a point of comparison to these common examples, the Earth itself has an MF of about 570 mG (USGS 2007). Unlike the MF associated with power lines, appliances, or computers, the Earth's MF is steady; in every other respect, however, the Earth's MF has the same characteristics as MF emanating from man-made sources.

Concerns regarding the health effects of EMF arise in the context of electric transmission lines and distribution lines, which produce time-varying EMF, sometimes called extremely-low frequency electric and magnetic fields, or ELF-EMF. As the weight of scientific evidence indicates that exposure to electric fields, beyond levels traditionally established for safety, does not cause adverse health effects, and as safety concerns for electric fields are sufficiently addressed by adherence to the National Electrical Safety Code, as amended, health concerns regarding EMF focus on MF rather than EF.

MF levels in the vicinity of transmission lines are dependent on the flow of electric current through them and fluctuate throughout the day as electrical demand increases and decreases. They can range from about 5 to 150 mG, depending on current load, height of the conductors, separation of the

conductors, and distance from the lines. The level of the MF produced by a transmission line decreases with increasing distance from the conductors, becoming indistinguishable from levels found inside or outside homes (exclusive of MF emanating from sources within the home) at a distance of 100 to 300 feet, depending on the design and current loading of the line (NIEHS, 2002).

In Connecticut, existing and proposed transmission lines are designed to carry electric power at voltages of 69, 115, or 345 kilovolts (kV). Distribution lines, i.e. those lines directly servicing the consumer's building, typically operate at voltages below 69 kV and may produce levels of MF similar to those of transmission lines. The purpose of this document is to address engineering practices for proposed electric transmission lines with a design capacity of 69 kV or more and MF health concerns related to these projects, but not other sources of MF.

II. Health Concerns from Power-Line MF

While more than 40 years of scientific research has addressed many questions about EMF, the continuing question of greatest interest to public health agencies is the possibility of an association between time weighted MF exposure and demonstrated health effects. The World Health Organization (WHO) published its latest findings on this question in an Electromagnetic Fields and Public Health fact sheet, June 2007) <http://www.who.int/peh-emf/publications/facts/fs322/en/index.html> The fact sheet is based on a review by a WHO Task Group of scientific experts who assessed risks associated with ELF-EMF. As part of this review, the group examined studies related to MF exposure and various health effects, including childhood cancers, cancers in adults, developmental disorders, and neurobehavioral effects, among others. Particular attention was paid to leukemia in children. The Task Group concluded "that scientific evidence supporting an association between ELF magnetic field exposure and all of these health effects is much weaker than for childhood leukemia". (WHO, 2007) For childhood leukemia, WHO concluded recent studies do not alter the existing position taken by the International Agency for Research on Cancer (IARC) in 2002, that ELF-MF is "possibly carcinogenic to humans."

Some epidemiology studies have reported an association between MF and childhood leukemia, while others have not. Two broad statistical analyses of these studies reported an association with estimated average exposures greater than 3 to 4 mG, but at this level of generalization it is difficult to determine whether the association is significant. In 2005, the National Cancer Institute (NCI) stated, "Among more recent studies, findings have been mixed. Some have found an association; others have not Currently, researchers conclude that there is limited evidence that magnetic fields from power lines cause childhood leukemia, and that there is inadequate evidence that these magnetic fields cause other cancers in children." The NCI stated further: "Animal studies have not found that magnetic field exposure is associated with increased risk of cancer. The absence of animal data supporting carcinogenicity makes it biologically less likely that magnetic field exposures in humans, at home or at work, are linked to increased cancer risk."

The National Institute of Environmental Health Sciences (NIEHS) concluded in 1999 that EMF exposure could not be recognized as "*entirely safe*" due to some statistical evidence of a link with childhood leukemia. Thus, although no public health agency has found that scientific research suggests a causal relationship between EMF and cancer, the NIEHS encourages "inexpensive and safe reductions in exposure" and "suggests that the power industry continue its current practice of siting power lines to reduce exposures" rather than adopting strict regulatory guidelines (NIEHS, 1999, pp. 37-38). In 2002 NIEHS restated that while this evidence was "weak" it was "still sufficient to warrant limited concern" and recommended "continued education on ways of reducing exposures" (NIEHS, 2002, p. 14).

Reviews by other study groups, including IARC (2002), the Australian Radiation Protection and Nuclear Safety Agency (ARPANSA) (2003), the British National Radiation Protection Board (NRPB) (2004a), and the Health Council of the Netherlands ELF Electromagnetic Fields Committee (2005), are similar to NIEHS and NCI in their uncertainty about reported associations of MF with childhood leukemia. In 2004, the view of the NRPB was:

"[T]he epidemiological evidence that time-weighted average exposure to power frequency magnetic fields above 0.4 microtesla [4 mG] is associated with a small absolute raised risk of leukemia in children is, at present, an observation for which there is no sound scientific explanation. There is no clear evidence of a carcinogenic effect of ELF EMFS in adults and no plausible biological explanation of the association can be obtained from experiments with animals or from cellular and molecular studies. Alternative explanations for this epidemiological association are possible. Thus: any judgments developed on the assumption that the association is causal would be subject to a very high level of uncertainty." (NRPB, 2004a, p. 15)

Although IARC classified MF as "possibly carcinogenic to humans" based upon pooling of the results from several epidemiologic studies, IARC further stated that the evidence suggesting an association between childhood leukemia and residential MF levels is "limited," with "inadequate" support for a relation to any other cancers. The WHO Task Group concluded "the evidence related to childhood leukemia is not strong enough to be considered causal" (WHO, 2007).

The Connecticut Department of Public Health (DPH) has produced an EMF Health Concerns Fact Sheet (May 2007) that incorporates the conclusions of national and international health panels. The fact sheet states that while "the current scientific evidence provides no definitive answers as to whether EMF exposure can increase health risks, there is enough uncertainty that some people may want to reduce their exposure to EMF."

http://www.ct.gov/dphlib/dph/environmental_health/eoha/pdf/emf_fact_sheet_-_2008.pdf

In the U.S., there are no state or federal exposure standards for 60-Hz MF based on demonstrated health effects. Nor are there any such standards world-wide. Among those international agencies that provide guidelines for acceptable MF exposure to the general public, the International Commission on Non-Ionizing Radiation Protection (ICNIRP) established a level of 833 mG, based on an extrapolation from experiments involving transient neural stimulation by MF at much higher exposures. Using a similar approach, the International Committee on Electromagnetic Safety (ICES) calculated a guideline of 9,040 mG for exposure to workers and the general public (ICNIRP, 1998; ICES/IEEE, 2002). This situation reflects the lack of credible scientific evidence for a causal relationship between MF exposure and adverse health effects.

In November 2010, ICNIRP updated its guidelines. The new guideline establishes 2,000 mG as an acceptable exposure level for the general public replacing the previous 1998 exposure guideline of 833 mG. (See "ICNIRP Statement- Guidelines for Limiting Exposure to Time-Varying Electric and Magnetic Fields (1 Hz to 100 kHz). Health Physics 99(6):818-836; 2010"

<http://www.icnirp.org/documents/LFgdl.pdf> and "Fact Sheet on the Guidelines for Limiting Exposure to Time-Varying Electric and Magnetic Fields (1 Hz to 100 kHz) Published in Health Physics 99(6):818-836;2010" <http://www.icnirp.org/documents/FactSheetLF.pdf> at www.icnirp.org.)

III. Policy of the Connecticut Siting Council

The Council recognizes that a causal link between power-line MF exposure and demonstrated health effects has not been established, even after much scientific investigation in the U.S. and abroad. Furthermore, the Council recognizes that timely additional research is unlikely to prove the safety of power-line MF to the satisfaction of all. Therefore, the Council will continue its cautious approach to transmission line siting that has guided its Best Management Practices since 1993. This continuing policy is based on the Council's recognition of and agreement with conclusions shared by a wide range of public health consensus groups, and also, in part, on a 2006 review which the Council commissioned as to the weight of scientific evidence regarding possible links between power-line MF and adverse health effects¹.

Under this policy, the Council will continue to advocate the use of effective no-cost and low-cost technologies and management techniques on a project-specific basis to reduce MF exposure to the public while allowing for the development of efficient and cost-effective electrical transmission projects. This approach does not imply that MF exposure will be lowered to any specific threshold or exposure limit, nor does it imply MF mitigation will be achieved with no regard to cost

The Council has developed its precautionary guidelines in conjunction with Section 16-50p(i) of the Connecticut General Statutes, enacted by the General Assembly to call special attention to their concern for children. Subject to technological feasibility, the Act restricts the siting of overhead 345-kV transmission lines in areas where children congregate. These restrictions cover transmission lines adjacent to "residential areas, public or private schools, licensed child day-care facilities, licensed youth camps, or public playgrounds."

Developing Policy Guidelines

One important way the Council seeks to update its Best Management Practices is to integrate policy with specific project development guidelines. In this effort, the Council has reviewed the actions of other states. Most states either have no specific guidelines or have established arbitrary MF levels at the edge of a right-of-way that are not based on any demonstrated health effects. California, however, established a no-cost/low-cost precautionary-based EMF policy in 1993 that was re-affirmed by the California Public Utilities Commission in 2006. California's policy aims to provide significant MF reductions at no cost or low cost, a precautionary approach consistent with the one Connecticut has itself taken since 1993, consistent with the conclusions of the major scientific reviews, and consistent with the policy recommendations of the Connecticut Department of Public Health and the WHO. Moreover, California specifies certain benchmarks integral to its policy. The benchmark for "low-cost/no-cost" is an increase in aggregate project costs of zero to four %. The benchmark for "significant MF reduction" is an MF reduction of at least 15 %. With a policy similar to Connecticut's, and concrete benchmarks as well, California offers the Council a useful model in developing policy guidelines.

¹ Current Status of Scientific Research, Consensus, and Regulation Regarding Potential Health Effects of Power-Line Electric and Magnetic Fields (EMF) http://www.ctgov/csc/lib/csc/emf_bmp/emf_report.pdf

No-Cost/Low-Cost MF Mitigation

The Council seeks to continue its precautionary policy, in place since 1993, while establishing a standard method to allocate funds for MF mitigation methods. The Council recognizes California's cost allotment strategy as an effective method to achieve MF reduction goals; thus, the Council will follow a similar strategy for no-cost/low-cost MF mitigation.

The Council directs the Applicant to initially develop a baseline Field Management Design Plan that depicts the proposed transmission line project designed according to standard good utility practice and incorporating "no-cost" MF mitigation design features. The Applicant shall then modify this base design by adding low-cost MF mitigation design features specifically where portions of the project are adjacent to residential areas, public or private schools, licensed child day-care facilities, licensed youth camps, or public playgrounds. The overall cost of low-cost design features are to be calculated at four % of the initial Field Management Design Plan, including related substations. The best estimates of total project costs that are worked out during the Council proceedings should be employed, with the amounts proposed to be incurred for MF mitigation excluded. It is important to note that the four % guideline is not an absolute cap, because the

Council does not want to eliminate prematurely a potential measure that might be available and effective but would cost more than the four %, or exclude arbitrarily an area adjacent to the ROW that might be suitable for MF mitigation. Nor is the four % an absolute threshold, since the Council wants to encourage the utilities to seek effective field reduction measures costing less than four %. In general, the Council recognizes that projects can vary widely in the extent of their impacts on statutory facilities, necessitating some variance above and below the four % figure.

The four % guideline for low-cost mitigation should aim at a magnetic field reduction of 15 % or more at the edge of the utility's ROW. This 15 % reduction should relate specifically to those portions of the project where the expenditures would be made. While experience with transmission projects in Connecticut since 1993 has shown that no-cost/low-cost designs can and do achieve reductions in MF on the order of 15 %, the 15 % guideline is no more absolute than the four % one, nor must the two guidelines be correlated by rote. The nature of guidelines is to be constructive, rather than absolute.

The Council will consider minor increases above the four % guideline if justified by unique circumstances, but not as a matter of routine. Any cost increases above the four % guideline should result in mitigation comparably above 15 %, and the total costs should still remain relatively low.

Undergrounding transmission lines puts MF issues out of sight, but it should not necessarily put them out of mind. After all, soils and other fill materials do not shield MF; rather, MF is reduced by the underground cable design (refer to page 9 for further information). However, special circumstances may warrant some additional cost in order to achieve further MF mitigation for underground lines. The utilities are encouraged, prior to submitting their application to the Council, to determine whether a project involves such special circumstances. Note that the extra costs of undergrounding done for purposes other than MF mitigation should be counted in the base project cost and not as part of the four % mitigation spending.

Additionally, the Council notes two general policies it follows in updating its EMF Best Management Practices and conducting other matters within its jurisdiction. One is a policy to support and monitor ongoing study. Accordingly, the Council, during the public hearing process for new transmission line projects, will consider and review evidence of any new developments in scientific research addressing MF and public health effects or changes in scientific consensus group positions

regarding MF. The second Council policy is to encourage public participation and education. The Council will continue to conduct public hearings open to all, update its website to contain the latest information regarding MF health effect research, and revise these Best Management Practices to take account of new developments in MF health effect research or in methods for achieving no-cost/low-cost MF mitigation.

During its review of two recent transmission-line projects-Docket No. 424, approved December 27, 2012 and Docket No. 435, approved September 5, 2013-the Council pursued its policy of monitoring research on EMF.

In Council Docket No. 424 the document titled, "*Current Status of Research on Extremely Low Frequency Electric and Magnetic Fields and Health: Interstate Reliability Project, June 10, 2011*" was centered around the WHO 2007 report examining reports or scientific statements regarding the potential health effects of ELF-EMF over the past previous five years. In Council Docket No. 435 the document titled, "*Update of Research on Extremely Low Frequency Electric and Magnetic Fields and Health May 1, 2011- July 31, 2012 Stamford Reliability Cable Project August 30, 2012*" provides a bibliography of peer-reviewed national and international research and reviews. In general, the conclusions of these two documents are consistent with the scientific consensus articulated by the WHO and other scientific organizations and have not found any *consistent* associations with regard to ELF EMF exposure and any type of cancer or disease, except childhood leukemia, nor have they concluded that there is a cause-and-effect link with any health effect, including childhood leukemia.

Applying its policy of encouraging public participation and education the Council will continue to require that notices of proposed overhead transmission lines provided in utility bill enclosures pursuant to Conn. Gen. Stats. §16-50(b) state the proposed line will meet the Council's Electric and Magnetic Fields Best Management Practices, specifying the design elements planned to reduce magnetic fields. The bill enclosure notice will inform residents how to obtain siting and MF information specific to the proposed line at the Council's website; this information will also be available at each respective town hall. Phone numbers for follow-up information will be made available, including those of DPH and utility representatives. The project's final post-construction structure and conductor specifications, including calculated MF levels, shall also be available at the Council's website and each respective town hall.

Finally, we note that Congress has directed the Department of Energy (DOE) periodically to assess congestion along critical transmission paths or corridors and apply special designation to the most significant ones. Additionally, Congress has given the Federal Regulatory Commission supplemental siting authority in DOE-designated areas. This means the Council must complete all matters in an expeditious and timely manner. Accordingly, the cooperation of all parties will be of particular importance in fulfilling the policies set forth above.

IV. MF Best Management Practices: Further Management Considerations

The Council's EMF Best Management Practices will apply to the construction of new electric transmission lines in the State, and to modifications of existing lines that require a certificate of environmental compatibility and public need. These practices are intended for use by public service utilities and the Council when considering the installation of such new or modified electric transmission lines. The practices are based on the established Council policy of reducing MF levels at the edge of a right-of-way (ROW), and in areas of particular interest, with no-cost/low-cost designs that do not compromise system reliability or worker safety, or environmental and aesthetic project goals.

Several practical engineering approaches are currently available for reducing MF, and more may be developed as technology advances. In proposing any particular methods of MF mitigation for a given project, the Applicant shall provide a detailed rationale to the Council that supports the proposed MF mitigation measures. The Council has the option to retain a consultant to confirm that the Field Management Design Plan and the proposed MF reduction strategies are consistent with these EMF Best Management Practices.

A. MF Calculations

When preparing a transmission line project, an applicant shall provide design alternatives and calculations of MF for pre-project and post-project conditions, under 1) peak load conditions at the time of the application filing, and 2) projected seasonal maximum 24-hour average current load on the line anticipated within five years after the line is placed into operation. This will allow for an evaluation of how MF levels differ between alternative power line configurations. The intent of requiring various design options is to achieve reduced MF levels when possible through practical design changes. The selection of a specific design will also be affected by other practical factors, such as the cost, system reliability, aesthetics, and environmental quality.

MF *values* shall be calculated from the ROW centerline out to a distance of 300 feet on each side of the centerline, at intervals of 25 feet, including at the edge of the ROW. In accordance with industry practice, the calculation shall be done at the location of maximum line sag (typically mid-span), and shall provide MF *values* at 1 meter *above ground level*, with the assumption of flat terrain and balanced currents. The calculations shall assume "all lines in" and projected load growth *five years* beyond the time the lines are expected to be put into operation, and shall include changes to the electric system approved by the Council and the Independent System Operator- New England.

As part of this determination, the applicant shall provide the locations of, and anticipated MF *levels* encompassing, residential areas, private or public schools, licensed child day care facilities, licensed youth camps, or public playgrounds within 300 feet of the proposed transmission line. The Council, at its discretion, may order the field measurement of post-construction MF values in select areas, as appropriate, and compare and contrast projected *values* with actual measured *values*.

B. Buffer Zones and limits on MF

As enacted by the General Assembly in Section 4 of Public Act No. 04-246, a buffer zone in the context of transmission line siting is deemed, at minimum, to be the distance between the proposed transmission line and the edge of the utility ROW. Buffer zone distances may also be guided by the standards presented in the National Electrical Safety Code (NESC), published by the Institute of Electrical and Electronic Engineers (IEEE). These standards provide for the safe installation, operation, and maintenance of electrical utility lines, including clearance requirements from vegetation, buildings, and other natural and man-made objects that may arise in the ROW. The safety of power-line workers and the general public are considered in the NESC standards. None of these standards include MF limits.

In assessing whether a right-of-way provides a sufficient "buffer zone," the Council will emphasize compliance with its own Best Management Practices, but may also take into account approaches of other states, such as those of Massachusetts, New York, and Florida.

Since 1985, the Massachusetts Energy Facilities Siting Board (EFSB) has used an edge-of-ROW *level* of 85 mG as a benchmark for comparing different design alternatives. This benchmark, however, has not served as a generally applicable standard or guide. Rather, in particular cases since 1985 where a proposed transmission line has caused public concern, such as in densely populated areas and near schools, EFSB has "encouraged the use of practical and cost-effective design to minimize magnetic fields along transmission ROW. The EFSB requires EMF mitigation which in its judgment is consistent with minimizing cost" (Massachusetts Energy and Environmental Affairs Case No. EFSB 08-2/08-105/08-106:page 84) This approach is similar to Connecticut's.

Massachusetts has not adopted any generally applicable standards or guidelines concerning transmission facility magnetic fields. However, since 1985, the EFSB has considered projected magnetic field exposures in its proceedings for approval of electric transmission lines and substations. Where a transmission line is proposed in densely populated areas and near schools, the EFSB will "require EMF mitigation which in its judgment is consistent with minimizing cost."

New York and Florida have general MF guidelines that are designed to maintain the "status quo", i.e., that fields from new transmission lines not exceed those of existing transmission lines. In 1991, the New York Public Service Commission established an interim policy based on limits to MF. It required new high-voltage transmission lines to be designed so that the maximum magnetic fields at the edge of the ROW, one meter above ground, would not exceed 200 mG if the line were to operate at its highest continuous current rating. This 200 mG *level* represents the maximum calculated magnetic field level for 345 kV lines that were then in operation in New York State. The Council confirms no change to the New York policy.

The Florida Environmental Regulation Commission established a maximum magnetic field limit for new transmission lines and substations in 1989. The MF limits established for the edge of 230-kV to 500-kV transmission line ROWs and the property boundaries for substations ranged from 150 mG to 250 mG, depending on the voltage of the new transmission line and whether an existing 500-kV line was already present. In 2008, the Florida policy was revised to add a provision making the 250 mG magnetic field limit at the edge of the ROW and at substation property boundaries applicable to transmission lines and substations with a nominal voltage greater than 500-kV. Florida limits apply to one meter above ground level under an assumption that the transmission line is operating at its maximum continuous current rating.

Although scientific evidence to date does not warrant the establishment of MF exposure limits at the edge of a ROW, the Council will continue to monitor the ways in which states and other jurisdictions determine MF limits on new transmission lines.

C. Engineering Controls that Modify MF Level

When considering an overhead electric transmission-line application, the Council will expect the applicant to examine the following engineering controls to limit MF in publicly accessible areas: distance, height, conductor separation, conductor configuration, optimum phasing, increased voltage, and underground installation. Any design change may also affect the line's impedance, corona discharge, mechanical behavior, system performance, cost, noise levels and visual impact. The Council will consider all of these factors in relation to the MF levels achieved by any particular engineering control. Thus, utilities are encouraged to evaluate other possible engineering controls that might be applied to the entire line, or just specific segments, depending upon land use, to best minimize MF at a low or no cost.

Consistent with these Best Management Practices and absent any line performance and visual impacts, the Council expects that applicants will propose no-cost/low-cost measures to reduce magnetic fields by one or more engineering controls, including:

Distance

MF levels from transmission lines (or any electrical source) decrease with distance; thus, increased distance results in lower MF. Horizontal distances can be increased by purchasing wider ROWs, where available. Other distances can be increased in a variety of ways, as described below.

Height of Support Structures

Increasing the vertical distance between the conductors and the edge of the ROW will decrease MF; this can be done by increasing the height of the support structures. The main drawbacks of this approach are an increase in the cost of supporting structures, possible environmental effects from larger foundations, potential detrimental visual effects, and the modest MF reductions achieved, unless the ROW width is unusually narrow.

Conductor Separation

Decreasing the distances between individual phase conductors can reduce MF. Because at any instant in time the sum of the currents in the individual phase conductors is zero, or close to zero, moving the conductors closer together improves their partial cancellation of each other's MF. In other words, the net MF produced by the closer conductors reduces the MF level associated with the line. Placing the conductors closer together has practical limits, however. The distance between the conductors must be sufficient to maintain adequate electric code clearance at all times, and to assure utility employees' safety when working on energized lines. One drawback of a close conductor installation is the need for more support structures per mile (to reduce conductor sway in the wind and sag at mid-span); in turn, costs increase, and so do visual impacts.

Conductor Configuration

The arrangement of conductors influences MF. Conductors arranged in a flat, horizontal pattern at standard clearances generally have greater MF levels than conductors arranged vertically. This is due to the wider spacing between conductors found typically on H-frame structure designs, and to the closer distance between all three conductors and the ground. For single-circuit lines, a compact triangular configuration, called a "delta configuration", generally offers the lowest MF levels. A simple vertical configuration -one conductor above another-may cost more and may have increased visual impact. Where the design goal is to minimize MF levels at a specific location within or beyond the ROW, conductor configurations other than vertical or delta may produce equivalent or lower fields.

Optimum Phasing

Optimum phasing applies in situations where more than one circuit exists in an overhead ROW or in a duct bank installed underground. Electric transmission circuits utilize a three-phase system with each phase carried by one conductor, or a bundle of conductors. Optimum phasing reduces MF through partial cancellation. For a ROW with more than two circuits, the phasing arrangement of the conductors of each circuit can generally be optimized to reduce MF levels under typical conditions. The amount of MF cancellation will also vary depending upon the relative loading of each circuit. For

transmission lines on the same ROW, optimizing the phasing of the new line with respect to that of existing lines is usually a low-cost method of reducing MF. MF levels can be reduced for a single circuit line by constructing it as a "split-phase" line with twice as many conductors, and arranging the conductors for optimum cancellation. Disadvantages of the split-phase design include higher cost and increased visual impact.

Increased Voltage

MF are proportional to current, so, for example, replacing a 69-kV line with a 138-kV line, which delivers the same power at half the current, will result in lower MF. This could be an expensive mitigation to address MF alone because it would require the replacement of transformers and substation equipment.

Underground Installation

Burying transmission lines in the earth does not, by itself, provide a shield against MF, since magnetic fields, unlike electric fields, can pass through soil. Instead, certain inherent features of an underground design can reduce MF. The closer proximity of the currents in the wires provides some cancellation of MF, but does not eliminate it entirely. Underground transmission lines are typically three to five feet below ground, a near distance to anyone passing above them, and MF can be quite high directly over the line. MF on either side of an underground line, however, decreases more rapidly with increased distance than the MF from an overhead line.

The greatest reduction in MF can be achieved by "pipe-type" cable installation. This type of cable has all of the wires installed inside a steel pipe, with a pressurized dielectric fluid inside for electrical insulation and cooling. Low MF is achieved through close proximity of the wires, as described above, and through partial shielding provided by the surrounding steel pipe. While this method to reduce MF is effective, system reliability and the environment can be put at risk if the cable is breached and fluid is released.

Lengthy high-voltage underground transmission lines can be problematic due to the operational limits posed by the inherent design. They also can have significantly greater environmental impacts, although visual impacts associated with overhead lines are eliminated. The Council recognizes the operational and reliability concerns associated with current underground technologies and further understands that engineering research regarding the efficiency of operating underground transmission lines is ongoing. Thus, in any new application, the Council may require updates on the feasibility and reliability of the latest technological developments in underground transmission line design.

V. Bibliography

Australian Radiation Protection and Nuclear Safety Agency (ARPNSA). Electricity and Health Fact Sheet web page updated April 5, 2013.

http://www.arpansa.gov.au/radiationprotection/Factsheets/is_electricity.cfm (accessed 12/19/13)

Bennett, Jr., W., Health and Low Frequency Electromagnetic Fields, Yale University Press, 1994. British National Radiation Protection Board (NRPB) (now Health Protection Agency or HPA).

2004a. Advice on Limiting Exposure to Electromagnetic Fields (0-300 GHz). Documents of the NRPB. 15(2)

<http://www.hpa.org.uk/Publications/Radiation/NRPBArchive/DocumentsOITheNRPB/Absd1502/> (accessed 12/16/13)

British National Radiation Protection Board (NRPB) (now Health Protection Agency or HPA).

2004b. Review of the Scientific Evidence for Limiting Exposure to (0 to 300 GHz) Electromagnetic Fields. Documents of the NRPB. 15(3)

<http://www.hpa.org.uk/Publications/Radiation/NRPBArchive/DocumentsOITheNRPB/Absd1503/> (accessed 12/16/13)

California Public Utilities Commission. Order Instituting Investigation on the Commission's Own Motion to Develop Policies and Procedures for Addressing the Potential Health Effects of Electric and Magnetic Fields of Utility Facilities. Decision No. 93-11-013, Investigation No. 91-01-012 (Filed January 15, 1991). November 2, 1993. San Francisco, CA.

California Public Utilities Commission. Order Instituting Rulemaking to update the Commission's policies and procedures related to electromagnetic fields emanating from regulated utility facilities.

Decision 06-01-042 (Filed August 19, 2004). January 26, 2006. San Francisco, CA.

http://www.cpuc.ca.gov/PUBLISHED/FINAL_DECISION/53181.htm. (accessed 12/16/13)

California Public Utilities Commission. EMF Design Guidelines for Electrical Facilities. July 21, 2006.

<ftp://ftp.cpuc.ca.gov/puc/energy/environmentelectromagnetic+fields/california+guidelines+for+electrical+facilities+072106+published.pdf> (accessed 12/16/13)

Commonwealth Associates, Inc. and liT Research Institute, Electric and Magnetic Fields (EMF) RAPID Program Engineering Project 8 FINAL REPORT, Evaluation of Field Reduction Technologies, Volume 1 (Report) and Volume 2 (Appendices), 1997.

Connecticut Department of Public Health (DPH). 2004. EMF Health Concerns Fact Sheet.

http://www.ct.gov/dph/lib/dph/environmental_health/eoha/pdf/emf_fact_sheet_-_2008.pdf (accessed 12/16/13)

Exponent Inc. January 10, 2011. Current Status of Research on Extremely Low Frequency Electric and Magnetic Fields and Health: Interstate Reliability Project

http://www.ct.gov/csc/lib/csc/pendingproceeds/docket_424/424_application/v1interstate_application_v1.pdf (Appendix D EMF Health Report) (accessed 12/16/13)

Exponent Inc. August 30, 2012. Update of Research on Extremely Low Frequency Electric and Magnetic Fields and Health May 1, 2011 - July 31, 2012 Stamford Reliability Cable Project

http://www.ct.gov/csc/lib/csc/pendingproceeds/docket_435/app_d_emf_supporting_documentation.Qqf (accessed 12/16/13)

Institute of Electrical and Electronics Engineers (IEEE). 2002. C95.6-2002 IEEE Standard for Safety Levels with Respect to Human Exposure to Electromagnetic Fields, 0-3 kHz, Prepared by Subcommittee 3, Safety Levels with Respect to Human Exposure ISBN 0-7381-3389-2, 2002.

Institute of Electrical and Electronics Engineers (IEEE). 2002. C2-2002 National Electric Safety Code, American National Standards Institute, 2002.

International Committee on Electromagnetic Safety (ICES) / International Agency for Research on Cancer (IARC). 2002. Static and Extremely Low-Frequency Electric and Magnetic Fields: <http://monographs.iarc.fr/ENG/Monographs/vol80/mono80.pdf> (accessed 12/16/13)

International Commission on Non-Ionizing Radiation Protection (ICNIRP). 1998. Guidelines for Limiting Exposure to Time-Varying Electric, Magnetic, and Electromagnetic Fields (Up to 300 GHz). <http://www.icnirp.org/documents/LFgdl.pdf> (accessed 12/16/13)

Johnson, G.B., Power Research Engineering, Field Management Technologies, EMF Engineering Symposium, 1998.

Minnesota State Interagency Working Group on EMF Issues, A White Paper of Electric and Magnetic Field (EMF) Policy and Mitigation Options, 2002.

National Cancer Institute. Magnetic Field Exposures and Cancer: Questions and Answers. April 21, 2005. <http://www.cancer.gov/cancertopics/factsheet/Risk/magnetic-fields> (accessed 12/16/13)

National Institute of Environmental Health Sciences. 2002. EMF Questions and Answers. EMF RAPID Program. http://www.niehs.nih.gov/health/materials/electric_and_magnetic_fields_associated_with_the_use_of_electric_power_questions_and_answers_english_508.pdf#search-%20emf%20rapid%20report (accessed 12/19/13)

National Institute of Environmental Health Sciences, Report on Health Effects from Exposure to Power-Line Frequency Electric and Magnetic Fields, 1999.

National Research Council. 1999. Research on Power Frequency Fields Completed Under the Energy Policy Act of 1992. <http://www.nap.edu/catalog/9587.html> (accessed 12/16/13)

Public Service Commission of Wisconsin. May 2013. EMF – Electric and Magnetic Fields Brochure. <http://psc.wi.gov/thelibrary/publications/electric/Electric12.pdf> (accessed 12/19/13)

United States Geological Survey
<http://geomag.usgs.gov/learn/introtogeomag.php> (accessed 12/19/13)

World Health Organization (2007) Fact Sheet N322, Electromagnetic Fields and Public Health, Exposure to extremely low frequency fields. <http://www.who.int/peh-emf/publications/facts/fs322/en/index.html> (accessed 12/19/13)

8. PROPOSED PROJECT SCHEDULE

Figure 8-1 illustrates the key activities in Eversource’s proposed schedule for developing the Frost Bridge to Campville Project. As indicated on the schedule, Eversource would submit the siting application the 4th quarter of 2015 after completing the MCF process. The schedule in Figure 8-1 does not list the planning activities that Eversource performed on the Project prior to the submittal of the MCF, but rather focuses on the future Project timeline.

Figure 8-1: Frost Bridge to Campville Project – Estimated Timeline

	Q3 '15	Q4 '15	Q1 '16	Q2 '16	Q3 '16	Q4 '16	Q1 '17	Q2 '17	Q3 '17	Q4 '17	2018
Municipal Consultation Filing Issued to Towns											
Public Open House Period											
Siting Application Filed with the CT Siting Council (CSC)											
CSC Hearing and Decision (12 months)											
CSC Decision											
Development & Management (D&M) Plans											
State & Federal Permitting											
Construction											
Project Outreach											

*Note that the construction timeline refers to the installation of the new 115-kV transmission lines and substation modifications, and does not necessarily include the completion of all ROW restoration and post-installation monitoring activities.

Note: This page intentionally left blank.

9. PERMITS, APPROVALS, AND CONSULTATIONS

As part of the Project planning process, Eversource initiated consultations with representatives of the towns that would be traversed by the proposed new 115-kV transmission line along the Proposed Route, as well as with representatives of the federal and state regulatory agencies from whom approvals for the Project would be required. Eversource will continue such proactive consultations as the planning for and review of the Project proceeds. This section identifies the permits and approvals that would be required for the construction and operation of the Project, and summarizes the federal and state agency and municipal consultations that Eversource has conducted to date.

9.1 AGENCY PERMITS AND APPROVALS REQUIRED FOR THE PROJECT

In addition to a Certificate of Environmental Compatibility and Public Need from the Council, the Project will require permits and approvals from other Connecticut and federal agencies. At the federal level, the Project must comply with the Clean Water Act (CWA), the Endangered Species Act and the National Historic Preservation Act. At the state level, along with compliance with the Council's requirements, Eversource will have to obtain Project-specific permits or approvals pertaining to water quality (pursuant to Section 401 of the CWA), stormwater management, threatened and endangered species, and cultural resources. Additional state approvals may be required, depending on the final design of the Project.

Table 9-1 summarizes the federal and state permits and approvals expected to be required for the proposed Project. This summary is based on currently available data concerning the Project, and may be modified as the Project planning, design, and review process moves forward.

Table 9-1: Potential Permits, Reviews, and Approvals Required for the Project

Agency	Certificate, Permit, Review, Approval or Confirmation	Activity Regulated
FEDERAL		
U.S. Army Corps of Engineers (USACE), New England District	Section 404 CWA	Discharge of dredge or fill material into waters of the U.S. (wetlands or watercourses)
U.S. Fish and Wildlife Service	Coordinates with USACE regarding endangered or threatened species (non-marine); provides input to USACE permit application review	Construction or operation activities that may affect federally-listed endangered or threatened species
U.S. Environmental Protection Agency	Provides input to USACE permit application review	Construction or operation activities that may affect water, air, or other resources
U.S. Department of the Interior, National Park Service	Provides input to USACE permit application review	Input regarding Naugatuck River greenway, which extends across USACE property
Advisory Council on Historic Preservation	Involved if significant cultural resource sites would be potentially affected by the Project	Section 106 National Historic Preservation Act compliance; input to USACE permit review, if applicable
CONNECTICUT		
Connecticut Siting Council	Certificate of Environmental Compatibility and Public Need Development & Management Plan approval prior to construction	General transmission line need, siting, construction, environmental compatibility, safety, maintenance, and ROW management procedures
Department of Energy and Environmental Protection (CT DEEP)	401 Water Quality Certification	Conformance to Section 401 of the CWA; Section 401 approval from CTDEEP is required prior to USACE permit issuance
	Water Discharge General Permit	Stormwater management during construction
	Water Diversion Permit	Installation of permanent culverts across streams with a watershed of 100 acres or more
	Threatened, Endangered, and Special Concern Species	Approval of species-specific mitigation plans as part of Council's process, 401 Water Quality Certification approval
CT DEEP Public Utilities Regulatory Authority	Approval pursuant to C.G.S. Section 16-243	Method & Manner of Construction Approval to Energize Lines
State Historic Preservation Office (SHPO) ⁸⁵	Approval of proposed Project consistency with the National Historic Preservation Act; comments during Council and USACE processes	Construction and operation activities that may affect archaeological or historic resources.
Connecticut Department of Transportation (ConnDOT)	Encroachment permit	Transmission line crossing of state highways

⁸⁵ The SHPO is part of the Connecticut Commission on Culture and Tourism, Historic Preservation and Museum Division.

9.2 FEDERAL AND STATE AGENCY CONSULTATIONS

In conjunction with the overall Project planning, Eversource initiated consultations with the federal and state agencies likely to be involved in the review or approval of the new 115-kV transmission line and related substation modifications. The purpose of these initial consultations was to provide the agencies with preliminary information regarding the proposed Project, and to solicit baseline information concerning the Project area or input concerning potential Project-related issues. Table 9-2 summarizes the federal and state agency consultations conducted to date.

Table 9-2: List of Federal and State Agency Consultations to Date

AGENCY	DATE	AGENCY CONTACT
FEDERAL		
USACE, New England District	7/20/2015	Susan Lee
U.S. Department of Interior - Fish & Wildlife Service	7/30/2015	Jenny Dickson (CT DEEP)
National Park Service	8/17/2015	John Monroe
CONNECTICUT		
CT DEEP – Mattatuck State Forest / Black Rock State Park	8/11/2015	Tammy Talbot
CT DEEP – Natural Diversity Database	5/14/2015	Dawn M. McKay
	5/19/2015	Jenny Dickson
	7/30/2015	Laura Saucier
SHPO	8/18/2015	Cathy Labadia

9.3 MUNICIPAL, PUBLIC, AND OTHER CONSULTATIONS

In April of 2015, Eversource initiated consultations with public officials of the towns in which the Project would be located. The purpose of these consultations was to inform the public officials of the proposed Project and solicit their input about it. In addition, key state and federal elected officials, non-governmental environmental groups, and other stakeholders were or will be offered briefings and consulted regarding the proposed Project.

Property owners and abutters of the proposed new transmission line ROW will be notified about the proposed Project and offered briefings shortly after the submittal of the MCF. Open houses, which are expected to be held in the project area in late September or early October, will be scheduled to provide information to the public about the Project. This public outreach process conforms to the Council's MCF requirements. Eversource intends to continue this proactive outreach as the Project moves forward.

The overall objective of the municipal consultation process is to obtain input regarding the proposed Project from representatives of each of the towns potentially affected by the proposed transmission facilities, as well as from the interested public. In accordance with the Council's requirements, within 15 days of filing the Application for the Project, Eversource will provide to the Council a summary of the consultations with the towns, including any comments or recommendations issued by the municipalities, as well as copies of comments received from the public.

Table 9-3 summarizes the primary meetings that Eversource has held to date with municipal officials and state and federal officials.

Table 9-3: Meetings Held To-Date with Municipal Officials, State and Federal Officials, and Other Key Stakeholder Groups

Stakeholder Group	Date of Meeting	Purpose of Meeting
Municipal Officials		
Town of Watertown Town Manager Robert M. Scannell	April 7, 2015	Project Introduction
Town of Thomaston First Selectman Edmond V. Mone	April 8, 2015	Project Introduction
Town of Litchfield First Selectman Leo Paul	April 9, 2015	Project Introduction
Town of Harwinton First Selectman Michael R. Criss	April 8, 2015	Project Introduction
State and Federal Officials		
Congresswoman Elizabeth Esty 5th District	Weeks of April 13 and April 20, 2015	Project Introduction
Senator Chris Murphy	Weeks of April 13 and April 20, 2015	Project Introduction
Senator Richard Blumenthal	Weeks of April 13 and April 20, 2015	Project Introduction
State Senator Clark Chapin 30th District	Weeks of April 13 and April 20, 2015	Project Introduction
State Representative Craig Miner 66th District	Weeks of April 13 and April 20, 2015	Project Introduction
State Representative John Piscopo 76th District	Weeks of April 13 and April 20, 2015	Project Introduction
State Senator Henri Martin 31st District	Weeks of April 13 and April 20, 2015	Project Introduction
State Senator Kevin Witkos 8th District	Weeks of April 13 and April 20, 2015	Project Introduction
Representative Eric Berthel 68th District	Weeks of April 13 and April 20, 2015	Project Introduction
State Senator Robert Kane 32nd District	Weeks of April 13 and April 20, 2015	Project Introduction

Note: This page intentionally left blank.

10. SYSTEM ALTERNATIVES

This section complies with the provision in the Council’s Application Guide (April 2010) that requires an applicant to identify “system alternatives and the advantages and disadvantages of each.” First, in Section 10.1, a “No Action” alternative is briefly discussed. Next, in Section 10.2, transmission system alternatives are discussed. This section describes the process by which a preferred transmission solution for NWCT was developed as part of the GHCC studies. Finally, in Section 10.3, the evaluation of potential non-transmission system alternatives (NTAs) is discussed. NTAs include the addition of generation resources, often referred to as “supply-side” measures, and strategies to reduce load, often referred to as demand-side management or “DSM” measures.

10.1 NO ACTION ALTERNATIVE

Under the no-action alternative, no new transmission facilities would be developed and no improvements would be made to the existing electrical transmission system or to supply or demand resources in NWCT. This alternative was rejected because it would do nothing to correct violations of national and regional reliability standards and criteria; and thus the NWCT sub-area would continue to be at risk for electric outages and Eversource would be exposed to being fined by FERC for its failure to take action to resolve identified criteria violations. Failure to take action to bring the NWCT electric supply into conformity with applicable reliability standards and criteria would also undermine the long-range plan of ISO-NE and Eversource for providing reliable transmission service throughout Connecticut and neighboring states.

10.2 TRANSMISSION ALTERNATIVES

Transmission alternatives are improvements to the transmission system that would resolve reliability problems with different electrical configurations or technologies than those of the preferred solution. As part of the GHCC studies, an ISO-NE Working Group comprised of transmission planners from ISO-NE, Eversource Utilities Service Company, and The United Illuminating Company evaluated transmission alternatives in all of the sub-areas studied, including NWCT.

10.2.1 Process for Developing the NWCT Transmission Alternatives

Using their engineering judgment and knowledge of the Connecticut and New England transmission systems, the Working Group first identified potential transmission solutions and then conducted testing to evaluate their performance. The Working Group's approach to developing potential solutions was to look for ways to strengthen connections to the load pockets, which could be done by adding a new source into the pocket, by improving the elements that would remain in service after N-1-1 contingency events so that they could adequately handle the additional loading, or by eliminating the contingency condition causing the violations (such as by separating the circuits of a double circuit line.) All of the alternative solutions were first evaluated to ensure that the solution components resolved all the target criteria violations identified in the *GHCC Needs Report*. The next step was to compare the alternative solution components in terms of cost, constructability, environmental concerns, and other criteria.

The Working Group presented interim results of this evaluation to the ISO-NE Planning Advisory Committee (PAC) in March, 2014; and presented the preferred solution to the PAC in July, 2014. The PAC is composed of stakeholders, including generator owners, suppliers, load serving entities, energy efficiency entities, state regulators and transmission owners, who are given the opportunity to provide input throughout the study process. The *GHCC Solutions Report*, which explains and justifies the selection of the preferred solution, was published in February, 2015.

In the course of its work, the Working Group determined that the solutions for the several subareas within the greater GHCC area could be analyzed independently of one another, since the needs for the area were largely driven by load-serving issues following the loss of critical 115-kV sources into each subarea.

The potential transmission solutions were tested by simulations using assumptions and procedures consistent with those that had been applied to identify the reliability needs in the study area, with adjustments for changes in system resources and transmission topology that had occurred since the *GHCC Needs Assessment* had been completed. These changes are discussed in detail at pages 15-17 of the *GHCC Solutions Report*.

10.2.2 Transmission Alternatives Considered

Having determined that the best way to solve the violations in the NWCT sub-area was to provide a new 115 kV source into it, the Working Group considered what the effective terminal locations of such a line were likely to be. The terminal locations outside the NWCT subarea that were considered were the North


Bloomfield Substation (located to the east of the NWCT subarea in the Greater Hartford subarea) and Frost Bridge Substation (located in the SWCT subarea, just to the south of the NWCT subarea). Terminal locations within the NWCT sub-area that were considered were the Canton and Campville substations.

The potential new 115-kV transmission line connections initially considered were thus:

- North Bloomfield to Canton;
- North Bloomfield to Campville; and
- Frost Bridge to Campville.

Each of these transmission lines would have associated minor upgrades as well. The terminal points of the three lines initially considered are illustrated in Figure 10-1.

Figure 10.1: Alternative Terminations for a New Line into the NWCT Sub-area



10.2.3 Comparison of the Transmission Alternatives

The Working Group quickly dismissed the North Bloomfield to Campville transmission system alternative because of its much greater length, as compared to the North Bloomfield to Canton alternative (approximately 25 vs. 12.8 miles), made it far more expensive, with more environmental effects. The Working Group accordingly analyzed only the other two alternatives in detail, referring to the Frost Bridge to Campville system as Alternative A and the North Bloomfield to Canton system as Alternative B.

Using load flow simulations, the Working Group identified the full scope of the improvements that would be required for each alternative, as shown in Table 10-1:

Table 10-1: Northwestern Connecticut Subarea Solution Alternatives

Component ID	Description	Included in Alternative A	Included in Alternative B
1	Add a new 10.4-mile, 115-kV line from Frost Bridge to Campville and associated terminal equipment	Y	
2	Add a new 12.8-mile, 115-kV-line from North Bloomfield to Canton and associated terminal equipment		Y
3	Separation of 115-kV DCT corresponding to the Frost Bridge to Campville (1191) line and the Thomaston to Campville (1921) line and add a breaker at Campville 115-kV substation	Y	
4	Upgrade terminal equipment on the 115-kV line between Chippen Hill and Lake Avenue Junction (1810-3)	Y	Y
5	Reconductor the 115-kV line between Southington and Lake Avenue Junction (1810-1) – 5.2 miles		
6	Add a 25.2 MVAR capacitor at Campville Substation		Y

10.2.3.1 Comparative Performance

Both alternative solutions would resolve the thermal and voltage criteria violations in their respective study sub-areas, with the following exceptions, which will be separately addressed: (a) criteria violations related to the loss of certain distribution voltage transformers at substations in the sub-area, which Eversource will address separately with local upgrades; and (b) violations associated with the 69-kV system in NWCT, including the No. 690 line between the Smithfield Substation in Amenia, New York and the Salisbury Substation in Salisbury, Connecticut. These issues will be resolved separately by a joint effort of ISO-NE and the New York ISO.

The study results are discussed in detail in the *GHCC Solutions Study*. Although both alternatives would solve the same criteria violations, the voltage performance of the Frost Bridge to Campville line (Alternative A) was better than that of the North Bloomfield to Canton line (Alternative B) in that Alternative B required additional reactive support to be installed at Campville in order to boost voltages in the area under certain conditions.

10.2.3.2 Comparative Cost

The cost of Alternative B was determined to be much higher than that of Alternative A, the preferred alternative. The unique elements of Alternative A were estimated to cost approximately \$51 million in

2017 dollars, whereas the cost of the unique elements of Alternative B were estimated to cost approximately \$74 million. In addition, each alternative required common elements with an estimated cost of approximately \$12 million, thus making the overall cost comparison, approximately \$63 million for Alternative A and approximately \$86 million for Alternative B.

The elements common to both alternatives were those listed as Items (4) and (5) in Table 10-1 above. The comparison of the estimated costs of the unique elements was as shown in Table 10-2:

Table 10-2: Cost Estimates of Unique Components of NWCT Solution Components

ID	Solution Component	Cost (\$M)	Included in Alternative A	Included in Alternative B
1	Add a new 10.4-mile, 115 kV-line from Frost Bridge to Campville and associated terminal equipment	45.5	Y	
2	Add a new 12.8-mile, 115-kV line from North Bloomfield to Canton and associated terminal equipment	66.9		Y
3	Separation of 115-kV DCT corresponding to the Frost Bridge to Campville (1191) line and the Thomaston to Campville (1921) line and add a breaker at Campville 115-kV Substation	5.5	Y	
6	Add a 25.2 MVAR capacitor at Campville Substation	7.0		Y
Solution Alternative Totals (\$M)			51.0	73.9

This difference in cost was due to a number of factors, including Alternative B's more extensive and costly substation improvements and longer length. In addition, the Alternative B estimate included higher labor and material costs and a greater contingency allowance because the North Bloomfield to Canton ROW was estimated to include approximately 6 times more wetlands than the Frost Bridge to Campville ROW.

10.2.3.3 Comparative Environmental and Social Effects

Compared to the Frost Bridge to Campville transmission line, a new 115-kV transmission line between North Bloomfield and Canton would be approximately 24% (2.3 miles) longer; would extend through generally more densely populated areas; and would cross more wetlands. As a result, the North Bloomfield to Canton line would result in comparatively greater potential environmental and social impacts than the Frost Bridge to Campville line.

For example, the Frost Bridge to Campville ROW extends primarily through undeveloped or sparsely populated areas; only 55 residences are located within 300 feet of the centerline of the new transmission line route. In comparison, the centerline of the North Bloomfield to Canton 115-kV line would be within 300 feet of approximately 207 homes.

The North Bloomfield to Canton line ROW also would affect six times as many wetland resources as the Frost Bridge to Campville line. Assuming a 90-foot-wide ROW would be involved in the construction of the new 115-kV line along either route and based on a review of National Wetlands Inventory mapping, the North Bloomfield to Canton line would impact approximately 13 acres of wetlands, whereas the Frost Bridge to Campville line would affect approximately 2.2 acres of wetlands. Based on these significantly greater potential adverse effects on water resources, a new line along the North Bloomfield to Canton ROW would not be considered the least environmentally damaging practical alternative, pursuant to the Clean Water Act, and thus also would be difficult to permit, given the availability of the Frost Bridge to Campville alternative.

10.2.3.4 Conclusion

As compared to Alternative B, Alternative A would cost less, perform slightly better, and have fewer environmental and social impacts. Accordingly, Eversource has selected Alternative A as preferred and is proposing its major elements in this proceeding.

10.3 NON-TRANSMISSION ALTERNATIVES (NTA)

As part of its examination of electric system needs and solutions in the Greater Hartford, Manchester / Barbour Hill, Middletown, and NWCT subareas, ISO-NE conducted two studies to identify hypothetical solutions to the identified needs that would not require expansion of the regulated transmission system. Because these non-transmission solutions could, at least potentially, be implemented by participants in competitive markets, ISO-NE referred to them as “Market Resource Alternatives” (MRAs). Pursuant to the ISO-NE Open Access Transmission Tariff, transmission owners such as Eversource are obliged to pursue regulated transmission solutions to address system needs only where the needs are not addressed by market forces. The ISO-NE MRA studies served as a signal to private developers of a potential need for such market alternatives.

In the MRA studies, ISO-NE evaluated the effects of adding new demand side and supply side resources in the same way that it evaluated system needs and transmission solutions – by running power-flow simulations to determine if the target reliability criteria violations could be eliminated by the addition of the extra resources or reductions in load. After extensive studies and testing, ISO-NE presented to the PAC the results of two separate MRA studies, one of which considered exclusively demand-side alternatives, and the other supply-side alternatives. These studies identified MRAs for each of the four GHCC subareas.

The ISO-NE MRA analyses identified quantities of injections of power into the electrical system or load reductions that would be required at particular electrical locations in order to obviate the need for regulated transmission improvements. However, ISO-NE did not determine the types of resources and technology that could, in reality, provide such injections or reductions of demand at each location. Such a determination requires consideration of the suitability of the available technologies for the particular application, including performance characteristics, cost, land requirements and access to cooling water (if necessary), availability of fuel supplies, and other factors for developing and bringing to commercial operations a new demand reduction program or supply-side resource. The ISO-NE MRA studies also did not undertake to estimate the cost of the NTA solutions compared to the cost of the transmission solution.

Accordingly, Eversource engaged an expert consultant, London Economics International, LLC (LEI), to study of non-transmission alternatives to the preferred transmission solution for the NWCT sub-area identified in the GHCC *Solutions Report*, which includes the proposed transmission improvements that are the subject of this document. LEI is a consulting firm with expertise in analyses of the New England

power markets, including economic evaluations, simulation modeling, asset valuation, price forecasting, and market design.

Using the ISO MRA analyses as the point of departure for its investigations, LEI considered the potential technology that could deliver the requisite energy injections to satisfy the reliability needs of the local areas, the associated costs of the NTA technology, and practical feasibility of the least-cost NTA solution. The results of LEI's studies, as well as a detailed description of their analyses, are contained in a report (LEI Report), a copy of which is included in Volume 4.

As detailed in the LEI Report, the ISO-NE analyses showed that an NTA for the NWCT sub-area would require an injection of 48 MW of energy at Torrington Substation and 181 MW of energy at Campville Substation, or commensurate reductions in the loads served at these substations. Based on these ISO-NE analyses, LEI then examined what actual supply-side and demand-side resources would be capable of providing these injections or reductions and selected hypothetical, technically feasible NTA technologies for cost analysis. LEI considered technically "feasible" technologies to be those that would address the reliability need and could be hypothetically implemented based on planning criteria and technology-specific operating profiles.

As technically feasible NTA technologies at the Torrington and Campville substation locations, LEI identified peaker aeroderivative turbines (turbines modelled on turbojet fans), Combined Cycle Gas Turbines ("CCGT"), energy storage, fuel cells, and passive demand response (energy efficiency). Next, LEI assessed whether these technically feasible NTAs could be cost-effective or practical.

First, with the assistance of Eversource personnel responsible for energy efficiency programs, LEI identified the maximum incremental demand response that could likely be implemented at each of the two substation locations, in addition to what is currently planned to be implemented pursuant to the ISO-NE Forward Capacity Market, and above and beyond what is forecast by ISO-NE to occur on the basis of current utility programs for DSM and energy efficiency. Given the projected net load at each substation, the maximum likely achievable incremental demand response was modest – 10 MW at Campville Substation and 2 MW at Torrington Substation. Taking into consideration this incremental demand response, LEI then employed industry-standard levelized costing principles to select from the group of technically feasible NTA technologies, components to supply the large remaining balance of the requirements for each substation (i.e., 171 MW at Campville and 46 MW at Torrington).

Based on operational factors and the balance of the requirements for each substation, LEI concluded that the best solution would be to construct a 180 MW combined-cycle natural gas fueled turbine generator (CCGT) at Campville and 54 MW of aeroderivative peaking generation units at Torrington. Table 10-3 summarizes the total requirements and technically feasible NTA technologies, by substation.

Table 10-3: List of qualified technologies and requirements for each substation

Substations	Torrington	Campville
Requirements at substation (MW)	48	181
NTA Technologies		
Energy Efficiency (MW)	2	10
CCGT (MW)		180
Aeroderivative peaker (MW)	54	

LEI then computed the net direct cost to Connecticut ratepayers of this least-cost NTA portfolio by deducting from the NTA's gross annual costs the projected average annual market-related revenues that the NTAs could be projected to earn. The total net direct cost to ratepayers of this least cost technically feasible NTA solution for NWCT was estimated to range from \$22 million to \$36 million a year, not including the cost of constructing lateral pipelines to reach the nearest existing natural gas pipeline supply, or any transmission system upgrade costs required to implement the NTA technologies. Furthermore, the costs are not inclusive of any locational premiums associated with developing and building in Connecticut as opposed to more generally in New England. In contrast, Connecticut ratepayers' share of the revenue requirement associated with the NWCT transmission solution would be approximately \$2.7 million a year. This enormous cost differential compelled the conclusion that an NTA would not provide a practical alternative to the transmission solution and to terminate the analysis.

If the NTA identified by LEI were to be considered further, it would be necessary to test it in the same manner as the transmission solution was tested in the ISO-NE solution study. In such a study, a generation dispatch would be constructed that would assume one or two of the most critical units in the NWCT sub-area to be out of service and that approximately 80% of the fast start units in the subarea (which would include the aeroderivative units at Torrington) would come on when requested. The results of this study could have indicated that additional capacity beyond that included in the LEI NTA would be necessary to provide, with the required degree of reliability, the injection quantities determined by the ISO-NE MRA studies to be necessary.

Such further studies would also have to evaluate a full range of the non-economic costs and benefits of the NTAs, compared to those of the transmission solution. For instance, the environmental effects of the NTAs (e.g., noise impacts and air emissions from the aeroderivative and CCGT plants) would have to be specifically determined and subsequently compared to those of the transmission alternative, which are extensively described in this document (refer to Section 6). In addition, forward-looking simulation modeling would have to be performed to assess the relative longevity of both the transmission solution and the potential NTA technologies, and to compare the various services and other benefits that each could provide.

However, the cost difference between the NTA and transmission solutions in this case is decisive, illustrating that an NTA solutions in this case was economically impractical. Indeed, the economic impracticality of the NTA solution here is suggested by the fact that no one has proposed to implement such an NTA for the NWCT sub-area since ISO-NE identified potential MRAs for the GHCC projects in 2012. Pursuant to the ISO-NE Open Access Transmission Tariff, since no market solution for a reliability need has been implemented, Eversource is required to proceed with a “backstop” regulated transmission solution, as proposed in this document.

Note: This page intentionally left blank.

11. TRANSMISSION LINE ROUTE / CONFIGURATION ALTERNATIVES

11.1. ROUTING OBJECTIVES AND ALTERNATIVE ROUTE ANALYSIS PROCESS

After the Project (a new 115-kV transmission line to connect Frost Bridge and Campville substations) was selected as the preferred transmission system solution, Eversource identified and evaluated alternative routes and configurations for the new transmission line. All of the potential alternative routes for the new 115-kV transmission line necessarily had to interconnect the two substations, as required to achieve the Project's technical objectives. This section describes the approach that Eversource used to identify and evaluate route alternatives for the proposed 115-kV transmission line and, from among these alternatives, select the preferred route and design for the Project.⁸⁶

11.1.1 Routing Objectives

For the alternatives analysis, Eversource applied an established set of route selection objectives to identify and compare potential routes for the new 115-kV transmission line between Frost Bridge Substation and Campville Substation. These defined line routing objectives, which are listed in Table 11-1, include the following overarching goals:

- The selection of a cost-effective and technically feasible solution to achieve the required transmission system reliability improvements and to interconnect the specified substations; and
- The avoidance, minimization, or mitigation of adverse environmental and cultural effects and minimizing impacts to the community to the extent possible.

⁸⁶ There are no feasible "routing" alternatives to the proposed separation of the existing 1191 and 1921 Lines at the Naugatuck River crossing. An alternative transmission line structure configuration was considered for the circuit separation and is discussed in Section 12.

Table 11-1: Eversource Transmission Line Route Selection Objectives

- Comply with all statutory requirements, regulations, and state and federal siting agency policies
- Maximize the reasonable, practical, and feasible use of existing linear corridors (e.g., transmission line, highway, railroad, pipeline rights-of-way)
- Minimize adverse effects to sensitive environmental resources
- Minimize adverse effects to significant cultural resources (archaeological and historical)
- Minimize adverse effects on designated scenic resources
- Minimize conflicts with local, state and federal land use plans and resource policies
- Minimize the need to acquire property by eminent domain
- Maintain public health and safety
- Achieve a reliable, operable and cost-effective solution

11.1.2 Alternative Route Analysis Process: Overview and Summary

Eversource applied the transmission line route selection objectives to identify potential 115-kV transmission line route alternatives involving both overhead and underground configurations. These potential route alternatives were then examined, using Eversource's route evaluation criteria for overhead transmission lines (as discussed in Section 11.2) and underground transmission cables (as discussed in Section 11.3), to assess the viability of each option based on operability and reliability, technical feasibility, potential effects on property, potential effects on environmental and cultural resources, and cost. Because overhead and underground transmission line construction and operation are inherently different, the emphasis placed on some of the route evaluation criteria in the analysis of potential route options varied for these two line designs.

As the first step in the alternative route analyses, Eversource⁸⁷ reviewed the general region between Frost Bridge Substation and Campville Substation to identify major, geographically distinct, existing linear corridors (e.g., railroad, road, pipeline, transmission line ROWs) for further investigation. The Project region was also reviewed to determine the potential viability of new "greenfield" routes (i.e., not adjacent to any existing corridors) for the new transmission line.

⁸⁷ The alternative routes were identified and evaluated by a team consisting of Eversource staff, as well as specialized engineering and environmental consultants. This team conducted field reconnaissance, performed baseline data collection, prepared cost estimates, and reviewed aerial photography to determine the characteristics of each route alternative and to assess each in terms of the Project objectives and Eversource's route evaluation criteria.

The initial examination of potential alternative line routes involved the review of Eversource records regarding transmission line ROWs, road atlases, USGS topographic maps, Google Earth® and similar databases. Aerial photography of the Project region was also reviewed to identify general land uses and environmental features (e.g., vegetative communities, water resources, major designated recreational areas, and developed residential, commercial, and industrial areas).

Using this baseline information and reconnaissance of the Project region, Eversource identified and reviewed various existing linear corridors to determine if the new 115-kV line could be co-located within or adjacent to such ROWs. Existing corridors reviewed included State Routes 8, 848, 254, 807, 262, and 109; local roads; Eversource's existing transmission line ROWs; and railroads. In addition, Eversource assessed regional topographic and land use conditions to determine whether a new 115-kV transmission line could be practically developed along an entirely new ROW.

Eversource evaluated each potential route alternative using the criteria identified in Sections 11.2.1 (for overhead transmission lines) and 11.3.1 (for underground transmission cable systems). As a result of these route evaluations, most of the alternatives were quickly found to be impractical because of overriding environmental issues, lack of easements or property, engineering constraints, and/or cost factors, or were determined to be infeasible after field reconnaissance and closer investigation of potential environmental, social, and cultural effects, engineering concerns, or costs. (Refer to Sections 11.2.2 and 11.3.3 for discussions of alternative overhead and underground line routes that were eliminated from further consideration.)

Based on this evaluation process, Eversource identified three route alternatives (refer to Figure 11-1) for further consideration:

- a. **Overhead 115-kV Transmission Line within Existing ROW.** Alignment of the proposed approximately 10.4-mile 115-kV transmission line in an overhead configuration within Eversource's existing ROW between Frost Bridge Substation and Campville Substation. There is sufficient space to accommodate the new transmission line within Eversource's existing ROW, without having to acquire new easements.
- b. **Underground 115-kV Transmission Cable System along Road ROWs.** Development of approximately 11.2 miles of 115-kV transmission line, predominantly in an underground configuration (cable system) within or adjacent to existing road ROWs between the two substations. This route alternative would be constructed entirely underground, except for an approximately 0.2-mile overhead line segment extending from the Frost Bridge Substation, east across the Naugatuck River to Waterbury Road (State Route 262/848). The overhead line segment would be located primarily on new ROW but between two existing overhead

ROWs and would avoid a difficult underground cable installation beneath the Naugatuck River.

- c. **Underground 115-kV Transmission Cable System along Road ROWs with Overhead 115-kV Transmission Line Segment in Litchfield / Harwinton.** Development of approximately 9.8 miles of new 115-kV transmission line, predominantly in an underground configuration (cable system), as described in (b), except that the northern end of the route would transition to an overhead configuration in the Town of Litchfield and would be aligned within Eversource's existing ROW for approximately 1.8 miles across State Route 8 and the Naugatuck River to the Campville Substation. Overall, this route alternative would consist of approximately 7.8 miles of underground transmission cable and 2 miles of overhead transmission line.

As described in Sections 11.2 and 11.3, Eversource conducted more detailed analyses of each of these alternatives, taking into consideration environmental and social impacts, constructability, and cost, among other factors. Subsequently, from among these alternatives, for the reasons described further below, Eversource identified the preferred Project alternative as an overhead 10.4-mile 115-kV transmission line, aligned within Eversource's existing transmission line ROW between Frost Bridge Substation and Campville Substation.


11.2 OVERHEAD TRANSMISSION LINE ROUTES: ALTERNATIVES ANALYSIS

11.2.1 Route Evaluation Criteria

Along with the route selection objectives listed in Table 11-1, Eversource applied an established set of route evaluation criteria to identify and compare potential overhead transmission line routes. These standard route evaluation criteria, as described below, were used to locate and assess alternative overhead transmission line routes for the proposed Project.

Overhead transmission lines allow some design flexibility, provided that a continuous ROW of adequate width is available. Individual transmission line structures often can be located to avoid, or to allow the conductors to span over, sensitive environmental areas (e.g., wetlands, watercourses and lakes, steep slopes, important wildlife habitat).

Overhead lines require ROWs within which certain land uses (such as building a new permanent structure) are precluded and along which vegetation must be managed to prevent tall-growing trees within conductor zones. (Refer to Volume 1, Section 4 for information regarding overhead transmission line construction and ROW vegetation management procedures.)



Taking these factors into account, Eversource gives primary consideration to the criteria listed in Table 11-2 when evaluating potential routes for a new overhead 115-kV transmission line. These overhead line routing criteria were applied to examine and compare alternative overhead line routes for the Project.

11.2.2 Alternative Overhead Line Routes Considered but Eliminated

In addition to the alignment of the new 115-kV transmission line within the existing ROW between Frost Bridge and Campville substations, Eversource identified and reviewed a number of overhead transmission line-route options. These included the development of the new 115-kV line on a new ROW and within or adjacent to existing linear corridors in the Project region, including State Routes 8, 848, 254, 807, 262, and 109; local roads; and the Naugatuck Railroad Company railroad corridor (which is leased from ConnDOT) along the Naugatuck River.

However, as summarized below, all of these potential alternative routes were eliminated from detailed consideration because they were found to be unsuitable for the development of a new transmission line due to factors such as engineering constraints, geographic location, lack of easements or property owned in fee, and/or potential for significant environmental, social, or economic effects.

11.2.2.1 New Rights-of-Way Alternative

This alternative would involve the development of the new overhead 115-kV transmission line between Frost Bridge Substation and Campville Substation along an entirely new ROW (referred to as a “greenfield” corridor) not adjacent to any other existing linear corridors. In the absence of any environmental, social, or engineering constraints, such a “greenfield” corridor could provide the shortest, straight-line alignment between the required substation interconnection points.

However, an entirely new corridor for the 115-kV overhead transmission line would have to be aligned to avoid both developed areas and constraints posed by topography. Assuming the use of a delta structure configuration (refer to Table 11-2), a minimum 90-foot-wide ROW width would be required. Even (unrealistically) assuming a minimum straight-line 8.8-mile distance between Frost Bridge Substation, this alternative route would require the acquisition of easements applicable to more than 96 acres of property for the new overhead transmission line.⁸⁸

⁸⁸ Using a vertical (monopole structure) conductor configuration on the new 115-kV line would reduce the ROW width, but would require taller structures.

Table 11-2: Route Evaluation Criteria for 115-kV Overhead Transmission Line Siting

ROUTING CRITERIA	DESCRIPTION
Availability of Existing ROWs for the New Line to Follow	<p>The potential co-location of the 115-kV transmission facilities along existing ROWs where linear uses are already established (e.g., transmission lines, highways, railroads, pipelines) is a primary routing consideration. The co-location of linear utilities within existing utility corridors is strongly favored by the Federal Energy Regulatory Commission's <i>Guidelines for the Protection of Natural, Historic, Scenic, and Recreational Values in the Design and Location of Rights-of-Way and Transmission Facilities</i>, with which any electric transmission line approved by the Council must be consistent.⁸⁹</p> <p><u>New ROW.</u> The ROW width required for an entirely new 115-kV overhead line route would vary depending on the type of transmission line structure, which affects the conductor clearance required from vegetation. Typically, a line with a delta configuration would require a minimum 90-foot-wide ROW, a line with a horizontal (H-frame) configuration would require a, 100-foot-wide ROW, and a line with a vertical configuration would require a 70-foot-wide ROW.</p> <p><u>Existing ROW.</u> The placement of a new 115-kV transmission line within an existing corridor (parallel to existing transmission lines) may require a lesser expansion of an existing ROW or may not require any additional ROW at all, providing that the existing ROW is wide enough and has sufficient un-used space for the new 115-kV transmission line. Typically, to accommodate a new 115-kV delta transmission line adjacent to an existing H-frame or delta 115-kV transmission line, approximately 50 feet of additional ROW would be required. Aligning a new 115-kV H-frame adjacent to an H-Frame or delta 115-kV transmission line would require approximately additional 60 feet. A new vertically-configured 115-kV line, located adjacent to an existing 115-kV line, supported on H-frame or delta structures, would require only an additional 30 feet of ROW.</p>
Engineering Considerations	<p>Whether on existing or new ROWs, the terrain and location of the transmission line route and constructability issues must be considered since both may have a significant bearing on cost and effects on environmental resources. Among the constructability factors considered is the ability to avoid or minimize the location of structures along steep slopes or embankments, in areas of rock outcroppings, or within environmentally sensitive areas, such as wetlands. Engineering requirements for the transmission line and access roads (as necessary) to cross streams, railroads, and other facilities are also assessed. Terrain and access constraints (e.g., side slopes, rugged topography) due to extreme side slopes are assessed.</p>
Avoidance or Minimization of Conflicts with Developed Areas	<p>Where possible, it is preferable to avoid or minimize conflicts with residential, commercial, and industrial land uses such as homes, businesses, and airport approach zones. One of Eversource's primary routing objectives for any proposed transmission line is to minimize the need to acquire (by condemnation or voluntary sale) homes or commercial buildings to accommodate the new transmission facilities (refer to Table 11-1).</p>
Consideration of Visual Effects	<p>Because 115-kV transmission line structures are typically range from 70 to 105 feet tall (depending on structure configuration), structure visibility is a design consideration. In recognition of public opinion regarding structure visibility, it is desirable to avoid placing structures in areas of visual or historic sensitivity; to consider designs for minimizing structure height; and to assess the potential visual effects of removing mature trees along ROWs, as required to conform to electrical clearance requirements (i.e., the potential implications of removing trees that provide vegetative screening). Vertical structures typically have the greatest visibility effects. However, structure visibility effects are incremental if new overhead lines are placed within existing ROWs along which overhead transmission lines are already part of the visual landscape.</p>
Avoidance or Minimization of Environmental Resource Effects	<p>In accordance with federal, state, and municipal environmental protection policies, the avoidance or minimization of new or expanded corridors through sensitive environmental resource or recreation areas such as parks, wildlife management areas, and wetlands is desired.</p>
Accessibility	<p>An overhead line must be accessible to both construction and maintenance equipment. Although access along the entire overhead line route is typically not needed, vehicular access to each structure location from some access point is required.</p>

⁸⁹ CGS Section 16-50p(a)(3)(D)

In addition to these easement acquisition issues, the development of the 115-kV transmission line along a “greenfield” corridor was determined to be impractical for environmental reasons. For instance, to construct the proposed 115-kV transmission line, the majority of the vegetation along the “greenfield” corridor would have to be removed and access roads would have to be created within the new ROW. Compared to the use of an existing ROW, the creation and maintenance of such a “greenfield” corridor can cause greater environmental impacts (e.g., permanent fill in wetlands due to new access roads and structures, development of a new linear corridor through undisturbed forested communities, crossings of water resources, and preclusion of certain other land uses within the corridor).

In addition, the creation of a new transmission line corridor, when existing ROWs are available and practical to use, does not conform to federal and state policies regarding the co-location of linear facilities, and likely would not conform to federal criteria (pursuant to the Clean Water Act) for selecting the “least environmentally damaging practical alternative” to avoid or minimize adverse effects to water resources and other environmental and cultural resource features. In general, the installation of new transmission line facilities along existing ROWs (e.g., transmission line ROWs, pipeline corridors, highways, railroads) is environmentally preferable to creating entirely new corridors through properties previously unaffected by linear developments.

Operation of the new 115-kV transmission line within a new ROW would require restrictions on property owners’ land uses. Specifically, land uses within the ROW would be limited to those that are compatible with the transmission facilities and utility operation; buildings and other uses would be precluded. For an overhead transmission line, the ROW would have to be managed in low-growing vegetation, and access to the transmission line structures would typically be required.

Overall, the all-new ROW alternative was determined to be impractical based on existing land use, and environmental considerations and the ready availability of a viable alternative (i.e., the use of Eversource’s existing ROW). The all-new ROW alternative would not conform to federal and state policies for the co-location of linear corridors to the extent practical and Eversource’s acquisition of such easements from private property owners would be both costly and time-consuming.

11.2.2.2 Alternative Routes along Highway Rights-of-Way

This alternative would involve the development of the new 115-kV transmission line between Frost Bridge and Campville substations in overhead configurations within or adjacent to highway corridors, including State Route 8 (a limited access highway) and local roads. Key considerations in the review of

this alternative were the locations of roads in relation to the existing two substations that must be interconnected, as well as construction feasibility and potential environmental resource and social effects.

State Route 8: Limited Access State Highway. State Route 8 was reviewed as a potential route for the new 115-kV line because, compared to most local roads, state highways typically have wider ROWs, including undeveloped areas outside of paved travel lanes, where land may be available to accommodate an overhead transmission line. This situation is particularly true of limited-access highways such as State Route 8.

Generally, in order to construct a new overhead, delta-configured, 115-kV transmission line, a 90-foot-wide ROW would be required.⁹⁰ Along state highways, if an agreement could be reached with ConnDOT to share the outer portion of a highway ROW with an aerial easement, the required new ROW width could be reduced.

However, longitudinal co-location of transmission lines in ConnDOT limited access highway corridors is not permitted except in special circumstances, as provided in ConnDOT's *Utility Accommodation Manual* (2009). On April 9, 2015, Eversource met with ConnDOT to discuss this policy, with respect to the potential for the co-location of new 115-kV transmission line(s) along state highways. ConnDOT representatives affirmed that the agency opposes the co-location of transmission lines in state road ROWs, particularly if other routing alternatives, such as the use of existing utility ROWs, are available.

In addition to ConnDOT's policy against the co-location of transmission lines within its highway ROWs, the State Route 8 corridor would pose particular challenges for the development of a new transmission line because of the steep topography, bedrock outcrops, and numerous water resources (including reservoirs) adjacent to the highway. Further, because portions of State Route 8 extend through suburban or urban areas, the development of the transmission line adjacent to the highway would be constrained by residential, commercial, or industrial land uses. Wherever the transmission line ROW could not be located within the highway easement, new ROW would have to be acquired from private landowners. In addition, the linear alignment of an overhead transmission line along State Route 8, would be highly visible, affecting the aesthetic environment.

⁹⁰ Other common configurations of an overhead 115-kV line use shorter structures, but would require a wider ROW (e.g., up to 150 feet). Existing highway easement widths vary. As a result, depending on the actual widths of a state highway corridor, an overhead transmission line could have to be located either within or adjacent to highway property.

- **Local Road and Other State Highway ROWs.** The alignment of the new 115-kV transmission line within or adjacent to local road ROWs or other state highways (not limited access, typically two-lane) poses similar constraints. For example, the primary determinant of construction feasibility was adequate space for a new overhead 115-kV transmission line ROW without having to displace homes or businesses located adjacent to the highway.

The development and operation of a new overhead transmission line adjacent to either two-lane state highways or local road ROWs also would affect the aesthetic environment because the new transmission line would be visible both to travelers on the highways and to local residents and business patrons. Additionally, while overhead electric distribution lines and telephone lines can be configured to follow winding roads, high voltage transmission lines are designed for mostly straight-line, longer-span construction. As a result, the design and construction of a new 115-kV transmission line adjacent to these roads would be both technically difficult and costly, and would result in potentially significant land use and environmental impacts (e.g., as a result of the removal of vegetation adjacent to road ROWs to achieve mandated conductor clearances, possible need to acquire new utility easements from private landowners, depending on the width of the road ROWs). Further, compared to structure heights along a typical transmission line ROW, the transmission line structures along a local road ROW would likely have to be taller to maintain conductor clearances over the distribution and telephone lines that are presently aligned along the roads.

Summary. Overall, Eversource dismissed all of the highway route alternatives from further consideration as potential overhead transmission line routes for the Project due to inconsistency with ConnDOT policies; significant construction difficulties and constraints; and the unacceptable social effects associated with the need to remove homes and businesses where a new ROW could not be located within the highway corridor. The complexity of construction, the need to follow road ROWs that do not provide direct routes between the substations that must be interconnected, and the amount of land acquisition required also would result in comparatively higher costs than would the development of an overhead line within the unused portions of Eversource's existing transmission line ROW that already extends directly between Frost Bridge and Campville substations.

11.2.2.3 Alternative Route along Railroad Rights-of-Way

Within the Project region, the only railroad corridor in the vicinity of Frost Bridge and Campville Substations is aligned adjacent to the Naugatuck River. ConnDOT owns this railroad track, which in the Project area, extends from Waterbury to Torrington. ConnDOT leases the portion of the track between Waterbury (Waterville area) and Thomaston to the Railroad Museum of New England (RMNE), a not-

for-profit educational and historical organization based in Thomaston. The RMNE operates the Naugatuck Railroad as a heritage railway, using historic train equipment and offering excursions for recreational / scenic purposes within the Naugatuck River valley. The RMNE trains operate between Thomaston Railroad Station to Waterbury, from April through December.

Portions of the railroad corridor are also being investigated as part of a greenway trail system along the Naugatuck River. In addition, the train tracks extend through densely populated portions of Thomaston and other towns, and are adjacent to the Naugatuck River. Further, the train tracks traverse beneath Reynolds Bridge, an open-span concrete arch bridge constructed over the Naugatuck River in 1928; this bridge is listed on the NRHP because it was the longest bridge of its kind built by the then-Connecticut State Highway Department.

Given the current use of the Thomaston-Waterbury portion of railroad corridor for scenic excursions, the presence of the NRHP-listed Reynolds Bridge, and the land use developments adjacent to the railroad corridor in Thomaston and elsewhere, the alignment of a new overhead 115-kV transmission line along the ConnDOT / Naugatuck Railroad ROW was quickly determined to be impractical based on overriding environmental, social, constructability, and cost considerations.

11.2.2.4 Alternative Routes along Other Transmission Line Rights-of-Way

Eversource reviewed its existing transmission line ROWs in the vicinity of Frost Bridge Substation and Campville Substation to assess whether the new 115-kV line could practically be constructed within ROWs other than the Proposed Route (which extends west and then north-northeast between the two substations). Three other ROWs (occupied by 115- and 345-kV lines) extend into Frost Bridge Substation from the south, southeast, and east. However, none of these ROWs, individually or in combination, extend north toward Campville Substation, which is presently interconnected to only one existing ROW from the south (i.e., the Proposed Route) and one 115-kV ROW that extends out of the substation to the north. Consequently, the use of any other transmission line ROWs for the new 115-kV line was determined to be infeasible.

11.3 UNDERGROUND TRANSMISSION LINE-ROUTE ALTERNATIVES

The vast majority of transmission lines in Connecticut and in the United States consist of overhead lines. However, underground transmission cable systems, consisting of both buried electric cables and splice

chambers⁹¹ (or “splice vaults”, which are required at specified intervals along a cable route), may warrant consideration when overhead lines are impractical due to site-specific environmental, social, construction, or regulatory factors, and in the rare case where there is not a large cost difference between overhead and underground alternatives.⁹² Within the past 12 years, Eversource has sited and installed underground transmission cable systems in Connecticut as part of the Bethel-Norwalk Project (345-kV and 115-kV transmission cables), Middletown-Norwalk Project (345-kV and 115-kV transmission cables), the Glenbrook Cables Project (115-kV transmission cables), and the Stamford Cables Project (115-kV transmission cables). As a result, Eversource has extensive, recent experience in underground transmission cable routing, construction, and cost analysis.

11.3.1 Cable Technology Considerations and Route Evaluation Criteria

Underground cable systems and overhead transmission lines represent different technologies for transporting power. In a given system application, one of these line types may not be practical to use, given specific project considerations such as the length of the transmission line to be installed, terrain, availability of ROWs, urbanization, etc. In addition, there are many technical issues with respect to the installation of underground cables in a predominantly overhead system, such that extensive technical studies by power-system engineers may be required to determine the feasibility of a particular underground installation. In this case, power system studies that would be required to analyze the performance and possible technical limitations of an underground system were not performed. Rather, the practicality of the identified underground alternative was assumed for the purpose of further economic and routing analysis.

11.3.1.1 Selection of Underground Transmission Cable Technology

There are two distinct types of 115-kV underground cables that are in common use in the Eversource transmission system: High Pressure Fluid Filled (HPFF) and Cross-linked Polyethylene (XLPE). The principal characteristics of each of these technologies are:

- **HPFF.** HPFF cable was traditionally the primary underground technology used for 115-kV underground transmission lines in the United States. Three individual cables, called cores, are used to form a circuit. The cores are encased in a steel pipe that is filled with insulating fluid and

⁹¹ Appendix 11A describes the components of a 115-kV cable system, as well as cable system construction procedures.

⁹² The typical costs for constructing an underground 115-kV transmission cable system are five to ten times greater than those for installing an equivalent length of overhead 115-kV transmission line within an existing transmission line ROW. Cost considerations are discussed separately in Section 11.3.1.4.

then pressurized to a nominal 200 pounds per square inch (psi), which requires pressurization plants and reservoirs. These reservoirs hold thousands of gallons of insulating fluid.

- **7XLPE.** XLPE cables are the newer technology. Here again, three single cores are necessary to form a circuit. However, they are installed separately, often within individual ducts, usually made from a plastic material. Each XLPE core is surrounded with a solid insulating material rather than fluid, and the insulating material is protected by a water-impervious sheath. No insulating fluid is involved.

HPFF and XLPE cables are both reliable at 115-kV, but each has different features and requirements that are considered in choosing between them when either is suitable for a given application.

For example, HPFF cables can be provided in longer lengths, such that fewer splice vaults and cable splices are necessary, resulting in lower construction costs compared to XLPE cables. HPFF cable systems also have the ability to circulate the dielectric fluid to smooth out (mitigate) hot spots along the cable route, effectively increasing the circuit capacity. This provides an advantage over XLPE cable systems when the cable system is aligned parallel to existing heat sources (i.e., existing distribution circuits near substations, capable of de-rating the circuit). In addition, for many applications, the cost of HPFF cables will be lower.

However, the fluid system within HPFF cable systems requires more maintenance and planned outages than XLPE cable systems. In addition, HPFF cables have higher electrical losses, lower capacity for equivalent size conductors, and much higher capacitive charging requirements. Further, over rugged terrain with variable topography, such as characterizes the Project area, the ability to maintain the required pressure in the HPFF cable system would be difficult.

Based on the capacity required for the Frost Bridge to Campville solution and Eversource's experience on recent underground cable projects, XLPE cable was selected as the preferred cable technology for the underground route analyses for the Project.

11.3.1.2 Route Evaluation Criteria

Compared to overhead transmission lines, an underground cable system requires a narrower ROW. However, an underground cable system entails a continuous trench and the installation of underground splice vaults, both of which must remain completely accessible by large vehicles for utility maintenance purposes. Environmentally sensitive areas, such as wetlands and streams, cannot be spanned as with overhead lines. Careful siting is required to avoid or minimize significant effects to environmental

resources and other utilities as a result of trenching activities, as well as to ensure that the cable system is immediately accessible in the event that maintenance is required during the operation of the facility.

When performing analyses of potential underground cable-system routes, Eversource typically applies a set of standard routing criteria, reflecting the consideration of environmental, social, construction, engineering, and economic factors. Given typical cable-system design, installation, and maintenance considerations, the criteria summarized in Table 11-3 are factored into the identification and evaluation of potential underground cable-system route alternatives. Cost, as described separately in the following section, also is a critical factor in the consideration of underground cable systems.

Table 11-3: Route Evaluation Criteria for Underground Transmission Cable-System Siting

ROUTING CRITERIA	DESCRIPTION
Environmental Considerations	<p>Underground cables are preferably sited away from, rather than through, significant environmental resources. Whereas an overhead transmission line can span wetlands, watercourses, vegetation, rock outcroppings and, steep slopes, the installation of an underground cable system requires the excavation of a continuous trench. The operation of the cable system requires continuous permanent access along the entire route so that any splice vault or portion of the cable duct bank can be reached by heavy equipment as necessary for maintenance and repairs. Therefore, any sensitive environmental resources (such as watercourses, wetlands, or endangered species habitat) located along an underground cable route may be directly affected by the excavations required for the cable system. To mitigate such impacts, the cables can be installed, for relatively short distances, beneath these resources using subsurface construction technology, such as jack and bore or horizontal directional drilling, but at great expense.</p> <p>Existing public road corridors are usually considered for the installation of underground cables in preference to overland electric transmission line ROWs. Road corridors typically provide continuous permanent access along the underground cable route and often are characterized by gradual slopes. However, when sited in or adjacent to roadways, underground cables must avoid conflicts with existing underground utilities. Furthermore, alignment of underground cables along road ROWs may pose other potential environmental issues, such as excavation through areas of contaminated groundwater or soils; traffic congestion; difficult crossings of watercourses and wetlands that the roads traverse or bridge; and disturbance to vegetation and land uses adjacent to the roads (due to construction staging, heavy equipment operation, etc.).</p>
Engineering Considerations	<p>Steep terrain poses serious problems for underground cable construction and may cause down-hill migration and overstraining of the cable and cable splices (the point where two cables are physically connected together). Accordingly, one of the primary engineering objectives for an underground cable system is to identify routes that are relatively straight, direct, and have gradual slopes and inclines to minimize construction and maintenance costs, and to avoid downhill cable migration.</p>
Availability of Useable ROW	<p>A new 115-kV underground XLPE cable system typically requires a minimum 30-to-40-foot-wide work area for construction. Additionally, land must be available for burying splice vaults, each of which is approximately 9 feet wide by 9 feet deep and up to 24 feet in length. The installation of each vault would typically require an excavation of 13 feet wide, 13 feet deep, and 30 feet in length. Such vaults, which must be placed at approximately 1,600-to-2000 foot intervals along a 115-kV cable route, are required to allow the individual cable lengths to be spliced together and also must be accessible, via manholes, for cable-system maintenance and repair. Due to constraints posed by buried utilities within road travel lanes or conflicts with public highway use policies, vaults must sometimes be located beneath road shoulders or on private lands adjacent to public road corridors.</p>
Social Considerations	<p>Cable construction requires considerable time and results in noise, disruptions to traffic and impediments to access to adjacent land uses, and potential conflicts with existing in-ground utilities. Consequently, where possible, a routing consideration is to limit the length of cable installation through densely developed residential areas and central business districts. These social effects must be carefully considered and balanced against the potential lesser effects of constructing and operating overhead line segments in comparable areas.</p>
Availability of Land for Line Transition Stations	<p>Unless terminated at a substation, underground transmission systems require separate above-ground transition stations at each location where the underground cables interconnect to overhead transmission lines. In general, transition stations require the purchase and conversion of land to industrial (utility) use, and consist of above-ground facilities within a graded, fenced area, similar in appearance to a transmission substation. Routing analyses must consider the availability of land required for transition stations, as well as the environmental and social effects resulting from station development (e.g., surrounding land uses and potential effects on natural resources, cultural resources, neighborhoods, and the visual environment).</p>

11.3.1.4 Cost

Cost is a key consideration in the evaluation of underground cable technology versus overhead technology. As noted previously, the typical costs for constructing an underground 115-kV transmission cable system are five to ten times greater than those for installing an equivalent length of overhead 115-kV transmission line on an existing ROW.

In addition, except where underground cable routes can be aligned entirely within highway ROWs and/or within existing Eversource ROWs where Eversource's easements include underground cable rights, Eversource would have to acquire new easement rights from private landowners for the installation and operation of the cable system. Along state highway ROWs, ConnDOT policy requires the locations of splice vaults outside of the highway ROW; as a result, for any cable systems aligned along state roads, easements from private landowners would be required to accommodate the splice vaults and the interconnecting portions of the duct bank.

As a result, where existing ROWs have sufficient space to accommodate a new overhead transmission line or can be expanded for comparatively low cost, the capital costs of building the overhead transmission line are significantly less than the costs of building a comparable underground 115-kV cable system.

The difference in the cost to Connecticut consumers for a 115-kV underground cable system, compared to an overhead line, is even greater because of federal tariff provisions. Because this Project is expected to qualify for inclusion in New England regional transmission rates, the Project costs would be shared by consumers throughout New England, based on each electric transmission company's share of the regional electric load. Connecticut accounts for approximately 25% of the New England load; therefore, Connecticut consumers would bear approximately 25% of the Project cost included in regional rates.

Recovery of Project costs through regional rates, however, is not automatic. Only costs determined by ISO-NE to be eligible for regionalization according to specific tariff provisions would be included in regional rates. Experience has shown that where a transmission line (or a line segment) that would normally be constructed overhead, in conformity with good utility practice, is instead constructed underground, ISO-NE typically does not allow the extra costs of underground line construction to be included in regional rates. Instead, such extra costs are "localized" and must be recovered solely from consumers in the area in which the underground system is situated.

In Connecticut, the effect of localizing excess underground cable costs is that in-state consumers would bear approximately 25% of the cost of an overhead line (or segment), plus 100% of the difference between that cost and the cost of an underground cable system. For example, if Eversource were to build an all-underground line that cost 10 times more than a comparable overhead line (constructed in accordance with standard good utility practice), the cost to Connecticut consumers for the underground cable system could be 37 times more than that of the overhead line $[(1 \times 25\%) + (9 \times 100\%)] = (9.25 \div 0.25) = 37.0$

11.3.2 Construction Considerations and Procedures

Underground cable-system construction requires vastly different procedures and considerations than overhead transmission line construction. Such systems are most often located within or adjacent to public roads, which provide both a linear corridor for the cable route and roadway access along the entire cable system for construction and maintenance. Appendix 11A describes the construction procedures that would typically be used to install an underground XLPE 115-kV transmission cable system. The appendix includes the following information:

- The typical construction activities and sequence for underground cable-system installation within or adjacent to road ROWs;
- The different construction procedures that would be required to develop a cable system outside of road ROWs (e.g., along transmission line ROWs or along a “greenfield” utility corridor);
- The typical requirements for equipment staging areas, as well as the dimensions for cable trenches and splice vaults; and
- Data regarding specific underground cable construction considerations (e.g., splice vault locations, erosion controls, traffic management).

11.3.3 Alternative Underground Line Routes Considered but Eliminated

Although overhead circuits are the most efficient and reliable method for delivering power over long distances, Eversource identified and reviewed, using the routing objectives, technology considerations, and evaluation criteria described in Sections 12.1 and 12.3.1, respectively, several underground cable-route alternatives to interconnect Frost Bridge Substation and Campville Substation. As summarized in this section, after considering constructability, cost, and environmental factors, most of the “all-underground” cable-system options initially identified were quickly eliminated from further consideration due to significant cost, constructability, and environmental issues. The underground routes considered but eliminated

from further consideration included cable system alignments along State Route 8, along the Naugatuck Railroad, and within Eversource's existing transmission line ROW between Frost Bridge and Campville substations (refer to Sections 11.3.3.1 through 11.3.3.4).

In addition to these potential underground cable routes that were quickly eliminated from consideration, Eversource identified and further reviewed two routes between Frost Bridge and Campville substations: (1) an "all underground" cable system along state and local roads; and (2) a variation of the "all-underground" route, which also would include a segment of overhead line within Eversource's existing ROW between Campville Road (Town of Litchfield) and the Campville Substation. For these two route alternatives, which are described in Sections 11.3.3.5 and 11.3.3.6, Eversource conducted additional studies and estimated the life-cycle costs compared to that of the overhead 115-kV transmission line proposed for the Project.

Eversource determined that the development of the new 115-kV line using a cable system installed along either of these underground line routes would be less reliable than the proposed overhead 115-kV transmission line, would be significantly more costly (by an order of magnitude, with high costs to Connecticut consumers), and would pose environmental and engineering issues. Further, either route alternative would add an estimated six to 12 months to the construction period, thereby extending construction impacts, increasing costs, and delaying energization of the Project.

11.3.3.1 New Rights-of-Way Alternative

Similar to the discussion in Section 11.2.2.1 of a new ROW alternative for an overhead transmission line, this alternative would involve the construction and operation of a new 115-kV underground cable system between Frost Bridge Substation and Campville Substation along a "greenfield" corridor, not within or adjacent to any existing roads or other linear corridors. As was the case for the corresponding overhead transmission line "greenfield" ROW alternative, Eversource's initial review determined that this underground line-route option would not conform to regulatory guidelines for the co-location of linear corridors to the extent practical, would result in comparatively significant, unavoidable environmental impacts, and would not be cost-effective. As a result, Eversource eliminated this option from any further consideration. The following briefly reviews the key constraints to any underground "greenfield" route.

To develop a "greenfield" corridor, for a new cross-country (non-street) underground transmission cable system, Eversource would first have to acquire new easements from private property owners along the

entire length of the route. A minimum easement width of 40 feet would be required.⁹³ This property acquisition process would be both costly and time-consuming.

Moreover, the development of the 115-kV underground cable system along a “greenfield” corridor would be considerably more costly and result in significantly greater environmental effects than other potential route alternatives. To install the cable system, all of the vegetation along the “greenfield” corridor would have to be cleared and the entire corridor would have to be graded to create work space for construction equipment, access roads, and for the excavation of the cable duct bank and splice vaults. Given the rugged terrain and bedrock in the Project region, extensive grading (and likely blasting), representing permanent topographic changes, would be required to install the continuous trench for the cables and to excavate the splice vaults.

The continuous trenching needed for the duct bank would result in adverse effects to wetlands and watercourses as a direct result of filling (i.e., installing the duct bank and surrounding the conduits with fluidized thermal backfill [FTB]). In addition, permanent access roads would be required along the ROW to access splice vaults for maintenance. The cable system would have to be installed beneath watercourses using either conventional trenching (which would result in direct disturbance to the stream beds and water quality impacts) or more costly subsurface installation methods (e.g., jack and bore, horizontal directional drilling [HDD]) that would minimize direct impacts to the stream beds.

The development of the cable system along a “greenfield” corridor also would require the conversion of previously undisturbed forested wetland habitats to scrub-shrub communities, development of a new ROW through upland forest, preclusion of certain land uses within the corridor, and potential direct disturbance to archaeological sites. For the operation of the underground cable system, permanent access roads would have to be maintained along most of the length of the ROW in order to maintain access to all splice vaults, and other (non-access road) portions of the ROW would have to be managed in low-growing vegetation.

11.3.3.2 Alternative Underground Route along Existing Railroad Rights-of-Way

Eversource determined that the alignment of a cable transmission system along the ConnDOT / Naugatuck Railroad corridor would be impractical for the same general reasons as described for the routing of an overhead 115-kV transmission line (refer to Section 11.2.2.2).

⁹³ This easement would be required for the construction and subsequent operation and maintenance of the cable system. Additional easements would be required for property on which splice vaults would be located.

11.3.3.3 Alternative Underground Route along Existing Transmission Line Right-of-Way

At first glance, aligning an underground cable system within Eversource's existing ROW between Frost Bridge and Campville substation appears to offer some advantages, in terms of not only co-locating the underground and overhead transmission lines within the same corridor, but also avoiding underground cable construction conflicts with other buried utility lines and the potential for traffic congestion and similar public nuisance issues that are caused by underground cable-system construction within or adjacent to public roads. Compared to an in-road cable system, underground cable construction within an existing transmission line ROW is usually less expensive and typically has the following advantages:

- Duct banks and splice vaults can be installed at uniform depths because buried utilities are only encountered at road crossings;
- No special construction design and scheduling is required to maintain traffic flow patterns or to avoid construction conflicts with adjacent land uses; and
- Construction does not require road pavement removal or replacement.

In addition, because the existing transmission line ROW already extends between the Frost Bridge and Campville substations, it would provide the most direct (shortest) route between these two terminal points. In contrast, an underground cable system following road ROWs must follow more circuitous, and longer, routes between the two substations, and therefore are more expensive to construct and operate.

However, aligning an underground cable system within Eversource's existing overhead transmission line ROW between Frost Bridge and Campville substations is not feasible due to the extreme terrain (extensive bedrock outcrops, shallow depth to bedrock, steep slopes, and continuous access constraints) and water resources that would have to be crossed. These areas would pose difficult, if not insurmountable, obstacles in terms of underground cable-system construction.

Environmental impacts would result from the continuous trenching required for the duct banks along the ROW, the excavations for splice vaults, and the use of construction support areas along the ROW, such as material staging sites and crane pads for the vault installations. Assuming the placement of splice vaults at intervals of approximately 1,600 feet, an estimated 35 vault locations would be required for the installation of an underground cable system along the 10.4-mile ROW between Frost Bridge Substation and Campville Substation.

The construction of the duct bank would involve not only continuous trenching, but also the use of an estimated 40-foot-wide construction work space along the length of the ROWs. Within this construction

work space, all vegetation would have to be removed, grading and filling would have to be performed as necessary, and a construction access road must be developed. Overall, based on the minimum use of a 40-foot-wide work space along the 10.4-mile route, cable-system construction would directly affect a minimum of approximately 50 acres; some of this acreage is already managed in low growth vegetation for compatibility with the existing overhead transmission lines in the corridor. Additional land would be affected by splice vaults and the temporary equipment and material staging sites.

In addition, a permanent, typically 20-foot-wide access road would typically be required along the cable route. Some of Eversource's existing on-ROW access roads could likely be used. However, all of these roads would likely have to be improved to provide a permanent, contiguous road adjacent to the cable system. The access road would traverse wetlands along the ROWs, where the permanent fill would constitute a long-term loss of wetland habitat.

Furthermore, Eversource's easements for overhead transmission lines along the ROW do not uniformly encompass the use of the ROW for underground cable installation. In these cases, Eversource would have to purchase additional easement rights for the development of an underground cable system from private landowners.

For these and cost reasons, the development of an underground 115-kV cable system within Eversource's ROW was determined to be impractical.

11.3.3.4 Alternative Routes along Highway Rights-of-Way

Eversource investigated possible cable-system alignments along various road ROWs in the Project area. In-road alignments for underground cable systems usually offer environmental advantages, particularly if the underground cable construction can be confined principally to paved or previously disturbed portions of the road ROWs. As a result, compared to underground line construction in overhead transmission line ROWs, in-road cable-system construction would typically affect fewer environmental resources (e.g., forested areas, wetlands) and fewer cultural resources.

To install the underground cable system within road ROWs, an approximately 40-foot-wide working area would be required adjacent to or within the existing highway travel lanes. The exact location of the cable system would depend on agreements with ConnDOT (for state highways) or local highway authorities. Eversource's recent 345-kV and 115-kV underground cable systems have been installed primarily along non-limited access state road ROWs. An encroachment agreement must be negotiated between

Eversource and ConnDOT for the use of the road ROWs. For the most part, although the cable duct banks may be aligned beneath the highway pavement, ConnDOT does not permit the location of splice vaults within paved road ROWs. As a result, Eversource typically must obtain easements for splice vaults and the associated cable-duct-bank interconnections from private landowners.

If the underground cable system could not be installed within public road ROWs, the availability of land for a transmission line easement, without having to displace homes or businesses located adjacent to the highways, would be a major concern. Furthermore, the costs and schedule of acquiring easements for the cable system from private landowners would be significant.

Key construction, engineering, maintenance, and environmental issues related to the identification and evaluation of potentially viable routes for an underground cable system within or adjacent to public road ROWs in the Project region included:

- Presence of road embankments and elevated portions of road ROWs, which would make cable-system excavations difficult.
- Presence of areas of rock, where excavation would potentially require highway closures for blasting.
- Location of wetlands and waterways adjacent to or crossed by the road ROWs, beneath which the underground cable system would have to be buried.
- Construction and future maintenance activities causing traffic delays and congestion.
- ConnDOT policy of not allowing co-location of transmission lines within and parallel to the ROWs of limited access highways.
- Taking these factors into consideration, an alignment of an underground cable system within or adjacent to State Route 8 was quickly eliminated from consideration due to insurmountable cost, constructability, and environmental constraints. The two potential routes involving underground cable systems that Eversource evaluated in greater detail are illustrated on Figure 11-1 and discussed in Sections 11.3.3.5 and 11.3.3.6.

11.3.3.5 Road Rights-of-Way Underground Alternative Route

Eversource assessed the alignment of the new 115-kV transmission line, as an underground cable system, along various road ROWs. Roads were investigated for the potential cable system, taking into consideration the objectives of minimizing the overall length of the route, avoiding or minimizing adverse

environmental and social effects; and minimizing cable-system costs.⁹⁴ Accordingly, Eversource identified an 11.2-mile route that would use a combination of state and local road ROWs to optimize the alignment of the cable system (refer to Figure 11-1 and to Table 11-4, which identifies the public road ROWs along which the route would be aligned).⁹⁵

Table 11-4: Summary of ROWs along Road ROWs Underground Alternative Route

Existing ROW Followed by Underground Route	Distance (miles)*	Town
Frost Bridge Substation to Campville Substation		
OVERHEAD TRANSMISSION SEGMENT		
Frost Bridge Substation (Overhead tap across the Naugatuck River)**	0.2	Watertown/Thomaston
UNDERGROUND CABLE SYSTEM		
Waterbury Road (State Routes 262, 848, and 254)	3.8	Thomaston
Waterbury Road (State Hwy 254)	0.2	Thomaston
South Main Street (State Routes 254 and 807)	1.0	Thomaston
Clay Street	0.6	Thomaston
High Street Extension	1.3	Thomaston
Campville Road	2.6	Litchfield
Northfield Road	0.2	Litchfield/Harwinton
Valley Road	0.1	Harwinton
Campville Hill Road	1.0	Harwinton
Wildcat Hill Road	0.1	Harwinton
Campville Substation (Access Road)	0.1	Harwinton
TOTAL	11.2	

** Near existing overhead ROW

* Mileage estimates rounded to nearest tenth.

Along approximately 11 miles of the route, the new 115-kV line would be configured as an underground cable system; the remaining 0.2-mile segment of the route, extending east from Frost Bridge Substation, would be aligned overhead across the Naugatuck River, before transitioning to underground cable.

⁹⁴ Note: Any underground 115-kV cable system for the Project would be significantly more costly than an overhead 115-kV line. Consequently, the goal in the underground cable-route alternatives evaluation was to identify the most potentially desirable underground cable alignment - that is, the route that would minimize the costs and environmental and social effects compared to other cable routing options.

⁹⁵ The use of this underground route alternative would avoid the alignment of a new 115-kV transmission line along Eversource's existing ROW; however, as part of the Project, the 1191 and 1291 Line circuits would still be separated along the Eversource ROW at the Naugatuck River crossing. This work would require construction activities along the Eversource ROW from approximately State Route 8 in the Town of Litchfield northeast to the Valley Road area in the Town of Harwinton.

The alternative route was selected to maximize, to the extent possible, conformance to Eversource's routing objectives and underground cable-system routing criteria. For example, as illustrated in Figure 11-1 and summarized in Table 11-4, the Road ROWs Underground Alternative Route would follow both state and local roads.

The development of the cable system along the highway ROWs would involve the land requirements and construction procedures detailed in Section 11.3.2. If the underground transmission line could not be installed within the road ROWs (due to conflict with ConnDOT policy, etc.), the availability of adjacent land for the installation and operation of the cable system, without having to displace homes or businesses located adjacent to the highways, would be a major concern. Furthermore, the costs and schedule impacts of acquiring easements from private landowners would be significant. Table 11-5 summarizes the key characteristics of the combined underground line-route.

Table 11-5: Summary of Key Features: Road ROWs Underground Alternative Route

Characteristic	Description
ROW / Land	(Miles / Acres)
Underground Within or Adjacent to Road ROWs	10.9 miles
Underground Within Eversource Property	0.1 miles
Overhead Within Eversource Property or ROW	0.1 miles
Overhead Within New ROW	0.1 miles
Total	11.2
Towns Traversed by Route	(Miles)
Watertown	0.1
Thomaston	6.9
Litchfield	2.8
Harwinton	1.4
Highway Characteristics	% along each lane type
Two-lane State Roads (State Hwys 848, 254 and 807)	45%
Two-lane Local Roads (Clay Street, High Street Ext, Campville Road, Northfield Road, Valley Road, Campville Hill Road, and Wildcat Hill Road)	55%
Adjacent Land Use	(Percent of Total Route)
Residential	44%
Commercial	10%
Public	10%
Forested	19%
Undeveloped (Open Land)	4%
Industrial	13%
Total	100%
Watercourse Crossings	(Number)
Major crossings (Naugatuck River)	3
100-year floodplain crossings (Naugatuck River)	4,450 linear feet
Wetlands Crossed*	(Number)
Underground Portion along Road ROWs	12
Overhead Portion adjacent to Transmission line ROW	1
Railroad Crossings	(Number)
ConnDOT and Naugatuck Railroad Company	3

*Wetland crossings identified based on the review of publically available GIS data, typically underestimates wetland resources.

The cable system would have to be installed across all of the watercourses using methods such as a bridge attachment (if the bridges have the design capacity to handle the weight of the cable system and if ConnDOT permits the attachment) or a trenchless crossing method (jack and bore, HDD). In addition, the cable system would have to also need to be installed beneath State Route 8 and railroads using HDD or horizontal bores. The installation of the cable system beneath watercourses, roads, and railroads would also require substantial staging areas, typically on private property, on either side of the crossing in order to position construction equipment and materials.

Except for the isolated crossings where trenchless technologies (such as HDD or jack and bore) could be used, the cable-system installation would require continuous excavations for the duct banks, as well as excavations for the splice vaults. As described previously, ConnDOT would likely require that splice vaults be located outside of state road ROWs, which would require the acquisition of easements from private property owners and land disturbance on such private property. Furthermore, where the cable system could be installed within the paved portions of the road ROWs, lane closures (resulting in traffic delays), trench dewatering (where groundwater is encountered), and trimming of trees overhanging or adjacent to the ROWs, would be required.

The majority of the road ROWs along which the route would be located were selected because they are generally wide enough to accommodate the construction of a cable system, using lane closures, rather than full road closures. However, these roads also represent important components of the regional highway system. As a result, they generally traverse more developed areas and, in some locations, residential, commercial, and industrial uses about the road ROWs. Such land uses would be affected in areas where the construction or alignment of the cable system would have to occur on private property (e.g., at splice-vault locations, or areas where in-street buried utilities leave no space for the cable system).

Although the road ROW route reflects the optimal “all-underground” cable system between Frost Bridge and Campville substations, this alternative is not a practical, cost-effective, or environmentally-sound solution for meeting the Project objectives. Compared to an overhead transmission line configuration along the existing Eversource ROW, the use of the cable system along the road ROW route would be significantly more expensive and would require substantially more time to construct, delaying the Project’s scheduled energization by at least one year.

As explained in Section 11.3.1.3, most of the costs of constructing an overhead transmission line are expected to be shared with the rest of New England. However, the significantly higher costs of building the same line underground would be expected to be recovered from Connecticut consumers alone and that incremental increased cost would be dramatically higher than that of an overhead line.

As previously stated, the estimated capital cost for the construction of the new 115-kV transmission line overhead is approximately \$51 million⁹⁶. In comparison, the estimated initial cost for the road ROW underground alternative is estimated at approximately \$328 million. Similarly, the life-cycle cost, which reflects the estimated capital cost and the anticipated maintenance costs of a project over its anticipated useful life, also would be substantially greater for the underground cable system along the road ROW route alternative than for an all-overhead 115-kV transmission line, installed along Eversource's ROW. Specifically, the life-cycle cost for the proposed overhead transmission lines is estimated to be approximately \$76 million. For all-underground transmission lines, the life-cycle cost is estimated to be approximately \$540 million.

In sum, although identified to minimize, to the extent possible, the effects typically associated with cable-system construction and operation, the road ROW route alternative between the Frost Bridge and Campville substations nonetheless does not represent a practical, cost-effective, or environmentally-sound solution for meeting the Project objectives. Construction of the alternative would be prohibitively costly, would require more time to construct, would disrupt local traffic patterns, would result in potential environmental impacts associated with major watercourse crossings and land use/soil disturbance adjacent to roads, and would be more difficult to operate within the system than a comparable overhead line. For these reasons, this alternative route was eliminated from further consideration as a viable option.

⁹⁶ Note: All cost estimates include the approximately \$5.5 million for separating the two existing 115-kV circuits in the Naugatuck River crossing vicinity.

11.3.3.6 Overhead Variation to Portion of Road Rights-of-Way Underground Alternative Route

Eversource assessed the combination of both highway and transmission line ROWs to achieve the objectives of minimizing the overall length of the route, avoiding or minimizing adverse environmental effects, and minimizing impacts to the community and cable-system costs.⁹⁷ Accordingly, Eversource identified an approximately 9.8-mile route that would consist of:

- The same combination of ROWs (including an underground cable system along approximately 7.8 miles of road ROWs in the towns of Watertown, Thomaston, and Litchfield and the 0.2-mile overhead segment extending east from Frost Bridge Substation⁹⁸) as described for the “all underground” cable system in Section 11.3.3.5; and
- An approximately 1.8-mile segment of Eversource’s existing ROW between Campville Road (Town of Litchfield) and Campville Substation, along which the route would be aligned in an overhead configuration.

As illustrated in Figure 11-1, this route variation would diverge from the Road ROWs Underground Alternative Route at the intersection of Eversource’s existing ROW and Campville Road in the Town of Litchfield. At this point, the 115-kV line would transition from underground to overhead, following Eversource’s existing ROW northeast to the Campville Substation. The configuration of the overhead line segment would be as shown on XS-4 through XS-6 for the proposed Project (refer to Volume 1, Section 3).⁹⁹

Table 11-6 summarizes and compares the key features of this variation compared to the portion of the “all underground” cable route that it would replace. The combined underground / overhead route would have the same issues as described in Section 11.3.3.5 and would be significantly more costly than an overhead line built along Eversource’s existing ROW.

As previously stated, the estimated cost for the construction of the new 115-kV transmission line overhead is approximately \$51 million. In comparison, the estimated cost for the Road ROW underground alternative would be approximately \$264 million. Similarly, the life-cycle cost, which

⁹⁷ Note: Any underground 115-kV cable system for the Project would be significantly more costly than an overhead 115-kV line. Consequently, the goal in the underground cable-route alternatives evaluation was to identify the most potentially desirable underground cable alignment - that is, the route that would minimize the costs and environmental and social effects compared to other cable routing options.

⁹⁸ The 0.2-mile overhead segment would extend east from Frost Bridge Substation, crossing the Naugatuck River, before transitioning to an underground cable configuration.

⁹⁹ Using this route alternative, the construction activities to separate the 1191 and 1291 circuits at the Naugatuck River crossing would be combined with the new 115-kV overhead transmission line work along Eversource’s ROW.

reflects the estimated capital cost and the anticipated maintenance costs of a project over its anticipated useful life, also would be substantially greater for the underground cable system along the road ROWs route alternative than for an all-overhead 115-kV transmission line, installed along Eversource's ROW. Specifically, the life-cycle cost for the proposed overhead transmission lines is estimated to be approximately \$76 million. For all-underground transmission lines, the life-cycle cost is estimated to be approximately \$432 million.

**Table 11-6: Comparative Summary of Key Features: Road ROWs Underground
Alternative with and without the Litchfield-Harwinton Overhead Variation**

Characteristic	Description	
	All Underground Road ROW Route Alternative	Combined Road ROW Route Alternative with Overhead Variation
ROW / Land	(Miles / Acres)	(Miles / Acres)
Underground Within or Adjacent to Road ROWs	10.9 miles	7.7 miles
Underground Within Eversource Property	0.1 miles	0.1 miles
Overhead Within Eversource Property or ROW	0.1 miles	1.9 miles
Overhead Within New ROW	0.1 miles	0.1 miles
Total	11.2 miles	9.8 miles
Towns Traversed by Route	(Miles)	(Miles)
Watertown	0.1	0.1
Thomaston	6.9	6.9
Litchfield	2.8	1.6
Harwinton	1.4	1.2
Highway Characteristics	% along each lane type	% along each lane type
Two-lane State Roads (State Routes 262, 848, 254 and 807)	45%	35%
Two-lane Local Roads (Clay Street, High Street Ext, Campville Road, Northfield Road, Valley Road, Campville Hill Road, and Wildcat Hill Road)	55%	65%
Adjacent Land Use	(Percent of Total Route)	(Percent of Total Route)
Residential	44%	33%
Commercial	10%	12%
Public	10%	10%
Forested	19%	28%
Undeveloped (Open Land)	4%	4%
Industrial	13%	13%
Total	100%	100%
Watercourse Crossings	(Number)	(Number)
Major crossings (Naugatuck River)	3	3
100-year floodplain crossings (Naugatuck River)	4,450 linear feet	930 linear feet
Wetlands Crossed	(Number)	(Number)
Underground Portion along Road ROWs	12	6
Underground Portion along Transmission line ROW	-	0
Overhead Portion along or adjacent to Transmission line ROW	1	10
Railroad Crossings	(Number)	(Number)
ConnDOT and Naugatuck Railroad Company	3	3

11.4 JUSTIFICATION FOR THE SELECTION OF THE PROPOSED TRANSMISSION LINE ROUTE AND CONFIGURATION

After considering various alternative technologies and routes for the Project, Eversource identified an overhead line as the preferred configuration and the use the existing transmission line ROW as the preferred alignment for the new 115-kV line between Frost Bridge and Campville substations. This proposed route and configuration meets all Project objectives and represents the most cost-effective, least environmentally damaging practical alternative.

The proposed route and overhead line design represent the optimal Project configuration for the following reasons:

- **Maximizes the Use of Existing ROW and Avoids the Need to Acquire Additional Property for Utility Use.** The new overhead 115-kV line would be located entirely within Eversource's existing ROW, which is already devoted to utility use and has sufficient unutilized space to accommodate the new lines without requiring relocation of the existing lines or the acquisition of additional easements.
- **Minimizes Environmental and Land Use Effects.** Although temporary effects to site-specific environmental resources would occur as a result of the construction and operation of the proposed 115-kV transmission line within Eversource's existing ROW, the development of the Project along this existing utility corridor would be consistent with federal, state, and local land use policies and would minimize long-term adverse environmental impacts.
- **Achieves a Reliable, Operable, and Cost-Effective Solution.** The proposed route and overhead line design represent the most cost-effective alternative to Connecticut consumers and offer the optimal solution to the defined reliability issues.

NOTE: This page left blank intentionally

APPENDIX 11A - UNDERGROUND CABLE CONSTRUCTION

Note: This page left blank intentionally

INTRODUCTION

This appendix provides information regarding the construction procedures that would generally be used to install an underground XLPE 115-kV transmission cable system. The appendix includes the following information:

- The typical construction activities and sequence for underground cable-system installation within or adjacent to road ROWs;
- The different construction procedures that would be required to development of a cable system outside of road ROWs (e.g., along transmission line ROWs or along a “greenfield” utility corridor);
- Data regarding specific underground cable construction considerations (e.g., splice vault locations, erosion controls, traffic management).

11A.1 General Construction Sequence: Cable Systems in or Adjacent to Road ROWs

Underground transmission cable systems are most often situated within or adjacent to public roads. Public roads provide both linear corridors for the cable route and roadway access along the entire cable system for construction and maintenance. This section summarizes the typical construction activities involved in underground cable installation within or adjacent to roads.

The sequence in which some of these activities are performed depends on site-specific factors and construction scheduling. The types of activities generally involved in a 115-kV cable system installation along or adjacent to a road ROW are summarized below.

Most of the following activities also apply to underground cable construction outside of road ROWs. (Refer to Section 11A.2 for additional information regarding the differences in cable-system installation and operation in non-road areas).

Cable-System Land Requirements and General Sequence


Construction Staging, Storage, and Laydown Areas. Cable-system construction requires construction contractor yard(s), as well as a combination of other staging, storage, and laydown support areas. These areas, which typically would range in size from 2 to 5 acres, would optimally be located on previously disturbed sites and would be selected based on availability and proximity to work locations. Construction support sites near the cable-system route are preferred to facilitate the construction work and to minimize adverse effects on traffic resulting from the movement of equipment and materials to work sites.

- Generally, these support sites would be used for construction offices, parking for workers' personal vehicles, equipment staging, the storage of cable-system construction materials (e.g., conduit, trench boxes, backfill), and the temporary storage of excavated materials (e.g., rock, soil, dewatering wastewater).
- **Install Erosion Controls and Pavement Cutting / Removal.** The first step in the construction process would be to deploy appropriate erosion and sedimentation controls (e.g., catch basin protection, silt fence, or straw bales) at locations where pavement or soils would be disturbed. Within roads and other paved areas, the pavement over the cable route and splice vault locations would then be saw-cut and removed.
- **Excavate and Install Splice Vaults.** At approximately 1,600-to-2,000-foot intervals along the cable route, pre-cast concrete splice vaults would be installed below ground. The length of an underground cable section between splice vaults (and therefore the location of the splice vaults) is determined based upon engineering requirements (such as maximum allowable pulling tensions, the cable weight/length that can fit on a reel and be safely shipped, and cross-bonding requirements) and land constraints. The specific locations of splice vaults would be determined during final engineering design, and in some areas, distances between vaults could be significantly less than the typical 1,600-to-2000-foot interval stated above.
- The outside dimensions of splice vaults for 115-kV XLPE cables are approximately 9 feet wide by 9 feet high and up to 24 feet long. The installation of each splice vault therefore typically requires an excavation area approximately 13 feet wide, 13 feet deep, and 30 feet long. The actual burial depth of each vault would vary, based on site-specific topographic conditions and on the depth of the adjacent cable sections that must interconnect within the vault (the depth of the cables at any location would be based on factors such as the avoidance of other buried utilities).
- For safety purposes, the splice vault excavations would be shored and fenced. Vault sites may also be isolated by concrete (Jersey) barriers or the equivalent. Vault installation within roadways may require the closure of two travel lanes in the immediate vicinity of the vault construction. Each vault would have two entry points to the surface. The splice vaults would be installed at a minimum depth of cover (depth from existing ground surface to top-of-vault) of approximately 2.5 feet. Backfill would be placed on top of each vault to bring the ground surface back to the pre-construction elevation. After backfilling, these entry points are identifiable as manhole covers, which are set flush with the ground or road surface.
- **Trench and Install Duct Bank.** To install the duct bank for the XLPE-insulated cables, a trench typically 7 to 10 feet deep and approximately 5 feet wide would be excavated within a typical linear 30-to-40-foot-wide construction area. This trench would typically be stabilized using trench boxes or another type of shoring.
- Excavated material (e.g., pavement, subsoil) would be placed directly into dump trucks and hauled away to a suitable disposal site, or hauled to a temporary storage site for screening/testing prior to final disposal or re-use in the excavations for backfill. If groundwater is encountered, dewatering would be performed in accordance with authorizations from applicable regulatory agencies and may involve discharge to catch basins, temporary settling basins, frac tanks, surface waters, or vacuum trucks.
- Because underground cable installation would involve both the excavation of a continuous trench and areas for splice vaults, it is very probable that rock would be encountered. Such rock would have to be removed using mechanical methods, or possibly mechanical methods supplemented by drilling and controlled blasting. Should drilling and controlled blasting be necessary for the underground cable, it would be performed only pursuant to a plan incorporating multiple

safeguards that would be subject to specific approval by the Council, and in consultation with local authorities.

- The duct bank system that would be required for this Project, which is a function of both the system voltage and the required loading, would consist of six 6-inch polyvinyl chloride (PVC) conduits for the XLPE-insulated cables, two 6-inch PVC conduits as spare power cable conduits, two 2-inch PVC conduits for the ground-continuity conductors, two 4-inch PVC conduits for the fiber optic relaying cables, and two 2-inch conduits for the temperature-sensing fiber optic cables. Figure 11A-2 illustrates this 115-kV duct bank cross-section.
- The conduit would be installed in sections, each about 10 to 20 feet long, and would have a bell and spigot connection. Conduit sections would be joined by swabbing the bell and spigot with glue and then pushing the sections together. After installation in the trench, the conduits would be encased in concrete. The duct bank would then be backfilled with approved backfill with sufficient thermal characteristics to dissipate the heat generated by the cable system.
- Trenching, conduit installation, and backfilling would proceed progressively along the route such that relatively short sections of trench (under favorable conditions, typically 200 feet per crew) would be open at any given time and location. During non-work hours, temporary cover (steel plates) would be installed over the open trench within paved roads to maintain traffic flow over the work area. After backfilling, the trench area would be repaved using a temporary asphalt patch or equivalent. Disturbed areas would be permanently repaved as part of final restoration.

Figure 11A-2: Typical Duct-Bank Cross Section for 115-kV XLPE Cables System and Project Loading



- **Trenchless Duct Installation.** The installation of an underground cable system beneath certain obstacles (such as waterways, railroads, and limited-access highways) where excavating an open trench may present constructability or regulatory issues, may require the use of trenchless construction methods. Trenchless installation involves subsurface excavation to align the cable duct beneath the obstacle in question.
- Two trenchless installation methods are typically used in underground cable construction – horizontal directional drilling (HDD) and horizontal boring. HDD involves the excavation of a bore along a curved path starting and ending near the ground surface on either side of the obstacle. As necessary, the bore path is enlarged from its initial size with successive passes with larger drill heads. Once the final bore path diameter is reached, the pre-assembled conduit package is pulled through. Alternatively, a horizontal bore involves the excavation of a vertical shaft on each side of the obstacle, and then the excavation of a straight, horizontal bore between the two shafts. Various methods exist to accomplish this, including pipe jacking, auger boring, and microtunneling; with the choice of method a function of bore length, size, soil conditions, and presence of ground water.
- Any trenchless installation technique involves staging areas on either side of the subsurface crossing. These staging areas, which typically must be at least 0.3 acre on the launching side and 0.1 acre on the receiving side, are required to accommodate the specialized HDD and boring equipment, as well as the materials needed for the subsurface crossing.
- **Duct Swabbing and Testing.** After the vaults and duct bank are in place, the ducts would be swabbed and tested (proofed), using an internal inspection device (mandrel) to check for defects. Mandrelling is a testing procedure in which a ‘pig’ (a painted aluminum or wood cylindrical object slightly smaller in diameter than the conduit) is pulled through the conduit. This is done to ensure the ‘pig’ can pass easily, verifying the conduit has not been crushed, damaged, or installed improperly. After successful proofing, the transmission cables and ground-continuity conductors would be installed and spliced. Cable reels would be delivered by special tractor trailers to the vaults, where the cable would be pulled into the conduit using a truck-mounted winch and cable handling equipment.
- **Cable Installation.** To install each transmission cable and ground-continuity conductor within the conduits, a large cable reel would be set up over a splice vault, and a winch would be set up at one of the adjacent splice-vault locations. The cables and ground-continuity conductors (during separate mobilizations) would then be pulled into their conduits by winching a pull rope attached to the ends of each cable. In a separate pulling operation, the splice vaults would also be used as pull points for installing the temperature-sensing fiber optic cables. Additionally, pull boxes would be installed near the splice vaults for the pulling and splicing operations required for the remaining fiber optic cables.
- **Cable Splicing.** After the transmission cables and ground-continuity conductors are pulled into their respective conduits, the ends would be spliced together in the vaults. Because of the time-consuming and precise nature of splicing high-voltage transmission cables, the sensitivity of the cables to moisture (moisture is detrimental to the life of the cable), and the need to maintain a clean working environment, splicing XLPE-insulated cables involves a complex procedure and requires a controlled atmosphere. The ‘clean room’ atmosphere would be provided by an enclosure or vehicle that must be located over the manhole access points during the splicing process.
- It typically takes 7 to 10 days to complete the splices in each vault (three XLPE 115-kV cable splices in each splice vault). Each cable and associated splice would then be stacked vertically and supported on the wall of the splice vault.

- **Cable Termination.** At each end of a 115-kV cable system, termination equipment is required. This would consist of steel structures on which the cable terminations would be mounted. The duct bank itself would be routed to the termination structure, and the ducts turned to vertical to allow the cables to be pulled up and out of the duct bank and attached to the terminations assemblies. The terminations are typically located with substations on each end of the underground cable system; however, terminations could also be located where an overhead line segment transitions to underground or vice versa.
- **Restoration.** After the installation of the duct banks and splice vaults, disturbed road ROWs or other paved areas (e.g., parking lots) would be restored to appropriate grade levels and re-paved. Sidewalks, curbs, and road shoulder or median areas affected by construction also would be restored. Non-paved areas affected by construction (e.g., vegetated road shoulders, lawns, or other previously vegetated areas disturbed by cable-system construction) would be seeded, mulched, and allowed to vegetate.

11A.2 Additional Requirements for Cable-System Construction Outside of Road ROWs

To install and operate a transmission cable system within or adjacent to non-road ROWs (such as Eversource's existing overhead transmission line ROW) or along an entirely new cross-country ("greenfield") ROW, the ROW requirements and typical construction procedures described in Section 11A.1 would be used, with the following exceptions:

- **Construction Workspace.** Because the cable system would not be aligned along existing roads, the workspace required to construct the system could be wider than 40 feet to accommodate construction equipment, trench excavation, splice vaults, and access roads along the entire cable route. Additional ROW width and temporary construction work spaces also could be needed in certain areas to account for topography and subsurface conditions, which may affect the width of the excavations that would be required to achieve the specified cable and splice vault depths. The required width of the construction workspace would depend on site-specific conditions.
- **Easement Requirements.** Eversource might need to purchase easements from private landowners for an underground cable system installed outside of road ROWs, even for transmission cables aligned along its own overhead transmission line ROW (where the existing easements do not encompass sufficient rights for underground transmission systems). Permanent underground easements would have to be acquired.
- **Vegetation Clearing and Grading.** For any cable system located outside of paved corridors, all vegetation would have to be cleared and removed along the entire width of the construction ROW, which would then have to be graded both to create an access road along the length of the cable route and to achieve appropriate elevations for the installation of the duct banks and splice vaults. Additional construction work spaces, such as in areas of side slopes, wetlands, and adjacent to stream crossings, and temporary construction support areas (e.g., crane pads adjacent to splice vaults, temporary material staging sites) also would have to be cleared and graded as appropriate to site-specific conditions. Because the Project region is characterized by rugged, forested, terrain with bedrock outcrops, shallow depth to bedrock, and multiple water resources (wetlands and streams), the vegetation clearing and grading that would be required to create an acceptable ROW for an underground cable system would involve significant environmental impacts. Extensive hammering and/or blasting would be required to create level grades for work pads and for the cable system ROW, permanently altering topography along the cable route.

- **Access Roads.** Because permanent access would be required along the entire route for cable-system maintenance purposes (i.e., for immediate access to the duct banks and splice vaults), gravel-type roads, with a typical 20-foot-wide travel area, would likely be developed during the construction phase. The roads would have to be constructed to handle all anticipated construction equipment and material deliveries, including trench boxes, concrete trucks, splice vaults, cranes, and cable reel trucks. Access road construction would involve cutting and filling activities (including permanent fill in wetlands along the cable route), as well as the installation of permanent watercourse crossings (e.g., culverts, bridges) as needed.
- **Erosion and Sedimentation Controls.** Because of the soil disturbance along the length of the cable-system route, erosion and sedimentation controls would have to be deployed and maintained both along and across the ROW as necessary to minimize the potential for impacts to adjacent properties and to environmental resources. Soil erosion and sedimentation controls would consist of the measures as summarized in Section 11A.1. Where the ROW intersects public roads, crushed stone anti-tracking pads would have to be installed along the ROW to minimize the amount of soil tracked onto the pavement from construction-related activities.
- **Restoration.** Restoration activities would consist of reseeded and mulching disturbed soil areas. With the exception of the permanent access road, disturbed areas would be allowed to revegetate, but would be managed in low-growth vegetation, consistent with the operation of the underground cable system.

Underground cable-system construction outside of roadway ROWs also typically must address site-specific environmental conditions. For example, wetlands are typically characterized by soils that are relatively poor in terms of thermal characteristics for heat dissipation, compared to granular soils typically found beneath roadways. Organic soils require over-excavation, or the use of different phase spacing within the duct bank. In addition, wetlands and watercourses could pose significant obstacles to underground construction, requiring either direct trenching or costly and time-consuming trenchless duct-bank installation methods (such as jack and bore or horizontal directional drill [HDD], both of which would require potentially extensive staging areas on either side of the water crossing).

11A.3 Splice-Vault Requirements

Due to current-carrying limitations and the assumed underground duct-bank configuration requiring two cables per phase, two separate splice vaults would be required at each cable-splice interval along the length of an underground line. The outside dimensions of a splice vault for 115-kV XLPE cables are approximately 9 feet wide by 9 feet deep and up to 24 feet in length (one vault per three XLPE cables).

The installation of each splice vault therefore requires an excavation area approximately 13 feet wide, 13 feet deep, and 30 feet long. At each splice-vault location, pre-cast splice vaults would be installed below ground. Splice vaults located along, but outside of public road ROWs, require a minimum of 12,000 square feet of permanent easement for future access to perform maintenance and repairs. An additional

minimum 4,300 square feet of temporary easement would be required for cable-system construction. Therefore, the construction of each vault would require approximately 0.4 acre (exclusive of access).

Along a cable route, the actual burial depth of each vault would vary, depending on site-specific topographic conditions and the depth of the interconnecting duct bank. For cable systems aligned along roads, the below-grade elevation of the duct banks (and therefore the depth at which vaults must be placed) often depends on the depth required to avoid conflicts with other buried utilities.

Vaults may be installed beneath public road travel lanes or, in order to avoid conflicts with other utilities buried beneath the roads, may be installed in other suitable locations adjacent to roads (e.g., beneath parking lots, sidewalks, road shoulders, road medians). However, in locations where the duct bank extends beneath a road but vaults must be installed off-road, the duct bank may need to cross other parallel buried utilities twice to interconnect each vault, greatly complicating the cable-system design and construction process.

For cable-systems aligned along linear corridors other than road ROWs (e.g., Eversource's overhead transmission line ROW, railroad ROW), vaults would be installed within or adjacent to these ROWs so as to avoid conflicts with the existing facilities. However, along such ROWs, vault installation may be more difficult due to factors such as unfavorable topographic conditions (e.g., need for grading or filling, presence of rock that must be excavated and removed, dewatering needs, and needs for developing and maintaining suitable access for the heavy construction equipment such as cranes). Extra work areas adjacent to the vaults also would be required for crane pads, which would be needed to place each vault. The crane-pad area required at each splice vault would be approximately 80 feet wide by 130 feet long.

11A.4 Temporary Erosion and Sedimentation Controls

Temporary erosion and sedimentation controls (e.g., silt fence, hay/straw bales, filter socks, inlet and catch basin protection) would be installed as needed prior to or in conjunction with the commencement of cable-system construction activities that would involve soil disturbance. The controls would be installed in compliance with the 2002 Connecticut *Guidelines for Soil Erosion and Sedimentation Control*. The need for, type, and extent of erosion and sedimentation controls would be a function of considerations such as:

- Whether the underground cable route is within or adjacent to road ROWs or along Eversource transmission line or other utility ROWs (for example, catch basin protection would be required for cable-system construction within roads)

- Slope (steepness, potential for erosion) and presence of resources, such as wetlands or streams, at the bottom of the slope
- Type of soil disturbed
- Soil moisture regimes
- Schedule of future construction activities
- Proximity of cleared areas to water resources, roads, or other sensitive environmental resources
- Time of year, as this dictates the types of erosion and sedimentation control methods for a particular area. For example, re-seeding is not typically effective during the winter months. In winter, with frozen ground, controls other than re-seeding (such as wood chips, straw and hay, geotextile fabric, waterbars, or crushed stone) would be used to stabilize disturbed areas until seeding can be performed.
- Extreme weather conditions during or immediately following soil disturbance.

11A.5 Vegetation Clearing (Within / Adjacent to Roads vs. Other Sites)

Only minimum vegetation clearing is typically required for underground cable-system construction within or adjacent to road ROWs. Some landscaping or other vegetation bordering the cable route within roads may need to be removed or trimmed to allow the safe operation of construction equipment, and vegetation also would have to be removed at off-road splice vault locations (unless the vaults are located in paved areas). Similarly, vegetation may be affected by temporary staging or material storage sites.

In contrast, underground cable-system construction within Eversource's transmission line ROWs or other non-roadway corridors would involve the removal of all vegetation within a typical minimum 40-foot-wide construction work area. Additional vegetation clearing would also be needed at the locations of line transition stations, splice vaults, splice vault work (crane) pads, and staging areas.

11A.6 Special Procedures: Rock Removal (Drilling/Blasting), Dewatering, Material Handling

Based on a review of field conditions, it is likely that the excavations for any cable system would encounter rock and groundwater in many locations. Compared to the installation of overhead transmission line structures at defined locations, underground cable construction, which involves both the excavation of a continuous trench and areas for splice vaults, would require substantially more rock digging and removal and would require the management of significantly greater quantities of both dewatering wastewater and excavated soils. All of these excavated materials must be properly disposed.

Generally, rock encountered during underground cable-system construction would be removed using mechanical methods, or mechanical methods supplemented by controlled drilling and blasting. If drilling

and blasting are necessary, Eversource would adhere to the same standard procedures as described for the overhead transmission line construction in Volume 1, Section 4. Similarly, dewatering wastewaters and excess excavated soils would be managed as described for overhead transmission line construction in Section 4; however, substantially greater quantities of excess soil and dewatering wastewater would be involved in the underground cable-system installation. Further, dewatering could result in discharges to catch basins, sanitary sewers, temporary settling basins, tanker trucks (for eventual off-site transport), or watercourses.

11A.7 Traffic Management

Traffic issues are often of primary concern with respect to the construction of underground cable systems within or adjacent to public road ROWs. The installation of the duct banks and splice vaults typically requires temporary travel lane closures, which would potentially cause traffic disruption, delays, detours, or congestion.

To minimize traffic-related impacts, Eversource would typically coordinate with municipal and state highway authorities regarding peak and non-peak travel times in order to identify construction schedules that would limit potential interference with traffic flow along public roads. Eversource also would employ personnel to direct traffic at construction sites, and would erect appropriate traffic signs and install work area protection measures and signs to clearly denote the presence of construction work zones.

11A.8 Construction Scheduling and Work Hours

Cable-system construction is time-consuming and highly dependent on subsurface conditions. Duct-bank construction could proceed at a rate of only 50 feet / day and the excavation and installation of a splice vault could require a week to complete.

In addition, cable-system construction schedules would depend on the location of the underground route (e.g., within public road travel lanes, near developed land uses, timing for crossing of sensitive environmental resources, such as streams that support fisheries). Where underground cables are routed within public road ROWs, construction work must be coordinated with state or local highway authorities to avoid peak travel times and thus may occur at night. In contrast, in areas where the underground cable system traverses adjacent to residential areas, work would be scheduled during daylight hours, to minimize nighttime noise disturbance to residents.

Cable-system installation beneath watercourses that support fishery resources or that are classified as high quality waters would be performed and scheduled in accordance with CT DEEP and USACE requirements. Often, cables must be installed beneath larger watercourses using trenchless technologies such as horizontal directional drilling or jack and bore. Using either of these techniques, the installation of the duct bank beneath a watercourse typically requires several weeks or months to complete.

12. POTENTIAL TRANSMISSION LINE ROUTE AND CONFIGURATION VARIATIONS

As part of the process that led to the selection of the proposed route for the new 115-kV transmission line within Eversource's existing ROW or on Eversource-owned property and a preferred overhead transmission line design for each ROW segment, Eversource also evaluated the following:

- Potentially viable site-specific variations to portions of the Proposed Route, in either overhead or underground configurations; and
- Different overhead configurations (structure types) for the new 115-kV line.

These potential variations are discussed in the following sections.

12.1 ROUTE VARIATIONS: GENERAL

Except for the portion of the route in the vicinity of Frost Bridge Substation (refer to XS-1 and the discussion in Section 12.2), the proposed new transmission line would be aligned entirely within an existing Eversource ROW that has been devoted to utility use (and occupied by other overhead transmission lines) for many years. For these segments of the ROW (i.e., XS-2 through XS-6), no viable alignment variations to the proposed route were identified. Compared to the Proposed Route and overhead line design, any route variation outside of the established ROW or in an underground configuration would increase environmental impacts, community impacts, and Project costs.

12.2 FROST BRIDGE SUBSTATION LINE EXIT UNDERGROUND / OVERHEAD ROUTE VARIATIONS

In contrast to the other portions of the Proposed Route, on the Eversource property at and near the Frost Bridge Substation, the new 115-kV line would follow a new alignment (not adjacent to any existing transmission lines). In order to avoid conflicts with the existing transmission facilities that are located within and interconnect to the substation, Eversource currently proposes to extend the new 115-kV transmission line out of the southeastern side of the substation in an overhead three-pole configuration. The new transmission line then would be aligned around the eastern and the northern portions of the substation fence line. Five new three-pole structures and two new monopole structures (Structures 1A-F, Structure 2) would be required along this 0.4-mile portion of the route (refer to Figure 12-1).

In addition, this alignment would place the new 115-kV line on variable terrain upslope of the Naugatuck Railroad and the Naugatuck River and would require the new transmission line to cross existing transmission lines that interconnect to Frost Bridge Substation on the east. Due to the topography in this area, considerable cut and fill would be required to establish the access roads and work pads required to install and maintain the new structures.

As options to this overhead alignment around the substation, Eversource is in the process of investigating two different route variations for this segment, each of which would involve a short underground 115-kV transmission cable segment for the 115-kV line exit at Frost Bridge Substation and which would then transition to an overhead configuration outside the substation fence before reconnecting to the Proposed Route at new Structure 3. These underground / overhead route variations, referred to as Frost Bridge Route Variation 1 and Frost Bridge Route Variation 2, are illustrated on Figure 12-1.

For each of these variations, the underground cable segment would be located entirely within the Frost Bridge Substation or on Eversource-owned property. As Figure 12-1 shows, one variation would exit the Frost Bridge Substation to the north and the other to the west. Both route variations would extend, in an overhead configuration, over State Route 8 and Echo Lake Road. However, after exiting from the substation, Frost Bridge Route Variation 2 would be aligned along the north side of the ROW, following the same alignment as the Proposed Route. In comparison, Frost Bridge Route Variation 1 would be aligned near the center of the ROW, and would involve the replacement of one existing 115-kV lattice steel structure on the 1191 Line (Structure 3080) with a steel monopole in order to provide room for an adjacent structure (Structure 2) on the proposed 1304 Line.

The characteristics of these route variations, compared to the portion of the Proposed Route (i.e., overhead configuration around the east and north of the substation), are as follows:

Table 12-1: Comparison of Frost Bridge Line Exit OH/UG Route Variations

Feature	Proposed Route (XS-1) (all Overhead; East Exit from Substation)	Frost Bridge Route Variation 1 (West Underground Exit from Substation)	Frost Bridge Route Variation 2 (North Underground Exit from Substation)
Miles (total)	0.44	0.63	0.43
Miles (Overhead)	0.44	0.50	0.31
Miles Underground)	0	0.14	0.12
New Overhead Structures (No.)	7	4*	5*

Footnote:

* Includes (2) Riser (UG-OH Transition) Structures

Figure 12-1: Frost Bridge Substation Underground / Overhead Route Variations




Figure 12-1
PRELIMINARY - SUBJECT TO CHANGE

Either of the Frost Bridge Substation Variations would provide a more direct exit for the new line from the substation and would avoid the need for the installation of two new overhead transmission line structures (Variation 2) or three new overhead structures (Variation 1) east/north of the substation fence line. Compared to the portion of the Proposed Route that they would replace, either of the variations also would eliminate multiple overhead line crossings and also would avoid new transmission line construction outside the substation fence, in proximity to the Naugatuck River.

Project engineers are currently in the process of evaluating the technical feasibility and constructability of the underground cable portions of each route variation. These analyses involve the evaluation of the potential cable alignments within and exiting from the substation, taking into consideration the location of existing substation facilities.

As detail engineering proceeds, additional information regarding these potential underground segments is expected to be available in the Application to the Council.

12.3 STRUCTURE CONFIGURATION VARIATIONS

As part of the Project planning process, Eversource evaluated the use of three overhead structure configuration types for proposed 115-kV transmission line: steel monopoles with either a delta or vertical configuration and steel H-frames. Eversource determined that monopole type structures were preferred rather than H-frames due to constructability, less ROW clearing, less environmental impacts and more cost effective. Specifically, steel monopoles are better suited for installation along the rugged/uneven topography that characterizes most of the Proposed Route. Further, compared to H-frame structures, monopoles require less new vegetation removal to meet conductor clearance requirements to the edge of the ROW. The principal engineering, construction, and environmental factors associated with each of the three structure configurations (delta monopoles, vertical monopoles, and H-frame structures) are described briefly below and summarized in Table 12-1.

Steel Monopole Structures

Steel monopoles in delta and vertical configuration were identified as the preferred structure types for the development of the new 115-kV transmission line within the Frost Bridge Substation to Campville Substation ROW. Along the majority of the ROW, Eversource proposes to use delta steel monopole structures to support the new transmission line.

Delta steel monopoles were selected for use along most portions of the ROW because, compared to vertical steel monopole structures, they are shorter (and thus have a lower visual profile) and more cost-effective to install (shorter embedment depths), but will typically require slightly more new forested vegetation removal.

However, along the 400-foot-wide ROW segment from north of Frost Bridge Substation to Purgatory Junction in the Town of Watertown (refer to XS-2), vertical steel monopoles would be installed to optimize the use of the existing ROW usage, which already supports three other transmission lines. Similarly, in other select locations along the rest of the ROW, vertical steel monopoles are proposed to further minimize environmental impacts (e.g., to avoid a water resource or to minimize clearing within a wetland).

Appendix 12A includes cross-sections depicting the alternative use of vertical monopoles for the new 115-kV line within ROW segments 3 through 6 (i.e., XS-3, XS-4, XS-5, and XS-6).

Table 12-1: Transmission Line Structure Configuration Variations: Summary of Structure Heights and Additional Vegetation Clearing Required to Expand the Edge of the Managed Portion of the ROW

Cross-Section No.* / Description	Total Row Width (feet)	Monopole Line w/ Delta Configuration	Monopole Line w/ Vertical Configuration	H-Frame Variation Line Configuration
XS-2 (Watertown)	400			
• Structure height (typical)		90 feet	105 feet	75 feet
• Additional vegetation clearing required to expand edge of managed ROW		None	None	None
XS-3 (Watertown & Thomaston)	250			
• Structure height (typical)		90 feet	105 feet	75 feet
• Additional vegetation clearing required to expand edge of managed ROW		45 feet	35 feet	55 feet
XS-4 (Thomaston & Litchfield)	250			
• Structure height (typical)		90 feet	105 feet	75 feet
• Additional vegetation clearing required to expand edge of managed ROW		40 feet	30 feet	50 feet
XS-5 (Litchfield & Harwinton)	250			
• Structure height (typical)		155 feet	170 feet	135 feet
• Additional vegetation clearing required to expand edge of managed ROW		70 feet	70 feet	80 feet
XS-6 (Harwinton)	250			
• Structure height (typical)		90 feet	105 feet	75feet
• Additional vegetation clearing required to expand edge of managed ROW		40 feet	30 feet	50feet

*Note: This table excludes the 0.4-mile segment of the ROW extending northwest from Frost Bridge Substation (XS-1) because specific types of angle structures would be required to align the new 115-kV line around the back of the substation. Further, as discussed in Section 12.2, Eversource is in the process of assessing route variations (consisting of underground and overhead configurations) to this 0.4-mile segment of the ROW. Shading indicates proposed structure configuration.

H-Frame Structures

Cross-sections depicting views of the new 115-kV line supported on H-frame structures are included in Appendix 12B. Compared to either of the proposed monopole designs, steel H-frame structures would present a lower profile. For example, a typical 115-kV H-frame structure would be approximately 75 feet tall, compared to the typical 90-105-foot heights of the delta or vertical monopoles. However, as explained below, compared to the proposed line design, Eversource found the H-Frame line configuration variation less desirable due to constructability, engineering, environmental, and/or cost factors.

One of the existing 115-kV lines that occupy the Project ROW (i.e., the 1191 Line) is currently supported on H-frame structures. In some cases, configuring a new transmission line to match an existing line can be used to minimize incremental visual effects. However, the existing 1191 Line was installed in 1942. As a result, the H-frames used to support that line differ significantly in appearance from modern steel H-frame structures. Specifically, transmission line materials and standards have changed substantially over the last 70 years, and new H-frame structures also would be taller than the existing structures.

In addition, the use of H-frames to support the new 115-kV transmission line would pose engineering and constructability challenges, given the extreme slide slopes and steep topography within the Frost Bridge to Campville ROW. This type of rugged terrain presents construction issues associated with installing and leveling the two poles that are required for each H-frame structure.

Further, compared to the proposed monopoles, use of the wider H-frame structures would require additional forested vegetation clearing along a majority of the ROW (XS-3 through XS-6; refer to Table 12-1). If H-frames were to be used instead of the proposed monopoles along the Proposed Route, an estimated 8.84 additional acres of forest would have to be removed along the ROW to achieve the required conductor clearances, per utility industry standards.


For the above reasons, although H-frame structures may warrant site-specific consideration for short sections of the new 115-kV line, the topographic conditions that characterize most of the ROW make this structure type impractical for overall use for the entirety of the Project.

NOTE: This page left blank intentionally


Appendix 12A – Vertical Configuration Cross-Sections

Note: This page left blank intentionally

G:\GIS\CT\EversourceEnergy\N0915_43_FrostBridgetoCampville\MapDocuments\HighLevelOverview\FrostBridgetoCampville_HighLevelOverview_XSections_Letter_Portrait_A_20150903.mxd




EVERSOURCE
ENERGY



Source: CT DEEP, Tighe & Bond

**Cross-Section
Location Map**
**Frost Bridge to Campville
115-kV Project**

Note: This page left blank intentionally




**PROPOSED CONFIGURATION
3-POLE DEADEND DESIGN**

**FROST BRIDGE SUBSTATION
TO
0.4 MILE OUT OF FROSTBRIDGE SUBSTATION**

**IN THE TOWN OF
WATERTOWN**

**LOOKING
EAST, NORTH AND WEST
(0.4 MILE)**




**KEY MAP
NOT TO SCALE**

NOTES:

1. NEW TRANSMISSION LINE ALIGNMENT ON EXISTING EVERSOURCE-OWNED PROPERTY.
2. AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
3. DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL 3-POLE DEADEND STRUCTURES TO BE PLACED ON CONCRETE FOUNDATIONS. TANGENT STRUCTURES WILL UTILIZE DIRECT EMBEDDED FOUNDATIONS, WHILE VERTICAL DEADEND STRUCTURES WILL BE PLACED ON CONCRETE FOUNDATIONS.

TITLE			
FROST BRIDGE TO CAMPVILLE 115-kV PROJECT			
ALTERNATIVE VERTICAL CROSS SECTIONS			
FROST BRIDGE S/S TO 0.4 MILE OUT OF FROST BRIDGE S/S			
BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-1A
P.A. #			

Note: This page left blank intentionally




**PROPOSED CONFIGURATION
DELTA DESIGN**

0.4 MILE OUT OF FROST BRIDGE SUBSTATION
TO
PURGATORY JUNCTION

IN THE TOWN OF
WATERTOWN

LOOKING
WEST

(2.3 MILES)



KEY MAP
NOT TO SCALE




NOTES:

1. EXISTING LINES TO REMAIN.
2. PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
3. EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
4. AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
5. DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL TANGENT STRUCTURES UTILIZING CONCRETE FOUNDATIONS. ANGLE AND DEADEND STRUCTURES WILL ALSO BE PLACED ON CONCRETE FOUNDATIONS.

TITLE
**FROST BRIDGE TO CAMPVILLE 115-kV PROJECT
ALTERNATIVE VERTICAL CROSS SECTIONS
0.4 MILE OUT OF FROST BRIDGE S/S TO PURGATORY JCT.**

BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-2A
P.A. #			

Note: This page left blank intentionally




**PROPOSED CONFIGURATION
VERTICAL DESIGN**

PURGATORY JUNCTION
TO
WALNUT HILL JUNCTION
IN THE TOWNS OF
WATERTOWN & THOMASTON

LOOKING
NORTH

(3.8 MILES)



KEY MAP
NOT TO SCALE




NOTES:

- EXISTING LINES TO REMAIN.
- PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
- EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
- AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
- DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL TANGENT STRUCTURES UTILIZING CONCRETE FOUNDATIONS. ANGLE AND DEADEND STRUCTURES WILL ALSO BE PLACED ON CONCRETE FOUNDATIONS.

TITLE FROST BRIDGE TO CAMPVILLE 115-kV PROJECT ALTERNATIVE VERTICAL CROSS SECTIONS PURGATORY JCT. TO WALNUT HILL JCT.			
BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-3A
P.A. #			

Note: This page left blank intentionally




**PROPOSED CONFIGURATION
VERTICAL DESIGN**

WALNUT HILL JUNCTION
TO
SOUTH BANK OF NAUGATUCK RIVER

IN THE TOWNS OF
THOMASTON & LITCHFIELD

LOOKING
NORTH

(2.5 MILES)




KEY MAP
NOT TO SCALE

NOTES:

1. EXISTING LINES TO REMAIN.
2. PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
3. EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
4. AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
5. DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL TANGENT STRUCTURES UTILIZING CONCRETE FOUNDATIONS. ANGLE AND DEADEND STRUCTURES WILL ALSO BE PLACED ON CONCRETE FOUNDATIONS.

TITLE			
FROST BRIDGE TO CAMPVILLE 115-kV PROJECT ALTERNATIVE VERTICAL CROSS SECTIONS WALNUT HILL JCT. TO S. BANK OF NAUGATUCK RIVER			
BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-4A
P.A. #			

Note: This page left blank intentionally



250' EXISTING RIGHT-OF-WAY
NO ADDITIONAL RIGHT-OF-WAY REQUIRED

**PROPOSED CONFIGURATION
VERTICAL DESIGN**

SOUTH BANK OF NAUGATUCK RIVER
TO
NORTH BANK OF NAUGATUCK RIVER


IN THE TOWNS OF
LITCHFIELD & HARWINTON

LOOKING
NORTH

(0.4 MILE)

NOTES:


- EXISTING LINES TO REMAIN.
- PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
- EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
- AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.



KEY MAP
NOT TO SCALE

TITLE FROST BRIDGE TO CAMPVILLE 115-kV PROJECT ALTERNATIVE VERTICAL CROSS SECTIONS S. BANK OF NAUGATUCK RIVER TO N. BANK OF NAUGATUCK RIVER			
BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-5A
P.A. #			

Note: This page left blank intentionally




**PROPOSED CONFIGURATION
VERTICAL DESIGN**

NORTH BANK OF NAUGATUCK RIVER
TO
CAMPVILLE SUBSTATION

IN THE TOWN OF
HARWINTON

LOOKING
NORTH

(1.0 MILES)



NOTES:

1. EXISTING LINES TO REMAIN.
2. PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
3. EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
4. AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
5. DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL TANGENT STRUCTURES UTILIZING CONCRETE FOUNDATIONS. ANGLE AND DEADEND STRUCTURES WILL ALSO BE PLACED ON CONCRETE FOUNDATIONS.


TITLE			
FROST BRIDGE TO CAMPVILLE 115-kV PROJECT ALTERNATIVE VERTICAL CROSS SECTIONS N. BANK OF NAUGATUCK RIVER TO CAMPVILLE SUBSTATION			
BY	D. LAURSEN	CHKD	V. MONTEMURRO
DATE	8/31/15	DATE	8/31/15
SCALE	NONE	MICROFILM DATE	DWG. NO.
P.A. #			XS-6A

Note: This page left blank intentionally


Appendix 12B – H-Frame Configuration Cross-Sections

Note: This page left blank intentionally

G:\GIS\CT\EversourceEnergy\N0915\N0915_43_FrostBridgeToCampville\MapDocuments\HighLevelOverview\FrostBridgeToCampville_HighLevelOverview_XSections_Letter_Portrait_B_20150903.mxd




EVERSOURCE
ENERGY



Source: CT DEEP, Tighe & Bond

**Cross-Section
Location Map**
**Frost Bridge to Campville
115-kV Project**

Note: This page left blank intentionally



PROPOSED CONFIGURATION
3-POLE DEADEND DESIGN


FROST BRIDGE SUBSTATION
 TO
 0.4 MILE OUT OF FROSTBRIDGE SUBSTATION

IN THE TOWN OF
 WATERTOWN

LOOKING
 EAST, NORTH AND WEST
 (0.4 MILE)

NOTES:

1. NEW TRANSMISSION LINE ALIGNMENT ON EXISTING EVERSOURCE-OWNED PROPERTY.
2. AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
3. DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL 3-POLE DEADEND STRUCTURES TO BE PLACED ON CONCRETE FOUNDATIONS. TANGENT STRUCTURES WILL UTILIZE DIRECT EMBEDDED FOUNDATIONS, WHILE VERTICAL DEADEND STRUCTURES WILL BE PLACED ON CONCRETE FOUNDATIONS.




KEY MAP
 NOT TO SCALE



TITLE FROST BRIDGE TO CAMPVILLE 115-kV PROJECT ALTERNATIVE H-FRAME CROSS SECTIONS FROST BRIDGE S/S TO 0.4 MILE OUT OF FROST BRIDGE S/S			
BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-1B
P.A. #			

Note: This page left blank intentionally




**PROPOSED CONFIGURATION
H-FRAME DESIGN**

0.4 MILE OUT OF FROST BRIDGE SUBSTATION
TO
PURGATORY JUNCTION

IN THE TOWN OF
WATERTOWN

LOOKING
WEST

(2.3 MILES)




NOTES:

1. EXISTING LINES TO REMAIN.
2. PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
3. EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
4. AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
5. DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL TANGENT STRUCTURES UTILIZING DIRECT EMBEDDED FOUNDATIONS. ANGLE AND DEADEND STRUCTURES WILL DIFFER AND BE PLACED ON CONCRETE FOUNDATIONS.

TITLE FROST BRIDGE TO CAMPVILLE 115-kV PROJECT ALTERNATIVE H-FRAME CROSS SECTIONS 0.4 MILE OUT OF FROST BRIDGE S/S TO PURGATORY JCT.			
BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-2B
P.A. #			

Note: This page left blank intentionally




**PROPOSED CONFIGURATION
H-FRAME DESIGN**

**PURGATORY JUNCTION
TO
WALNUT HILL JUNCTION
IN THE TOWNS OF
WATERTOWN & THOMASTON**

**LOOKING
NORTH**

(3.8 MILES)



KEY MAP
NOT TO SCALE




NOTES:

1. EXISTING LINES TO REMAIN.
2. PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
3. EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
4. AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
5. DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL TANGENT STRUCTURES UTILIZING DIRECT EMBEDDED FOUNDATIONS. ANGLE AND DEADEND STRUCTURES WILL DIFFER AND BE PLACED ON CONCRETE FOUNDATIONS.

TITLE
FROST BRIDGE TO CAMPVILLE 115-kV PROJECT
ALTERNATIVE H-FRAME CROSS SECTIONS
PURGATORY JCT. TO WALNUT HILL JCT.

BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-3B
P.A. #			

Note: This page left blank intentionally




**PROPOSED CONFIGURATION
H-FRAME DESIGN**

WALNUT HILL JUNCTION
TO
SOUTH BANK OF NAUGATUCK RIVER

IN THE TOWNS OF
THOMASTON & LITCHFIELD

LOOKING
NORTH

(2.5 MILES)



KEY MAP
NOT TO SCALE





NOTES:

1. EXISTING LINES TO REMAIN.
2. PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
3. EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
4. AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
5. DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL TANGENT STRUCTURES UTILIZING DIRECT EMBEDDED FOUNDATIONS. ANGLE AND DEADEND STRUCTURES WILL DIFFER AND BE PLACED ON CONCRETE FOUNDATIONS.

TITLE FROST BRIDGE TO CAMPVILLE 115-kV PROJECT ALTERNATIVE H-FRAME CROSS SECTIONS WALNUT HILL JCT. TO S. BANK OF NAUGATUCK RIVER			
BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-4B
P.A. #			

Note: This page left blank intentionally



KEY MAP
NOT TO SCALE

**PROPOSED CONFIGURATION
H-FRAME DESIGN**

SOUTH BANK OF NAUGATUCK RIVER
TO
NORTH BANK OF NAUGATUCK RIVER

IN THE TOWNS OF
LITCHFIELD & HARWINTON

LOOKING
NORTH

(0.4 MILE)


NOTES:

- EXISTING LINES TO REMAIN.
- PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
- EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
- AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.

TITLE
**FROST BRIDGE TO CAMPVILLE 115-kV PROJECT
ALTERNATIVE H-FRAME CROSS SECTIONS
S. BANK OF NAUGATUCK RIVER. TO N. BANK OF NAUGATUCK RIVER**

BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-5B
P.A. #			

Note: This page left blank intentionally




**PROPOSED CONFIGURATION
H-FRAME DESIGN**

**NORTH BANK OF NAUGATUCK RIVER
TO
CAMPVILLE SUBSTATION**

**IN THE TOWN OF
HARWINTON**

**LOOKING
NORTH**

(1.0 MILES)



KEY MAP
NOT TO SCALE



NOTES:

1. EXISTING LINES TO REMAIN.
2. PRELIMINARY STRUCTURE SPOTTING IS BASED ON STRUCTURE-FOR-STRUCTURE INSTALLATION.
3. EXISTING VEGETATION MANAGEMENT EDGES ARE TYPICAL.
4. AFTER THE CONDUCTORS HAVE BEEN INSTALLED, A REFERENCE IS ESTABLISHED THAT MAY IDENTIFY ADDITIONAL DANGER TREES OUTSIDE THE INITIALLY CLEARED AREA THAT MIGHT NEED TO BE REMOVED.
5. DEPICTED REPRESENTATIVE STRUCTURES ARE STEEL TANGENT STRUCTURES UTILIZING DIRECT EMBEDDED FOUNDATIONS. ANGLE AND DEADEND STRUCTURES WILL DIFFER AND BE PLACED ON CONCRETE FOUNDATIONS.

TITLE FROST BRIDGE TO CAMPVILLE 115-kV PROJECT ALTERNATIVE H-FRAME CROSS SECTIONS N. BANK OF NAUGATUCK RIVER TO CAMPVILLE SUBSTATION			
BY D. LAURSEN	CHKD V. MONTEMURRO	APP	APP
DATE 8/31/15	DATE 8/31/15	DATE	DATE
SCALE NONE	MICROFILM DATE	DWG. NO.	XS-6B
P.A. #			

Note: This page left blank intentionally

13. PROPOSED SUBSTATION MODIFICATIONS: ALTERNATIVES REVIEW

To meet the Project objectives, the new 115-kV transmission line must extend between and connect to the existing Frost Bridge and Campville substations. As a result, there are no alternative, geographically distinct substation sites that could be developed or modified to achieve the Project objectives. Similarly, for the reasons summarized below, the minor modifications to the Frost Bridge and Campville substations, as proposed, would avoid or minimize environmental impacts and represent the most cost-effective and efficient approach for interconnecting the new 115-kV line to the power grid.

Both the Frost Bridge and Campville substations were developed approximately 90 years ago and each is situated within a larger parcel of Eversource-owned property. Specifically, the 5.7-acre Frost Bridge Substation is situated on a 128-acre Eversource property, whereas the existing 1.7-acre Campville Substation is located within a 42.3-acre Eversource parcel.

The Project modifications to the Frost Bridge Substation would be located within the presently developed, fenced portion of the substation. Although seven existing 115-kV lines currently connect to the Frost Bridge Substation, sufficient space is available within the fenced portion of the station to accommodate all of the equipment required to interconnect the proposed 115-kV transmission line.

However, the proposed modifications to the Campville Substation could not be accommodated entirely within the footprint of the existing substation, which includes both 115-kV and 27.6-kV facilities. As a result, Eversource proposes to expand the developed portion of the substation (extending the existing substation fence) by approximately 0.4 acre. The location of the Campville Substation expansion (i.e., on the east side of the existing station fence) is proposed based on where new Project equipment and a new control house are needed to allow interconnections to the new 115-kV transmission line, which would extend into the substation from the south.

Within the existing Campville Substation, the 115-kV facilities are located on the east side of the yard and the 27.6-kV facilities are situated on the west side of the yard. The substation's two existing energized transformers are located between the 115-kV and 27.6-kV equipment. To accommodate the facilities required to interconnect the proposed 115-kV line while adhering to industry and Eversource standards for equipment (i.e., ring bus) separation, the existing 115-kV portion of the yard must be modified and expanded. Because the existing 115-kV yard is located on the eastern portion of the substation, the most cost-effective and least environmentally intrusive option is to expand the substation to the east, as is proposed.

Alternative locations for the Campville Substation modifications (e.g., outside of the western or southern substation fence lines) would be cost-ineffective, requiring the relocation of the existing transformers and the 27.6-kV equipment. Further, expansion of the substation footprint to the west or south would require the location of the proposed new control house and other new 115-kV equipment closer to Wildcat Hill Road. In contrast, the proposed substation expansion to the east would align the expansion to the back of the existing station, away from Wildcat Hill Road.

14. GLOSSARY AND TERMS

115-kV: 115 kilovolts or 115,000 volts

345-kV: 345 kilovolts or 345,000 volts

AAL: Annual average loads

AC (alternating current): An electric current that reverses its direction of flow periodically. (In the United States this occurs 60 times a second-60 cycles or 60 Hertz.) This is the type of current supplied to homes and businesses.

ACSR: Aluminum Conductor, Steel Reinforced, a common type of overhead conductor.

ACSS: Aluminum Conductor with Steel Support, a common type of overhead conductor.

Ampere: (Amp): A unit measure for the flow (current) of electricity. A typical home service capability (i.e., size) is 100 amps; 200 amps is required for homes with electric heat.

AMSL: Above mean sea level

ANSI: American National Standards Institute

APL: Annual peak load

Arrester: Equipment that protects lines, transformers and equipment from lightning and other voltage surges by carrying the charge to ground. Arresters serve the same purpose as a safety valve on a steam boiler.

ASTM: American Society for Testing and Materials

Auxiliary Transformers: Equipment installed at substations to provide voltage or current information for relaying and/or metering purposes.

BMP: Best Management Practice

BMP Manual: Eversource's Best Management Practices Manual: Connecticut Construction & Maintenance Environmental Requirements (2011)

C&D: Conservation and Development (plan)

C&LM: Conservation and Load Management.

Cable: A fully insulated conductor usually installed underground but in some circumstances can be installed overhead.

CCGT: Combined Cycle Gas Turbines

CCRP: Central Connecticut Reliability Project

CCVT: Capacitor coupling voltage transformers

CEII: Confidential Energy Infrastructure Information

CELT: ISO-NE, Forecast Report of Capacity, Energy, Loads and Transmission

Certificate: Certificate of Environmental Compatibility and Public Need (from the Connecticut Siting Council)

CFPA: Connecticut Forests and Park Association

CGS: Connecticut General Statutes

Circuit: A system of conductors (three conductors or three bundles of conductors) through which an electrical current is intended to flow and which may be supported above ground by transmission structures or placed underground.

Circuit Breaker: A switch that automatically disconnects power to the circuit in the event of a fault condition. Located in substations. Performs the same function as a circuit breaker in a home.
CL&P: The Connecticut Light and Power Company, a legal entity authorized to provide electric transmission and distribution service in Connecticut, now known as Eversource Energy.

CLEAR: Center for Land Use Education and Research

CLL: Critical Load Level

CMEEC: Connecticut Municipal Electrical Cooperative

COGCNV: Council of Governments of Central Naugatuck Valley

- ConnDOT:** Connecticut Department of Transportation
- Conductor:** A metallic wire, busbar, rod, tube or cable that serves as a path for electric current flow.
- Conduit:** Pipes, usually PVC plastic, typically encased in concrete, for housing underground power cables.
- Contingency:** The unexpected failure or outage of a system component, such as a generator, transmission line, circuit breaker, switch or other electrical element
- Conversion:** Change made to an existing transmission line for use at a higher voltage, sometimes requiring the installation of more insulators. (Lines are sometimes pre-built for future operation at the higher voltage.)
- CONVEX:** Connecticut Valley Electric Exchange.
- Corona:** A luminous discharge due to ionization of the air surrounding conductors, hardware, accessories, or insulators caused by a voltage gradient exceeding a certain critical value. Surface irregularities such as stranding, nicks, scratches, and semiconducting or insulating protrusions are usual corona sites, and weather has a pronounced influence on the occurrence and characteristics of overhead power-line corona.
- Council:** Connecticut Siting Council
- CT DEEP:** Connecticut Department of Energy and Environmental Protection.
- CWA:** Clean Water Act (federal)
- D&M Plan:** Development and Management Plan (required by the Connecticut Siting Council)
- dBA:** Decibel, on the A-weighted scale.
- DBH:** Diameter breast height
- DC:** (direct current): Electricity that flows continuously in one direction. A battery produces DC power.
- DCT:** Double-circuit transmission line
- Deadend Structure:** A line structure that is designed to have the capacity to hold the lateral strain of the conductor in one direction
- Demand:** The total amount of electricity required at any given time by an electric supplier's customers.
- DG:** Distributed Generation. Refers to modular electric generation or storage, located near the point of electric use, and generally involves the use of small generators located close to electric demand sources, to decrease end-users' electric purchases and to reduce the need for electricity generated by large, centrally-located power plants and power transport to load centers on transmission lines.
- Distribution:** Line, system. The facilities that transport electrical energy from the transmission system to the customer.
- Disconnect Switch:** Equipment installed to isolate circuit breakers, transmission lines or other equipment for maintenance or sectionalizing purposes.
- DR:** Demand response
- DRP:** Demand-response program.
- DRSP:** Demand-response service provider
- DSM:** Demand side management
- Duct:** Pipe or tubular runway for underground power cables (see also Conduit).
- Duct Bank:** A group of ducts or conduit usually encased in concrete in a trench.
- Electric Field:** Produced by voltage applied to conductors and equipment. The electric field is expressed in measurement units of volts per meter (V/m) or kilovolts per meter (kV/m); 1 kV/m is equal to 1,000 V/m.
- Electric Transmission:** The facilities (69 kV+) that transport electrical energy from generating plants to distribution substations.
- EMF:** Electric and magnetic fields.
- EMF BMPs:** Electric and Magnetic Fields Best Management Practices for the Construction of Electric Transmission Lines in Connecticut.
- EPA:** United States Environmental Protection Agency
- EPAct:** Electric Policy Act of 2005
- ERO:** Electric Reliability Organization

- ESRI:** Environmental Systems Research Institute, Inc. (database of environmental information)
- Eversource:** also referred to as “the **Company**”: The Connecticut Light and Power Company doing business as Eversource Energy.
- Eversource Service:** Eversource Energy Service Company (formerly, Northeast Utilities Service Company); a company within the Eversource Energy organization that provides services to public utility subsidiaries, such as Eversource.
- FAA:** Federal Aviation Administration
- Fault:** A failure (short circuit) or interruption in an electrical circuit.
- FCM:** Forward Capacity Market
- FEMA:** Federal Emergency Management Agency
- FERC:** Federal Energy Regulatory Commission
- FMD:** Field Management Design (Plan) (for EMF)
- FTB:** Fluidized thermal backfill
- G:** Gauss; 1G = 1,000 mG (milligauss); the unit of measure for magnetic fields.
- GHCC:** Greater Hartford Central Connecticut
- GIS:** Geographic Information System
- GPS:** Global Positioning System
- Ground Wire:** Cable/wire used to connect wires and metallic structure parts to the earth. Sometimes used to describe the lightning shield wire.
- GSRP:** Greater Springfield Reliability Project (part of NEEWS)
- HAER:** Historic American Engineering Record
- HDD:** Horizontal directional drill
- H-frame Structure:** A wood or steel structure constructed of two upright poles with a horizontal cross-arm and bracings.
- HPFF Pipe Cable System:** High-pressure fluid-filled; a type of underground transmission line.
- HVDC:** High voltage direct current
- Hz:** Hertz, a measure of alternating current frequency; one cycle/second.
- ICES:** International Committee on Electromagnetic Safety, a committee of the Institute of Electrical and Electronics Engineers)
- ICNIRP:** International Council on Non-Ionizing Radiation Protection, a specially chartered independent scientific organization
- IEEE:** Institute of Electrical and Electronics Engineers
- IFR:** Instrument Flight Rules
- Impedance:** The combined resistance and reactance of the line or piece of electrical equipment which determines the current flow when an alternating voltage is applied
- Interstate:** Interstate Reliability Project (also, IRP)
- iPac:** Information, Planning, and Conservation System (USFWS)
- ISO:** Independent System Operator
- ISO-NE:** Independent System Operator New England, Inc. New England’s independent system operator.
- kcml:** 1,000 circular mils, approximately 0.0008 sq. in.
- kV:** kilovolt, equals 1,000 volts
- kV/m:** Electric field unit of measurement (kilovolts/meter)
- Lattice-type Structure:** Transmission or substation structure constructed of lightweight steel members.
- LEI:** London Economics International, LLC
- Lightning Shield Wire:** Electric cable located to prevent lightning from striking transmission circuit conductors.
- Line:** A series of overhead transmission structures that support one or more circuits; or in the case of underground construction, a duct bank housing one or more cable circuits.
- LMP:** Locational marginal pricing

- Load:** Amount of power delivered as required at any point or points in the system. Load is created by the power demands of customers' equipment (residential, commercial, industrial).
- Load Pocket:** A load area that has insufficient transmission import capacity and must rely on out-of-merit order local generation.
- LOLE:** Loss of Load Expectation; a measure of bulk-power system reliability.
- LPP:** Laminated paper-polypropylene; a type of cable insulation.
- LSR:** Local Sourcing Requirement
- LTE:** Long-term Emergency (rating on transmission line)
- Magnetic Field:** Produced by the flow of electric currents; however, unlike electric fields, most materials do not readily block magnetic fields. The level of a magnetic field is commonly expressed as magnetic flux density in units called gauss (G), or in milligauss (mG), where 1 G = 1,000 mG.
- Magnetic Flux Density:** See Magnetic Field
- Manhole:** See Splice Vault
- MCF:** Municipal Consultation Filing (required by Connecticut Siting Council)
- MF:** Magnetic field
- MHG:** Material Handling Guidelines
- mG:** milligauss (see Magnetic Field)
- MRA:** Market Resource Alternatives
- MVA:** (Megavolt Ampere) Measure of electrical capacity equal to the product of the voltage times the current times the square root of 3. Electrical equipment capacities are sometimes stated in MVA.
- MVAR:** (Megavolt Ampere Reactive) Measure of reactive power.
- MW(s):** (Megawatt(s)) One megawatt equals 1 million watts, measure of the work electricity can do.
- MWh:** Megawatt hour
- NAAQS:** National Ambient Air Quality Standards
- NDDB:** Connecticut Natural Diversity Data Base (CT DEEP)
- NECCOG:** Northeastern Connecticut Council of Governments
- NEEWS:** New England East – West Solution
- NEPOOL:** New England Power Pool
- NERC:** North American Electric Reliability Council, Inc. (initially, the National Electric Reliability Council)
- NESC:** National Electrical Safety Code
- NGVD:** National Geodetic Survey Datum
- NHD:** National Hydrography Database
- NHPA:** National Historic Preservation Act
- NPCC:** Northeast Power Coordinating Council
- NPH:** Notice of Presumed Hazard (FAA)
- NPS:** United States National Park Service
- NRCS:** Natural Resources Conservation Service (United States Department of Agriculture)
- NRHP:** National Register of Historic Places
- NTAs:** Non-transmission alternatives
- NU:** Northeast Utilities (former name of Eversource Energy)
- NHCOG:** Northwest Hills Council of Governments
- NWCT:** Northwest Connecticut (electric sub-area); includes more than 20 towns
- NWI:** National Wetlands Inventory
- NY-ISO:** New York Independent System Operator
- OH (Overhead):** Electrical facilities installed above the surface of the earth.
- OOS:** Out-of-service (as in a generating unit or station)
- OPGW:** Optical groundwire (a shield wire containing optical glass fibers for communication purposes)
- PAC:** Planning Advisory Committee (ISO-NE)
- PDAL:** Peak average daily loads
- PEM:** Palustrine emergent (wetlands)

- PFO:** Palustrine forested (wetlands)
- Phases:** Transmission (and some distribution) AC circuits are comprised of three phases that have a voltage differential between them.
- Pothhead:** See Terminator
- POW:** Palustrine open water (wetlands)
- Protection/Control Equipment:** Devices used to detect faults, transients and other disturbances in the electrical system in the shortest possible time. They are customized or controlled per an entity's operational requirements.
- PSI:** Pounds per square inch
- PSS:** Palustrine scrub-shrub (wetlands)
- PT:** Potential transformer
- PUB:** Palustrine unconsolidated bottom (wetlands)
- PURA:** Public Utilities Regulatory Authority (part of CT DEEP)
- PVC:** Polyvinyl chloride (conduits for XLPE-insulated cable)
- Reactive Power:** The portion of electricity that establishes and sustains the electric and magnetic fields of alternating-current lines and equipment owing to their inductive and capacitive characteristics. Reactive power is provided by generators, synchronous condensers, and capacitors, absorbed by reactive loads, and directly influences electric system voltage. Shunt capacitor and reactor capacities are usually stated in MVAR.
- Rebuild:** Replacement of an existing overhead transmission line with new structures and conductors generally along the same route as the replaced line.
- Reconductor:** Replacement of existing conductors with new conductors, but with little if any replacement or modification of existing structures.
- RGGI:** Regional Greenhouse Gas Initiative
- Reinforcement:** Any of a number of approaches to improve the capacity of the transmission system, including rebuild, reconductor, conversion and bundling methods.
- RFP:** Request for Proposal
- RIRP:** Rhode Island Reliability Project
- ROW:** Right-of-Way; as used in this document, a defined strip of land over which Eversource has rights to construct, operate, and maintain electric transmission lines, together with various ancillary rights. Typically, these rights have been conveyed to Eversource by the owner of the underlying land. In some cases, Eversource may own the land itself in fee.
- RPS:** Renewable Portfolio Standards
- RSP:** Regional System Plan prepared annually by ISO-NE.
- RTE:** Rare, threatened and endangered (see also T&E)
- RTEP:** Regional Transmission Expansion Plan
- SCADA:** Supervisory Control and Data Acquisition
- Series Reactor:** A device used for introducing impedance into an electrical circuit, the principal element of which is inductive reactance.
- SF₆:** Sulfur hexafluoride, an insulating gas used in GIS substations and circuit breakers.
- SGCN:** Species of Greatest Conservation Need (as classified by Connecticut's Wildlife Action Plan [WPA])
- Shield Wire:** See Lightning Shield Wire
- SHPO:** State Historic Preservation Office
- Shunt Reactor:** An electrical reactive power device primarily used to compensate for reactive power demands by high voltage underground transmission cables.
- SNE:** Southern New England
- SPCC:** Spill Prevention, Containment, and Control (plan)
- Splice:** A device to connect together the ends of bare conductor or insulated cable.
- Splice Vault:** A buried concrete enclosure where underground cable ends are spliced and cable-sheath bonding and grounding is installed.

SRHP: State Register of Historic Places

S/S (Substation): A fenced-in yard containing switches, transformers, line-terminal structures, and other equipment enclosures and structures. Adjustments of voltage, monitoring of circuits and other service functions take place in this installation.

Steel Lattice Tower: See Lattice-Type Structure

Steel Monopole Structure: Transmission structure consisting of a single tubular steel column with horizontal arms to support insulators and conductors.

Step-down Transformer: See Transformer

Step-up Transformer: See Transformer

Switchgear: General term covering electrical switching and interrupting devices. Device used to close or open, or both, one or more electric circuits.

Stormwater Pollution Control Plan: Is a sediment and erosion control plan that also describes all the construction site operator's activities to prevent stormwater contamination, control sedimentation and erosion, and comply with the requirements of the Clean Water Act

SWCT: Southwest quadrant of the State of Connecticut

Terminal Points: The substation or switching station at which a transmission line terminates.

Terminal Structure: Structure typically within a substation that ends a section of transmission line.

Terminator: A flared pot-shaped insulated fitting used to connect underground cables to overhead lines

T&E: Threatened and endangered species (see also RTE)

TOs: Transmission owners

Transformer: A device used to transform voltage levels to facilitate the efficient transfer of power from the generating plant to the customer. A step-up transformer increases the voltage while a step-down transformer decreases it.

Transmission Line: Any line operating at 69,000 or more volts.

UG (Underground): Electrical facilities installed below the surface of the earth.

Upgrade: See Reinforcement

USACE: United States Army Corps of Engineers (New England District)

USDA: United States Department of Agriculture

USFWS: United States Fish and Wildlife Service

USGS: United States Geological Survey (U.S. Department of the Interior).

VAR: Volt-ampere reactive power. The unit of measure for reactive power.

Vault: See Splice Vault.

VFR: Visual Flight Rules

V/m: volts per meter, kilovolt per meter: 1,000 V/m = 1 kV/m; electric field measurement

Voltage: A measure of the push or force that transmits energy.

WAP: Wildlife Action Plan (Connecticut)

Watercourse: Rivers, streams, brooks, waterways, lakes, ponds, marshes, swamps, bogs, and all other bodies of water, natural or artificial, public or private.

Wetland: An area of land consisting of soil that is saturated with moisture, such as a swamp, marsh, or bog.

WMA: Wildlife Management Area (CT DEEP)

XS: Cross section (drawing)

XLPE: Cross-linked polyethylene (solid dielectric) insulation for transmission