

**NEW POLICE FACILITY FOR
EASTERN CONNECTICUT STATE UNIVERSITY
WILLIMANTIC, CONNECTICUT
PROJECT: BI- RW - 260**

BID OPENING	1:00 P.M.	MAY, 14, 2008
ADDENDUM NUMBER ONE	DATE OF ADDENDUM	MAY, 1, 2008

The following clarifications are applicable to drawings and specifications for the project referenced above.

Item 1

Drawing E-3 was issued with miscellaneous graphic information missing. Replace with the attached Drawing E-3.

Item 2

Drawing E-4, revise the following:

1. Move the "KP" "Key Pads" for the local security zones at the Records and Chief's suite to the corridor side of the doors or where directed in field by owner.
2. Change all window "C" contact switches to Insect Screen wired sensors. Make arrangements with Window supplier to have the screens wired for security.

Item 3

Drawing E-6, revise the following:

1. Change the wording on the symbol legend for the "CR" symbol - These devices shall be proximity type card readers - Andover HID type "Thin Line Series" (They are NOT scramble pads).
2. The Access Control System shown shall be an NCR-R-008000000 with AC-1 Door Modules and Input Modules (The specifications section listed the panels as Model Number CX9200 & ACX781, which are obsolete numbers). Use the current model number type.
3. The "RISER DIAGRAM OF INTERCOM SYSTEMS" has an intercom symbol missing at the right side, this shall be added (plotting error). **Note: for exact counts of devices for the project, refer to the floor plans. Assume that the riser diagrams are schematic only and should not be used for fixture counts.**
4. The "CCTV WIRING AND EQUIPMENT RISER DIAGRAM" is also missing one camera symbol on the right side. In addition, delete the lower hard drive noted as a 260 GB. Provide a single master DVR that will incorporate at least a 360 GB hard drive, with built in Mutiplexer/Controller and remote desktop joystick controller. Also provide the Digital

Recorder and install where directed. The CCTV Monitors shall be changed to 32" and shall be Flat Screen LCD type monitors - Provide a total of four (4) as shown on the riser diagram and on the floor plans. **Note: for exact counts of devices for the project, refer to the floor plans. Assume that the riser diagrams are schematic only and should not be used for fixture counts.**

5. Security Access System - For bidding purposes, assume that the central CPU for the system will be installed where directed in the Dispatch Communications Center Room. The power supplies, Aux relay panels, etc shall be rack mounted within the Communications Equipment Room.

Item 4

In Section 01580, entire section:

CLARIFICATION: ALL the requirements of this section shall apply to this project. As indicated, the field office is for the sole use of Construction Administrator and the Owner, and is in addition to the General Contractor's own field office.

Item 5

In Section 16700, 2.4 Card Access Security System, Paragraph A:


DELETE: Delete the (50) laminated cards. The cards shall be supplied by the owner.

Item 6

In Section 16700, 2.5 CCTV System, B, 1, first paragraph:

DELETE: Delete the word "CELL" from the description on the first line. Also delete the option for the zoom, pan and tilt operations. All camera locations shall be fixed position type.

End of Addendum Number One



David Busanet, Bidding & Contracts Supervisor
Department of Public Works