



# Connecticut Department of Energy and Environmental Protection



Connecticut Department of  
**ENERGY &  
ENVIRONMENTAL  
PROTECTION**

Public Informational Meeting  
Improvements to Bashan Lake Dam  
DEEP Dam No. 4113  
East Haddam, Connecticut

June 27, 2013  
WMC Consulting Engineers, Newington, CT  
East Haddam Grange Hall



Connecticut Department of Energy and Environmental Protection


# Bashan Lake Dam



Connecticut Department of Energy and Environmental Protection



# Project Location



Connecticut Department of Energy and Environmental Protection

# DEEP Responsibilities

- Maintain State-owned dams (eg, Bashan) in a safe condition
- Ensure that all dam owners (both State and private) maintain their dams in a safe condition



# Key Personnel

## DEEP, Inland Water Resources Division

Cheryl Chase, Director

Jennifer Perry, Supervising Environmental Analyst

Dan Biron, Senior Environmental Analyst

## WMC Consulting Engineers

Steve McDonnell, Vice President



Connecticut Department of Energy and Environmental Protection

# Dam History

- A smaller natural lake probably existed prior to the construction of the original dam
- First dam originally constructed circa 1734 to provide power for saw and grist mill operations
- Present dam constructed around 1900, raising lake levels  $\pm 16$  feet
- Around 1939 upstream stone masonry walls covered with shotcrete (Gunitite) to reduce seepage through dam. Photos show cofferdam between two small islands located at mouth of northerly cove.



# Dam History

- Around 1966 dam ownership transferred from Moodus Reservoir Company to State of Connecticut
- June 1982 flood overtopped dam, causing some damage
- 1983 State repaired dam. Lake levels down  $\pm 16$  feet during repairs.
- March 2010 flood overtopped dam, no damages





# Terminology



Connecticut Department of Energy and Environmental Protection



# Terminology



Connecticut Department of Energy and Environmental Protection



# Terminology



Connecticut Department of Energy and Environmental Protection



# Terminology



Connecticut Department of Energy and Environmental Protection


# Proposed Major Repair Components

- Replace existing gate structure






# Replace Gate Chamber



Connecticut Department of Energy and Environmental Protection

# Replace Gate Chamber



# Connecticut Department of Energy and Environmental Protection



# Existing Gate Chamber (1983)



Connecticut Department of Energy and Environmental Protection



# New Moodus Reservoir Gate Chamber



Connecticut Department of Energy and Environmental Protection


# Proposed Major Repair Components

- Replace existing gate structure
- Raise dam embankments one foot to provide one foot of overtopping freeboard for the 100 year design flood






# Raise Embankments One Foot



Connecticut Department of Energy and Environmental Protection

# Raise Embankments One Foot



Connecticut Department of Energy and Environmental Protection

# Dam Overtopping (March 2010)



Connecticut Department of Energy and Environmental Protection


# Proposed Major Repair Components

- Replace existing gate structure
- Raise dam embankments one foot to provide one foot of overtopping freeboard for the 100 year design flood
- Install new full-height concrete cut-off wall along upstream right embankment to correct repetitive concrete deterioration





# New Right Embankment Cut-Off Wall




Connecticut Department of Energy and Environmental Protection






# New Right Embankment Cut-Off Wall



Connecticut Department of Energy and Environmental Protection

# New Right Embankment Cut-Off Wall



Connecticut Department of Energy and Environmental Protection



# Spalling Concrete



Connecticut Department of Energy and Environmental Protection




# Proposed Major Repair Components

- Replace existing gate structure
- Raise dam embankments one foot to provide one foot of overtopping freeboard for the 100 year design flood
- Install new full-height concrete cut-off wall along upstream right embankment to correct repetitive concrete deterioration
- Reconstruct spillway cut-off wall for existing seepage




# Reconstruct Spillway Cut-Off Wall



Connecticut Department of Energy and Environmental Protection

# Reconstruct Spillway Cut-Off Wall



Connecticut Department of Energy and Environmental Protection



# Downstream Spillway Face



Connecticut Department of Energy and Environmental Protection



# Existing Spillway Seepage



Connecticut Department of Energy and Environmental Protection


# Proposed Major Repair Components

- Replace existing gate structure
- Raise dam embankments one foot to provide one foot of overtopping freeboard for the 100 year design flood
- Install new full-height concrete cut-off wall along upstream right embankment to correct repetitive concrete deterioration
- Reconstruct spillway cut-off wall for existing seepage
- Construct new concrete buttress to reinforce downstream stone masonry wall






# New Downstream Concrete Buttress



Connecticut Department of Energy and Environmental Protection




# New Downstream Concrete Buttress




Connecticut Department of Energy and Environmental Protection

# New Downstream Concrete Buttress



Connecticut Department of Energy and Environmental Protection

# New Downstream Concrete Buttress



Connecticut Department of Energy and Environmental Protection




# Proposed Major Repair Components

- Replace existing gate structure
- Raise dam embankments one foot to provide one foot of overtopping freeboard for the 100 year design flood
- Install new full-height concrete cut-off wall along upstream right embankment to correct repetitive concrete deterioration
- Reconstruct spillway cut-off wall for existing seepage
- Construct new concrete buttress to reinforce downstream stone masonry wall
- Install new prefabricated steel access bridge over spillway




# New Maintenance Access Bridge



Connecticut Department of Energy and Environmental Protection

# New Maintenance Access Bridge



Connecticut Department of Energy and Environmental Protection



# Typical Maintenance Access Bridge



Connecticut Department of Energy and Environmental Protection

# Water Handling Options

Option A- Maintain full lake level

Option B- Approximate 5 foot lake drawdown

Option C- Approximate 13 foot lake drawdown

Option D- Approximate 16 foot lake drawdown



# Option A Water Handling


## Option A- Maintain full lake level

190 foot long, up to 25 foot high cofferdam just upstream of dam





# Option A Cofferddam Location



Connecticut Department of Energy and Environmental Protection

# Option A Impacts

## Option A- Maintain full lake level

190 foot long, up to 25 foot high cofferdam just upstream of dam

## Impacts

- Recreation- Minimal impacts
- Aquatic Vegetation- No positive/negative impacts
- Fisheries- Minimal impacts
- Abutters- Minimal impacts
- Cost- ±\$750,000 (most expensive option)
- Lake Refilling- 0 months



# Option B Water Handlings

## Option B- 5 foot lake drawdown

120 foot long, 10 foot high cofferdam between two islands  
located at mouth of northerly cove





# Option B Cofferddam Location



# Option B Impacts

## Option B- 5 foot lake drawdown

120 foot long, 10 foot high cofferdam between two islands located at mouth of northerly cove

## Impacts

- Recreation-  $\pm 1$  foot down first summer
- Aquatic Vegetation- Potentially more growth
- Fisheries- Reduced impacts to Bridle Shiner
- Abutters- Primarily limited to first spring
- Cost-  $\pm \$150,000$  (second most expensive option)
- Lake Refilling-  $\pm 10$  months



# Option C Water Handling

## Option C- 13 foot lake drawdown

Install stop logs in existing cofferdam located between two islands at mouth of northerly cove





# Existing Cofferdam (1983 Repairs)



Connecticut Department of Energy and Environmental Protection

# Option C Impacts

## Option C- 13 foot lake drawdown

Install stop logs in existing cofferdam located between two islands at mouth of northerly cove

## Impacts

- Recreation-  $\pm 4$ ft down 1<sup>st</sup> summer,  $\pm \frac{1}{2}$ ft down 2<sup>nd</sup> summer
- Aquatic Vegetation- Potentially reduced growth
- Fisheries- Possible notable impacts to Bridle Shiner
- Abutters- Notable first summer
- Cost-  $\pm \$5,000$  (minimal project cost)
- Lake Refilling-  $\pm 22$  months



# Option D Water Handling

## Option D- 16 foot lake drawdown

Utilize existing cofferdam located between two islands,  
without stop logs





# ±16 Foot Drawdown (1983)



Connecticut Department of Energy and Environmental Protection

# ±16 Foot Drawdown (1983)



Connecticut Department of Energy and Environmental Protection

# Option D Impacts

## Option D- 16 foot lake drawdown

Utilize existing cofferdam located between two islands, without stop logs


### Impacts

- Recreation-  $\pm 5$ ft down 1<sup>st</sup> summer,  $\pm 1\frac{1}{2}$ ft down 2<sup>nd</sup> summer
- Aquatic Vegetation- Potentially reduced growth
- Fisheries- Possible notable impacts to Bridle Shiner
- Abutters- Notable first summer, minor second summer
- Cost-  $\pm \$0$  (minimal project cost)
- Lake Refilling-  $\pm 25$  months






# Option A- Full Lake Level



Connecticut Department of Energy and Environmental Protection




# Option B- 5 Foot Lake Drawdown



Connecticut Department of Energy and Environmental Protection




# Option C- 13 Foot Lake Drawdown



Connecticut Department of Energy and Environmental Protection



# Option D- 16 Foot Lake Drawdown



Connecticut Department of Energy and Environmental Protection

# Water Handling Summary

	Water Handling Options			
	A 0 ft	B -5 ft	C -13 ft	D -16 ft
Impacts				
Recreation	++	+	-	--
Vegetation	0	--	+	++
Fisheries	++	+	-	--
Abutters	++	+	-	--
Cost	--	-	++	++
Lake Refilling	++	+	-	--

++ Notable Positive Impact

-- Notable Negative Impact

+ Positive Impact

- Negative Impact

0 Neither Positive nor Negative Impact



Connecticut Department of Energy and Environmental Protection

# Project Schedule

- Start Lake Drawdown- Day after Labor Day, 2014
- Start Lake Refilling- No later than February 1, 2015
- Total Estimated Construction Duration- 6 Months
- Construction Estimate- \$1.2 million (excluding water handling)





# DEEP Contact

Mr. Dan Biron

Senior Environmental Analyst

Inland Water Resources Division

Department of Energy and Environmental Protection

Hartford, CT

(860) 424-3892

[dan.biron@ct.gov](mailto:dan.biron@ct.gov)



Connecticut Department of Energy and Environmental Protection

# WMC Contact

Mr. Steve McDonnell

Vice President

WMC Consulting Engineers

Newington, CT

(860) 667-9624

[smcdonnell@wmcengineers.com](mailto:smcdonnell@wmcengineers.com)



Connecticut Department of Energy and Environmental Protection



# Questions?



Connecticut Department of Energy and Environmental Protection