

AMAYA ARCHITECTS

ADDENDUM NUMBER 2

For:

**Niznansky Residence
619 Penfield Road
Fairfield, Connecticut**

Project Number 1329

25th of July 2016

The Drawings and Specifications prepared by Amaya Architects and its Consultants entitled “**Existing Structure Raised on New Concrete Piers – and the Demolition and Reconstruction of the Lower Level**”, and known as the “**Niznansky Residence**” and located at “**619 Penfield Road, Fairfield, Connecticut 06824 – Drawings and Specifications dated the 5th of July 2016 - Project Number 1329**”, are hereby amended in the following particulars:

<u>Item #</u>	<u>Section/Dwg</u>	<u>Description</u>
1		<p>Clarification - AZEK Trim Boards – Alternate One – As outlined in the Bid Package - Provide alternate pricing to wrap all outside perimeter LVL Support Members with AZEK Trim Material in lieu of Aluminum</p> <p>Also included as part of the Base Bid - All interior LVL Support Members (located under the house) shall be wrapped using 5/8" Plywood and Painted - similar to ceiling under the house</p> <p>Additional language - Use AZEK single width board stock to wrap LVL Members – Cut material (per manufacturer's recommendations) to suit full dimension of installed LVL Members – Refer to Specification Section 06600 – Plastic Fabrications (included in the Bid Package) for additional information</p> <p>Be sure to indicate whether Alternate Pricing is an Add or Deduct to the overall cost of the proposed construction work</p>
2		<p>Clarification – The General Contractor will be responsible for “re-instating” the site back to original conditions following the completion of the proposed construction activities</p>

		This work includes, but may not be limited to; Repair of the Driveway, Grass Areas, and Walkways to Stairways
--	--	---

END OF ADDENDUM TWO