


## SECOND FLOOR LAYOUT



THIS MAP IS A COPYRIGHTED WORK OF MARTINEZ COUCH AND ASSOCIATES, LLC. ALL RIGHTS RESERVED.



1084 Cromwell Avenue, Suite A-2  
Rocky Hill, CT 06067  
Telephone: (860) 436-4364  
Fax: (860) 436-4626  
[www.martinezcouch.com](http://www.martinezcouch.com)

PROJECT 2178  
100 JEWETT AVENUE  
BRIDGEPORT, CONNECTICUT 06606

**ISSUED FOR BID**  
**NOT FOR CONSTRUCTION**

[illegible]

## BUILDING SCHEMATIC LAYOUT 2

JOB NO.	DRAWING NUMBER	SHEET
33-262-2178	BASEMAP 33-262-2178.dwg	A-1.1



LEAD HAZARD REMEDIATION CHART				
#	LOCATION	COMPONENT	ABATEMENT METHOD	COMMENTS
2	DINING ROOM	WINDOW WELL/TROUGH WINDOW JAMB (SIDE 4)	REPLACE WITH NEW X1	REMOVE AND REPLACE. ARCHITECTURAL REPLACEMENT COMPONENTS SHALL CONFORM WITH ALL CONTRACT REQUIREMENTS AND SPECIFICATIONS
4	BATH	WINDOW	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
6	REAR EXIT	DOOR JAMB SIDE 1	PAINT REMOVAL	REMOVE PAINT
6	REAR EXIT	THRESHOLD	REMOVE PAINT	REMOVE PAINT
6	REAR EXIT	WALL SIDE 1	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
8	STAIRS TO SECOND FLOOR	WINDOW WELL/TROUGH WINDOW JAMB (SIDE 2)	REPLACE WITH NEW X1	REMOVE AND REPLACE. ARCHITECTURAL REPLACEMENT COMPONENTS SHALL CONFORM WITH ALL CONTRACT REQUIREMENTS AND SPECIFICATIONS
8	SECOND FLOOR HALL	DOOR JAMB	PAINT REMOVAL	REMOVE PAINT
8	SECOND FLOOR HALL	DOOR CASING	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
9	2ND FL BATH	WINDOW	REPLACE WITH NEW X1	REMOVE AND REPLACE. ARCHITECTURAL REPLACEMENT COMPONENTS SHALL CONFORM WITH ALL CONTRACT REQUIREMENTS AND SPECIFICATIONS
10	REAR LEFT BEDROOM	DOOR JAMB	PAINT REMOVAL	REMOVE PAINT
10	REAR LEFT BEDROOM	WINDOW SHASH, WELL/TROUGH/ JAMB	REPLACE WITH NEW X2	REMOVE AND REPLACE. ARCHITECTURAL REPLACEMENT COMPONENTS SHALL CONFORM WITH ALL CONTRACT REQUIREMENTS AND SPECIFICATIONS
10	REAR LEFT BEDROOM	WINDOW SILL/STOOL, WINDOW TRIM, APRON	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
11	REAR RIGHT BEDROOM	DOOR JAMB	PAINT REMOVAL	REMOVE PAINT
11	REAR RIGHT BEDROOM	DOOR CASING	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
11	REAR RIGHT BEDROOM	WINDOW SASH, WELL/TROUGH, JAMB	REPLACE WITH NEW X2	REMOVE AND REPLACE. ARCHITECTURAL REPLACEMENT COMPONENTS SHALL CONFORM WITH ALL CONTRACT REQUIREMENTS AND SPECIFICATIONS
11	REAR RIGHT BEDROOM	WINDOW SILL/STOOL, WINDOW TRIM, APRON	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
11	REAR RIGHT BEDROOM	CLOSET DOOR JAMB	PAINT REMOVAL	REMOVE PAINT

LEAD HAZARD REMEDIATION CHART				
#	LOCATION	COMPONENT	ABATEMENT METHOD	COMMENTS
12	FRONT RIGHT BEDROOM	DOOR JAMB	PAINT REMOVAL	REMOVE PAINT
12	FRONT RIGHT BEDROOM	DOOR CASING	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
12	FRONT RIGHT BEDROOM	CLOSET DOOR JAMB	PAINT REMOVAL	REMOVE PAINT
12	FRONT RIGHT BEDROOM	CLOSET DOOR CASING	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
12	FRONT RIGHT BEDROOM	CLOSET SHELF SUPPORT	REPLACE	REMOVE AND REPLACE. ARCHITECTURAL REPLACEMENT COMPONENTS SHALL CONFORM WITH ALL CONTRACT REQUIREMENTS AND SPECIFICATIONS
12	FRONT RIGHT BEDROOM	WINDOW SASH, WELL/TROUGH, JAMB	REPLACE WITH NEW X3	REMOVE AND REPLACE. ARCHITECTURAL REPLACEMENT COMPONENTS SHALL CONFORM WITH ALL CONTRACT REQUIREMENTS AND SPECIFICATIONS
12	FRONT RIGHT BEDROOM	WINDOW SILL/STOOL, TRIM, APRON	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
13	LITTLE FRONT ROOM	DOOR JAMB *NO DOOR	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
13	LITTLE FRONT ROOM	DOOR CASING	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
13	LITTLE FRONT ROOM	WINDOW SASH, WELL/TROUGH, JAMB	REPLACE WITH NEW X1	REMOVE AND REPLACE. ARCHITECTURAL REPLACEMENT COMPONENTS SHALL CONFORM WITH ALL CONTRACT REQUIREMENTS AND SPECIFICATIONS
13	LITTLE FRONT ROOM	WINDOW SILL/STOOL, TRIM, APRON	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
14	EXTERIOR	THRESHOLD AT FRONT DOOR	PAINT REMOVAL	REMOVE PAINT
14	EXTERIOR	SASH AROUND DOOR LIGHTS	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
14	EXTERIOR	PORCH FLOOR	PAINT REMOVAL	REMOVE PAINT
14	EXTERIOR	BASEMENT WINDOW	LIQUID ENCAPSULATE X5	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
14	EXTERIOR	WINDOW ABOVE REAR DOOR (SHED DOOR?)	LIQUID ENCAPSULATE	LIQUID ENCAPSULATION WITH STATE APPROVED ENCAPSULANT
ALL			DUST CLEAN-UP	WINDOW WELL, WINDOW SILL, FLOOR TO MEET HUD CHAPTER 7 LEAD IN DUST REOCCUPANCY CRITERIA FOR ALL ROOMS/AREAS

- GENERAL NOTES**
- ALL DRAWNGS SHOWN ARE SCHEMATIC LAYOUTS. CONTRACTOR TO FIELD VERIFY ALL MEASUREMENTS AND CONDITIONS.
  - ANY DISCREPANCIES BETWEEN DRAWNGS AND CONTRACT SPECIFICATIONS AND/OR SCOPE OF WORK SHALL BE SUBMITTED IN WRITING TO MARTINEZ, COUCH, & ASSOCIATES FOR RESOLUTION.
  - WORK SHALL BE IN ACCORDANCE WITH ALL CONTRACT DOCUMENTS AND SPECIFICATIONS.
  - ANY AND ALL FINISHES, SITE FEATURES, OR OTHER PROPERTY OF THE OWNER IF DAMAGED BY THE CONTRACTOR DURING PROJECT WORK SHALL BE RESTORED OR REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER OR THE CONNECTICUT DEPARTMENT OF HOUSING

**LEAD PAINT ABATEMENT GENERAL NOTES**

FOR COMPREHENSIVE LEAD INSPECTION REPORT AND FULL LEAD ABATEMENT PLAN SEE CONTRACT SPECIFICATIONS. ALL LEAD ABATEMENT WORK TO BE PERFORMED IN ACCORDANCE WITH CONTRACT SPECIFICATIONS AND LEAD ABATEMENT PLAN PREPARED BY GILBERTCO LEAD INSPECTIONS LLC. CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS APPLICABLE TO PROJECT ABATEMENT WORK AND AS INDICATED IN ABATEMENT SPECIFICATION SECTION 02 83 19 OF THE CONTRACT SPECIFICATIONS

ALL SURFACES SCHEDULED FOR REMOVAL OF LEADED PAINT SHALL BE REPAINTED TO MATCH ADJACENT FINISHES OR ORIGINAL COLOR OR LIQUID ENCAPSULATION AS BEST POSSIBLE COLOR MATCHING.

SURFACES SCHEDULED FOR LIQUID ENCAPSULATION SHALL BE PROPERLY STABILIZED TO ESTABLISH AN ACCEPTABLE SUBSTRATE FOR APPLICATION OF APPROVED LIQUID ENCAPSULATE MATERIAL.

ALL DEMOLITION MATERIALS ASSOCIATED WITH LEAD ABATEMENT WORK SHALL BE DISPOSED PER THE LEAD ABATEMENT PLAN AS HAZARDOUS WASTE WITH A TCLP READING GREATER THAN 5 mg/L.

THIS MAP IS A COPYRIGHTED WORK OF MARTINEZ COUCH AND ASSOCIATES, LLC. ALL RIGHTS RESERVED.



1084 Cromwell Avenue, Suite A-2  
Rocky Hill, CT 06067  
Telephone: (860) 436-4364  
Fax: (860) 436-4626  
www.martinezcouch.com

PROJECT 2178  
100 JEWETT AVENUE  
BRIDGEPORT, CONNECTICUT 06606

ISSUED FOR BID  
NOT FOR CONSTRUCTION

NO.	DATE	REVISIONS				BY	CHK	APPV	
DRAWN: AM/CP		CHECKED: MBR	APPROVED: REC	SCALE: NTS	DATE: 3/31/2015				

HAZARDOUS MATERIAL CHART

	JOB NO.	DRAWING NUMBER	SHEET
	33-262-2178	BASEMAP 33-262-2178.dwg	HM-1.0