



Lothrop Associates LLP Architects

100 Pearl Street

14th Floor

Hartford, Connecticut 06103

860-249-7251

THE STATE OF CONNECTICUT
DEPARTMENT OF HOUSING (DOH)
COMMUNITY DEVELOPMENT BLOCK GRANT DISASTER RECOVERY PROGRAM (CDBG-DR)

OWNER OCCUPIED REHABILITATION AND REBUILDING PROGRAM (OORR)

**HAZARDOUS MATERIAL ABATEMENT
CONSTRUCTION OF NEW FOUNDATIONS
RAISING EXISTING RESIDENCE
ADDITIONS AND ALTERATIONS
GLORIA SILVIA RESIDENCE
45 SECOND AVENUE
EAST HAVEN, CONNECTICUT 06512**

ADDENDUM NO. 2339-2

Date: June 22, 2015

Application No. 2339
LAA Project No. 1524-09

This Addendum forms part of the Contract Documents and amends the original Bidding Documents dated June 1, 2015, only in the following particulars. Original provisions of the Contract Documents shall remain in effect except as specifically amended by this Addendum.

Bidders shall consider amendments and the resulting cost differences shall be included in all bids.

Acknowledge receipt of this Addendum in the space provided on the Bid Proposal Form. Failure to do so may subject the bidder to disqualification.

A. SPECIFICATIONS

1. Delete Section 013233 "Photo Documentation".
2. Section 015000 "Temporary Facilities":
 - a. P. 015000-2, Par.3.1-B-3- Add at end of sentence: ... **and pay all costs associated with temporary power.**
3. Section 024119 "Selective Demolition":
 - a. P.024119-1, Par. 1.1-A, Add the following:
3. Raising and lowering of existing building.
 - b. P. 024119-2, Par.1.3, Add the following:
K. Existing raising and lowering sequence prepared by Contractor performing the work.
 - c. P. 024119-2, Par. 2.1, Add the following:
B. Building raising and lowering by a qualified Contractor with not less than 10 years experience in building moving and lifting.

- d. P. 024119-4, Par.3.4, Add the following:
D. Raise and lower existing building according to a procedure established by the Contractor. Provide all necessary equipment, shoring, bracing, labor necessary for a safe and complete operation. Arrange temporary supports so as not to interfere with new construction, excavation and foundations.
4. Section 062013- "Exterior Finish Carpentry":
 - a. P. 062013-1, Par. 1.1-A-1- Revise to: **Exterior Stairs, Railings and Decks.**

B. DRAWINGS

1. Drawings HM-01, HM-02, HM-03 issued with this Addendum.
2. Drawing G-001: Symbols Legend- revise symbol for silt fence to a dashed line, consistent with that shown on the site plan.
3. Drawing AD-101: Add note to drawing as follows:
"House contents shall be removed, temporarily stored and returned to house by the Contractor under the Homeowner's supervision and under a Contract Allowance specified in Section 010200. Contents to be moved only in areas affected by new construction. Contents may be placed in an on site secured storage container raised off the ground a minimum of two feet".
4. Drawing A-102: At details 2 and 3, add a 1 ¼" diameter wood handrail at each stair run.
5. Drawing A-201: At Elevations 2 and 4 add and note a 1 ¼" diameter wood handrail on outboard side of each stair run.
6. Drawing S-106: In the last note column, add the following:

SUGGESTED LIFTING SEQUENCE

1. Install cribbing and support framing to elevate structure.
2. Brace structure as necessary to ensure stability and levelness.
3. Raise structure to required elevation necessary to provide clearance for construction of new foundation.
4. Demolish and remove existing foundations, piers, footings, slabs and first floor dropped beams as indicated on the drawings.
5. Construct new foundations, piers, framing as indicated on the drawings.
6. Lower structure on to new foundations, and fasten as indicated and specified.

Submit for the record a site specific lifting plan which has been coordinated with all new construction and site work.

END OF ADDENDUM 2339-2

Attachments: Dwgs HM-01, HM-02, HM-03 dated 6.22.15

