

Project Description

Project No. 172-433 is for the installation of durable epoxy resin pavement markings to maintain the legibility and retro reflectivity of centerlines, shoulder lines, lane lines, dotted lines as well as symbols and legends on various routes at the District 2 locations listed in the chart below. Where appropriate, the existing pavement surface shall be grooved to provide a location to install long line pavement markings, including broken lane lines. Sand or other material deposited on the pavement as a result of removing existing pavement markings shall be removed as the work progresses.

Epoxy Pavement Markings Installation Locations

Section	Route	Town (s)	Termini	Begin	End	Total
				Log Mile	Log Mile	Miles
1	2	Marlborough	Glastonbury/Marlborough TL to Underpass Park Rd.	12.67	14.55	1.88
2	2	North Stonington, Stonington	Milltown Rd. to 0.2 miles south of I-95 SB on-ramp	48.54	55.27	6.73
3	2A	Preston	Route 12 to Route 117 (Hallville-poquetanuck Rd.)	7.04	9.91	2.87
4	6	Windham, Chaplin, Hampton, Brooklyn, Killingly	Route 203 (N. Windham Rd.) to Rhode Island SL	95.00	116.33	21.33
5	9	Old Saybrook, Essex, Deep River, Chester, Haddam	I-95 TO Haddam/Middletown TL	0.00	18.76	18.76
6	11	Salem, Colchester	Beginning of Route 11 to merge with Route 2	10.38	17.80	7.42
7	44	Mansfield, Willington, Ashford, Eastford	Route 195 to 0.15 miles west of Route 198	76.61	86.80	10.19
8	44	Eastford, Pomfret, Putnam	0.9 miles west of Fayette Rd. to Rhode Island SL	88.27	106.23	17.96
9	169	Norwich	Route 2/Route 32 to Norwich/Lisbon TL	0.00	3.29	3.29
10	169	Lisbon, Canterbury, Brooklyn, Pomfret, Woodstock	Underpass I-395 to Massachusetts TL	5.36	38.25	32.89
11	I-95	Clinton, Westbrook, Old Saybrook	Madison/Clinton to 0.1 miles west of Baldwin Bridge	66.71	78.99	12.28