PRECAST CONC JERSEY BARRIER (PERMANENT)

850'

WIDEN BRIDGE

REMOVE EXISTING AND CONSTRUCT NEW NOISE BARRIER WALL

CROSS SECTION 10' - 12' - 12' - 12' - 10'

SILVER LANE

1170'

CROSS SECTION 10' - 12' - 12' - 12' - 10'

EAST RIVER DRIVE EXT.

REMOVE EXISTING AND CONSTRUCT NEW NOISE BARRIER WALL

WIDEN BRIDGE

CROSS SECTION 10' - 12' - 12' - 12' - 10'

MAIN STREET ROUTE 5

CROSS SECTION 10' - 12' - 12' - 12' - 12' - 10'

1900'

CROSS SECTION 4' - 11' - 11' - 11' - 11' - 10'

CROSS SECTION 4' - 11' - 11' - 11' - 11' - 10'

EXISTING WEAVE

ROUTE 15

I-91 ON RAMP

I-91 ON RAMP

ROUTE 15

PROPOSED WEAVE

SB RTE 15
HORIZONTAL RADIUS - 1976'
D.S. - 69 MPH

NB RTE 15
HORIZONTAL RADIUS - 2050'
D.S. - 70 MPH

I-91 TO RTE 15 CONNECTION
DESIGN SPEED 60 MPH

ROUTE 5/15

POSSIBLE DISTURBANCE TO ENTOMBED CONTAMINATED MATERIAL

MAJOR INTERCHANGE IMPROVEMENTS
NB I-91 & NB ROUTE 15 (to I-84 EAST)

ALTERNATIVE 8B

DOT PROJECT DEVELOPMENT UNIT