Federal /

### CONNECTICUT LOCAL BRIDGE PROGRAM

Fiscal Year 2007

# PRELIMINARY APPLICATION

**TOMLINSON AVENUE over** 

# **QUINNIPIAC RIVER**

Plainville, CT

ConnDOT Bridge No. 04546

Prepared for the
Connecticut Department of Transportation
Federal Local Bridge Program
Newington, Connecticut



### CONNECTICUT DEPARTMENT OF TRANSPORTATION



1,514,052

Stephen E. Korta, II, Commissioner

# PRELIMINARY APPLICATION FOR THE LOCAL BRIDGE PROGRAM

Preliminary application is hereby made by the Town/City/Borough of **Plainville** for possible inclusion in the Local Bridge Program for Fiscal **Year 2007** for the following structure:

Tomlinson Avenue over Quinnipiak River Bridge Location: Over Quinnipiak River Bridge Number: 04546 Length of Span: 12 feet Sufficiency Rating: 60.98 Priority Rating: 63.09 Evaluation & Rating Performed by: X State Forces \_\_\_\_ Others If Others, Name of Professional Engineer: Connecticut Professional Engineers License Number: Engineering Firm: Engineer's Address: Description of Existing Condition of Structure: (attach description) Description of Project Scope: A (note repair code; attach narrative/preliminary plans & specifications). Name of Municipal Official to Contact (name & title): John Bossi, P.E., Town Engineer Mailing Address: Town of Plainville, Municipal Center 1 Central Square, Plainville, CT 06062 Telephone: (860) 793-0221 FAX: (860) 793-2285 E-mail: bosse.plainville.ct.gov **Preliminary Cost Figures:** Preliminary Engineering Fees (Include Breakdown of Fees) 161.148 (Not to Exceed 15% of Construction Costs) Rights-of-Way Cost (If Applicable) 10,000 Municipally Owned Utility Relocation Cost N/A Estimated Construction Costs (Include Detailed Estimate) 1,074,324 Construction Engineering (Inspection, Materials Testing) 161,148 (Not to Exceed 15% of Construction Cost) Contingencies (10% of Construction Costs Only) 107,432

Rev. 2/06

Total Estimated Project Cost

### **Preliminary Application**

Local Bridge Program, FY 2007

### Financial Aid Data:

<u>Federal Reimbursement</u> : (Limit Total Estimated Project Cost n	ited to qualifying bridges – See Appendix1)
Project Reimoursement Reque	st \$1,211,241
State Local Bridge Project Gra	ant: (Cannot be combined with Federal reimbursement)
Allowable Grant Percentage _	
Project Grant Request \$	
State Local Bridge Project Loa	an: (Maximum 50% of total project cost)
Project Loan Request \$	
Schedule: (Anticipated Dates)	
Public Hearing Conducted:	April 30, 2008
Design Completion:	June 30, 2008
Property Acquisition Completion:	October 31, 2008
Utilities Coordination Completion:	June 30, 2008
Construction Advertising:	December 30, 2008/February 28, 2009
Supplemental Application Submiss	sion: April 30, 2009
Start of Construction:	April 30, 2010
Completion of Construction:	November 30, 2010
I hereby certify that the above	is accurate and true, to the best of my knowledge and belief.
Signatu	re: WASL
9	Elected Official, Town Manager, or other Officer Duly Authorized)
Date: _	5/18/06
	Mr. Stanley C. Juber Administrator of the Local Bridge Program

Connecticut Department of Transportation 2800 Berlin Turnpike, P.O. Box 317546 Newington, Connecticut 06131-7546

### 2. Description / Existing Condition

The bridge carrying Tomlinson Avenue over the Quinnipiac River consists of two asphalt coated corrugated metal elliptical arch pipes and approximately 30 inches of ballast with a bituminous concrete wearing surface. The original structure was built in 1968. There have been a number of minor maintenance repairs over the years; however, there is no record of rehabilitation. The existing bridge travel way width is approximately 28 feet and is referenced as ConnDOT Bridge No. 04546. The structure has an overall length of 25 feet with a maximum span of 12 feet and is eligible for State and Federal funding under the Local Bridge Program for the fiscal year 2007.

### Deck, Superstructure, Substructure (Rating=N)

According to the ConnDOT bridge inspection report, dated August 27, 2004, the deck, superstructure, and substructure have ratings = N (typical for a culvert). The bituminous overlay is in good condition (rating=7). However, the bituminous overlay shows longitudinal and transverse cracks and past crack sealing. There is a bituminous concrete lip curb on the north side only that shows open cracks. There is a water main located within the ballast on the north side.

### Channel and Channel Protection (Rating=6)

According to the ConnDOT bridge inspection report, dated August 27, 2004, the channel bank is in satisfactory condition (rating=6). The channel scour has not changed from the last inspection report, which noted that previous scour has undermined the culvert mitered ends. There is heavy embankment erosion at the outlet and downstream with areas of exposed tree root systems and trees leaning out over channel. The stream enters the structure at a slight angle to the structure's centerline from the west and is slightly diverted by encroachment with vegetation upstream & sand downstream at the southeast.

### Culverts & Retaining Wall (Rating=4)

According to the ConnDOT bridge inspection report, dated August 27, 2004, the culverts are in poor condition (rating=4). Both of the metal pipe barrels show some missing nuts at random plate connections and worn off protective coating mostly in the lower area. The invert in both barrels shows moderate rusting throughout. The invert in barrel #2 at the outlet mitered end shows areas of severe rusting and perforation holes ranging from a few inches to 8 ½ inches long by 1 to 2 inches wide.

### Approach Condition (Rating=7)

According to the ConnDOT bridge inspection report, August 27, 2004, the approach is in good condition (rating=7). The bituminous concrete pavement shows cracks and past crack sealing. Metal beam rail exists along both sides and shows minor scrapes.

### 3. Proposed Condition

According to the ConnDOT bridge inspection report, August 27, 2004, the existing structural evaluation rating is 4 (meets minimum tolerable limits to be left in place as-is). Based on the poor structural condition, the bridge warrants a complete replacement. The proposed replacement would include the following:

- 1) Remove the existing structure in its entirety.
- 2) Install new reinforced concrete abutments and wingwalls founded on steel piles.
- 3) Install a new prestressed concrete deck unit superstructure with a 28' travelway.
- 4) Install a new bridge rail system on new reinforced concrete parapets.
- 5) Place membrane waterproofing over the entire structure.
- 6) Install new guide railing and approaches.

Estimated construction cost for the work is \$1,074,324.00. A detailed estimate is provided on the following pages.

Town of Plainville Tomlinson Avenue over Quinnipiac River Bridge No. 04546 Federal Local Bridge Program

Preliminary Cost Opinion

1A B 1B B 2 M 3 R 4 C 5A F	Description re Items Bituminous Concrete Class 1 Bituminous Concrete Class 2	Ton	Quantity	Cost	Cost
1A B 1B B 2 M 3 R 4 C 5A F	Bituminous Concrete Class 1 Bituminous Concrete Class 2	Ton			
1B B 2 M 3 R 4 C 5A F	Bituminous Concrete Class 2	LOH	10	00.002	070
2 M 3 R 4 C 5A F		Ton	10	\$80.00	\$76
3 R 4 C 5A F	Membrane Waterproofing	S.Y.		\$110.00	\$55
4 C 5A F		L.S.	113	\$20.00	\$2,25
5A F	Remove Existing Structure Class "A" Concrete		1	\$25,000.00	\$25,00
	Furnish Steel Piles	C.Y.	377	\$500.00	\$188,63
EDIC	Orive Steel Piles	Lb.	177010	\$0.35	\$61,95
		L.F.	2394	\$20.00	\$47,87
	Deformed Steel Bars	LBS.	17357	\$1.50	\$26,03
	Elastomeric Bearing Pads	Ea.	32	\$250.00	\$8,00
	Prestressed Concrete Deck Units	L.F.	240	\$225.00	\$54,00
	Granite Curb	L.F.	60	\$35.00	\$2,10
	Metal Bridge Rail	L.F.	60	\$240.00	\$14,40
	Structure Excavation	C.Y.	1101	\$30.00	\$33,02
	Pervious Structural Backfill	C.Y.	835	\$40.00	\$33,39
13 8	Sheeting	S.Y.	400	\$25.00	\$10,00
				ructure Subtotal:	\$507,98
			20	0% Contingency:	\$101,59
				Structure Total	\$609,58
ighway	y & Stream Channel				
1 U	Insuitable Excavation	C.Y.	89	\$30.00	\$2,66
2 B	Borrow	C.Y.	257	\$20.00	\$5,14
3 M	Maintenance and Protection of Traffic	L.S.	1	\$15,000.00	\$15,00
	Roadway Excavation	C.Y.	5779	\$15.00	\$86,68
	Subbase	C.Y.	839	\$30.00	\$25,17
8 F	ormation of Subgrade	S.Y.	1099	\$3.00	\$3,29
	Bituminous Concrete	TON	548	\$80.00	\$43,82
	Mobilization	L.S.	1	\$50,000.00	\$50,00
		EA./DAY	780	\$1.50	\$1,17
	emporary Precast Concrete Barrier Curb		133	\$35.00	\$4,65
14 S		S.F.	7	\$20.00	\$13
		L.F.	187	\$25.00	\$4,67
		EA.	4	\$650.00	\$2,60
		L.S.	1	\$5,000.00	\$5,00
		Est	1	\$10,000.00	\$10,00
		L.F.	844	\$6.00	
		L.S.	1	\$7,500.00	\$5,06 \$7,50
		C.Y.	157	\$80.00	\$7,50
		EA	107		\$12,58
		L.F.	100	\$1,500.00	\$6,00
				\$30.00	\$3,00
	The state of the s	S.Y.	1296	\$10.00	\$12,96
20 00	onstruction trailer	Mo.	9	\$1,400.00	\$12,60
		Highwa	•	nannel Subtotal:	\$319,73
				% Contingency:	\$63,94
		Highway	& Stream Ch	annel Subtotal	\$383,687

# STRUCTURE NO. 04546

# TOMLINSON AVENUE over QUINNIPIAC RIVER PLAINVILLE

Routine Inspection on 8/27/2004

Inspected by Team 5 for Area 10

TEAM:	Forwarded to Senior	05-Ned Statchen	Date 11/8/04							
SENIOR:	Reviewed by Senior	Spumis	Date 1   85/ 05							
	BMM Required		NO							
	Town Bridge									
	Rating <= 5 (Iter	ms 58,59,60 or 62)								
	Forwarded to Supervisor	Stumas	Date 2/18/05							
	Forwarded to "To Be Copied	Drawer"	Date							
Date BRI-19 Entered										
SUPERVIS	SOR: Reviewed by Supe	ervisor Silv	man Date 2/18/05	-						
SUPPOR	C Date Copies Made		BMM No							

1057

STATE OF CONNECTICUT
DÉPARTMENT OF TRANSPORTATION
RUREAU OF HIGHWAYS

INSPECTION REPORT TRANSMITTAL FORM
Form BRI-27, Rev. 6/00

Structure No.
Inspection Date

04546 8/27/2004

Town

PLAINVILLE

Inspectors Team 5

# TABLE OF CONTENTS

Loose Forms (not bou	und in report)	Number of Sheets Enclosed
Maintenance Mem	o	0
Flagging Memos		0
PONTIS Element D	Oata Collection Form	1
Plan Sheets	Already on file $\Box$	0
<b>Bound Report Pages</b>		
Title Cover Sheet		1 BIRM sheet
<b>Table of Contents</b>		1 /
Executive Summa	ry	0
Field Notes		.01
Calculations:	Load Rating Evaluation	0
	<b>Quantities &amp; Cost Estimate</b>	0
Photo Sheets		5
Photo Images		10
<u>Forms</u>		
BRI-18, Bridge Ins	pection Form	3
BRI-19, Highway B	ridge Inventory Form	2

2	mm	200	te.
CO		ICI	ιιο.

(1) Attached sheet.

Need special in spection - monitor perforations.

Next inspection - note # 9 perforations - location from end.

6	Inspected By: D. Talmont & K. Weir BRIDGE SAFETY & EVA	SPORTATION	90) Inspection D	Deck Survey	91) Frequency Class 24 01 Access Flagman	5
		ALUATION	10/24/2000 Type	CRITICAL FEATURE INSPE	ECTIONS Date	FLAG
	BS&E Received Data Entry By: SHEET 2 OF 7 ( Copies Made Data Entry Date: 1/8/05	(INSP. REPORT)	Fracture: Uwater: Special:			RED
63	IDENTIFICATION			AGE AND SERVICE -		
	AND OF THE PROPERTY OF THE PRO	27) Year Built 19	68	106) Year Reconstruct	ted : 0000	T
	10.1000 11.100 1	42) Type of Service:	2000	-		
	5) Inventory Route:		lighway	B) Under	5 WATERWAY	
8	2 10 2 2	28) Number of Lanes:				
	B) Signing Prefix 5 City Street E) Directional Suffix 0 NA	A) On 2		B) Under	0.	T
		29) Average Daily Tra	ffic	2000		
		109) Percent Truck		2 %		District on the last
	<ul> <li>Committee or an experience of the State of Committee of the C</li></ul>	30) Year of ADT		1990		
13		19) Bypass, Detour Le	ength	2 miles		
	7) Facility Carried.	, ,,	0	GEOMETRIC DATA	L.	
	9) Location 600 FROM CYRENUS STREET	48) Length of Max Sp	oan	12 ft		
	9) LOCATION CONTROLLED STATE TO THE STATE OF	49) Structure Length				
		50) Curb or Sidewalk		Programme and the second		
82	11) Milepoint 1.69 Miles	Part	0.0 ft	. B) Righ	nt 0.0 ft	
ri .	16) Latitude 41 deg 39 min 48, sec deg min . sec	51) Brg Rdwy width,	4-1-1-14	0.0 ft		f
65	17) Longitude 72 deg 51 min 12.00 sec deg min sec	52) Deck Width, Out-		0.0 ft		f
	98) Border Bridge:	32) Approach Roadw		28 ft		f
	A) State Code B) Percent Responsibility %	33) Bridge Median		0 No Median		
	C) Border Town Name	Deck Area		1788 sqft		s
		34) Skew Angle		19 deg		
	99) Border Bridge Structure No	35) Structure Flared		0		
		10 )Inv. Rte. Min. Ver	t Clearance	99 ft 99 in	T ff F	1
	STRUCTURE TYPE AND MATERIAL	47) Log Inv. Rte. Tota		31.5 ft		f
	43) Structure Type, Main:	47) RLog Inv. Rte. To		ft		f
	A) Material 3 Steel B) Design Type 19 Culvert (includes fram	53) Min Vert Clearan		99 ft 99 in	ft	
	44) Structure Type, Approach:	54) Min Vert Under C	-	N Ref 0 ft 0 in	Ref ft	
	A) Material 0 Other B) Design Type 0 Other	55) Min Lat Under Cl			Ref .	f
0	A CONTRACT OF THE PERSON NAMED IN COLUMN NAMED	56) Min Lat Under CI		0.0 ft		f
	45) Number of Spans, Main Unit 2 46) Number of Approach Spans 0	,		1300		'
	107) Deck Structure Type N. Not Applicable		1	BRIDGE COMMENTS		
C.	<b>医动脉 外部</b>			DIADOL GOMMENTO		
	108) Wearing Surface/Protective System:					
	A) Type of Wearing Surface N Not Applicable					
ii.	B) Type of Membrane  Not Applicable					
	C) Type of Deck Protection Not Applicable					

	CL ASSIERO TION		
440) NDIC Bridge Length	CLASSIFICATION -	7	STRUCTURE EVALUATION Bridge Number 04546 NBIS Length
112) NBIS Bridge Length	Yes Contain	-	CHEET 2 OF 2 FORM PRI 10 PRIV 10/00
104) Highway System 26) Functional Class	0 Off System 19 Urban Local	-	Town Name (ELAINVILLE Yes 25
100) Defense Highway	Not Defense Highway		SHEET 3 OF 7 (INSP. REPORT) Facility Carried TOMLINSON AVENUE
101) Parallel Structure		-	Feature Crossed QUINNIPIAC RIVER
102) Direction of Traffic	No parallel structure exists	-	
103) Temporary Structure	2 2-way traffic	-	Inspected By: Almont & H. Weir
110) Designated National Network	0 Not on national network	-	LOAD RATING AND POSTING
20) Toll	10-72	-	31) Design Load 0 Evaluation Code L
manufacture of the second seco		-	63) Operating Rating Type 1 Year of Evaluation 2000
21) Maintain		-	64) Operating Rating 99:0 . 70) Bridge Posting 5
22) Owner	Town or Township Highway Agency	-	65) Inventory Rating Type 41) Structure Status A
Report Class	L LOCAL	-	
37) Historical Significance	Bridge is not eligible for National Register	_	66) Inventory Rating 65.0 Open, no restriction
D. i. D. i.o. i	WATERWAY	7	CONDITION — APPRAISALS —
DrainageBasinCode	5200	4	Rating By Rating By
38) Navigation Control	0 No navigation control on waterway	4	58) Deck No 67) Structure Evaluation 5 4 064
39) Navigation Vert Clr. 0	40) Navigation Horiz Clr. 0	-	59) Superstructure N. 07 68) Deck Geometry N.
116) Vert-Lift Brg Nav Min		4	60) Substructure N 69) Under Clear Vert & Horiz N
111) Pier Abutment Protection			61) Channel & Chan. Protection 6.7 71) Waterway Adequacy 5.7
	PROPOSED IMPROVEMENTS	_	62) Culverts 72) Approach Rdwy Alignment 8
75A) Type of Work Proposed		4	4 113) Scour Critical 8
75B) Work Done By		-	Items 58 Thru 72 Checked By: S Dumas 1/16/0.
76) Length of Struct. Improvement	ft	ft	
94) Bridge Improvement Cost	\$ [ ]		36) Traffic Safety Features:
95) Roadway Improvement Cost	\$		A) Bridge Railings
96) Total Project Cost			B) Transitions
97) Year of Improvement Cost Est.	88 J. W. 1944 ST 19673		C) Approach Guardrail
114) Future ADT	115) Year Future ADT		D) Approach Guardrail End
List No. Project No.	Advertised POSTED SIGNS & UTILITIES	_	OTHER FEATURES -
	POSTED SIGNS & UTILITIES	_	Fence Required No Barrel Ladder No
Other Posted Signs 1		4	Fence Present No. Stand Pipes No.
Other Posted Signs 2	Moderate		Fence Height 0.0 ft ft Cat Walks No
Actual P.L. Single Unit Truck	tons Actual P.L. 4Axle Truck tons		Fence Type Movable Inspection System No
Rec. P.L. Single Unit Truck	tons Rec. P.L. 4Axle Truck tons		Fence Material Loose Concrete Checked? No
Actual P.L. Semi-TrailerTruck	tons Actual P.L. 3S2 Truck tons		Fence Top Type
Rec. P.L. Semi-TrailerTruck	tons Rec. P.L. 3S2 Truck tons		\$289KLB
Rec. P.L. All Vehicles	tons Actual P.L. All Vehicles tons		INSPECTION COMMENTS —
Posted Vert Clearance On Bridge	ft in ft	In	Proposed Next Indepth Insp Year 2010
Posted Vert UnderClearance	ft in ft ft	In	
Posted Speed Limit	30 mph	mpl	h e
Utility			REVIEWED BY: Damas a Duncas Date 1/13/11
Utility	3 Electric	7	REVIEWED BY: Date Date

4 OF 7

# Connecticut Department of Transportation Bridge Inspection Report BRI-18

RIDGE #: 04546	6	INSPECTION DATE:	8/27/2004						
INSPECTION TYPE: INSPECTION PERFORMED	BY:		NOOPER REQUIRED: NO						
TOWN: PLAINVILLE  LOCATION: 600' FROM CY  MAIN MATERIAL: Steel	LOCATION: 600' FROM CYRENUS STRE FEATURE INTERSECTED QUINNIPIAC RIVER YEAR REBUILT: 0								
INSPECTION VISITS: Inspection Date: 8/27/200 Temperature: 68	)4 P F		tine Inspection						
58. DECK			OVERALL RATING P						
OVERLAY	7	Bituminous concrete over +/- 30 inches of ballast. Shows transverse and longitudinal cracks & past crack sealing.							
DECK STR. CONDITION	N								
CURBS	6	Bituminous concrete lip curb on north side only, shows open cracks.							
MEDIAN	N								
SIDEWALKS	N								
PARAPET	N								
RAILING	N	See Approach guide rail.							
PAINT	N								
FENCE	N								
DRAINS	N								
LIGHTING STANDARD	N								
UTILITIES TYPE/SIZE	N	Water main located in ballast on north side.							
CONSTRUCTION JOINTS	N								
EXPANSION JOINTS	N								
59. SUPERSTRUCTURE			OVERALL RATING N						
60. SUBSTRUCTURE			OVERALL RATING N						
61. CHANNEL & CHANNE	EL PI	ROTECTION	OVERALL RATING 6						
CHANNEL SCOUR	_	No change from the last report which noted: previous scour at the outlet he culvert mitered ends, see photo.	nas undermined the						
EMBANKMENT EROSION	4	Heavy erosion at outlet and downstream, areas of exposed tree root system over channel. See photo.	ems & trees lean out						
DEBRIS [	6	Debris - Minor trash in downstream channel.  Obstruction - Sand encroachment at southeast outlet end.							
VEGETATION [	6	Embankments are well vegetated but show areas of erosion.							
CHANNEL CHANGE	6	Freeboard approximately 6 feet - 8 inches.							

# Connecticut Department of Transportation Bridge Inspection Report BRI-18

BRIDGE #: 0454	6		INSPECTION DATE:	8/27/2004					
61. CHANNEL & CHANN	EL P	ROTECTIO		OVERALL RATING	6				
		Alignment - s	erdepth 3 to 8 inches.  tream enters structure at slight angle to structure centerline to a comment with vegetation upstream & sand encroachment	from west & is slightly t downstream at the					
FENDER SYSTEM	N								
SPUR DIKES & JETTIES	N								
RIP RAP	6		rap needed at outlet to support mitered end treatment and t	o control erosion of	$\neg$				
slope between pipe ends.  Appears some riprap has been added at outlet end of pipe #1.									
62. CULVERTS & RETAINING WALL Two Span Asphalt Coated Corrugated Metal Pipe.  OVERALL RATING									
	RATING		has good, smooth curvature, seams and joints are tight.						
BARREL		Darrei Silape	mas good, smooth curvature, seams and joints are ught.		=				
CONCRETE		D-th hl-			=				
STEEL	4	coating most Invert in Barre ranging from	show some missing nuts at random plate connections and w y in lower area. Invert in both barrels shows moderate rusting at #2 at outlet mitered end shows areas of severe rusting and few inches to 8-1/2 inches long by 1 to 2 inches +/- wide, se pipe measurement sheet.	ng generally thru-out. d perforation holes					
TIMBER	N				$\exists$				
HEADWALL	N				=				
CUTOFF WALL	N				=				
DEBRIS	7	Minor accumi	ulation of stones, silt in both barrels.		=				
RETAINING WALL STEM	N								
FOOTING	N								
APPROACH CONDITION				OVERALL RATING	7				
4000040110140	RATING	<u> </u>							
APPROACH SLAB									
RELIEF JOINTS									
APPROACH GUIDE RAIL			with steel posts, minor scrapes.						
APPROACH PAVEMENT	7	Bituminous C	oncrete show cracks and past crack sealing.						
APPROACH EMBANKMENT	8								
TRAFFIC SAFETY FEATURE									
BRIDGE RAILINGS	N				_				
TRANSITIONS	N								
	N				_				
APPR. GUARDRAIL ENDS	N								
LOAD POSTING									
SINGLE UNIT (TONS)									
HS (TONS)					$\overline{}$				

# Connecticut Department of Transportation Bridge Inspection Report BRI-18

BRIDGE #:	04546	INS	PECTION DATE:	8/27/2004
4 AXL	E (TONS)			9
33	S2 (TONS)			
ADVANCE WAR	RNING Y/N	1		
	EGIBILITY	1		
VISIBILITY/L	_			
		¹ L		
MISC.				
MIN VERT. UNDE	RCLR.			
POSTED CLR. UN	IDER BRIDGE			
POSTED CLR. ON	BRIDGE			
ADVANCE WARN	ING (Y/N)	No		
SPEED LIMIT (IF	ANY)	30 <sub>MPH</sub>		
CHARACTER OF	TRAFFIC	Light volume, mostly residential.		
ADDITIONAL NOT	ES			
Bridge ID numbe	er located at o	utlet end of pipe #1 west side.		
ADDITIONAL CON		no week to east 110 of come in worth		
Route inventory is	ogged direction	on west to east. Up stream is north.		
Inspectors' Signat	tures: 1	Denstohnt	Date: 8 27 200 Date: 8 27 04	24
	2	Kes A. Weir	Date: 8 127 04	2
	3		Date://	
	4		Date://	
P.E. Si	ignature:		Date://	
	P.E.#:			
Revi	ewed by:	Jandra a Dumas CDOT	Date: 1/5/05	
	,			

CHANGES




Exhibit 85. Shape inspection structural plate pipe arch.

MEASURE BF, ED, AND HORIZONTAL SPAN

2. IF AC EXCEEDS DESIGN BY 3% OR MORE

OF TOP ARC

### Structure Inventory and Appraisal Sheet (English Units)

Frequency 91:

Agency ID: 04546 Sufficiency Rating: 0 Bridge Key: 04546

	IDENTIFI	CATION		
State 1:	09 Connecticut	Struc Num 8:	04546	
Facility Carried 7:			600' FF	ROM CYRENUS T
Rte.(On/Under)5A:	Route On Structure	Rte. Signing P	refix 5B:	5 City Street

Level of Service 5C: 0 None of the below Rte. Number 5D: Directional Suffix 5E: 0 N/A (NBI) % Responsibility: SHD District 2: 01 County Code 3: 0.640 mi Mile Post 11:

Feature Intersected 6: QUINNIPIAC RIVER

41d 39' 48" Longitude 17: 072d 51' 12"

Border Bridge Code 98: Unknown (P) Border Bridge Number 99: NA

### STRUCTURE TYPE AND MATERIALS

Main Span Material/Design 43A/B:

19 Culvert

Deck Type 107: N N/A (NBI) Wearing Surface 108A: N N/A (no deck (NBI)) Membrane 108B: N N/A (no deck (NBI)) Deck Protection 108C: N N/A (no deck (NBI))

AGE AND SERVICE

Type of Service on 42A: Type of Service under 42B: 5 Waterway

Lanes on 28A: 2 Lanes Under 28B: 0 Detour Length 19: 1.9 mi ADT 29: 2.000 Truck ADT 109: 2 % Year of ADT 30: 1990

### GEOMETRIC DATA

Length Max Span 48: 12.1 ft Structure Length 49: 24.9 ft Curb/Sdwik Woth L 50A: 0.0 ft Curb/Sidewalk Width R 50B: 0.0 ft Width Curb to Curb 51: 0,0 ft Width Out to Out 52: 0.0 ft Median 33: 0 No median

Approach Roadway Width 32: 27.9 ft (w/ shoulders) Deck Area: . sq. ft

Skew 34: 19.00 ° Structure Flared 35: Minimum Vertical Clearance Over Bridge 53:

Minimum Vertical Underclearance Reference 54A:

Minimum Vertical Underclearance 54B: Minimum Lateral Underclearance Reference R 55A:

Minimum Lateral Undrelearance R 55: Minimum Lateral Undrolearance L 56:

328,1 ft

N Feature not hwy or RR 0.0 ft N Feature not hwy or RR

327.8 ft

Year Reconstructed 106: Unknown

08/27/2006 24 months Inspection Date 90: 8/27/2004 FC Frequency 92A: NA FC Inspection Date 93A: NA Next FC Inspection: NA UW Frequency 92B: NA UW Inspection Date 93B: NA Next UW Inspection: NA SI Date 93C: SI Frequency 92C: NA

Element Frequency: 24 months Element Inspection Date: 08/27/2004 Next Elem. Insp. Due: 08/27/2006

INSPECTION

### CLASSIFICATION

Defense Highway 100: 0 Not a STRAHNET hwy Parallel Structure 101: No II bridge exists Direction of Traffic 102: 2 2-way traffic Temporary Structure 103: Unknown (NBI) Highway System 104: 0 Not on NHS NBIS Length 112: Toll Facility 20: 3 On free road Functional Class 26: 19 Urban Local Historical Significance 37: 5 Not eligible for NRHP

Owner 22: 3 Town/Township Hwy Agency Custodian 21: 3 Town/Township Hwy Agency

#### CONDITION

Deck 58: N N/A (NBI) Super 59: N N/A (NBI) Channel/Channel Protection 61: 6 Bank Stumping Culvert 62: 5 Moderate Damage

#### LOAD RATING AND POSTING

Inventory Rating Method 65: 1 LF Load Factor Operating Rating Method 63: 1 LF Load Factor HS35.8 Operating Rating 64:

Design Load 31: Unknown (NBI)

Posting 70:

5 At/Above Legal Loads

Posting status 41: A Open, no restriction

### APPRAISAL

Bridge Rail 36A: N N/A or not required Approach Rail 36C: N N/A or not required Transition 368 Approach Rail Ends 36D: N N/A or not required Str. Evaluation 67: Deck Geometry 68: N Not applicable (NBI) Underclearance, Vertical and Horizontal 69: N Not applicable (NBI) Approach Alignment 72: Waterway Adequacy 71: 5 Above Tolerable 8 Equal Desirable Crit

8 Stable Above Footing

### PROPOSED IMPROVEMENTS

\$ 1,000 Type of Work 75: 38 Other Structural Bridge Cost 94: Roadway Cost 95: Length of Improvment 76: Future ADT 114: Total Cost 96: \$ 2,000 1,000 Year of Cost Estimate 97: 2000 Year of Future ADT 115: 2019

#### **NAVIGATION DATA**

Navigation Control 38: 0 Permit Not Required

Horizontal Clearance 40: Pier Protection 111: Lift Bridge Vertical Clearance 116:

### **ELEMENT CONDITION STATE DATA**

Str Unit	Elm/Env	Description	Units	Total Qty	% in 1	Qty. St. 1	% in 2	Qty. St. 2	% in 3	Qty. St. 3	% in 4	Qty. St. 4	% in 5	Qty. St. 5
UNITO	240/3	Steel Culvert	(LF)	141	77 %	112	15 %	20	8 %	10	0 %	0	0 %	0

Bridge No.	04546	Inspected by:	DENNIS TALMONT
Town:	Plainville	Inspected by:	KIRK WEIR
Feature Carried:	Tomlinson Avenue	Date Inspected:	Friday, August 27, 2004
Feature Crossed:	Quinnipiac River	Project No.:	



Photo # 1
Looking East from the West approach. {Inspector at structure.}




Photo # 2 Wearing surface.

		or substituting	
Bridge No.	04546	Inspected by:	DENNIS TALMONT
Town:	Plainville	Inspected by:	KIRK WEIR
Feature Carried:	Tomlinson Avenue	Date Inspected:	Friday, August 27, 2004
Feature Crossed:	Quinnipiac River	Project No.:	




Photo # 3 Inlet.




Photo # 4
Outlet.

Bridge No.	04546	Inspected by:	DENNIS TALMONT
Town:	Plainville	Inspected by:	KIRK WEIR
Feature Carried:	Tomlinson Avenue	Date Inspected:	Friday, August 27, 2004
Feature Crossed:	Quinnipiac River	Project No.:	




Photo # 5 The interior of pipe # 1.




Photo # 6 The interior of pipe # 2.

Bridge No.	04546	Inspected by:	DENNIS TALMONT
Town:	Plainville	Inspected by:	KIRK WEIR
Feature Carried:	Tomlinson Avenue	Date Inspected:	Friday, August 27, 2004
Feature Crossed:	Quinnipiac River	Project No.:	




Photo # 7 Hole in the invert of pipe # 2, near outlet.




Photo # 8
Exposed tree root's and heavy erosion at the Southwest embankment.

Bridge No.	04546	Inspected by:	DENNIS TALMONT
Town:	Plainville	Inspected by:	KIRK WEIR
Feature Carried:	Tomlinson Avenue	Date Inspected:	Friday, August 27, 2004
Feature Crossed:	Quinnipiac River	Project No.:	



Photo # 9 Looking upstream from the inlet.



Photo # 10 Looking downstream from the outlet.