

SAMPLE PROJECT USED FOR PLANS

The following sample project involves replacing an existing large pipe with a three-sided (open bottom) culvert. The project is planned to be constructed in 3 stages. A water handling pipe will be used and placed within the existing pipe. This project involves a roadway overbuild in the staging, therefore, an access road is not needed for construction of the project.

The following permits are anticipated for this project:

DEEP Inland Water Resources Division Flood Management Certification (IWRD FMC)

General Permit for Water Resource Construction Activities (IWRD GP)

US Army Corps of Engineers Category 1 (USACE Cat 1)

For this sample project, the cofferdam was designed using a 2-year frequency discharge. The culvert was designed for a 100-year storm. The sample project falls within a mapped FEMA area with no elevation provided on the FEMA map. A 100-year storm elevation (existing) has been calculated and this elevation is used in determining the floodplain impact area. An 8 1/2" x 11" FEMA map is provided within the permit application.


Impact areas include ALL areas to be impacted due to the project construction and activities related to the project, both temporary and permanent. On this project, additional impact area was included to allow the contractor to utilize different methods and equipment. Engineering judgement should be used to determine the amount of area the contractor needs to perform the work, while trying to minimize the disturbance to the wetland resources. The designer should also evaluate utility work needed as part of the project and include any impacts due to project related utility work.

NOTE: This sample project has been altered from the actual project to produce this sample set of plans.

GENERAL NOTES:

- 1. THESE PLANS ARE INTENDED ONLY FOR ENVIRONMENTAL PERMITTING PURPOSES. THESE PLANS HOLD AUTHORITY FOR ALL ACTIVITIES CONCERNING THE REGULATED AREA. FOR DETAILED PLANIMETRIC INFORMATION AND PAYMENT REFER TO THE APPLICABLE CONTRACT DOCUMENTS.
- 2. THE DEPARTMENT OF TRANSPORTATION WILL ONLY SUBMIT REVISIONS TO DEEP AND USACE FOR CHANGES TO THE DESIGN THAT WILL AFFECT REGULATED AREAS.
- 3. FOR A DESCRIPTION OF THE WATERCOURSES, WETLANDS AND WETLAND SOILS SEE RELEVANT SECTIONS OF THE PERMIT APPLICATION.
- 4. 400 FOOT GRID BASED ON CONNECTICUT COORDINATE SYSTEM N.A.D. 1927 VERTICAL DATUM BASED ON NGVD OF 1929.
- 5. ALL CONSTRUCTION ACTIVITIES WILL BE CONDUCTED IN ACCORDANCE WITH THE DEPARTMENT'S STANDARD SPECIFICATIONS FOR ROADS, BRIDGE, AND INCIDENTAL CONSTRUCTION, FORM 816, SECTION 1.10 AND WILL ALSO FOLLOW BEST MANAGEMENT PRACTICES (BMPs) AND SEDIMENT AND EROSION CONTROL MEASURES IN ACCORDANCE WITH THE 2002 EROSION & SEDIMENTATION CONTROL GUIDELINES AND THE 2004 STORMWATER QUALITY MANUAL.

ENVIRONMENTAL PERMIT PLANS STATE PROJECT NO. XXXX-XXXX REPLACEMENT OF BRIDGE NO. XXXXX IN THE TOWN OF



LOCATION PLAN

1" = 500'

GUIDE FOR THE DEVELOPMENT OF THE PERMIT PLAN SET

TITLE SHEET:

1. LOCATION PLAN AT AN APPROPRIATE SCALE THAT SHOWS PROJECT LOCATION AND NEARBY CROSS STREETS (EX. 1"=500', 1"=1000'). FOR LATERAL PROJECTS, DEPICT BEGINNING AND END OF PROJECT (PROJECT LIMITS).

2. STATE OF CONNECTICUT MAP WITH TOWN SHADED AND

CALL-OUT PROJECT LOCATION

3 GENERAL INDEX FOR "LIST OF DRAWINGS"

3. GENERAL INDEX FOR "LIST OF DRAWINGS"
4. GENERAL NOTES 1-5 (ADDITIONAL NOTES MAY BE ADDED AS APPROPRIATE FOR THE PROJECT)
5. SIGNATURE BLOCK FOR CONSULTANT ENGINEER, IF NEEDED.

5. SIGNATURE BLOCK FOR CONSULTANT ENGINEER, IF NEEDED.
6. PLAN DATE (LATEST REVISION DATE OF SHEET. DATES DO NOT NEED TO MATCH WITHIN PLAN SET)

ON ALL OTHER PLAN VIEWS:

1. WETLAND LIMITS BOLD (NOT SCREENED)
2. SHOW CUT/FILL LIMITS AND SEDIMENTATION CONTROL SYSTEM (SCS). (SCS NOT NECESSARY ON PLANTING PLAN)

3. SHOW ORDINARY HIGH WATER (OHW)
4. SHOW FLOOD LIMIT LINES ON PLAN VIEWS


A) CALCULATED ELEVATION ON A FEMA MAP GOVERNS. LABEL "FEMA 100-YR FLOOD (CALCULATED)"

B) OTHERWISE, SHOW HYDRAULIC ANALYSIS ELEVATION. LABEL "EXISTING 100-YR FLOOD (CALCULATED)"

C) IF NO CALCULATIONS WERE PERFORMED, SHOW MAPPED FEMA LINES. LABEL "MAPPED FEMA 100-YR FLOOD LIMIT" 5. FLOW ARROWS (EXISTING AND PROPOSED)


NOTE: FOR ADDITIONAL ENVIRONMENTAL INFORMATION, SEE ALSO THE DEPARTMENT'S OFFICE OF ENVIRONMENTAL PLANNING'S PERMIT PLAN CHECKLIST FOUND ON THE WATER & NATURAL RESOURCES WEBPAGE UNDER "PERMITTING PROCESS"


	LIST OF DRAWINGS					
DRAWING NO.	DRAWING TITLE					
PMT-01	TITLE SHEET					
PMT-02	GENERAL SITE PLAN					
PMT-03	WETLAND/WATERCOURSE IMPACT PLAN					
PMT-04	100-YEAR FLOOD IMPACT PLAN					
PMT-05	ELEVATIONS & SECTION PLAN					
PMT-06	STAGING AND WATER HANDLING PLAN					
PMT-07	PERMIT PLANTING PLAN					





PLAN DATE: APRIL 4, 2016

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO. WAY WARRANTED TO INDICATE	CHECKED BY:	STATE OF CONNECTICUT	SIGNATURE/ BLOCK:	REPLACEMENT OF BRIDGE NO. XXXXX	TOWN	XXX-XXX DRAWING NO. PMT-01
REV. DATE REVISION DESCRIPTION SHEET NO. Plotted Date: 6/7/2016	SCALE AS NOTED	DEPARTMENT OF TRANSPORTATION Filename: ATITLE SHEET - Proj XXX dan		ROUTE X OVER A BROOK	TITLE SHEET	SHEET NO.









DEPARTMENT OF TRANSPORTATION

Filename: ...\Elevations - Proj XXX.dgn

ROUTE X OVER A BROOK

ELEVATION AND

SECTION PLAN


IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

SHEET NO. Plotted Date: 6/7/2016

REVISION DESCRIPTION

REV. DATE

SCALE AS NOTED



STAGE 1 - SUGGESTED SEQUENCE

- 1. INSTALL SEDIMENTATION CONTROL SYSTEM (SCS).
- 2. PLACE TEMPORARY BARRIER. CONSTRUCT TEMPORARY WIDENING.
- 3. CONSTRUCT TEMPORARY DEWATERING BASIN. BASIN TO REMAIN THROUGH ALL STAGES.
- 4. INSTALL TEMPORARY WATER HANDLING SYSTEM INCLUDING COFFERDAMS AND TEMPORARY PIPE. DIVERT WATER THROUGH THE TEMPORARY PIPE. WATER HANDLING TO REMAIN THROUGH ALL STAGES.





TABLE VARY AND ARE **DEPENDENT** UPON **PROJECT SPECIFICS**

CALCULATED BY DOT's **HYDRAULICS** & DRAINAGE OR CONSULTANT

TEMPORARY HYDRAULIC DATA AVERAGE DAILY FLOW 3 CFS AVERAGE SPRING FLOW 6 CFS 2-YEAR FREQUENCY DISCHARGE 46 CFS TEMPORARY DESIGN DISCHARGE 46 CFS TEMPORARY DESIGN FREQUENCY 2-YEAR FLOW TEMPORARY WATER SURFACE 90.62 FT **ELEVATION UPSTREAM** TEMPORARY WATER SURFACE 89.02 FT

WATER HANDLING NOTES:

- 1. THE CONTRACTOR SHALL MAINTAIN WATER THROUGH THE TEMPORARY BYPASS PIPE AS SHOWN DURING CONSTRUCTION OF THE NEW STRUCTURE.
- 2. EQUIPMENT SHALL NOT BE PERMITTED IN THE STREAM WHEN TEMPORARY BYPASS PIPE IS NOT IN PLACE WIHOUT APPROVAL FROM THE ENGINEER.
- 3. A PUMP DISCHARGE BASIN SHALL BE ESTABLISHED OUTSIDE OF THE WETLAND LIMITS. THE LOCATION OF THE DEWATERING BASIN IS APPROXIMATE. THE EXACT POSITION MAY VARY BASED ON THE PUMPING DESIGN SUBMISSION AND APPROVED BY THE ENGINEER.
- 4. TEMPORARY COFFERDAM SHALL CONSIST OF PLASTIC LINER, SANDBAGS, OR ANY OTHER APPROVED SYSTEM THAT THE CONTRACTOR ELECTS TO USE WHICH WILL SAFELY CONVEY WATER FLOWS THROUGH THE CONSTRUCTION AREA, SHALL BE ABLE TO SUPPORT CONSTRUCTION ACTIVITY AND EXCAVATION, AND SHALL CONFORM TO PERMITS.



STAGE 2 - SUGGESTED SEQUENCE

- 1. EXCAVATE AND CONSTRUCT MICROPILES. CONSTRUCT STAGE 2 FOOTINGS.
- 2. PARTIALLY REMOVE TOP AND SIDE PORTIONS OF EXISTING CULVERT WHILE MAINTAINING WATER THROUGH THE TEMPORARY PIPE.
- 3. PARTIALLY CONSTRUCT THE FINAL CHANNEL OUTSIDE THE TEMPORARY
- 4. ERECT STAGE 2 PRECAST CONCRETE THREE-SIDED FRAME UNITS.
- 5. COMPLETE WINGWALLS 1A AND 2A. CONSTRUCT ENDWALLS AND BACKFILL.
- 6. COMPLETE STAGE 2 ROADWAY CONSTRUCTION.
- 7, COORDINATE WITH EXISTING OVERHEAD UTILITIES TO RELOCATE POLES AS SHOWN PRIOR TO STAGE 3 CONSTRUCTION.
- 8. COORDINATE WITH UTILITY TO RELOCATE THEIR FACILITIES TO THE PREMANENT LOCATION ALONG THE OUTSIDE OF WINGWALLS 1A AND 2A.

GUIDE FOR THE DEVELOPMENT OF THE PERMIT PLAN SET

STAGING/WATER HANDLING PLAN:

1. THE PURPOSE OF THIS PLAN SHEET IS TO SHOW THE REGULATING AGENCY THE GENERAL INTENDED SCHEME FOR CONSTRUCTION/STAGING OF THE PROJECT AND ALSO THE METHOD(S) INTENDED FOR WATER HANDLING. IT IS EXPECTED THAT MORE DETAILED PLANS MAY BE DEVELOPED FOR FINAL CONSTRUCTION AND ALSO SUBMITTED BY THE CONTRACTOR. IT IS INTENDED THAT THESE PERMIT PLANS BE GENERAL ENOUGH THAT LATER PLANS CAN COMPLY WITH THE INTENT OF THE PERMIT PLANS. 2. SEQUENCING STATES THE BASIC INFORMATION FOR CONSTRUCTION OF THE PROJECT. 3. FOR HANDLING OF THE STREAM, SHOW APPROXIMATE LOCATION OF WATER HANDLING TO BE INCLUDED IN THE STAGING. CALL-OUT SIZE OF TEMPORARY PIPE FOR GRAVITY FLOW (OR MINIMUM CHANNEL WIDTH, IF APPLICABLE). CALL-OUT THE HOSE IF PUMPING 4. SHOW LOCATION OF DEWATERING BASIN (IF NEEDED). LOCATION SHALL BE OUTSIDE OF WETLAND AREA AND, IF POSSIBLE, OUTSIDE OF THE FLOOD LIMITS. 5. PROVIDE CALL-OUTS FOR ITEM BEING CONSTRUCTED DURING THE SPECIFIC STAGE. 6. INCLUDE COFFERDAM DETAIL SHOWING DESIGN FREQUENCY ELEVATION AND PROPOSED TOP OF COFFERDAM. (COFFERDAM DETAIL IS NOT REQUIRED TO BE SANDBAGS) 7. INCLUDE TEMPORARY HYDRAULIC DATA TABLE AS APPROPRIATE FOR PROJECT. 8. PLAN DATE (LATEST REVISION DATE OF SHEET, DATES DO NOT NEED TO MATCH WITHIN PLAN SET)

PRECAST CONCRETE 3-SIDED RIGID FRAME —ENDWALL 2B ENDWALL 2A--15" R.C. PIPE ·15" R.C.C.E. 1' NATURAL STREAMBED ON -MODIFIED/RIPRAP (SEE PMT-05)

STAGE 3 - SUGGESTED SEQUENCE

- 1. RELOCATE TEMPORARY PRECAST BARRIER AND SHIFT TRAFFIC.
- 2. EXCAVATE AND CONSTRUCT MICROPILES. CONSTRUCT STAGE 3 FOOTINGS.
- 3. PARTIALLY REMOVE TOP AND SIDE PORTIONS OF EXISTING CULVERT WHILE MAINTAINING WATER THROUGH THE TEMPORARY PIPE.
- 4. PARTIALLY CONSTRUCT THE FINAL CHANNEL OUTSIDE THE TEMPORARY
- 5, ERECT STAGE 3 PRECAST CONCRETE THREE-SIDED FRAME UNITS.
- 6. COMPLETE ENDWALLS 2A AND 2B AND BACKFILL.
- 7. COMPLETE STAGE 3 ROADWAY CONSTRUCTION.
- 8. REMOVE THE REMAINING PORTION OF THE EXISTING CULVERT AND COMPLETE CHANNEL CONSTRUCTION, INSTALL RIPRAP OUTLET.
- 9. REMOVE TEMPORARY WATER HANDLING FACILITIES.
- 10. COORDINATE WITH GAS COMPANY TO RELOCATE FACILITIES TO THE PERMANENT LOCATION ALONG THE SOUTH FASCIA.
- 11. REMOVE EROSION AND SEDIMENTATION CONTROL UPON PERMANENT STABILIZATION.

LEGEND

SEDIMENTATION CONTROL SYSTEM (SCS) ——OHW—— ORDINARY HIGH WATER (OHW)

— ✓ ○ — STATE/FEDERAL WETLANDS

— 100YR — EXISTING 100-YR FLOOD ELEVATION (CALCULATED)

DRAWING NO.

ENVIRONMENTAL PERMIT PLANS PLAN DATE: APRIL 8, 2016

SIGNATURE/ BLOCK: REPLACEMENT OF BRIDGE NO. XXXXX ROUTE X OVER A BROOK

XXX-XXX **TOWN PMT-06** DRAWING TITLE: STAGING/ WATER HANDLING PLAN

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED. REVISION DESCRIPTION SHEET NO. Plotted Date: 6/7/2016 REV. DATE

ELEVATION DOWNSTREAM

SCALE IN FEET SCALE 1"=20'

STATE OF CONNECTICUT **DEPARTMENT OF TRANSPORTATION**

Filename: ...\Staging Plan - Proj XXX.dgn

