## **Public Information Meeting**

### Replacement of Bridge No. 05588

Route 74 over Hockanum River State Project No. 146-196

Vernon, Connecticut

## <u>Design Team</u>

**CTDOT Bureau of Engineering and Construction** 

**Contact:** Lesgie M. Ruiz

Consultant Liaison: Close, Jensen and Miller, P.C.

**Contact:** Edward M. Sakl, III, P.E.

Design Engineer: Zuvic, Carr and Associates, Inc.

Contact: John F. Schearer, Jr., P.E.

## CTDOT Role and Mission

## Bureau of Engineering and Construction

 Responsible for engineering design, construction and inspection of transportation projects

## Close, Jensen and Miller, P.C. Consultant Liaison Engineers

CTDOT has retained the firm of Close, Jensen and Miller to supervise the activities relative to the design of this bridge project.

## **Zuvic, Carr and Associates, Inc. Consulting Engineers**

CTDOT retained the firm of Zuvic, Carr and Associates to design the bridge project.

## **Project Goals**

- Replace the existing bridge
- Minimize disturbance to traveling public
- Complete construction in a timely manner
- Effectively use funds



### **Project Location**





## **Aerial View**

Looking North

Connecticut Department of Transportation

## Existing Route 74 Bridge

- Twin corrugated metal pipe arch structure originally built in 1955
- Carries two lanes of Route 74 (Windsorville Road) over Hockanum River
- Concrete floor and stems supporting corrugated metal pipes
- Very narrow roadway (20-foot curb to curb width)
- Metal beam guide rail protection
- Carries exposed 16-inch water main and buried 8-inch gas main
- Significant school bus traffic
- No sidewalks



## **North Elevation**

Looking West

Connecticut Department of Transportation





Route 74

Looking East, Bridge No. 05588

Connecticut Department of Transportation

## Reasons for Project



Deteriorated Condition of Pipe Arches; Pipe Size not Adequate for Flow

## Reasons for Project



**Narrow Roadway** 




## **Utility Coordination**

- Overhead utilities are present at the bridge:
  - Telecommunications
  - Electrical
  - Cable TV
- Underground utilities are present at the bridge:
  - Natural gas
  - Water, above ground at bridge
- CJM has notified the appropriate utility companies of the project, an initial coordination meeting with the utilities has been held


## Proposed Roadway

#### **Reconstruction of Route 74:**

- Maintain existing horizontal and vertical alignment
- Widen existing 20-foot curb-to-curb width to 32 feet
- Construct a 5-foot sidewalk over the bridge on the south side
- Hang the water and gas mains from the south parapet




## Proposed Roadway



## Proposed Replacement

- Accelerated bridge construction techniques
- Precast deck units on precast concrete abutments, and precast wingwalls
- Cast-in-place concrete parapets
- Addition of 5-foot concrete sidewalk on south side of bridge
- Attachment of water and gas mains to south side of bridge
- Repaving of 310 feet of Route 74

## **Proposed Bridge**



Typical Bridge Elevation (South Elevation Shown)



# Maintenance & Protection of Traffic

#### **Before the Detour:**

- Relocate and protect overhead utilities
- Construct temporary bridge for pedestrians and utilities
- Relocate the water main and gas main
- Use off-peak lane closures

## Maintenance & Protection of Traffic


#### **Vehicular Detour to Reduce Construction Duration:**

- Bridge closure duration: 7 weeks
- Detour: Route 74 (Windsorville Rd.) to Route 286 (Pinney St.) to Windermere Ave. to Route 74/83 (Windsor Ave) to Route 74 (Windsorville Rd.)
- Length of detour: 3.5 miles


#### **After the Detour:**

 Open bridge to traffic. Close shoulders to complete sidewalk, utility and parapet work, if necessary; use standard off-peak lane closure patterns to complete guiderail, paving

## <u>Detour</u>



## **After Detour**




Typical Section

## **Environmental Permitting**

#### **Required Permits:**


- Connecticut Department of Energy and Environmental Protection (CTDEEP) Inland Wetlands and Watercourse Permit
- CTDEEP Flood Management Certification
- U.S. Army Corps of Engineers / Connecticut Programmatic General Permit

## Water Handling Plan




Conceptual Plan

## Water Handling Plan



Conceptual Plan

## Water Handling Plan




Conceptual Plan

## **Property Impacts**

Construction Easements and Permanent Easements are anticipated for the Town of Vernon Property.

## Proposed Roadway



## Project Schedule & Cost

**Bridge No. 05588: Spring 2015 Construction\*** 

**Construction Duration: 5 Months** 

\$2,000,000 including incidentals and contingencies (State funding)

\* Schedule contingent upon funding and receipt of permits

## **Contact Information**

#### CTDOT

Ms. Lesgie M. Ruiz 2800 Berlin Turnpike, P.O. Box 317546 Newington, Connecticut 06131-7546 (860) 594-3351; <a href="mailto:lesgie.ruiz@ct.gov">lesgie.ruiz@ct.gov</a>

Close, Jensen and Miller, P.C.

Mr. Edward M. Sakl, III, P.E.

1137 Silas Deane Highway

Wethersfield, Connecticut 06109

(860) 563-9375; esakl@cjmpc.com

## THANK YOU...

### FOR YOUR TIME AND ATTENTION

