

**CENTRAL CONNECTICUT STATE UNIVERSITY  
NEW PUBLIC SAFETY BUILDING  
NEW BRITAIN,CT  
PROJECT: BI- RC - 311**

**BID OPENING**

**1:00 P.M.**

**APRIL 20, 2011**

**ADDENDUM NUMBER 3**

**APRIL 12, 2011**

The following clarifications are applicable to drawings and specifications for the project referenced above.

Item 1

To arrange a site visit, contact Robert Lebaron.

Item 2

To arrange for an electronic copy of the existing topography plans provided in Addendum #1 and #2 please e-mail Kathyann Cowles directly at [kcowles@id3Architecture.com](mailto:kcowles@id3Architecture.com)

Item 3

Drawing A2.2 REVISE section reference B/ A7.2 to A/A7.1.

Item 4

Sheet A8.1, REVISE door #104A to aluminum door and aluminum frame in lieu of hollow metal shown.

Item 5

Sheet A8.1, Door # 108C should meet the detention door specifications per section 083463.

Item 6

Drawing A2.3, Second Floor Plan, DELETE reference to 1/A5.4 which refers to a base cabinet. Provide pole and shelf as shown on 7/A5.4

Item 7

Drawing A.2.2 at Room 1120000, Evidence Processing, DELETE reference to spray fireproofing at this location only. Reference to

Item 8

BIDDERS QUESTIONS/CLARIFICATIONS


- A. A. There are three lockers in locker room 0040000 as shown on the architectural plans.
- B. B. The window detail A7.3 is correct. The window sill is GWB.

- C. Self adhered sheet membrane is required per the wall details for the air/ vapor barrier.
- D. Miscellaneous fasteners, angles, shims, etc are specified in 034500.
- E. Colors will be verified by the Architect during the submittal process
- F. Vanity countertops are specified in section 055000.
- G. Shelving length should be 9'-6" in lieu of the 9'-0" specified. Shelving is 7'5" high – allow 5 shelves
- H. Unsuitable materials below sub grade elevations shall be included in the bid.
- I. DELETE reference to integral sink. Drop-in sinks are required as indicated on the plumbing drawings.
- J. Clarification for the liquid filled XFMR:
  - Altitudes above 3300 ft need to be specified
  - Seismic zone needs to be specified if other than zone 1 (standard)
  - space limitations need to be specified if this need to be retro-fit
- K. Clarification for the Electrician's responsibilities:
  - Section 22 05 33 heat tracing for plumbing piping
  - Section 23 24 19 motor control center

Item 9

All questions must be in writing (not phone or e-mail) and must be forwarded to the consulting Architect/Engineer (Name and Fax Number) with copies sent to the DPW Project Manager Scott Dunnack 860-713-7264 and Architect Kathyann Cowles 860-657-0757

End of Addendum Number Three

  
David Busanet, Bidding & Contracts Supervisor  
Department of Public Works