INTERDEPARTMENTAL MEMORANDUM

TO: David Busanet, Bidding and Contracts Supervisor
Bidding & Contracts, Room G-35
165 Capitol Avenue, Hartford, CT 06106

FROM: John Nolan, Jr. Project Manager
Team General Gov't, Room 280
165 Capitol Avenue, Hartford, CT 06106

DATE: **January 13, 2010**

SUBJECT: ADDENDUM # 1

PROJECT TITLE: Bathrooms and Ramps
Veterans Affairs Campus – Buildings 2, 3 and 4
Rocky Hill, CT

PROJECT NO.: **BI-C-275**

SCHEDULED BID OPENING: **January 21, 2010 at 1:00PM**

Please expedite the attached **Addendum # 1**

1. The total number of pages in this addendum is: **16**
2. The total number of drawings in this addendum is: N/A
3. See attached Revised "Bid Released" form (55) dated: N/A
4. Addendum is clarifications to the Pre Bid Meeting that was held on 1/5/10.

Attachment
xc: Agency – John Wiltse/DVA
Team File – BI C 275
Project Manager – J. Nolan, C. Grodotzke

BATHROOMS AND RAMPS
VETERANS AFFAIRS CAMPUS – BUILDINGS 2, 3 & 4
ROCKY HILL, CONNECTICUT 06067
PROJECT: BI-C-275

BID OPENING	**1:00 P.M.**	**JANUARY 21, 2010**
ADDENDUM NUMBER 1	**DATE OF ADDENDUM**	**JANUARY 13, 2010**

The following clarifications are applicable to drawings and specifications for the project referenced above.

Item 1

ATTENDANCE RECORD for the Pre-Bid Meeting has been added and is attached as part of this addendum. (5 pages)

Item 2

See attached for RFIs. (7 pages)

Item 3

Project No. BI C 276, Upgrades to HVAC Systems for Buildings 3 and 4 will include replacing existing steam piping to the existing radiators on all floors, which will mean there will be no existing building heat during the construction of all phases. No allowance is going to be set up by DPW for temporary heating, cooling and ventilation. All projects will be required to provide their own heating, cooling and ventilation that is required for any finished work or comfort of their workers during the project. GC must supply his own temporary heat to maintain 50 degrees F in all bathrooms that are being renovated during the installation of floor and wall finishes, masonry work, interior painting, patching and testing of plumbing systems.

Item 4

Section 01 12 16, WORK SEQUENCE – PHASE(S), Page 3 of 56, Article C:

- Add the following:
  "Item No. 2 – the GC has the first ten (10) calendar days to removal all bathroom fixtures, tubs, shows, etc. prior to the start of asbestos abatement. The DPW's On Call Asbestos Contractor will then have eleven (11) calendar days for asbestos abatement.
  Item No. 3 – Change the Demo Phase for MEP from fourteen (14) calendar days to seven (7) calendar days."

Item 5

Section 10 21 13, TOILET PARTITIONS:

- Page 2, Article 1.7.A, revise "Class A" to read "Class B".
- Page 2, Article 2.1, add the following:

  "D. Global Partitions, Estanollee, GA (706.827.2700)

- Page 2, Article 2.2.A.3, revise "12 inches" to read "14 inches".
- Page 2, Article 2.2.A.4, revise "58 inches" to read "55 inches".
- Page 3, Article 2.3.A.1, revise "3/4 inch" to read "1 inch".
- Page 3, Article 2.3, add the following:
  "E. Hinges: 8 inch cast aluminum wrap around."

Item 6

Section 28 31 11, DIGITAL, ADDRESSABLE FIRE-ALARM SYSTEM :

- Page 1, Article 1.4, revise to read as follows:

  "Contractor shall be responsible for installing new fire alarm components to the existing Simplex Grinnell fire alarm system. This includes, but is not limited to, all programming, all reprogramming, testing, re-testing, connectors, conduit and all other materials associated with installing new devices to the existing fire alarm system."

- Page 5, Article 2.1.A.1, revise in its entirety to read "Simplex Grinnell".
- Page 5, Article 2.1.A.2, delete in its entirety.
- Page 5, Article 2.1.A.3, delete in its entirety.

Item 7

DRAWING SK-1, BUILDING #2 TOILET ROOMS DEMO & FLOOR PLANS has been added and is attached as part of this addendum. This revises information on Drawings D1 and A1.

Item 8

DRAWING E2, BLDGS 3 & 4 GANG BATHROOMS & BLDGS 2, 3 & 4 TOILET ROOMS ELECTRICAL PLAN:

- Electrical Notes, Note 4, revise to read as follows:

  "Provide 208V, 1 phase, 30A dedicated branch circuit and proper disconnecting means for power and controls for the dryer."

- Electrical 1-Line Diagram & Notes, Note 1, revise to read as follows:

  "Provide electrical panel 125A, MCB, 208Y/120V, 3 phase, Cutler-Hammer, NEMA 1A, recessed mounted, 22 KAIC, copper bus, 24 circuit with breakers as indicated. Rework existing branch circuits. Provide a 100A/3 phase feeder: 4 # 3 AWG & 1 # 8 ground in 2" conduit from electrical panel to main distribution panel location, use existing routing path of conduit. Contractor shall be responsible for field verifying all electrical panel equipment locations and existing conditions."

- Lighting Fixture Schedule, revise manufacturer/model number as follows:

  "A Omega Lighting/OM61H32PLTSRD-SHWR-120/277
  B1 Daybrite Lighting/BWN-328-UNV-1/3EB
  B1E Daybrite Lighting/BWN-328-UNV-1/3E6LP
  B2E Daybrite Lighting/2SPG-328-UNV-1/3E6LP"

  Also delete "vandal resistant" from the description of the above fixtures.

End of Addendum Number One

David Busanet, Bidding & Contracts Supervisor
Department of Public Works

Attendance Record

State of Connecticut

Department of Public Works

PROJECT NUMBER: BI-C-275 - Bittersweet Bridge - DVM/Rocky Hill & HC Ramps

DATE: 1/5/10

⊙ Pre-Bid Meeting ○ Pre-Construction Meeting ○ Progress Meeting ○ Special Meeting

	NAME/TITLE/FIRM	ADDRESS		PHONE/FAX/CELL
N	John Nolan, Jr	165 Capitol Ave., Rm 280	P	(860) 713 - 5838
T	DPW/Project Manager	Hartford, CT 06106	F	(860) 713 - 7251
F	DPW		C	(860) -
N	TJ Kronenberger	175 Industrial Park Rd.	P	860 347 4600
T	Estimating	Middletown, CT	F	860 343 0309
F	Kronenberger & Sons	06457	C	
N	Tom Esten	400 Middle St.	P	860-584-5971
T	Estimator	Bristol CT	F	860-585-8134
F	New Cambridge Painting	06010	C	tom-esten@ncpco.net
N	Luis Rodriguez	107 Old Windsor Rd	P	860-242-6586
T	Chief Estimator	Bloomfield, CT. 06002	F	860-242-8587
F	PDS Eng. & Const.		C	860-883-3183
N	Mazzarella Builders Inc	357 Newbritain Rd.	P	860-828-7663
T	Owner	Kensington CT.	F	860-828-1859
F	James Mazzarella	06037	C	860 883-5213
N	Rudolph Wetsch Const Co	77 Spring St	P	860-526-9246
T	VP	Chester Ct 06412	F	860-526-2844
F	Randolph Natsick		C	860-662-1399
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	

State of Connecticut

Attendance Record

Department of Public Works

PROJECT NUMBER: BI-C-275 - Bittmoor Pkwy. - DVA/Rocky Hill & HC Ramps

DATE: 1/5/10

⊙ Pre-Bid Meeting ○ Pre-Construction Meeting ○ Progress Meeting ○ Special Meeting

	NAME/TITLE/FIRM	ADDRESS		PHONE/FAX/CELL
N	John Nolan, Jr	165 Capitol Ave., Rm 280	P	(860) 713 - 5838
T	DPW/Project Manager	Hartford, CT 06106	F	(860) 713 - 7251
F	DPW		C	(860) -
N	Paul Hollmann	170 Commerce Way	P	860 - 291-9448
T	Vice President	Southwindsor, CT 06074	F	860- 289-6382
F	W.J. Mountford, Co.		C	—
N	Marco Caminito	336 Stamm Rd	P	860-666-2320
T	Project Manager	Newington, CT 06111	F	860-666-5156
F	Pioneer Builders, Inc		C	
N	Adam Zadrozny	596 John St	P	203-335-4204
T	PM	Bridgeport CT 06604	F	203-368-3425
F	Holzner Const.		C	
N	Sam Mosieur	53 Main St South	P	203-263-4557
T	Estimator	Woodbury CT	F	203-263 4426
F	Bond Hill Mechanical	06798	C	
N	Scott Schell	680 Main Street	P	860-274-8874
T	Estimator	Watertown, CT 06795	F	860-274-2118
F	Gar-San Corporation		C	Estimating@garsan.com
N	Christine Ezrell	627 Rte 32	P	860 642 6700x23
T	Estimator	Franklin, CT	F	860 642 7994
F	G. Donovan Associates	06254	C	—
N	TIMOTHY ELLIS	150 WATSON DR.	P	860-645-1105
T	ESTIMATOR	MANCHESTER, CT. 06042	F	860-645-1178
F	TITAN MECHANICAL CONT.		C	
N	Peter Noonan	150 Watson Dr	P	860-645 1105
T	Project Manager	Manchester, CT	F	860-645 1178
F	Titan Mech		C	
N	Steve Iuliano		P	
T	Elec Supv.	DVA	F	203-915-1188
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	

Attendance Record

State of Connecticut

Department of Public Works

PROJECT NUMBER: BI-C-275 - Bathroom Renov. - DVA/Rocky Hill & HC Ramps

DATE: 1/5/10

⦿ Pre-Bid Meeting ○ Pre-Construction Meeting ○ Progress Meeting ○ Special Meeting

	NAME/TITLE/FIRM	ADDRESS		PHONE/FAX/CELL
N	John Nolan, Jr	165 Capitol Ave., Rm 280	P	(860) 713 - 5838
T	DPW/Project Manager	Hartford, CT 06106	F	(860) 713 - 7251
F	DPW		C	(860) -
N	Howard Bishop	350 Bostwick Ave Bpt. CT	P	(203) 367-6220
T	Proj Manager		F	(203) 339-7095
F	Merritt Contractor Inc		C	(203) 556-2827
N	Ryan Gawel	42 Orick Dr	P	860-349-5449
T	estimator	Durham CT 06422	F	860-349-5448
F	A&S Electric		C	
N	Moe Villano	1850 Silas Deane Hwy	P	860-571-8812 xtn 18
T	Estimator	Rocky Hill, CT 06067	F	860-571-8891
F	Conn. Carpentry Corp.		C	MVillano@CTCarpentry.com
N	Jack Rawagnelli	15 Maple St	P	203 366 8957
T	E C Tramontano	Bpt CT 06608	F	203 333 0351
F	Gennaimi Court Co.		C	203 581 2747
N	Craig Pinney	227 Shunpike Rd.	P	860-632-6880 x301
T	Owner	Cromwell CT 06416	F	860-632-6884
F	Pinney Construction Corp.	cpinney@pinneycc.com	C	860-250-4062
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	

State of Connecticut

Attendance Record

Department of Public Works

PROJECT NUMBER: BI-C-275 - Bittersweet Pkwy. - DVA/Rocky Hill & I-tc Ramps DATE: 1/5/10

⊙ Pre-Bid Meeting ○ Pre-Construction Meeting ○ Progress Meeting ○ Special Meeting

	NAME/TITLE/FIRM	ADDRESS		PHONE/FAX/CELL
N	John Nolan, Jr	165 Capitol Ave., Rm 280	P	(860) 713 - 5838
T	DPW/Project Manager	Hartford, CT 06106	F	(860) 713 - 7251
F	DPW		C	(860) -
N	DEREK FLETCHER	196 EAST MAIN ST	P	860 283 6408
T	CHASE MECHANICAL	THOMASTON, CT	F	860 283 6019
F	CONTRACTORS INC	06787	C	860 989 6613
N	Samuel Walters	61 East Main street	P	860 585-1121
T	Quality Welding LLC	Bristol, CT 06010	F	860-940-6193
F			C	860-302-4634
N	Paul Hammell	69 Park ST	P	860-584-8844
T	Elite Mechanical	Bristol CT 06010	F	860-584-5457
F			C	
N	Richard Cheney	PO Box 396	P	860 928-1925
T			F	860 928 7868
F	Baker Inc	Pomfret Ct 06260	C	
N	Sean Miller	111 Utopia Road - PO Box 973	P	860-643-5888
T	Project Manager	Manchester, CT 06045	F	860.645.0897
F	Allied Construction Inc.		C	860-966-2583
N	OLYMPUS CONSTRUCTION	77 CHERRY ST	P	(203) 878-1544
T	PRESIDENT	MILFORD CT 06460	F	(203) 878-6430
F	JAMES PINO JR		C	(203) 258-8341
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	

Attendance Record

State of Connecticut

Department of Public Works

PROJECT NUMBER: BI-C-275 - Bathroom Rehoy. - DVA/Rocky Hill & HC Ramps

DATE: 1/5/10

⊙ Pre-Bid Meeting ○ Pre-Construction Meeting ○ Progress Meeting ○ Special Meeting

	NAME/TITLE/FIRM	ADDRESS		PHONE/FAX/CELL
N	John Nolan, Jr	165 Capitol Ave., Rm 280	P	(860) 713 - 5838
T	DPW/Project Manager	Hartford, CT 06106	F	(860) 713 - 7251
F	DPW		C	(860) -
N	ROEL LEGASPI	51 OZICK DRIVE, SUITE 100	P	860-349-5674
T	ESTIMATOR	DURHAM, CT 06422	F	860-349-5675
F	NOSAL BUILDERS, INC.	RLEGASPI@NOSALBUILDERS.COM	C	860-707-9953
N	Erica Levis	449 Cooke St	P	860-678-0678
T		Farmington, CT 06032	F	860-679-0474
F	All State Const., Inc		C	
N	MIKE GORMAN	112 NORTH WEST DR	P	860-436-4754
T		PLAINVILLE, CT	F	
F	FERGUSON & Co.		C	
N	ROB PEDIN	6 COMMERCE DRIVE	P	860-456-4576
T	PHONE ESTIMATOR	NORTH WINDHAM, CT	F	860-456-8937
F	SALAZIN GENERAL		C	
N	VICTOR GRANDKOLI	147 HALE RD	P	860-644-2427
T	ESTIMATOR	MANCHESTER CT 06042	F	860 644-6505
F	ORLANDO ANNULLI & SONS		C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	
N			P	
T			F	
F			C	

W. J. MOUNTFORD CO.
GENERAL CONTRACTOR • CONSTRUCTION MANAGER
170 Commerce Way, South Windsor, CT 06074, (860) 291-9448, Fax (860) 289-6382
License #00900574 • www.wjmountford.com

FAX TRANSMITTAL LETTER

Attention: Silver/Petrucelli + Associates **Company:** Dean Petrucelli

FAX: 1-203-230-8247

Number of pages, including this cover sheet 4

Reference: Bathrooms & Ramps
Veterans Affairs Campus – Buildings 2, 3 and 4
State Project BI-C-275
RFI #1

Message:

Dean,

Please respond to the attached questions.

Thank you.

From: Paul Hollmann **Date:** 12/9/09

Copy: Carlton Grodotzke 860-713-7261

PLEASE CALL IMMEDIATELY IF THERE ARE ANY PROBLEMS IN RECEIVING THIS TRANSMISSION (860) 291-9448. THANK YOU.

RFI #1
Bathrooms & Ramps
Veterans Affairs Campus – Buildings 2, 3 and 4
State Project BI-C-275
W. J. Mountford, Co.
December 30, 2009
Page 2

1. I'm having trouble coming up with the exact scope and phasing for the project work areas. Please see my references and suggestions below.

   From the Specifications

   a. In section 101100 – Summary of the Work, item E.1 indicates the scope includes 7 bathrooms and 4 mini bathrooms. – CORRECT = 13 TOTAL
   6, NOT 4

   b. In section 012300 – Supplemental Bids, it appears that each supplement adds 2 additional toilet rooms to the scope of the project. – YES (3) SUPP BIDS @ (2) EA = (6) TTHL

   c. In section 011216 – Work Sequence, the four phases are identified. The bathrooms are referenced by building, wing and floor level. This is a bit confusing, because all other references only use building and floor on the drawings and the small reference plans do not indicate the "wings." In addition, can you please indicate if the supplemental bids are accepted, which phase they will fall into? → EXAMPLE: PHASE ONE, A WING = FIRST FLR
   PHASE ONE, C WING = SECOND FLR
   SEE G1 AGAIN
   MINI BATHS { BLDG # 2 = PHASE TWO
   BLDG #3 = PHASE FOUR
   BLDG #4 = PHASE ONE

   From the Plans

   d. Drawing G1 indicates the phasing. It states there are 7 gang bathrooms and 6 small toilet rooms for a total of 13 in the project. This is contrary to what is stated in my item "a" above. (13) IS CORRECT NUMBER

   e. Drawing G1 shows the buildings, but doesn't specifically label the wings. I attempted to determine the wings based on the information indicated regarding the phasing and could not confirm for sure I had them all correct. The one that confused me is that in building #3 in phases 3 and 4, two work areas are identified in what I would call the same wing, however, phase 3 and 4 refer to four different wings. It would seem two have to be in the same wing based on the graphic markings on the building plans. ONE PHASE WILL INCLUDE FIRST & SECOND FLOORS. WING NAME ID & FLOOR ARE LISTED RESPECTIVELY.

   f. Drawing A1 leads me to believe there are 8 gang bathrooms and 6 small bathrooms in the base bid and leaves me uncertain regarding the number in the supplemental bids.
   6/A1, BLDG # 4 QTY IS MISLABELED. QTY OF BLDG #4 IS (3) (TYPICAL) (1) (ATYPICAL)
   " " "

Is it possible to prepare a table similar to the one at the end of this RFI that would clearly outline the building, the floor, the wing, the A1 plan reference and the phase for each toilet room in the project? It would be greatly appreciated.

QTY OF BLDG # 3 IS (3) TYPICAL
BLDG #1, WING E..
... IS NOT INCLUDED.

2. I'm having difficulty determining the full extent of new ceramic tile flooring work. It appears from the demolition drawing D1 that the existing tile flooring is being removed in all areas with the possible exception of the center area within the bathing and showering areas as noted on 1 and 4/AD1. On drawing A1 it is not fully clear that all new tile is required throughout the areas noted on partial plans 5, 6 and 7. Can you please confirm the requirements? DEMO NOTE #7. DEMO OF RAISED DECK CAN NOT BE ACHIEVED W/O DEMO OF FINISH TILE FIRST. TILE IS INCLUDED IN DEMO OF THIS AREA.

3. On plan reference detail 5/A1 the plans indicate new lockers in both toilet rooms but only states they are new in one. Are new required in both? Can you please confirm if supplemental bid # 3 requires new lockers in each bathroom as well?

NEW LOCKERS IN BOTH TOILET ROOMS.
SCOPE OF WORK IN TOILET ROOMS IS EXACTLY THE SAME.

DEMO NOTE #8 NEW FLOOR TILE WILL BE PROVIDED IN ALL AREAS PREVIOUSLY REMOVED. TILE THROUGH OUT.

State Project No. BI-C-275

Updated: 12/28/09

Work Areas and Sequences

	Base Bid	Supp. #1	Supp. #2	Supp. #3	Phases 1	2	3	4
Building # 3								
- Men's Gang Bathroom - 6/A1 - 1st Flr. – Wing ??	x	✓						
- Men's Gang Bathroom - 6/A1 - 2nd Flr. – Wing ??	x	✓						
- Men's Gang Bathroom - 6/A1 - 2nd Flr. – Wing ??	x	✓						
- Men's Comm. Area TR - 3/A1 - 2nd Flr. – Wing ??	x		X					
~~- Men's Comm. Area TR - 3/A1 - 2nd Flr. – Wing ??~~			x					
- Women's Common TR - 4/A1 - 1st Flr. – Wing ??	x		X					
~~- Women's Common TR - 4/A1 - ? Flr. – Wing ??~~			x					
-								
Building # 4								
- Men's Gang Bathroom - 6/A1 - 1st Flr. – Wing ??	x	✓						
~~- Men's Gang Bathroom - 6/A1 - 1st Flr. – Wing ??~~	x	✓						
- Men's Gang Bathroom - 6/A1 - 2nd Flr. – Wing ??	x	✓						
- Men's Gang Bathroom - 6/A1 - 2nd Flr. – Wing ??	x	✓						
~~- Men's/Women's Gang - 7/A1 - 1st Flr. – Wing ??~~	x	✓						
~~- Men's Comm. Area TR - 3/A1 - 1st Flr. – Wing ??~~	x							
~~- Men's Comm. Area TR - 3/A1 - 2nd Flr. – Wing ??~~	x							
- Men's Comm. Area TR - 3/A1 - 1st Flr. – Wing ??		x	✓					
- Men's Comm. Area TR - 3/A1 - 2nd Flr. – Wing ??		x	✓					
Building # 2								
- Dining Area TR - 5/A1 - 2nd Flr.	x			X				
- Dining Area TR - 5/A1 - 2nd Flr.	x			X				
~~- Dining Area TR - 5/A1 - ??? Flr.~~				x				
~~- Dining Area TR - 5/A1 - ??? Flr.~~				x				

WING F H G N.A. N.A.

WING A C D B OK

N.A. N.A.

SimplexGrinnell
80 Clark Drive
Suite 5D
East Berlin, CT 06023
860-438-3200
Fax 860-438-3258

Request for Information

To: Silver/Petrucelli & Assoc Request Date: 1/5/2010 Request No. 1
Carlton Grodotzke, PM DPW
Response Required By: ASAP

Attention:
Area Involved Proj # BI-C-275 Fire Alarm System
Document Referenced Spec
Specification Sec 28 31 11

Reason for Request:	Action Requested:	Probable Effect:
☐ Insufficient Information	☒ Clarification	☐ No Change
☐ Engineering Conflict	☐ Direction	☐ Increase Cost
☐ Alternative Proposal	☐ Approval	☒ Decrease Cost
☐ Other:	☐ Other:	☐ Impact Schedule

Question: The specification lists three acceptable (page 5) manufactures yet the existing Fire Alarm system is SimplexGrinnell which is not listed.
Should this be "add to existing system"?

SimplexGrinnell Representative's Signature: J Hersey Date: 1/5/2010

Response: THE SPECIFICATIONS NOW REFLECT THE ONLY ACCEPTABLE FIRE ALARM MANUFACTURER; SIMPLEX GRINNEL.
THIS WILL BE REFLECTED IN THE ADDENDUM
THAT WILL BE ISSUED NEXT WEEK
DAP 1-8-10

Owner Representative's Signature: Erik Dimeli Date: 1/8/10

CC:

CONNECTICUT CARPENTRY CORPORATION

- *General Contractors*
- *Residential Developers*
- *General Trade Package Contractors*
- *Commercial Wood Framing Crews*
- *Small Site Work Division*

Request for Information#1

To: Dean Petrucelli Copy To: Carlton Grodotzke
Fax: 1-203-230-8247 Fax: 860-713-7261
Phone:
Date: Thursday, January 07, 2010
Re: **Bath Renovations Veteran's Affairs BI-C-275**
From: Moe Villano
Pages: 1 , including this cover page

If all pages are not received, please notify us at once.

☒ URGENT – Please Reply ☐ FOR BIDS DUE:

MESSAGE: Please clarify the following for: Bath **Renovations Veteran's Affairs BI-C-275**

My Electrical subs have asked the following questions:
1. Does the contract include re-feeding the new LP-1 Bathrooms panels from the main distribution source? If yes, where are the main panels located? What size feeders are required? If main panel locations differ, could distances to the main panels be provided?

Please call me at 571-8812 (ext.#18) or mvillano@ctcarpentry.com with any questions.

Thank you
MOE V

RESPONSE THE CONTRACT INCLUDES RE-FEEDING LP-1 ELECTRICAL PANEL 125A, MCB, 208Y/120V, 3Ø FROM THE MDP SOURCE. THE EXACT LOCATION SHALL BE DETERMINED IN THE FIELD, VIA WALK-THROUGH. THE 100A/3Ø FEEDER SHALL CONSIST OF 4 #3 AWG & 1 #8 GROUND. ALL DISTANCES SHALL BE DETERMINED IN THE FIELD, VIA WALK-THROUGH.

S/P & A

ERIK BERARDI

Erik Berardi 1/8/10

1850 Silas Deane Highway, Rocky Hill, CT. 06067
– tel. (860) 571-8812 – fax (860) 571-8891

LINDQUIST
Builders Supply Company
Since 1919
240 Hathaway Drive Stratford Connecticut 06615-7392
203-381-5557 • 800-457-8478 • Fax 203-378-2233

Request for Information RFI#

Date: JANUARY 7,2010 Response Required By: JANUARY 12,2010

From: JONATHAN KING

To: CARLTON GRODOTZKE

Company: CONN. D.P.W.

Fax #: 860-713-7261

Job Name: V.A. BATHROOMS UPGRADE BIC275

Prev RFI#:

Information Required on the Following Issue:

1) WOOD DOOR SPECIFICATION 081416, PAGE 3,PARA. 2.5 - B CALLS FOR A MINIMUM STC SOUND RATING OF STC-35. STICK W/ SPECIFIED STC - 35

2) BASED ON AN APROX. QUANTITY OF 29 DOORS FOR THIS PROJECT, THIS SOUND RATING WOULD ADD APROX. $15,300.00 COMPARED TO STANDARD PARTICLE CORE DOORS.

3) DOUBLE LAYER ACCOUSTIC GLASS IS INCLUDED IN THIS ADD PRICE COMPARED TO STANDARD 1/4" TEMPERED GLASS SHOWN ON SHEET A1 DOOR ELEVATION TYPE-1 STICK W/ SPECIFIED GLAZING PER CDS/SPECS.

THANKS,

JONATHAN KING jking@lindquistbuildersupply.com EXT#331

NEW WOOD DR. & H.M. FRM
NEW WALL LOCKERS
PATCH EXTG FLR W/ REUSED, EXTG TERRAZZO.
NEW ACCESSIBLE WATER CLOSET
EXTG TERRAZZO FLR. TO REMAIN.
NEW ACCESSIBLE LAVATORY. NEW 6" CMU WALL
NEW WALL LOCKERS
TOILET ROOM
TOILET ROOM
1'-4"
5'-0"
9'-5" +/-
TYPICAL DINING AREA T.R. PLANS, BLDG #2
SCALE: 1/4" = 1'-0"
BLDG #2: TYPICAL OF (2) 2ND FLR.
BUILDING #2 DINING AREA TOILETS, SUPPLEMENTAL BID #3
TYPICAL DINING AREA T.R. DEMO, BLDG #2
SCALE: 1/4" = 1'-0"
BLDG #2: TYPICAL OF (2), 2ND FLRS.
BUILDING #2 DINING AREA TOILETS, SUPPLEMENTAL BID #3
1 ADDENDUM #1
Project Title: Bathrooms & Ramps Veterans Affairs Campus - Buildings 2,3,&4 Rocky Hill, CT.
SILVER / PETRUCELLI + ASSOCIATES
Architects and Engineers
3190 Whitney Avenue, Hamden, CT 06518-2340
Tel. 203 230 9007 Fax. 203 230 8247
www.silverpetrucelli.com
Drawing Title: Building #2 Toilet Rooms Demo and Floor Plans
Date: 11/1/10
Scale: 1/4" = 1'-0"
Drawn By: DW
Project Number: 09.013
Drawing Number: SK-1